

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Government of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 04-08-2025 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 04-08-2025 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 05-08-2025 at 10.30 AM.
4. Date of opening of Tender:- 05-08-2025 at 11.30 AM.

Sr. No	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	Repair and maintenance on link road Panjarda Hanoh Km 0/00 to 2/500 (SH:- C/O U- shape drain at RD 1/660 to 1/730)	97679/-	2000/-	Two Months	Rs. 350/-	Class-D
2	Restoration of Rain damages on link road from Bhumplu Da Ghat to Katoh (SH:- C/O R/wall at RD 0/950 to 0/954)	98189/-	2000/-	Two Months	Rs. 350/-	Class-D
3	Repair and maintenance on link road Panjarda Hanoh Km 0/00 to 2/500 (SH:- C/O U- shape drain at RD 1/730 to 1/800)	97679/-	2000/-	Two Months	Rs. 350/-	Class-D
4	A/R & M/O various road under Samirpur Sub Division (Section Dho (SH:- Painting and writing of sign board Km stone and village Board etc.)	99984/-	2000/-	Two Months	Rs. 350/-	Class-D
5	Restoration of rain damages on link rod from Bhumplu Da Ghat to Katoh (SH:- C/O R/wall at RD 0/945 to 0/950)	98900/-	2000/-	Two Months	Rs. 350/-	Class-D
6	A/R & M/O various road under Samirpur Sub Division (Section Samirpur) (SH:- Painting and writing of sign board Km. Stone and village board etc)	99980/-	2000/-	Two Months	Rs. 350/-	Class-D

7	C/O Una Aghar Mandi road km 79/00 to 90/00 (II) Link road from Lagmanwin Mandir to Chahab More via Samkari Km 0/00 to 3/015 under HPPWD Sub Division Bhoranj HPPWD Bhoranj (Providing & manufacturing sign Board)	98000/-	2000/-	Two Months	Rs. 350/-	Class-D
8	R/M of various roads under Samirpur Sub Division HPPWD Division (Section Chamboh) (SH:- Maintenance of earthen shoulder unlined surface drain and removal of slip)	99679/-	2000/-	Two Months	Rs. 350/-	Class-D
9	R/M of various roads under Samirpur Section , Samirpur Sub Division . (SH:- Maintenance of earthen shoulder , unlined surface drain and removal of slip)	99679/-	2000/-	Two Months	Rs. 350/-	Class-D
10	C/O Link road from Lagmanwin to Manoh (ii) Link road Mudkhar Ganda Chab to Harizan Basti under HPPWD Sub Division Bhoranj HPPWD Bhoranj (SH:- Providing & manufacturing sign Board)	98000/-	2000/-	Two Months	Rs. 350/-	Class-D
11	Restoration of rain damages on Town Bharari to Gharun Balet road (SH:- C/O R/wall at RD 0/249 to 0/253)	98532/-	2000/-	Two Months	Rs. 350/-	Class-D
12	R/M on link road I/C 1 No. Bridge from Ladrour Hatwar road at village Samlah to Dasmal via Tohu & Govt Promary School Tohu in road Km 0/00 to 1/510 (SH:- P/L C.Conc. pavement at RD 0/197 to 0/226)	95949/-	2000/-	Two Months	Rs. 350/-	Class-D
13	Restoration of Rain damages on Town Bhareri to Gharun Balet road. (SH:- C/O R/wall at RD0/245 to 0/249)	96898/-	2000/-	Two Months	Rs. 350/-	Class-D
14	R/M on link road including one No. Bridge from Ladrour Hatwar road at village Samlah to Dasmal via Tohu & Govt Promary School Tohu in road Km 0/00 to 1/510 (SH:- P/L C.Conc. pavement at RD 0/00 to 0/029)	95949/-	2000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPT No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

For and on behalf of Governor of HP

Dated:- 28-07-2025

No:-PW/BHD/TA/NIT/2024- 5143-83

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj.
12. Various Contractors/ Firms.

Executive Engineer,
Bhoranj Division,
HPPWD, Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair and Maintenance on link road Panjarla Hanoh km. 0/00 to 2/500 (SH:-C/O U-shape drain at RD 1/660 to 1/730.)

Estimated Cost
Earnest Money
Rs. 2000/-
Rs 97679/-
2 month
Amount

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	31.80	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm (twenty millimeters) nominal size in open foundations complete including cost of shuttering & form work as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	16.63	Per cubic meter			
Total						
Terms and Condition:-						
1 Work shall be executed as per PWD specification.						

Executive Engineer
Bholaraj Division
H.P.W.D. Bhorani

OF WORK:- Restoration of Rain Damages on link road from Bhumplu Da Ghat to Katoh . (Sh:- C/O R/Wall at RDO/950 to 0/954.)

SCHEDULE OF QUANTITY

Estimated Cost
Earnest Money
Time
Rs 98189/-
Rs. 2000/-
2 month

Sl No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring a structure and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	10.76	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.14	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plas/finolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogram per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire cartage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.67	Per Cubic Meter			
Total						
Terms and Condition:-						

1 Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
PWD Bhoranj

SCHEDULE OF QUANTITY

2 OF WORK:- Restoration of Rain Damages on link road from Bhumpu Da Ghat to Katoh . (SH:- C/O RWall at RD0/950 to 0/954.)

Estimated Cost Rs 98189/-
Earnest Money Rs. 2000/-
Time 2 month

Sl No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	10.76	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.14	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vedux pipe having pressure 4kg per centimeter square. (four kilogram per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in -Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.67	Per Cubic Meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
P.W.D Bhoranj

SCHEDULE OF QUANTITY

ME OF WORK:- Repair and Maintenance on link road Panlārda Hanoh km. 0/00 to 2/500, (SH-C/O U-shape drain at RD 1/730 to 1/800.)

Estimated Cost
Earnest Money
Time

Rs 97679/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	31.80	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete including cost of shuttering & form work as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	16.63	Per cubic meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.D. PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O various road under Samirpur Sub- Division (Section Dho)
(SH:- Painting and writing of sign board Km. Stone and village board etc.).

Estimated Cost Rs. 99984/-
 Earnest Money Rs. 2000/-
 Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One or more coats on old work as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	85.17	Per Square Meter			
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	41.76	Per Square Meter			
3	Re-lettering with black Japan paint of approved brand and manufacture as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	23396.00	Per letter/Per cm ht.			
Terms and Condition:-						
1. Work shall be executed as per PWD specification.						

Executive Engineer
 Bhoranj Division
 HRPWD Bhoranj

F WORK:- Restoration of Rain Damages on link road from Bhumpu Da Ghat to Katoh . (SH:- C/O RWall at RD 0/945 to 0/950.)

SCHEDULE OF QUANTITY

Estimated Cost
Earnest Money
Time
Rs 98900/-
Rs. 2000/-
2 month

Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1 Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etc/tera in all type of classification of soil (comprising of ordinary soil , ordinary rock , hard rock, chiselling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring a structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.29	Per Cubic Meter			
2 Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.73	Per Cubic Meter			
3 Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vactus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in -Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.00	Each			
4 Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.90	Per Cubic Meter			
Total					
Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhorani Division
(H)PWD Bhorani

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O various road under Samirpur Sub- Division (Section Samirpur) (SH:- Painting and writing of sign board Km. Stone and village board etc.):

Estimated Cost
Earnest Money

Rs. 999
Rs. 200

Sr No	Description of Items	Quantity	Unit	Rate	Time	
					Rates in Words	2 Month Amount
1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One or more coats on old work, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	77.42	Per Square Meter			
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	39.96	Per Square Meter			
3	Re-lettering with black Japan paint of approved brand and manufacture as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	23650.00	Per letter/Per cm ht.			
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhojanj Division
H/PWD Bhojanj

Draft Schedule of Quantity

Estimated Cost :- 98000.00
 Earnest Money:- 2000.00
 Time: - 3 months

Name of Work:- C/O Una Aghar Mandi Road km 79/0 to 90/00 (ii) Link road from Lagmanwin Mandir to Chahab More via Samkari km. 0/0 to 3/015 under HPPWD Sub-Division Bhoranj HPPWD Bhoranj. (Providing & manufacturing sign Borad)

Sr. No.	Description of items work	Qty	Unit	Rate In fig.	In words	Amount
1.	Providing and manufacturing steel fabrication of sign boards size following dias make of M.S sheet 1.60mm thickness with MS pipe 32mm dia. The height of board should not be less than 2430mm and size 4x3 including, welding, priming single coat complete in all respect and to the entire satisfaction of Engineer in Charge.	20	Each	4950/-		

TERMS AND CONDITIONS:

1. The work will be carried out as per PWD specification and to the entire satisfaction of the Engineer in charge.
2. The rates shall be inclusive with all taxes and carriage of material in all leads and lifts.
3. Nothing will be paid for rejected work/material.
4. The material shall be used of ISI marked/reputed make.

[Signature]
[Signature]
 H.P.W.D. Bhoranj
 Executive Engineer
 HPPWD Division,
 Bhoranj.

NAME OF WORK:- R.M. of Various roads under Samtampur sub Division HPPWD Division Bhoranj (Section Chamboli) (SH:- Maintenance of earthen shoulder,
Unlined Surface drain and Removal of Silt)

SCHEDULE OF QUANTITY

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost Earnest Money Time	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	735.00	Per square metre				
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire cartage of material in all lead and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.00	Per Running Mtr.				
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302,3.5 and 1611 and as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	260.00	Per Cubic metre				
Total							
Terms and Condition:-							
1. Work shall be executed as per PWD specification.							

Executive Engineer
Bhoranj Division
H.P.W.D. Bhoranj

SCHEDULE OF QUANTITY

OF WORK:-RM of Various roads under Samirpur Section Samirpur Sub-Division.
Maintenance of earthen shoulder ,unlined surface drain and Removal of slip.)

Estimated Cost Rs. 99679/-
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	735.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	200.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302,3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	260.00	Per cubic metre			
	Total					

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HIRPWD Bhoranj

Draft Schedule of Quantity

Estimated Cost :- 98000.00
Earnest Money:- 2000.00
Time:- 3 months

Name of Work:- C/O Link road from Lagmanwin to Manoh (ii) Link road Mundkhar Ganda Chab to Harizan Basti under HPPWD Sub- Division Bhoranj HPPWD Bhoranj. (Providing & manufacturing sign Borad)

Sr. No.	Description of items work	Qty	Unit	Rate In fig.	In words	Amount
1.	Providing and manufacturing steel fabrication of sign boards size following dias make of M.S sheet 1.60mm thickness with MS pipe 32mm dia. The height of board should not be less than 2430mm and size 4x3 including, welding, priming single coat complete in all respect and to the entire satisfaction of Engineer in Charge.	20	Each			

TERMS AND CONDITIONS:

1. The work will be carried out as per PWD specification and to the entire satisfaction of the Engineer in charge.
2. The rates shall be inclusive with all taxes and carriage of material in all leads and lifts.
3. Nothing will be paid for rejected work/material.
4. The material shall be used of ISI marked/reputed make.


Executive Engineer
HPPWD Division
Bhoranj.

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Rain Damages on Town Bharati to Gharun Balet road . (SH:- C/O R/Wall at RD 0/249 to 0/253.)

Estimated Cost
Earnest Money
Time
Rs 98532/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of slumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.60	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.00	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe. De-plas/finolex vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204,3.7 as per direction of Engineer- in -Charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire cartage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.80	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HB/PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M on LINK ROAD IIC 1 NO. BRIDGE FROM LADROUR, HARWAR ROAD AT VILLAGE SAMLAH TO DASMAL VIA TOHU & GOVT. PRIMARY SCHOOL TOHU IN ROAD KM. 0/0 TO 1/510.(SH:- P/L C.Conc. pavement at RD 0/197 to 0/226).

Estimated Cost Rs 95,949/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates In Words	Amount
1	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size/as per direction of Engineer-in-Charge including entire carriage of material within all leads and its and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.23	Per Cubic Meter			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Rain Damages on Town Bharrari to Gharun Balet road . (SH:- C/O R/Wall at RD 0/245 to 0/249.)

Estimated Cost
Earnest Money
Time
Rs 96898/-
Rs. 2000/-
2 month
Amount

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.00	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size)) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.41	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plas/Inolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1/V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.00	Per Cubic Meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bharrari Division
PWD Bharrari

SCHEDULE OF QUANTITY

OF WORK:- R/M on link road including one No. bridge from Ladrour Hatwar road at village Samlah to Dasmal via Tohu and Govt. Primary
 col Tohu km. 0/0 to 1/510.(SH:- P/L Cement Concrete Pavement in km. 0/00 to 0/029.)

Estimated Cost Rs 95949/-
 Earnest Money Rs. 2000/-
 Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size/as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.23	Per Cubic Meter			
	Total					

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
 Bhoranj Division
 H.P.W.D Bhoranj