

Offline

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PWD-Dal/TA/Tender /2025-26 1976 - 78
To

Dated: - 09.07.2025

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2


Subject: -

Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.


Copy forwarded to the Superintending Engineer, 7th Circle,
HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive
Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie


Certificate

Certified that the tenders called vide this office letter No. PWD-
TA/Tender /2025-26:- 1976-78 dated. 09.07.2025 is emergent nature and in Public
interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Certificate

Certified that the tenders called vide this office letter No. PWD-
TA/Tender /2025-26:- 1976-78 dated. 09.07.2025 is emergent nature and in Public
interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-


1. Date of receipt of application for the tender Form a /w requisite documents:- 15.07.2025 onward (between 2:00 p.m.to 4:30.p.m.)
2. Date of issue/sale of tender form against Cash payment (non refundable). 15.07.2025.

The tender shall be received up to 3:00 PM on 16.07.2025 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender will be sold by this office against cash payment as shown below (Non refundable) during the working hours on 15.07.2025

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie a must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Restoration of Rain damage on Dalhousie Jandrighat Chamba via Kohlari road km. 0/0 to 11/040 (SH:- Construction Of PCC Retaining wall at R.D. 10/220.40 to 10/222.10	95700.00	2000.00	350.00	Two Months	D & C
2.	Restoration of Rain damage on Banikhet Dalhousie Kahjjar road km. 15/600 to 27/00 SH:- Removal of Slips at various RD,s	99383.00	2000.00	350.00	One Months	D & C
3	Restoration of Rain Damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH:- Construction of PCC Retaining wall at RD. 10/223.80 to 1/350.)	95005.00	2000.00	350.00	Two Months	D & C
4	Restoration of Rain Damage on Orumour to Sherpur Road Km. 0/0 to 3/750 (SH:- Removal of Slips at RD, 1/340 to 1/370.)	96813.00	2000.00	350.00	One Months	D & C
5	Restoration of Rain Damage on Orumour to Sherpur Road Km. 0/0 to 3/750 (SH:- Removal of Slips at RD. 1/360 to 1/370.)	86979.00	1800.00	350.00	One Months	D & C
6	Restoration of Rain Damage on Link Road to Village Ruliyani Km. 0/0 to 3/0 (SH:- Removal of Slips at various RD,s)	96245.00	2000.00	350.00	One Months	D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory. .
2. GST No. Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
3. Application without all documents will not be entertained.
4. Proxy application will not be entertained.



 Executive Engineer,
 Dalhousie Division,
 HPPWD, Dalhousie.

No. PWD/TA/Tender /2025-26 1979 - 2029

Dated:- 09.07.2025

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.




Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost :- Rs.	95700.00
Earnest Money :- Rs.	2000.00
Time Limit :-	Two Months

Name of work: -Restoration of Rain damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Construction of PCC Retaining wall at RD. 10/220.40 to 10/222.10).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government.	6.22			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax , GST or any other taxes imposed by the Government.	17.92			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	2.72			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and tecdical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	6.00			Each	
					Total: -	


 Engineer
 Dalhousie Division
 U.F.P.W.D. Dalhousie


Schedule of Qty.

Job No. 02 TS 18

Estimated Cost :- Rs.

99383.00

Earnest Money :- Rs.


2000.00

Time Limit :-

One Month

Name of work: -Restoration of rain damage on Banikhet Dalhousie Kahjjiar road Km. 15/600 to 27/00 (SH: - Removal of Slips at various RD's.).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	795.70			Per Cubic Metre	
					Total:-	


Executive Engineer
Dalhousie Division
M.P.W.D. Dalhousie
2/5/20

Schedule of Qty.


Estimated Cost: - Rs. 95005.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Months

Name of work: -Restoration of Rain damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Construction of PCC Retaining wall at RD. 10/223.80 to 10/225.50).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government	5.34			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax , GST or any other taxes imposed by the Government.	17.92			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	2.45			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	6.00			Each	
Total: -						




 Executive Engineer
 Dalhousie Division
 W.P.W.D. Dalhousie
 10/22

Schedule of Qty.

Estimated Cost: - Rs.	96813.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

Name of work: -Restoration of rain damage on Orumour to Sherpur road Km. 0/0 to 3/750 (SH: - Removal of Slips at RD. 1/340 to 1/350).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	775.25			Per Cubic Metre	
					Total:-	


 Executive Engineer
 Dalhousie Division
 H.P.W.D. Dalhousie


Schedule of Qty.

Job No. 05 TS 20


Estimated Cost: - Rs. 86979.00

Earnest Money :- Rs. 1800.00

Time Limit :- One Month

Name of work: -Restoration of rain damage on Orumour to Sherpur road Km. 0/0 to 3/750 (SH: - Removal of Slips at RD. 1/360 to 1/370).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	696.50			Per Cubic Metre	
Total:-						



Executive Engineer
Dalhousie Division
P.W.D. Dalhousie

Schedule of Qty.

Estimated Cost: - Rs.	96245.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

Name of work: -Restoration of rain damage on link road to village Ruliyani Km. 0/0 to 3/0 (SH: - Removal of Slips at various RD's).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	770.58			Per Cubic Metre	
					Total:-	


 Executive Engineer
 Dalhousie Division
 P.W.D. Dalhousie