HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DPD/CB-Tender/2023- 1665-66 Dated:- 22-07-2025

To

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publishing of tender Notice.

Sir,

Enclosed please find herewith tender notice of work as given in the Notice inviting Tender along with Schedule of Quantities for uploading the same on department website as per Notification No. Pr. Secy. (PW) to the Govt. of HP letter No. PBW (B) A(3) 1/2024 dated Shimla-2, the 03.01.2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ As above.

Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

Copy along with its enclosures is forwarded to the Superintending Engineer, 15th Circle, HPPWD Una for information please.

Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

Scanned with OKEN Scanner

CERTIFICATE

Certified that tenders called vide this office letter No. PWD/DPD/CB-Tender/2025-1658-64 dated 22/07/2025 are required to be carried out immediately being emergent nature of work in the public interest.

Executive Engineer,
Daulatpur chowk Division,
HPPWD Daulatpur Chowk.

Scanned with OKEN Scanner

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed **Percentage rates** tenders on form 6 & 7 are hereby invited by the Executive Engineer Daulatpur Chowk Division, HPPWD, Daulatpur Chowk on behalf of Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office and opened as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tenders.

Date and time of receipt of applications for the tender form : 28.07.2025 up to 01.00 PM
Date and time of issue/sale of tender forms against cash Payment : 28.07.2025 (03.30 PM to 5.00 PM)
Date and time of receipt of tenders : 29.07.2025 up to 11.00 AM
Date and time of opening of tenders : 29.07.2025 at 11.30 AM

The tender forms will be issued against cash payment (non-refundable). The earnest money in the shape of NSC/Time Deposit/FDR of nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

Sr. No.	Name of Work	Estimated Cost	Earnest money	Time Limit	Cost of Form	Eligible Class of Contractor
`1	Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-I. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)	99571.00	2000.00	One Month	350-	C & D
2	VKV/2024/446, C/O (Construction of) Playground at Govt. Senior Secondary School Ghanari in Gagret constituency Tehsil Ghanari Distt. Una (H.P)	95179.00	2000.00	Three Month	350-	C & D
3	SDP/2024/252, C/O (Construction of) Playground & Stage in Govt. Sr. Sec. School Bhadarkali in G.P. Bhadarkali Tehsil Ghanari Distt. Una (H.P) Under SDP	66291.00	1400.00	Three Month	350-	C & D
4	Repair & Restoration of Rain Damages on various roads in Gagret Sub Division, Section Gagret-II. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)	99571.00	2000.00	One Month	350-	C & D
5	VKV/2024/449, C/O (Construction of) Stage at Govt. High School Babehar Tehsil Ghanari District Una (HP)	73813.00	1500.00	Three Month	350-	C & D
6	Repair & Restoration of Rain Damages on various roads in Gagret Sub Division, Section Mubarikpur. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)	99571.00	2000.00	One Month	350-	C & D
7	VKV/2024/448, C/O (Construction of) Boundary wall in Govt. High School Babehar in Gram Panchyat Babehar, District Una (H.P)	96317.00	2000.00	Three Month	350-	C & D
8	C/o Link road Amlehar Harijan Basti Km 0/0 to 0/500, (SH: Providing on temporary basis services of 1 No. Clerk for the month August 2025 to November 2025) Under MMSY	87230.00	1800.00	Four Month	350-	C & D
9	Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-II. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)	99571.00	2000.00	One Month	350-	C & D
10	Construction of College building (Ground Floor and First Floor) Two Nos. Class rooms with verandah in Govt. Degree College Daulatpur Chowk, Distt. Una , (SH:- Soil investigation and Prepare of Topographical & Contour site plan)	82575.00	1700.00	Three Month	350-	C & D

Scanned with OKEN Scanner

11	Providing and Installation Computer System with UPS, Printer in HPPWD Division office Daulatpur Chowk (UnderTelecom Deposit)	83400.00	1700.00	15 Days	350-	C & D
12	Construction of Rajiv Ghandhi Govt. Model Day Boarding School at Sanghnai in Legislative Assembly Constituency Gagret Distt. Una (HP), (SH:- Soil investigation for Rajiv Ghandhi Govt. Model Day Boarding School and Prepare of Topographical & Contour site plan of Govt. Senior Secondary School Sanghai in Distt. Una)	83340.00	1700.00	Three Month	350-	C & D

TE35RMS AND CONDITIONS: -

1. The contractor should produce a copy of enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his registration and GST No. and copy of the same be attached with the application.
3. The earnest money for the above works should be submitted duly pledged in favour of Executive Engineer, Daulatpur Chowk Division, HPPWD Daulatpur chowk with the application for the purchase of tender forms. The application received without earnest money shall be summarily rejected.
4. The contractor/firms are required to insert the rate in words as well as in figures failing which Executive Engineer reserves the right to accept/rejects any or all tenders.
5. If any of the date mentioned above happens to be Local/Gazetted Holidays the same shall be process on next date.
6. The tender form will be issued to those contractors who have relevant machinery and equipment, list of which may be attached with their application along with proof of ownership of machinery/legal tie up.
7. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.

Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

No. PWD/DPD/CB-Tender/2025- 1658-64 Dated: - 22/07/2025

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-Chief, HPPWD Nirman Bhawan Shimla.
2. The Chief Engineer (HZ) HPPWD Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD Una.
4. All the Assistant Engineers working under this division.
5. Drawing Branch in this office.
6. Notice Board.

Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

Scanned with OKEN Scanner

Job No – 1

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99571/-
Earnest Money: Rs.2000/-
Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-I. (SH: Maintenance of Earhen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earhen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	418.50 Square metre	80.00	Rupees Eighty Only	Per Square metre	33480.00
	Total Amount in Rs.					
	Quoted Rate in Figure	% above/below				**99571.00**
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Scanned with OKEN Scanner

Job No-2

DRAFT BILL OF QUANTITY

Estimate Cost :- Rs. 95179/-
Earnest Money :-Rs. 2000/-
Time Limit :- Three Month.

Name of Work:- VKV/2024/446, C/O (Construction of) Playground at Govt. Senior Secondary School Ghanari in Gagret contituency Tehsil Ghanari Distt. Una (H.P)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Construction of embankment with approved materials deposited at site obtained from roadway cutting and excavation from drains and foundation of all other structures or other sources, or obtained from borrow pits within all leads and lifts, graded and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor–Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 of MORD technical specification section 300 and 1600 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, toll tax, goods service tax, labour cess or any other taxes imposed by the Government.	135.00 Cubic metre.	220.00	Rupees Two Hundred Twenty Only	Per cubic metre	29700.00
2	Loosening, Levelling and Compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve minimum dry density as given in Tables 300.1 and 300.2 for embankment construction as per Technical Specification Clause 301.4 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, toll tax, goods service tax, labour cess or any other taxes imposed by the Government.	52.50 Cubic metre.	105.50	Rupees One Hundred Five And Paise Fifty Only	Per cubic metre	5539.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	16.65 Cubic metre.	3600.00	Rupees Three Thousand Six Hundred Only	Per cubic metre	59940.00
	TOTAL					**95179.00**
	Quoted Rate in Figure		% above/below			
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Scanned with OKEN Scanner

Job No- 3

DRAFT BILL OF QUANTITY

Estimate Cost :- Rs. 66291/-
Earnest Money :-Rs. 1400/-
Time Limit :- Three Month.

Name of Work:- SDP/2024/252, C/O (Construction of) Playground & Stage in Govt. Sr. Sec. School Bhadarkali in G.P. Bhadarkali Tehsil Ghanari Distt. Una (H.P) Under SDP

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Construction of embankment with approved materials deposited at site obtained from roadway cutting and excavation from drains and foundation of all other structures or other sources, or obtained from borrow pits within all leads and lifts, graded and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor–Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 of MORD technical specification section 300 and 1600 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, toll tax, goods service tax, labour cess or any other taxes imposed by the Government.	61.88 Cubic metre.	220.00	Rupees Two Hundred Twenty Only	Per cubic metre	13614.00
2	Loosening, Levelling and Compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve minimum dry density as given in Tables 300.1 and 300.2 for embankment construction as per Technical Specification Clause 301.4 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, toll tax, goods service tax, labour cess or any other taxes imposed by the Government.	45.00 Cubic metre.	105.00	Rupees One Hundred Five Only	Per cubic metre	4725.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	13.32 Cubic metre.	3600.00	Rupees Three Thousand Six Hundred Only	Per cubic metre	47952.00
	TOTAL					**66291.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Scanned with OKEN Scanner

Job No-4

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99571/-
Earnest Money: Rs.2000/-
Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on various roads in Gagret Sub Division, Section Gagret-II. (SH: Maintenance of Earhen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earhen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	418.50 Square metre	80.00	Rupees Eighty Only	Per Square metre	33480.00
	Total Amount in Rs.					**99571.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Scanned with OKEN Scanner

DRAFT BILL OF QUANTITY

Job No-05

Estimated Cost: Rs. 73813/-
Earnest Money: Rs. 1500/-
Time Limit : Three Month.

Name of Work:- VKV/2024/449, C/O (Construction of) Stage at Govt. High School Babehar Tehsil Amb District Una (HP)

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Excavation in all kind of soil work by mechanical means (Hydraulic Excavator (3D) with driver and fuel)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan) in all kind of soil, including dressing of sides and ramming of bottoms, upto any lift, including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead as per the direction by Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.900	Cubic meter	180.00	Rupees One Hundred Eighty Only	Per Cubic meter	522.00
2	Providing form work with steel plates 3.15mm (three point fifteen millimeter) thick welded with angle iron in frame 30×30×5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering, strutting and propping etcetera with wooden battens and ballies upto any height in all floor level of propping and centring below supporting floor to ceiling upto any height and removal of the same for in-situ reinforced cement concrete and plain concrete work as per CPWD specifications 2019 in foundations, footings, bases of columns, etc. for mass concrete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	13.920	Square meter	280.00	Rupees Two Hundred Eighty Only	Per Square meter	3898.00
3	Providing and laying in position cement concrete work M-25 (M-twenty five) design mix with minimum cement contents not less than 400 kgs.(four hundred kilogram) per cubic metre including curing complete excluding cost of form work in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to all floor level, excluding the cost of centering, shuttering and finishing upto all height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.160	Cubic meter	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic meter	13392.00

Scanned with OKEN Scanner

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
4	Providing and laying in position cement concrete 1:4:8(one cement: four coarse sand: eight graded/crushed stone aggregate 40mm (forty miillmeter) nominal size mechanically mixed and curing complete excluding cost of centering and shuttering in foundation and plinth level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.400	Cubic meter	3600.00	Rupees Three Thousand Six Hundred Only	Per Cubic meter	8640.00
5	Providing steel reinforcement and Thermo-Mechanically Treated bars of grade Fe-500D or more approved make i.e. SAIL, RINL,Shyam Steel/TISCO, Jindal Panther (JSPL) for reinforced cement concrete work including bending cutting straightning and placing in position binding all complete upto any floor level/height as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	86.440	Kg	85.50	Rupees Eighty Five And Paise Fifty Only	Per Kg	7391.00
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in cement mortor 1:6 (one cement: six coarse sand) as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.740	Cubic meter	7000.00	Rupees Seven Thousand Only	Per Cubic meter	19180.00
7	Steel work in built up tubular (round, square or rectangular hollow Hot finished welded type tubes etc.) trusses etc San HARVIC Steelman Industries P.D. Industries metal windows, Chandni Industires Ganpati Udyog (Rajpura) Tata and Jindal make., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete upto any floor level/ height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.510	Qtl.	9200.00	Rupees Nine Thousand Two Hundred Only	Per Qtl	4692.00
8	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete as per the direction by the Engineer in charge and including entire carriage of materials within all leads and lifts and other incidentials . The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	4.800	Square metre	750.00	Rupees Seven Hundred Fifty Only	Per square metre	3600.00

Scanned with OKEN Scanner

Sr. No.	Sub-Head and Items of work	Quantity		Rates in Figures	Rates in Words	Unit	Amount
9	40 mm(forty millimeter) thick with 20 mm (twenty millimeter) nominal size stone aggregate Cement concrete flooring 1:2:4 (one cement : two coarse sand : four graded/crushed stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etcetera complete upto any floor level/ height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	24.000	Square metre	360.00	Rupees Three Hundred Sixty Only	Per square metre	8640.00
10	15mm (fifteen millimeter) Cement plaster on the rough side of single or half brick wall of mix cement mortor 1:4 (one cement: four coarse sand) in any floor/any height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	10.000	Square metre	220.00	Rupees Two Hundred Twenty Only	Per square metre	2200.00
11	Finishing walls with Acrylic Smooth exterior paint of required shade with Nerolac/Asian/Berger make new work (Two or more coat applied @ 1.67 ltr/10 sqm (one point sixty seven liter per ten square meter) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two point twenty kilogram per ten square meter) in all floor level/ height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	18.420	Square metre	90.00	Rupees Ninety Only	Per square metre	1658.00
	Quoted Rate in Figure			% above/below			73813.00
	Quoted Rate in Words						

Executive Engineer,
HPPWD Division,
Daulatpur Chowk

Scanned with OKEN Scanner

Job No - 06

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99571/-
Earnest Money: Rs.2000/-
Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on various roads in Gagret Sub Division, Section Mubarikpur. (SH: Maintenance of Earhen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earhen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	418.50 Square metre	80.00	Rupees Eighty Only	Per Square metre	33480.00
	Total Amount in Rs.					**99571.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Scanned with OKEN Scanner

Job No - 07

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 96317/-
Earnest Money: Rs. 2000/-
Time Limit : Three Month.

Name of Work:- VKV/2024/448, C/O (Construction of) Boundary wall in Govt. High School Babehar in Gram Panchyat Babehar, District Una (H.P)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Excavation in all kind of soil work by mechanical means (Hydraulic Excavator (3D) with driver and fuel)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan) in all kind of soil, including dressing of sides and ramming of bottoms, upto any lift, including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead as per the direction by Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	3.84 Cubic meter	180.00	Rupees One Hundred Eighty Only	Per Cubic meter	691.00
2	Providing and laying in position cement concrete 1:3:6 (one cement:three sand: six graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and curing complete excluding cost of centring and shuttering in foundation and plinth level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.44 Cubic meter	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic meter	20672.00
3	Providing and laying cement concrete work 1:2:4 (1 Cement:2 Sand:4 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in (a) String courses, copings, bed plates, anchor blocks, plain windows sills etc. as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	0.44 Cubic meter	6050.00	Rupees Six Thousand Fifty Only	Per Cubic meter	2662.00
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to all floor level in all shapes and sizes in cement mortor 1:6 (one cement: six coarse sand) as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.04 Cubic meter	7050.00	Rupees Seven Thousand Fifty Only	Per Cubic meter	7332.00

Scanned with OKEN Scanner

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level in any floor/height in cement mortor 1:4 (one cement: four coarse sand) as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	44.80 Square metre	860.00	Rupees Eight Hundred Sixty Only	Per square metre	38528.00
6	15mm (fifteen millimeter) Cement plaster on the rough side of single or half brick wall of mix cement mortor 1:4 (one cement: four coarse sand) in any floor/any height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	89.60 Square meter	205.00	Rupees Two Hundred Five Only	Per Square meter	18368.00
7	Finishing walls with Acrylic Smooth exterior paint of required shade with Nerolac/Asian/Berger make new work (Two or more coat applied @ 1.67 ltr/10 sqm (one point sixty seven liter per ten square meter) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two point twenty kilogram per ten square meter) in all floor level/ height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royality, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	89.60 Square meter.	90.00	Rupees Ninety Only	Per Square meter.	8064.00
						96317.00
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk

Scanned with OKEN Scanner

Job No -08

DRAFT BILL OF QUANTITY

Estimated Cost: Rs.87230/-
Earnest Money: Rs.1800/-
Time Limit : Four Month

Name of Work:- C/o Link road Amlehar Harijan Basti Km 0/0 to 0/500, (SH: Providing on temporary basis services of 1 No. Clerk for the month August 2025 to November 2025) Under MMSY

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Providing services on temporary basis of clerk for attending the office for the month August 2025 to November 2025 (10:00 AM to 5:00 PM) as well as required by this office/by the officer in charge. The rate inclusive of all Taxes imposed by the Government time to time. (Note:- Paid Holiday after six working days & gazetted holidays will be paid as per approved rate).	122.00 Days	715.00	Rupees Seven Hundred Fifteen Only	Per Day	87230.00
	TOTAL					**87230.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Scanned with OKEN Scanner

Job No - 09

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99571/-
Earnest Money: Rs.2000/-
Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-II. (SH: Maintenance of Earhen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earhen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	418.50 Square metre	80.00	Rupees Eighty Only	Per Square metre	33480.00
	Total Amount in Rs.					**99571.00**
	Quoted Rate in Figure		% above/below			
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk

Scanned with OKEN Scanner

Job No- 10

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 82575/-
Earnest Money: Rs. 1700/-
Time Limit : Three Month.

Name of Work :- Construction of College building (Ground Floor and First Floor) Two no,s Class rooms with verandah in Govt. Degree College Daulatpur Chowk, Distt. Una , (SH:- Soil investigation and Prepare of Topographical & Contour site plan)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Soil investigation for construction of Class room at Govt. Degree College Daulatpur Distt. Una (HP) (3 no. Bore hole upto 6.0m depth) complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00 Number	18000	Rupees Eighteen Thousand Only	Each	54000.00
2	Preparation of Topographical & Contour site plan of Govt. Degree College Daulatpur Distt. Una (HP) which include showing all features like road, buildings, sheds, Electrical/ Telephone poles, drain, Manholes, Major trees, water bodies, open land, park, play ground, boundary etc. (Builtup area) complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.35 Acres	4500	Rupees Four Thousand Five Hundred Only	Per acres	28,575.00
	Total Amount in Rs.					**82575.00**
	Quoted Rate in Figure		% above/below			
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Scanned with OKEN Scanner

Job No- 11

BILL OF QUANTITY

Estimate Cost :- Rs.83400/-
Earnest Money :-Rs.1700/-
Time Limit :- One Month.

Name of work:- Providing and Installation Computer System with UPS, Printer in HPPWD Division office Daulatpur Chowk (UnderTelecom Deposit)

Sr. No.	Description of Item	Quantity		Rate in		Unit	Amount
				Figures	Words		
1	Providing and installation of Computer system of DELL INSPIRON 3030 Intel Core i3-12100 (12th Generation)/ 8GB RAM/ 512 SSD/ 20" TFT/ WIN 11SL/OFFICE with MS Office (Monitor/USB Key board/USB optical mouse/ PL-antivirus 60 days updating (3 years comprehensive on site warranty) complete. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Number	54200.00	Rupees Fifty Four Thousand Two Hundred Only	Each	54200.00
2	Providing and installation of Elnova: 650 VA offline UPS system (12Vx7AHx2 No.) with 25-30 Min battary backup 3 years warranty on UPS & 18 month on batteries from date of delievery. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Number	3100.00	Rupees Three Thousand One Hundred Only	Each	3100.00
3	Providing and installation of HP Laserjet MFP M233sdw Printer Multi-function WiFi Monochrome Laser Printer with Print speed up to 29 ppm (black), Auto-duplex Printing, Multifunction (Print Scan Copy), 2 in 1 (ID) Copy Button, LCD Display, 32 MB Memory, 250 Sheet Paper Tray, USB, Wi-Fi with one year warranty. The rates are inclusive octroi, royality, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Number	26100.00	Rupees Twenty Six Thousand One Hundred Only	Each	26100.00
	TOTAL						**83400.00**
	Quoted Rate in Figure			% above/below			
	Quoted Rate in Words						

Executive Engineer,
HPPWD Division,
Daulatpur Chowk

Scanned with OKEN Scanner

Job-12

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 83340/-
Earnest Money: Rs. 1700/-
Time Limit : Three Month.

Name of Work :- Construction of Rajiv Ghandhi Govt. Model Day Boarding School at Sanghnai in Legislative Assembly Contituency Gagret Distt. Una (HP), (SH:- Soil investigation for Rajiv Ghandhi Govt. Model Day Boarding School and Prepare of Topographical & Contour site plan of Govt. Senior Secondary School Sanghai in Distt. Una)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Soil investigation for construction of Rajiv Ghandhi Govt. Model Day Boarding School at Sanghnai in Legislative Assembly Contituency Gagret Distt. Una (HP) (3 no. Bore hole upto 6.0m depth) complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00 Number	18000	Rupees Eighteen Thousand Only	Each	54000.00
2	Preparation of Topographical & Contour site plan of Govt. Senior Secondary School Sanghai in Distt. Una which include showing all features like road, buildings, sheds, Electrical/ Telephone poles, drain, Manholes, Major trees, water bodies, open land, park, play ground, boundary etc. (Open Area) complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.52 Acres	4500	Rupees Four Thousand Five Hundred Only	Per acres	29,340.00
	Total Amount in Rs.					**83340.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Scanned with OKEN Scanner