

OFFICE OF

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department Jaisinghpur
176095 Phone No. 01894-228030 Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **16.07.2025 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **15.07.2025 up to 4:00 PM** and the application for issue of tender form shall be received on **15.07.2025 up to 1:00 PM**. The applications for issue of tender forms should be accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	C/O road from main road to village Gharloon KM 0/00 to 0/500 (SH:- Cutting in earth work KM 0/065 to 0/125) Deposit SDP/ 2023/1244	98651.00	2000.00	Two month	350/-
2	Restoration of rain damages on various roads under Sari Section in HP.PWD Sub-Division Jaisinghpur (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various roads under Sari Section)	99000.00	2000.00	One Month	350/-
3	R/O Jangal to Oach Kallan road Km 0/00 to 11/00 (SH:-C/O RCC crash barrier of existing slab culvert at RD 1/960) Deposit SDF/2024/1264	99982.00	2000.00	Two month	350/-
4	Restoration of rain damages on link road from Jalari Curve to Village Jalari (SH:-C/O B/wall at RD 0/970 to 0/980)	99158.00	2000.00	One Month	350/-
5	Restoration of rain damages on various roads under Jaisinghpur Section in HP.PWD Sub-Division Jaisinghpur (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various roads under Jaisinghpur Section)	99000.00	2000.00	One Month	350/-
6	R/O Jeepable road alongwith Tile work from Main road to Bhuria Basti Parnoh (SH:- P/L 60 mm thick paver block Km 0/00 to 0/034) (Deposit SDP/2024/961)	96150.00	2000.00	Two month	350/-
7	Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various roads under Balakrupi Section)	99550.00	2000.00	One Month	350/-
8	C/O Link road to Gogga Mandir at Rakkad Mohall Bhallunder GP lahru Km 0/00 to 0/180 (SH:-C/O E/wall at RD 0/00 to 0/006 and P/L CC pavement at RD 0/00 to 0/017) (Deposit BSP/2024/47)	99854.00	2000.00	Two Month	350/-
9	Restoration of rain damages on various roads under Jaisinghpur Section in HP.PWD Sub-Division Jaisinghpur (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various roads under Jaisinghpur Section)	99000.00	2000.00	One Month	350/-
10	C/O link road from Kuffer play Ground to Shamshan ghat oach Kuhan Km 0/00 to 1/00 (SH:-P/L CC Pavement at RD 0/120 to 0/150) (Deposit BSP/2024/49)	99346.00	2000.00	Two Month	350/-
11	Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various roads under Gander Section)	99550.00	2000.00	One Month	350/-
12	C/O link road from main road Dolla to Village Bhallunder Lahru Km 0/00 to 1/00 (SH:- C/O Edge wall at RD 0/750 to 0/781.40) (Deposit BSP/2024/51)	99819.00	2000.00	Two Month	350/-
13	Resoration of rain damages on Balakrupi Duhak Dhainara road Km 0/00 to 1/400 (SH:- P/L CC pavement at RD 0/032 to 0/054.50)	99900.00	2000.00	Two Month	350/-

One

Contd.

14	Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various roads under Gander Section)	99550.00	2000.00	One Month	350/-
15	Completion of Govt. Primary School Kuhan Building Mohal Kuhan (SH:- Applying Plaster work and Providing and laying precast terrazo tiles work) (Deposit BSP/2024/53)	99987.00	2000.00	Two Month	350/-
16	Repair and Completion of link road from Paprola to Mohinder Singh W.No. 7 (SH:- P/L 60 mm thick interlocking paver block tiles at RD 0/00 to 0/024) (Deposit SDF/2024/1975)	99723.00	2000.00	Two Month	350/-
17	Restoration of rain damages on link road from Jalari Curve to Village Jalari (SH:-C/O B/wall at RD 0/980 to 0/990)	99283.00	2000.00	One Month	350/-
18	C/O R/wall to protect the ground GP Tikkar (SH:-C/O R/wall) Deposit SDF/2024/970	98998.00	2000.00	Two Month	350/-

Certified that above works are of urgent nature and tenders are being called in exigency of works and in public interest.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.
On behalf of Governor of Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26-2669-78

Dated: 09.07-25

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineer under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.



OFFICE OF


Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works
Department Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders for the works as called vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 2669-78 dated 09.07.2025 are of very urgent nature and being called in exigency of works in public interest.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-C/O road from main road to Village Gharloon Km 0/00 to 0/500 (SH:-Cutting in earth work Km 0/035 to 0/125)				Estimated cost Rs.	98651.00	
Deposit SDP/2023/1244				Earnest Money Rs.	2000.00	
				Time Limits	Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M O R D technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 19.41 (nineteen cubic decimal four one) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	388.25	201.30	Rupees Two Hundred One And Paise Thirty Only	Per cubic metre	78155.00
2	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	192.45	106.50	Rupees One Hundred Six And Paise Fifty Only	Per cubic Metre	20496.00
Total						98651.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur

SCHEDULE OF QUANTITY


Name of work :- Restoration of rain damages on various roads under Sari Section in HP.PWD Sub-Division Jaisinghpur (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Sari Section)

Estimated cost Rs.	99000.00
Earnest Money Rs.	2000.00
Time Limits	One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99000.00
Total						99000.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-R/O Jangal to Oach kallar road Km 0/00 to 11/00 (SH:-C/O RCC crash barrier of existing slab culvert at RD 1/960) Deposit SDF/2024/1264)				Estimated cost Rs.		99982.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	C/O Reinforced cement concrete crash barrier at the bridge decks and approaches to bridge structures, constructed with M-40 (M-forty) grade concrete with HYSD reinforcement conforming MoRT&H Specification and as per details given IRC-5 including dowel bars, expansion joints filled filled with pre-moulded asphalt filler board etcetra and approved drawing and at locations directed by the Engineer, all as specified as per drawings and MORTH technical specification section 800 and as directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16.00	5864.10	Rupees Five Thousand Eight Hundred Sixty Four And Paise Ten Only	Per running Metre	93826.00
2	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With Water thinnable cement primer on wall surface having VOC content less than 50 grams/litre The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.05	48.00	Rupees Forty Eight Only	Per Square Metre	2066.00
3	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete on concrete work. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.05	95.00	Rupees Ninety Five Only	Per Square Metre	4090.00
Total						99982.00
Quoted Rate (in Figures) Percentage		Excess (+)		%		
		Less (-)		%		
G.Total in Figures						
G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 H.P.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on link road from Jalari Curve to Village Jalari (SH:-C/O B/wall at RD 0/970 to 0/980)

S. N.	Description of Item	Quantity	Estimated cost Rs.		Time Limits	
			Earnest Money Rs.		Two Month	
			In Figures	In Word	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.70	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	4658.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.60	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	92250.00

(4)

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Jaisinghpur Section in HP.PWD Sub-Division Jaisinghpur (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Jaisinghpur Section)


Estimated cost Rs.	99000.00
Earnest Money Rs.	2000.00
Time Limits	One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99000.00
	Total					99000.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

6

SCHEDULE OF QUANTITY						
Name of work :-R/O Jeepable road alongwith Tile work from Main road to Bhuria basti parnoh (SH:-P/L. 60 mm thick paver block Km 0/068 to 0/102) (Deposit SDP/2024/961)				Estimated cost Rs.	96150.00	
				Earnest Money Rs.	2000.00	
				Time Limits	Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2	4200.00	Rupees Four Thousand Two Hundred Only	Per Cubic Metre	8400.00
2	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	81.60	1000.00	Rupees One Thousand Only	Per square metre	81600.00
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:2:4 (One cement : Two coarse sand : four graded stone aggregate 20mm (Twenty milimetre) nominal size) in foundation and footing including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	1	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per Cubic Metre	6150.00
Total						96150.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


Executive Engineer,
Jaisinghpur Division,
H.P.WD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Balakrupi Section)

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	90.50	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99550.00
	Total					99550.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O Link road to Gogga Mandir at Rakkad Mohall Bhalunder GP lahru Km 0/00 to 0/180
(SH:-C/O E/wall at RD 0/00 to 0/006 and P/L CC pavement at RD 0/00 to 0/017) (Deposit BSP/2024/47)

Estimated cost Rs.	99854.00
Earnest Money Rs.	2000.00

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.86	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	1094.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	10.44	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	39150.00
3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.86	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	1767.00

4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	1500.00
5	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken/ crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.89	2100.00	Rupees Two Thousand One Hundred Only	Per Cubic Metre	8169.00
6	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	7.77	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic Metre	48174.00
Total						
Quoted Rate (in Figures) Percentage		Excess (+)			%	99854.00
		Less (-)			%	
G.Total in Figures						
G.Total in Words						

Executive Engineer,
Jaisinghpur Division,
HP/PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Jaisinghpur Section in HP.PWD Sub-Division Jaisinghpur (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Jaisinghpur Section)

Estimated cost Rs.	99000.00
Earnest Money Rs.	2000.00
Time Limits	One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99000.00
	Total					99000.00
	Quoted Rate (in Figures) Percentage				%	
					%	
					%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

⑪

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Gander Section)

SCHEDULE OF QUANTITY							
Name of work :-Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Gander Section)					Estimated cost Rs.		99550.00
					Earnest Money Rs.		2000.00
					Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	90.50	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99550.00	
	Total					99550.00	
	Quoted Rate (in Figures) Percentage	Excess (+)			%		
		Less (-)			%		
	G.Total in Figures						
	G.Total in Words						

Executive Engineer,
Jaisinghpur Division,
H.P.W.D Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O link road from main road Dolla to Village Bhallunder Lahru Km 0/00 to 1/00 (SH:- C/O Edge wall at RD 0/750 to 0/781.40) (Deposit BSP/2024/51)

Estimated cost Rs. 99819.00
Earnest Money Rs. 2000.00
Time Limits Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.73	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	2189.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	22.92	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	85950.00
3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200.1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.40	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	4180.00

4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	30.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	7500.00
	Total					99819.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Resoration of rain damages on Balakrupi Duhak Dhainara road Km 0/00 to 1/400 (SH:- P/L
CC pavement at RD 0/032 to 0/054.50)

		Estimated cost Rs.		Earnest Money Rs.		Time Limits	
		99900.00		2000.00		Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. for grading-I material and as per direction by the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	14.40	1500.00	Rupees One Thousand Five Hundred Only	Per cubic metre	21600.00	
2	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	5.40	2100.00	Rupees Two Thousand One Hundred Only	Per Cubic Metre	11340.00	

3	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	10.80	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic Metre	66960.00
		Total				99900.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

L

Estimated cost Rs.	99550.00
Earnest Money Rs.	2000.00

Executive Engineer,
Jaisinghpur Division,
HP/PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Completion of Govt. Primary School Kuan Building Mohal Kuan (SH:- Applying Plaster work and Providing and laying precast terrazo tiles work) (Deposit BSP/2024/53)

S. N.	Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
			Earnest Money Rs.	Time Limits		
			In Word	In Figures		
1	15 mm (fifteen millimetre) cement plaster in single coat on rough side of brick/stone masonry for interior plastering upto floor two level with CM 1:4 (One cement : four sand) carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	154.21	Rupees Two Hundred Forty One And Paise Twenty Only	241.20	Per Square Metre	37195.00
2	6 mm (Six millimetre) cement plaster to ceiling with CM 1:3 (One cement : Three Sand) including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	78.67	Rupees One Hundred Forty Two And Paise Thirty Five Only	142.35	Per Square Metre	11199.00
3	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetre) thick cement mortar 1:4 (one cement : four coarse sand), jointing with grey cement slurry @ 3.3 (three point three) Per Kilogram/Per Square Metre including grouting the joints with white cement and matching pigments etc., complete 600x600 mm (six hundred into six hundred millimetre) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	47.96	Rupees Nine Hundred Seventy Five And Paise Thirty Five Only	975.35	Per Square Metre	46778.00

4	Providing and laying Virrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm (twelve millimetre) thick bed of cement mortar 1:3 (one cement: three coarse sand), jointing with grey cement slurry @ 3.3 (three point three) Per Kilogram/ Per Square Metre including grouting the joint with white cement & matching pigments etc. complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	3.94	1222.10	Rupees One Thousand Two Hundred Twenty Two And Paise Ten Only	Per Square Metre	4815.00
	Total					99987.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Repair and Completion of link road from Paprola to Mohinder Singh W.No. 7 (SH:- P/L 60 mm thick interlocking paver block tiles at RD 0/00 to 0/024) (Deposit SDF/2024/1975)

S. N.	Description of Item	Quantity	Time Limits		Amount
			Rate	Unit	
1	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	5.52	In Figures 4250.00 Rate In Word Rupess Four Thousand Two Hundred Fifty Only	Per Cubic Metre	23460.00
2	Providing and laying 60 mm thick interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	55.20	1210.00 Rupess One Thousand Two Hundred Ten Only	Per square metre	66792.00
3	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.54	6150.00 Rupess Six Thousand One Hundred Fifty Only	Per Cubic Metre	9471.00
Total					
Quoted Rate (in Figures) Percentage			Excess (+)	%	99723.00
			Less (-)	%	
G.Total in Figures					
G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP/PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on link road from Jalari Curve to Village Jalari (SH:-C/O B/wall at RD 0/980 to 0/990)

S. N.	Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
			Earnest Money Rs.	Time Limits		
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.70	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	4658.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.60	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	92250.00

SCHEDULE OF QUANTITY

Name of work :- C/O R/wall to protect the ground GP Tikkar (SH:-C/O R/wall) Deposit SDF/2024/970

SCHEDULE OF QUANTITY						
Name of work :-C/O R/wall to protect the ground GP Tikkar (SH:-C/O R/wall) Deposit SDF/2024/970				Estimated cost Rs.		98998.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The	11.90	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	2678.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.27	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	93440.00
3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/cement masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST and all other taxes imposed by the Government.	8.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	2000.00

4	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.20	275.00	Rupees Two Hundred Seventy Five Only	Per cubic Metre	880.00
	Total				%	98998.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

4

Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.

3.20

275.00

Rupees Two Hundred Seventy Five Only	Per cubic Metre
--	--------------------

Per cubic
Metre

880.00

Total

98998.00

Quoted Rate (in Figures) Percentage

G.Total in Figures

G.Total in Words

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur