

Himachal Pradesh
Public Works Department

No.PWJ/CB/TA/Tender/2025:- 2842

Dated:- 22-07-2025

To

The Executive Engineer (IT Cell),
Nigam Vihar Shimla.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Notice Inviting Tender to be published on department website vide this office letter No. 2810-11 dated 22.07.2025, in compliance to the Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBD-B-AO (3)/1/2024-241828 dated Shimla-2 the 17th July 2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA/Tender Notice
a/w Schedule of quantity.

Executive Engineer,
Jawali Division HP PWD,
Jawali.

Himachal Pradesh
Public Works Department

CERTIFICATE

Certified that the works are of urgent in nature and for larger public interest, so there is exigencies/emergency in calling these tender without press vide this office letter No. PWJ/CB/TA/Tender/2025-2810-11 dated-22.07.2025

Executive Engineer,
Jawali Division HP PWD,
Jawali.

HP.P.W.D.TENDER
Notice Inviting Tender

Sealed percentage rate offline tender on PWD form Number 6 are hereby invited by the Executive Engineer, Jawali Division H.P.P.W.D. Jawali on behalf of the Governor of H.P. for the following work from the approved and eligible contractors C&D enlisted in H.P.P.W.D, so as to reach in this office in the waxed sealed cover on or before. 30.07.2025 (AM) and will be opened on the same day at 11:30 (A.M.) in the presence of the intending contractors or their authorized representative who may like to be present. The application for purchase of tender will be received on 28.07.2025 up to 4.00 P.M. The tender form can be obtained from this office on dated 29.07.2025 at 11.00 A.M to 4.30 P.M.

The amount of earnest money in shape of FDR of any nationalized Bank in HP duly pledged in the name of the Executive Engineer, Jawali Division H.P.P.W.D. Jawali should be deposited first with the application then the tender documents will be issued. Conditional tender and tender application without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tender without assigning any reason.

Sr. No.	Name of Work	Estimated Cost Rs.	Earnest Money Rs.	Time Limit	Cost of Form Rs.
1	Restoration of Rain Damages on various roads under HP:PWD. Sub Division Nagrota Surian (Section Nagrota Surian-I). (SH: - Construction of unlined surface drain and Maintenance of Earthen Shoulders)	98976/-	2000/-	Two Months	350/-
2	Restoration of Rain Damages on various roads under HP:PWD. Sub Division Jawali (Section Bharmar) . (SH: - Removal of land slide in Hilly area, construction of Unlined surface drains, Maintenance of Earthen Shoulders)	98,742/-	2000/-	Two Months	350/-
3	Restoration of Rain Damages on various roads under HP:PWD. Sub Division Jawali (Section Sidhatha and Jawali-II) . (SH: - Removal of land slide in Hilly area, construction of Unlined surface drains and Maintenance of Earthen Shoulders)	97555/-	2000/-	Two Months	350/-
4	Restoration of Rain Damages on various roads under HP:PWD. Sub Division Kotla (Section Trilokpur) . (SH: - Construction of Unlined surface drains, Maintenance of Earthen Shoulder and removal of land slide slips)	99807/-	2000/-	Two Months	350/-
5	Restoration of Rain Damages on various roads under HP:PWD. Sub Division Kotla (Section Jounta) . (SH: - Construction of Unlined surface drains, Maintenance of Earthen Shoulder and removal of land slide slips)	99406/-	2000/-	Two Months	350/-
6	Restoration of Rain Damages on various roads under HP:PWD. Sub Division Kotla (Section Bhalli) . (SH: - Construction of Unlined surface drains, Maintenance of Earthen Shoulder and removal of land slide slips)	99573/-	2000/-	Two Months	350/-
7	Restoration of Rain Damages on Jawalamukhi Dehra Jawali Raja Ka Talab Road (MDR-80) km. 39/180 to 79/600. . (SH: - Construction of Unlined surface drain, Maintenance of Earthen Shoulder at RD. 72/500 to 75/0)	99300/-	2000/-	Two Months	350/-
8	Restoration of Rain Damages on Bhatoli Dhar Bara Chicher Bhalli road km. 0/0 to 4/345. (SH: - Removal of slips, Unlined Surface Drain and Maintenance of Earthen Shoulder at RD. 0/0 to 1/200)	98464/-	2000/-	Two Months	350/-
9	Restoration of Rain Damages on various roads under HP:PWD. Sub Division Jawali (Section Bharmar) . (SH: - Removal of land slide in Hilly area, construction of Unlined surface drains, Maintenance of Earthen Shoulders)	99826/-	2000/-	Two Months	350/-
10	Construction of culvert to connect Community Building and link road Neel Nallah to Railway Station Harsar Gram Panchayat Harsar Development Block Nagrota Surian (Under Deposit) VKV/2024/395. (SH: - Construction of super structure of 6.00 Metre span RCC slab culvert alongwith Railing etc.)	76628/-	1600/-	Two Months	350/-
11	Construction of Pucca Path from road to the House of Sh. Ajay Kumar, Mala Devi etc. Bakan Mohal in G.P. Dol (Under Deposit) VKV/2021/2910. (SH: - Providing and laying WBM G-II and Cement Concrete Pavement at RD. 0/0 to 0/012.50 and Edge wall at RD. 0/008 to 0/012)	47969/-	1000/-	Two Months	350/-
12	Construction of Pucca Path from main road to the House of Sh. Pritam Singh etc. Ward No.8 Mohal G.P. Ghar-II (Under Deposit) SDP/2024/1452. (SH: - Providing and laying Cement Concrete Pavement at RD. 0/0 to 0/028)	94815/-	1900/-	Two Months	350/-
13	Construction of Pucca Path from the House of Milkhi Ram to the House of Manohar Lal Harizan Basti Ward No.4 Mohal (G.P. Kuthar) (Under Deposit) VKV/2017/1670. (SH: - Providing and laying Cement Concrete Pavement at RD. 0/545 to 0/575).	97124/-	2000/-	Two Months	350/-

14	A/R & M/O Type-III Residential Quarter for PWD Colony at Jawali. (SH: - Distempering and Painting work)	47206/-	1000/-	Two Months	350/-
15	A/R & M/O Sub Judge Residence at Jawali. (SH: - Repair of Boundary wall, Parking Shed, Water Supply and Sanitary Installation item etc.)	98685/-	2000/-	Two Months	350/-
16	Repair and Maintenance of Veterinary Hospital Jawali (Under Deposit). (SH: - Providing and fixing shutter for Door, Window and Tile work etc.)	93716/-	1900/-	Two Months	350/-

1. The contractor should be registered as a dealer under HPST Act 1968 (GST number) from the Excise and Taxation Department.
2. The Cess charges@ 1% (One percent) will be deducted from gross amount of work done by the contractor.
3. The contractors are required to be produce copy of their PAN No. at time of application.
4. The contractor should produce a copy of enlistment/ renewal letter at time of application.
5. The Executive Engineer reserves the right to accept/cancel any tender without assigning any reason at any stage.
6. Telegraphically/ Fax tenders are not acceptable.
7. Special care should be taken to write the rates both in figures and in words, failing which tender likely to be rejected to be circumstances.
8. If the office happens to be closed on the date of opening of the tenders as specified, the tenders will be opened on the next working day at the same time and venue.
9. It is certified that all the works being processed for Notice Inviting Tender due to emergency/urgency of works.

HIM SUCHANA AVAM JAN SAMPARK

No PWJ/CB/TA/E-26/2025:- **2810-11**
COPY FORWARDED TO THE FOLLOWING:-

1. The Drawing Branch of this office.
2. The Notice Board.

Executive Engineer
Jawali Divn. HP PWD,
Jawali
For on behalf of Governor of H.P.

[Dated:-

22-07-2025

Executive Engineer,
Jawali Divn. HPPWD,
Jawali

SCHEDULE OF QUANTITY						
Name of work:-Restoration of Rain Damages on various roads under HP:PWD. Sub Division Nagrota Surian (Section Nagrota Surian-I). (SH:- Construction of unlined surface drain and Maintenance of Earthen Shoulders)				Estimated Cost : Rs. 98,976/- Earnest Money : Rs. 2,000/- Time Limit : Two Months		
S.No	Description of items	Quantity	Rates (In Rupees)		Unit	Amount
			In Figures 4	In words 5		
1	2	3	4	5	6	7
1	Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment within all lift as per MORD technical specification clause 307, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1000.00	18.00	Rupees eighteen only	Per Running Metre	18000
2	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per MORD technical specification Clause1903, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2530.50	32.00	Rupees thirty two only	Per Square Metre	80976
					Total:	98976
	Quoted rate in figure (%)		(Amount to be quoted by the contractor in figure)			
	Quoted rate in words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Jawali Division, H.P. P.W.D.,
Jawali-176023

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY	
Name of work:-	Restoration of Rain Damages on various roads under HP:PWD, Sub Division Jawali (Section Bharmar) . (SH: - Removal of land slide in Hilly area, construction of Unlined surface drains, Maintenance of Earthen Shoulders)
1.	Removal of land slide in Hilly area
2.	Construction of Unlined surface drains
3.	Maintenance of Earthen Shoulders

Estimated Cost : Rs. 98,742/-

Earnest Money : Rs2000/-

Time Limit : Two Months

Sl. No.	Description of items	Quantity	Rates (In Rupees)		Unit	Amount
			In Figures	In words		
			4	5		
1	2	3				
1	Removal of land slide on hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within all lead as per technical specification 302.3.5 and 1611, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	521 ⁵⁹	Cubic Metre	Rupees one hundred fifty seven and paisa ten only	Per Cubic Metre	81942
2	Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment within all lift as per MORD technical specification clause 307, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	400.00	Running Metres	Rupees eighteen only	Per Running Metre	7200
3	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per MORD technical specification Clause 1903, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	300.00	Square Metre	Rupees thirty two only	Per Square Metre	9600
	Quoted rate in figure (%)				Total:	98742
	Quoted rate in words (%)					

Executive Engineer;
Jawali Division, H.P. P.W.D.
Jawali-176023

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various roads under HP:PWD. Sub Division Jawali (Section Sidhatha and Jawali-II) . (SH: - Removal of land slide in Hilly area, construction of Unlined surface drains and Maintenance of Earthen Shoulders)

Estimated Cost : Rs. 97,555/-

Earnest Money : Rs2000/-

Time Limit : Two Months

S.No.	Description of items	Quantity	Rates (In Rupees)		Unit	Amount
			In Figures	In words		
1	2	3	4	5	6	7
1	Removal of land slide on hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within all lead as per technical specification 302.3.5 and 1611, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	281.70	157.10	Rupees one hundred fifty seven and paisa ten only	Per Cubic Metre	44255
2	Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment within all lift as per MORD technical specification clause 307, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	650.00	18.00	Rupees eighteen only	Per Running Metre	11700
3	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per MORD technical specification Clause 1903, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1300.00	32.00	Rupees thirty two only	Per Square Metre	41600
					Total:	97555
	Quoted rate in figure (%)	(Amount to be quoted by the contractor in figure)				
	Quoted rate in words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Jawali Division, H.P. P.W.D.
Jawali-176023

SCHEDULE OF QUANTITY

Name of work:-Restoration of Rain Damages on various roads under HP:PWD, Sub Division Kotla (Section Trilokpur) . (SH: - Construction of Unlined surface drains, Maintenance of Earthen Shoulder and removal of land slide slips)										Estimated Cost : Rs. 99,807/-	
										Earnest Money : Rs.2000/-	
										Time Limit : Two Months	
S.No	Description of items	Quantity		Rates (In Rupees)		Unit	Amount				
				In Figures	In words						
1	2	3	4	5	6	7					
1	Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment within all lift as per MORD technical specification clause 307, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	690.00	Running Metres	18.00	Rupees eighteen only	Per Running Metre	12420				
2	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per MORD technical specification Clause 1903, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	697.50	Square Metre	32.00	Rupees thirty two only	Per Square Metre	22320				
3	Removal of land slide on hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within all lead as per technical specification 302.3.5 and 1611, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	413.65	Cubic Metre	157.30	Rupees one hundred fifty seven and paisa thirty only	Per Cubic Metre	65067				
								Total:	99807		
	Quoted rate in figure (%)	(Amount to be quoted by the contractor in figure)									
	Quoted rate in words (%)	(Amount to be quoted by the contractor in words)									

Executive Engineer,
Jawali Division, H.P. P.W.D.
Jawali-176023

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various roads under HP:PWD. Sub Division Kotla (Section Jounta) .
 (SH: - Construction of Unlined surface drains, Maintenance of Earthen Shoulder and removal of land slide slips)

Estimated Cost : Rs. 99,406/-

Earnest Money : Rs.2000/-

Time Limit : Two Months

S.No.	Description of items	Quantity		Rates (In Rupees)		Unit	Amount
		In Figures	In words	In Figures	In words		
1	2	3	4	5	6	7	
1	Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment within all lift as per MORD technical specification clause 307, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	480.00	Running Metres	18.00	Rupees eighteen only	Per Running Metre	8640
2	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per MORD technical specification Clause 1903, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2176.50	Square Metre	32.00	Rupees thirty two only	Per Square Metre	69648
3	Removal of land slide on hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within all lead as per technical specification 302.3.5 and 1611, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	134.25	Cubic Metre	157.30	Rupees one hundred fifty seven and paisa thirty only	Per Cubic Metre	21118
						Total:	99406
	Quoted rate in figure (%)	(Amount to be quoted by the contractor in figure)					
	Quoted rate in words (%)	(Amount to be quoted by the contractor in words)					

Executive Engineer,
Jawahar Division, H.P. P.W.D.
Jawahar-176023

SCHEDULE OF QUANTITY

Name of work:-Restoration of Rain Damages on various roads under HP:PWD. Sub Division Kotla (Section Bhalli) , (SH: - Construction of Unlined surface drains, Maintenance of Earthen Shoulder and removal of land slide slips)							Estimated Cost : Rs. 99,573/-	
							Earnest Money : Rs.2000/-	
							Time Limit : Two Months	
S.No.	Description of items	Quantity		Rates (In Rupees)		Unit	Amount	
		In Figures	In words					
	2	3	4	5	6	7		
1	Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment within all lift as per MORD technical specification clause 307, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	525.00	Running Metres	18.00	Rupees eighteen only	Per Running Metre	9450	
2	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per MORD technical specification Clause1903, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	768.00	Square Metre	32.00	Rupees thirty two only	Per Square Metre	24576	
3	Removal of land slide on hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within all lead as per technical specification 302.3.5 and 1611, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	416.70	Cubic Metre	157.30	Rupees one hundred fifty seven and paisa thirty only	Per Cubic Metre	65547	
						Total:	99573	
	Quoted rate in figure (%)	(Amount to be quoted by the contractor in figure)						
	Quoted rate in words (%)	(Amount to be quoted by the contractor in words)						

Executive Engineer,
Jawali Division, H.P. P.W.D.
Jawali-176023

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY															
Name of work:-Restoration of Rain Damages on Jawalamukhi Dehra Jawali Raja Ka Talab Road (MDR-80) km.			Estimated Cost : Rs. 99,300/-												
39/180 to 79/600. . (SH: - Construction of Unlined surface drain, Maintenance of Earthen Shoulder at RD. 72/500 to 75/0)			Earnest Money : Rs. 2000/-												
S.No			Description of items		Quantity		Rates (In Rupees)		Unit	Amount					
			2		3		In Figures 4		In words 5						
1	1		Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment within all lift as per MORD technical specification clause 307, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.		1250.00		Running Metres		18.00	Rupees eighteen only	Per Running Metre	6	7	22500	
2	2		Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per MORD technical specification Clause1903, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.		2400.00		Square Metre		32.00	Rupees thirty two only	Per Square Metre			76800	
			Quoted rate in figure (%)									Total:			99300
			Quoted rate in words (%)												

Executive Engineer,
Jawahar Division, H.P. P.W.D.
Jawahar-176023

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Bhatoli Dhar Bara Chicher Bhalli road km. 0/0 to 4/345. (SH: - Removal of slips, Unlined Surface Drain and Maintenance of Earthen Shoulder at RD. 0/0 to 1/200)

Estimated Cost : Rs. 98,464/-
Earnest Money : Rs.2000/-

S.No.		Description of items	Time Limit : Two Months				
			Quantity	Rates (In Rupees)		Unit	Amount
				In Figures	In words		
1		2	3	4	5	6	7
1		Removal of land slide on hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within all lead as per technical specification 302.3.5 and 1611, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	452.14	Cubic Metre	Rupees one hundred fifty seven and paisa thirty only	Per Cubic Metre	71122
2		Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment within all lift as per MORD technical specification clause 307, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	355.00	Running Metres	Rupees eighteen only	Per Running Metre	6390
3		Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per MORD technical specification Clause1903, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	654.75	Square Metre	Rupees thirty two only	Per Square Metre	20952
						Total:	98464
		Quoted rate in figure (%)	(Amount to be quoted by the contractor in figure)				
		Quoted rate in words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Jawali Division, H.P. P.W.D.
Jawali-176023

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various roads under HP:PWD. Sub Division Jawali (Section Bharmar) . (SH:- Removal of land slide in Hilly area, construction of Unlined surface drains, Maintenance of Earthen Shoulders)

Estimated Cost : Rs. 99,826/-
Earnest Money : Rs. 2000/-
Time Limit : Two Months

S.No	Description of items	Quantity	Rates (In Rupees)		Unit	Amount
			In Figures	In words		
1	2	3	4	5	6	7
1	Removal of land slide on hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within all lead as per technical specification 302.3.5 and 1611, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	392.27	157.10	Rupees one hundred fifty seven and paisa ten only	Per Cubic Metre	61626
2	Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment within all lift as per MORD technical specification clause 307, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	700.00	18.00	Rupees eighteen only	Per Running Metre	12600
3	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per MORD technical specification Clause 1903, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	800.00	32.00	Rupees thirty two only	Per Square Metre	25600
					Total:	99826
	Quoted rate in figure (%)	(Amount to be quoted by the contractor in figure)				
	Quoted rate in words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Jawali Division, H.P. P.W.D.
Jawali-176023

SCHEDULE OF QUANTITY

Name of work:-Construction of culvert to connect Community Building and link road Neel Nallah to Railway Station Harsar Gram Panchayat Harsar Development Block Nagrota Surian (Under Deposit) VKV/2024/395. (SH: - Construction of super structure of 6.00 Metre span RCC slab culvert alongwith Railing etc.)							Estimated Cost : Rs.76,628/-	
							Earnest Money : Rs. 1600/-	
							Time Limit : Two Months	
S.No	Description of items	Quantity		Rates (In Rupees)		Unit	Amount	
				In Figures	In words			
1	2	3	4	5	6	7		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera and other similar structure in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) complete in accordance with the line and dimensions shown in the drawings as per M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer-in - Charge including setting out shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not exceeding 150mm (One hundred fifty millimeter) compacted thickness including shoring, strutting and pumping and bailing out water (surface and sub soil water) upto any depth and quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and direction of Engineer-in-Charge. including carriage of materials within all leads, lifts, other incidental . The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	5.63	Cubic Metres	270.00	Rupees two hundred seventy only	Per Cubic Metre	1520	
2	Providing and laying mechanically mixed and vibrated concrete for reinforced cement concrete in super structure design mix R.C.C. grade M-20 (M-twenty) with graded crushed stone aggregate 20mm (Twenty millimetres) nominal size having cement contents not less than 350kg (Three hundred fifty kilogram) per cubic metre and curing complete for all heights/ depths including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block, dirt wall etcetera as per drawings and M.O.R.D. technical specifications section 800, 900 and 1200 complete including carriage of materials within all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge . The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1.93	Cubic Metre	6890.80	Rupees six thousand eight hundred ninety and paisa eighty only	Per Cubic Metre	13299	

3	Supplying fitting and placing HYSD bars reinforcement in super structure complete as per drawing and MORD technical specification section 1000 and 1400 including cutting, bending binding and placing in position complete in all respect including cost of binding wire as per directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	232.00	Kilogram	85.00	Rupees eighty five only	Per kilogram	19720
4	Steel work welded in built up sections, trusses and framed work, in beams joists channels angles, tee, flats with connected plates or angles cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like, including cutting, fixing, lifting, hoisting and placing in position complete and applying a priming coat of red lead paint complete as per HP:PWD. Specifications or as directed by the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	140.16	Kilogram	98.10	Rupees ninety eight and paisa ten only	Per Kilogram	13750
5	Providing and laying of boulder apron laid in Wire Crates with 4mm (four millimetres) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (One hundred millimetres into one hundred millimetres) mesh (woven diagonally) including 10 percent (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specifications clause 1301, and as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including of octroi, Malkana, royalty, toll tax, GST or other taxes imposed by the Government.	11.71	Cubic Metre	2420.10	Rupees two thousand four hundred twenty and paisa ten only	Per Cubic Metre	28339
	Quoted rate in figure (%)					Total:	76628
	Quoted rate in words (%)					(Amount to be quoted by the contractor in figure)	
						(Amount to be quoted by the contractor in words)	

Executive Engineer,
Jawali Division, H.P. P.W.D.,
Jawali-176023

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca Path from road to the House of Sh. Ajay Kumar, Mala Devi etc. Bakan Mohal in G.P. Dol (Under Deposit) VKV/2021/2910. (SH:- Providing and laying WBM G-II and Cement Concrete Pavement at RD. 0/0 to 0/012.50 and Edge wall at RD. 0/008 to 0/012)							Estimated Cost : Rs. 47,969/-	
							Earnest Money : Rs.1000/-	
							Time Limit : Two Months	
S.No	Description of items	Quantity		Rates (In Rupees)		Unit	Amount	
				In Figures	In words			
1	2	3	4	5	6	7		
1	Providing, laying spreading and compacting by mechanical means stone aggregate of specified size to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 (Eighty/Hundred) K.N. static Road roller in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.20 (zero point two zero) cubic metre per 10 sqmt (Ten square metre) of road surface and binding material of approved quality at the rate of 0.06 (zero point zero six) cubic metre per 10sqmt (ten square metre) of road surface to fill up the interstices of course aggregate, watering and compacting to the required density grading –II 63mm to 45mm (Sixty three millimetres to forty five millimetres) size 75mm (Seventy Five millimetres) compacted thickness as per M.O.R.D. technical specifications section 400 including hauling of material within all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	3.20	Cubic Metres	1850.00	Rupees one thousand eight hundred fifty only	Per Cubic Metre	5920	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structures Grade M-20 (M-twenty) nominal mix 1:2:4 (One cement : two sand : four graded crushed/ broken stone aggregate 20mm (Twenty millimetres) nominal size in flooring on ground or under water and curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all heights/ depths including cost of form work as per Drawing and M.O.R.D. technical specification section 800, 900 and 1200 as per entire satisfaction and directions of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidental . The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.39	Cubic Metre	5954.35	Rupees five thousand nine hundred fifty four and paisa thirty five only	Per Cubic Metre	38048	

3	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera and other similar structure in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) complete in accordance with the line and dimensions shown in the drawings as per M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer-in - Charge including setting out shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not exceeding 150mm (One hundred fifty millimeter) compacted thickness including shoring, strutting and pumping and bailing out water (surface and sub soil water) upto any depth and quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and direction of Engineer-in-Charge, including carriage of materials within all leads, lifts, other incidental . The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	0.54	Cubic Metres	260.00	Rupees two hundred sixty only	Per Cubic Metre	140
4	Providing and laying mechanically mixed and vibrated plain cement concrete for all type of structure nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering (surface and sub soil water) and removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in retaining wall, breast wall etcetera as per drawings and M.O.R.D. technical specification section 800,900, 1200 and 1600 as per the direction and entire satisfaction of Engineer-in-Charge Including carriage of material within all leads, lifts and other incidental . The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.90	Cubic Metre	4290.00	Rupees four thousand two hundred ninety only	Per Cubic Metre	3861
						Total:	47969
	Quoted rate in figure (%)	(Amount to be quoted by the contractor in figure)					
	Quoted rate in words (%)	(Amount to be quoted by the contractor in words)					

Executive Engineer,
Jawali Division H.P, P.W.D.
Jawali-176023

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca Path from main road to the House of Sh. Pritam Singh etc. Ward No.8 Mohal G.P. Ghar-II (Under Deposit) SDP/2024/1452. (SH:- Providing and laying Cement Concrete Pavement at RD. 0/0 to 0/028)			Estimated Cost : Rs. 94,815/- Earnest Money : Rs.1900/- Time Limit : Two Months		
S.No.	Description of items	Quantity	Rates (In Rupees)		Amount
			In Figures	In words	
1	2 Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structures Grade M-20 (M-twenty) nominal mix 1:2:4 (One cement: two sand : four graded crushed/ broken stone aggregate 20mm (Twenty millimetres) nominal size in flooring on ground or under water and curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all heights/ depths including cost of form work as per Drawing and M.O.R.D. technical specification section 800, 900 and 1200 as per entire satisfaction and directions of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidental . The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	3 14.70 Cubic Metre	4 6450.00	5 Rupees six thousand four hundred fifty only	7 94815 Per Cubic Metre
	Quoted rate in figure (%)	(Amount to be quoted by the contractor in figure)	Total:		94815
	Quoted rate in words (%)	(Amount to be quoted by the contractor in words)			

Executive Engineer,
Jawali Division, H.P., P.W.D.
Jawali-176023

SCHEDULE OF QUANTITY

Name of work:- Construction of Pucca Path from the House of Milkhi Ram to the House of Manohar Lal Harizan Basti Ward No.4 Mohal (G.P. Kuther) (Under Deposit) VKV/2017/1670. (SH: - Providing and laying Cement Concrete Pavement at RD. 0/545 to 0/575).									
Estimated Cost : Rs. 97,124/-				Earnest Money : Rs.2000/-					
Time Limit : Two Months									
S.No.	Description of items	Quantity		Rates (In Rupees)		Unit	Amount		
				In Figures	In words				
1	2	3	4	5	6	7	8		
1	Providing, laying spreading and compacting by mechanical means stone aggregate of specified size to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 (Eighty/Hundred) K.N. static Road roller in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.20 (zero point two zero) cubic metre per 10 sqmt (Ten square metre) of road surface and binding material of approved quality at the rate of 0.06 (zero point zero six) cubic metre per 10sqmt (ten square metre) of road surface to fill up the interstices of course aggregate, watering and compacting to the required density grading -II 63mm to 45mm (Sixty three millimetres to forty five millimetres) size 75mm (Seventy Five millimetres) compacted thickness as per M.O.R.D. technical specifications section 400 including hauling of material within all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	7.09	Cubic Metres	1790.00	Rupees one thousand seven hundred ninety only	Per Cubic Metre	12691		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structures Grade M-20 (M-twenty) nominal mix 1:2:4 (One cement : two sand : four graded crushed/ broken stone aggregate 40mm (Forty millimetres) nominal size in flooring on ground or under water and curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all heights/ depths including cost of form work as per Drawing and M.O.R.D. technical specification section 800, 900 and 1200 as per entire satisfaction and directions of the Engineer-in-Charge including haulage of material within all leads, lifts and other incidental . The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	14.18	Cubic Metre	5954.35	Rupees five thousand nine hundred fifty four and paisa thirty five only	Per Cubic Metre	84433		
							Total:	97124	
							(Amount to be quoted by the contractor in figure)		
							(Amount to be quoted by the contractor in words)		
							Quoted rate in figure (%)		
							Quoted rate in words (%)		

Executive Engineer,
 Jawali Division, H.P. P.W.D.
 Jawali-176022

SCHEDULE OF QUANTITY

Name of work:-A/R & M/O Type-III Residential Quarter for PWD Colony at Jawali. (SH: - Distempering and Painting work)									
				Estimated Cost : Rs. 47,206/-					
				Earnest Money : Rs. 1000/-					
				Time Limit : Two Months					
S.No	Description of items	Quantity		Rates (In Rupees)			Unit	Amount	
				In Figures	In words				
		3	4	5	6	7			
1	Removing dry or oil bound distemper water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etcetera complete, as per direction of the Engineer - in- Charge, including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	512.63	Square Metre	11.15	Rupees eleven and paisa fifteen only	Per Square Metre	5716		
2	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50grams/ litre fifty gram per litre of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour, as per direction of the Engineer - in- Charge, including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	512.63	Square Metre	51.00	Rupees fifty one only	Per Square Metre	26144		
3	Painting two or more coats (excluding priming coat) on new wood and wood based surfaces with enamel paint to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete with enamel paint other than white, as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental . The rate is including royalty , octroi, GST, Toll tax, malkana and all other taxes as imposed by the Government.	45.32	Square Metres	94.30	Rupees ninety four and paisa thirty only	Per Square Metre	4274		
4	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied at the rate of 3.84 kg/10 sqm) (three point eight four kilogram oblique ten square metre), as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	114.34	Square metre	61.20	Rupees sixty one and paisa twenty only	Per Square Metre	6998		

Painting two or more coats (excluding priming coat) on new steel and other metal surface under coat with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter, enamel mixed paint other than white, as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including royalty, octroi, GST, Toll tax, malkana and all other taxes as imposed by the Government.	45.32	Square Metres	89.90	Rupees eighty nine and paise ninety only	Per Square Metre	4074
					Total Amount	47206
Quoted rate in figure (%)	(Amount to be quoted by the contractor in figure)					
Quoted rate in words (%)	(Amount to be quoted by the contractor in words)					


 Jawahar Division, H.P. P.W.D.
 Jawahar-176023

SCHEDULE OF QUANTITY

Name of work:-A/R & M/O Sub Judge Residence at Jawali. (SH: - Repair of Boundary wall, Parking Shed, Water Supply and Sanitary Installation item,etc.)			Estimated Cost : Rs. 98,685/-			
			Earnest Money : Rs. 2000/-			
			Time Limit : Two Months			
S.No.	Description of items	Quantity	Rates (In Rupees)		Unit	Amount
			In Figures	In words		
	2	3	4	5	6	7
1	Dismantling roofing including ridges, hips, valleys and gutters etcetera and stacking the material within all lead, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	26.78	69.80	Rupees sixty nine and paise eighty only	Per Square Metre	1869
2	Providing and fixing prepainted steel sheet roofing over steel trusses providing and fixing Kotar metal or equivalent prepainted single skin trapezoidal profile sheeting 0.60mm (zero point six zero millimeter) thick having 1060mm (one thousand six hundred millimeter) cover width (overall width 1126mm (one thousand one hundred twenty six millimeter) 28mm (twenty eight millimeter) crest depth at 353 (three hundred fifty three) + (plus minus) 2mm (two millimeter) centre to centre crest distance there will be two ribs at the centre for stiffening having depth of 2.5mm (two point five millimeter), main crest width at top 25mm (twenty five millimeter) and at the lower 81mm (eighty one millimeter) base metal of cold rolled steel coil with zinc coating top coat with regular modified polyster coating of approved shade and balancing reverse coat with polyster paint, fixing of sheet shall be with self drilling and self tapping screws of size 5.5mm (five point five millimeter) dia 75.5mm (seventy five point five millimeter) length with EPDM seal. The material supply will be accompanied by test certificate and against corrosion/ fading colour and manufactured defects, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.56	1418.50	Rupees one thousand four hundred eighteen and paise fifty only	Per Square Metre	43349

3	Steel work welded in built up sections, trusses and framed work, in beams joists channels angles, tee, flats with connected plates or angles cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like, including cutting, fixing, lifting, hoisting and placing in position complete and applying a priming coat of red lead paint complete as per HP:PWD. Specifications, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government..	57.35	Kilogram	120.20	Rupees one hundred twenty and paisa twenty only	Per Kilogram	6893
4	Second class brick work using common burnt clay building bricks in super structure above plinth level upto all heights/ floor level in cement mortar 1:6 (One cement : six sand) and curing complete, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government..	3.09	Cubic Metre	6450.20	Rupees six thousand four hundred fifty and paisa twenty only	Per Cubic Metre	19931
5	15mm (Fifteen millimetres) thick cement plaster with cement mortar 1:6 (One cement : six sand) in single coat on the rough side of brick/concrete/stone walls for interior plastering upto all floor level, including arrises internal rounded angles, chamfers and/or rounded angle in all girth and finished even and smooth complete, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government..	13.42	Square Metre	197.45	Rupees one hundred ninety seven and paisa forty five only	Per Square Metre	2650
6	Providing and fixing 25mm (Twenty five milimetre) dia (heavy type) nickel plated M.S. pipe curtain rods with nickel plated brackets, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government..	25.55	Running Metre	162.35	Rupees one hundred sixty two and paisa thirty five only	Per Running Metre	4148
7	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government..	21.00	Running Metre	280.20	Rupees two hundred eighty and paisa twenty only	Per Running Metre	5884

8	Providing and fixing wall mixing faucet for shower and bath hand shower with angular rest holder with complete accessories adhesive, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government..	1	Number	2550.00	Rupees two thousand five hundred fifty only	Each	2550
9	Providing and fixing 15 mm (fifteen milimetre) nominal bore with 45 cm (forty five centimetre) length unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government..	4	Number	72.85	Rupees seventy two and paisa eighty five only	Each	291
10	Providing and fixing 15 mm nominal bore C.P. brass bib cock of ISI mark of standard design and of approved make conforming to IS:8931 within all leads, and lifts disposed earth to be levelled and neatly dressed, including carriage of material within all leads, lifts and other incidental . The rate is including royalty , octroi, GST, Toll tax, malkana and all other taxes as imposed by the Government	4	Number	350.55	Rupees three hundred fifty and paisa fifty five only	Each	1402
11	Providing and fixing PTMT Tower Rail 600mm (six hundred milimetre) long towel rail with total length of 645 mm,(six hundred forty five milimetre) width 78 mm (seventy eight milimetre) and effective height of 88 mm (eighty eight milimetre) weighing not less than 190 gms (one hundred ninety gram) complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour, as per approved drawing, design, specification and direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental . The rate is including royalty , octroi, GST, Toll tax, malkana and all other taxes as imposed by the Government	2	Number	655.30	Rupees six hundred fifty five and paisa thirty only	Each	1311
12	Providing and fixing 600x120x5 mm (six hundred into one hundred twenty into five milimetre) glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm (forty milimetre) long screws, rawl plugs etcetera complete, as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including royalty , octroi, GST, Toll tax, malkana and all other taxes as imposed by the Government	1	Number	660.60	Rupees six hundred sixty six and paisa sixty only	Each	661

13	Providing and fixing 15mm (fifteen millimetre) nominal bore (Mixture) C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms.(eight hundred ten gram), as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including royalty, octroi, GST, Toll tax, malkana and all other taxes as imposed by the Government	1	Number	2450.00	Rupees two thousand four hundred fifty only	Each	2450
14	Cleaning of under ground sump, Over Head R.C.C. Tank (independent staging) including disposal of slit and rubbish, including carriage of material within all leads, lifts and other incidental. The rate is including royalty, octroi, GST, Toll tax, malkana and all other taxes as imposed by the Government	21.00	Running Metre	246.70	Rupees two hundred forty six and paisa seventy only	Per Running Metre	5181
15	Providing and fixing 125mm (One hundred twenty five millimetre) M.S. handles bright finished or/ and black ebamelled with nut and screws etcetera complete, as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental . The rate is including royalty, octroi, GST, Toll tax, malkana and all other taxes as imposed by the Government	2	Number	57.55	Rupees fifty seven and paisa fifty five only	Each	115
	Quoted rate in figure (%)					Total:	98685
	Quoted rate in words (%)						


Executive Engineer,
Jawali Division, H.P. P.W.D
Jawali-176023

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work:Repair and Maintenance of Veterinary Hospital Jawali (Under Deposit). (SH: - Providing and fixing shutter for Door, Window and Tile work etc.)		Estimated Cost : Rs. 93,716/-				
		Earnest Money : Rs.1900/-				
		Time Limit : Tw0 Months				
S.No	Description of items	Quantity	Rates (In Rupees)		Unit	Amount
			In Figures	In words		
		3	4	5	6	7
1	Providing and fixing Sal wood 40mm (forty millimetre) thick shutters for panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete, as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.90	4200.65	Rupees four thousand two hundred and paise sixty five only	Per Square Metre	16383
2	Providing and fixing 40mm (Forty millimetres) thick second class deodar wood wire gauge shutters using galvanized M.S. wire gauge of I.S. gauge designation 85G (eighty five galvanized) with wire of dia 0.56mm (Zero decimal five six millimetres) for doors, windows and clerestory windows including bright finished black enamelled iron butt hinges with necessary screws, as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental . The rate is including royalty , octroi, GST, Toll tax, malkana and all other taxes as imposed by the Government.	3.90	3345.10	Rupees three thousand three hundred forty five and paise ten only	Per Square Metre	13046
3	Providing and laying mechanically mixed and vibrated plain cement concrete for all type of structure nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering (surface and sub soil water) and removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in retaining wall, breast wall etcetera as per drawings and M.O.R.D. technical specification section 800,900, 1200 and 1600 as per the direction and entire satisfaction of Engineer-in-Charge Including carriage of material within all leads, lifts and other incidental . The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.74	4150.20	Rupeesn four thousand one hundred fifty and paise twenty only	Per Cubic Metre	11372

4	Providing and laying 600x600mm (Six hundred into six hundred millimetre) vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight percent) and conforming to IS: 15622, of approved make, in all colours and shades in flooring, laid on 20mm (twenty millimetre) thick cement mortar 1:4 (one cement :four sand), jointing with grey cement slurry at the rate of 3.3 kg/ sqm (three point three kilogram per square metre), including grouting the joints with white cement and matching pigments etcetera complete, as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	18.42	Square metre	1360.70	Rupees one thousand three hundred sixty and paise seventy only	Per Square Metre	25064
5	Providing and laying 500x500mm (five hundred into five hundred millimetre) Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% (zero point zero eight percent) and conforming to IS: 15622, of approved brand and manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm (six millimetre) thickness, including grouting of joints (Payment for grouting of joints to be made separately), as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.74	Square metre	1254.95	Rupees one thousand two hundred fifty four and paise ninety five only	Per Square Metre	2184
6	Painting steel work with Deluxe Multi Surface Paint of required shade. Two or more coat applied at the rate of 0.90 ltr/10 sqm (zero point nine zero litre per ten square metre) over an under coat of primer applied at the rate of 0.80 ltr/10 sqm (zero point eight zero litre per ten square metre) of approved brand and manufacture, as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.96	Square metre	110.15	Rupees one hundred ten and paise fifteen only	Per Square Metre	216
7	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied at the rate of 0.90 ltr/10 sqm (zero point nine zero litre per ten square metre) over an under coat of primer applied at the rate of 0.75 ltr/10 sqm (zero point seven five litre per ten square metre) of approved brand and manufacture, as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.8	Square metre	105.20	Rupees one hundred five and paise twenty only	Per Square Metre	821

8	Steel work welded in built up sections, trusses and framed work, in beams joists channels angles, tee, flats with connected plates or angles cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like, including cutting, fixing, lifting, hoisting and placing in position complete and applying a priming coat of red lead paint complete as per HP:PWD. Specifications as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	77.34	Kilogram	86.65	Rupees eighty six and paise sixty five only	Per Kilogram	6702
9	Providing and fixing 12mm (twelve millimetre) thick insulating board ceiling of approved quality with necessary nails etc. complete (frame work to be paid separately), as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	18.42	Square metre	582.65	Rupees five hundred eighty two and paise sixty five only	Per Square Metre	10732
10	Providing and laying 60mm (sixty millimetre) thick cement concrete paver block of M-35 (M-thirty five) grade with approved colour, design and pattern. factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour and pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete, as per direction of the Engineer-in-Charge, as per approved drawing, design, specifications, as per direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.00	Square metre	799.50	Rupees seven hundred ninety nine and paise fifty only	Per Square Metre	7196
						Total:	93716
	Quoted rate in figure (%)	(Amount to be quoted by the contractor in figure)					
	Quoted rate in words (%)	(Amount to be quoted by the contractor in words)					


Executive Engineer,
Jawali Division H.P. P.W.D.
Jawali-176023