



OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG

PH: 01907-222229 Fax: 222229, e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024-
To

3398

Dated:- 23 ⁷/₂₀₂₅

✓ The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.


Subject :-

Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.


Executive Engineer,
B&R Division,
HP PWD Karsog

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **01.08.2025 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 31.07.2025** for which the application should reach in this office **upto 1.00 PM 31.07.2025**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R Damages on Kotlu Nanj Road Km 0/00 to 6/150 (SH:- C/O PCC R/Wall at RD 0/430 to 0/443)	4,98,294/-	10,000/-	One month	350/-
2	R/R damages on Bakhrot Sanarli Kelodhar Luhri road Km. 0/00 to 41/800 (SH:- C/o R/wall at RD 14/860 to 14/873)	4,52,342/-	9,100/-	Two months	350/-
3	R/R damages on Shanker Tuman road Km.0/0 to 2/700 (SH:- Hiring of JCB for removal of slips at various RDs)	98,900/-	2,000/-	One month	350/-

TERMS & CONDITIONS:-

- No tender form will be issued to those contractors who are not registered under HPGST Act.
- The Contractor/firm should be registered as or dealer GST NO.
- If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
- No tender form will be issued to those contractors who are not registered under EPF Act.
- The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- The earnest money for the above work should be attached with the application

8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

Executive Engineer
B&R Division
HPPWD Karsog

No. PW-E-Tender-NIT/2025-26-

3392-97

Dated:- 23/7/2025

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage BOQ

E. 0085 - 4,98,294.03
 E. Money 10,000/-
 Total = 6,11,000/-

Name of the Bidder/ Bidding Firm / Company _____
 (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only							
PRICE SCHEDULE							
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT with all taxes including GST Rs. P	TOTAL AMOUNT with all taxes including GST Rs. P	TOTAL AMOUNT with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stumps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	33.15	Per Cubic Meter	390.20	12935.13	12935.13	INR Twelve Thousand Nine Hundred Thirty Five & Paise Thirteen Only
2	Providing and laying concrete for plain/reinforcement concrete 1:4:8 (one cement : eight sand : eight graded stone aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	64.35	Per Cubic Meter	5500.00	353925.00	353925.00	INR Three Lakh Fifty Three Thousand Nine Hundred Twenty Five & Paise Zero Only
3	Providing weepholes in bricks masonry/stone masonry plain/reinforced complete abutment wing wall, return wall with 100 mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 70, 1204.3.7 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	26.00	Each	373.15	9701.90	9701.90	INR Nine Thousand Seven Hundred One & Paise Ninety Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3, or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals	20.28	Per Cubic Meter	1200.00	24336.00	24336.00	INR Twenty Four Thousand Three Hundred Thirty Six & Paise Zero Only
5	Maintenance of earthen shoulder by adding fresh approved soil surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and technical specification Clause 1903 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals	1612.50	Per Square Meter	22.00	35475.00	35475.00	INR Thirty Five Thousand Four Hundred Seventy Five & Paise Zero Only
6	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge for smooth riding. The recovery of 19.00 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 5700/- only, shall be done on pro-rata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases, or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	190.00	Per Cubic Meter	325.90	61921.00	61921.00	INR Sixty One Thousand Nine Hundred Twenty One & Paise Zero Only
Total In Figures					498294.03	498294.03	INR Four Lakh Ninety Eight Thousand Two Hundred Ninety Four & Paise Zero Three Only
Quoted Rate In Figures			Select		0.00	0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only		

Bill of quantity checked and approved for Rs. 498,294.03
11.11.2025

Bill of Quantity checked and approved for Rs. 4,98,294.03
 For the year 2025-26 SR-H069

Executive Engineer
 Karagol Division
 APPWD Karagol

Validate

Print

Help

Order Inviting Authority:

Name of Work: R/R Damages on Bakhtol Sanaril Kelodhar Luthi Road Km 0/00 to 41/800. (SH.- C/O. RW/ail at RD 14/860 to 14/873)

Contract No:

Name of the Bidder/ Bidding Firm / Company

Percentage BoQ

E.C. 452342
E.M. 91,00/-
Time - Two Months

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. p	TOTAL AMOUNT with all taxes including GST Rs. p	TOTAL AMOUNT with all taxes including GST Rs. p	TOTAL AMOUNT with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	39.59	Per Cubic Meter	390.20	15448.02	15448.02	INR Fifteen Thousand Four Hundred Forty Eight & Paise Zero Two Only
2	Providing and laying concrete for plain/reinforcement concrete 1:4:8 (one cement : eight sand : eight graded stone aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	74.94	Per Cubic Meter	5500.00	412170.00	412170.00	INR Four Lakh Twelve Thousand One Hundred Seventy & Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals	16.25	Per Cubic Meter	1200.00	19500.00	19500.00	INR Nineteen Thousand Five Hundred & Paise Zero Only
4	Providing weepholes in bricks masonry/stone masonry plain/reinforced complete abutment wing wall, return wall with 100 mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 70, 1204.3.7 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	14.00	Each	373.15	5224.10	5224.10	INR Five Thousand Two Hundred Twenty Four & Paise Ten Only
Total in Figures					452342.12	452342.12	INR Four Lakh Fifty Two Thousand Three Hundred Forty Two & Paise Twelve Only
Quoted Rate in Figures			Select		0.00	0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only		

Bill of Quantity checked and approved for Rs. 452342.
only for the year 2025-26 - Sec. No. 72

Approved By
Karsog Division
GPPWD Karsog

Percentage Bill of quantity

name of Work:- R/R Damages on Shakelar Tuman Road Km 0/0 to 2/700 (SH:- Hiring of JCB for removal of slips at various RD's)

Sl. No.	Description of work	Qty.	Unit	Estimated cost:-	
				Earnest Money	98900.00
				Time	2000
				RATE	AMOUNT
				Words	One month
1	Hiring of JCB/Excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or Un-serviceable materials from the road surface upto any leads and lifts as per direction of the Engineer-in-Charge. The machine/JCB should work 8 Any loss to the public/private property or any accident etc happened hrs daily and remove at least 25.0 cum quantity of slips per hour. Any loss to the public/private property or any accident etc. shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	86.00	Hour	1150.00	98900.00
Total in Figures					98900.00
	Quoted rate in figure				
	Quoted rate in words				

Bill of quantity approved for Rs. 98900.00 only.
Sr. No. 55 For year 2025-26

Assistant Engineer
Sub Division Karsog
HPPWD Karsog

Executive Engineer,
Karsog Division,
HPPWD, Karsog.