

Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2024-25/

5558-587

Dated/ 22-7-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter No. PBW(B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office NIT No. PWP/ Agr. Asstt/ NIT/ 2025/- 5558-587 dated 22.07.2025 are urgent in nature and in public interest.

Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **02.08.2025** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 01.08.2025 up to 4.00 P.M and the application for issue of tender form shall be received 31.07.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o Pucca Path Alongwith Retaining Wall from Main road to Sh. Prakash Chand House Ward No. 1 GP Lahla (SW:- C/o R/Wall (Deposit)	Rs. 73,420.00	Rs. 1,500.00	Two Month
2	Restoration of Rain damages on Parour Lahla Chachian road Km 0/00 to 10/00 (SW:- C/o Edge Wall at RD 6/200 to 6/221)	Rs. 99,998.00	Rs. 2,000.00	Two Month
3	Repair of road from Dharamshala Yol Dadh Palampur Chadiyar Sandhole road (SW:- Providing and fixing dual directional reflective speed breaker at RD 27/00 to 33/00 (DC Deposit)	Rs. 98,400.00	Rs. 2,000.00	One Month
4	Repair of road from Dharamshala Yol Dadh Palampur Chadiyar Sandhole road (SW:- Providing and fixing dual directional reflective speed breaker at RD 33/00 to 38/00 (DC Deposit)	Rs. 98,400.00	Rs. 2,000.00	One Month
5	Restoration of Rain damages on Rajnali Harizan Basti Dharer road Km 0/00 to 1/600 (SH:- C/o R/Wall at RD 0/630 to 0/645)	Rs. 97,510.00	Rs. 2000.00	Two Month
6	Repair of link road from Dyala via Ward No. 3 GP Badsar to Harizan Basti KM 0/00 to 1/500 (SW:- C/o R/Wall at RD 0/015 to 0/022 (DC Deposit)	Rs. 88,770.00	Rs. 1,800.00	Two Months
7	C/o link road to Bhagotla Dharer Rajnali road Km 0/00 to 5/00 (SW:- Providing and laying Patch work on various RD'd Between KM 0/00 to 5/00 (Under MMSRRY)	Rs. 99,366.00	Rs. 2,000.00	Two Months
8	C/o Lugri Bhatti Kandi to Rajnali road Km 0/00 to 2/00 (SW:- P/L Patch work on various RD's between KM 0/00 to 2/00 (MMSRRY)	Rs. 99,313.00	Rs. 2,000.00	Two Months
9	R/D link road from Drognu Km 0/00 to 1/600 (SH:- P/L Patch work on various Rd's between 1/220 to 1/295) (DC Deposit)	Rs. 88,936.00	Rs. 1,800.00	Two Months
10	C/o Path from main road Ree to Sh. Vipan Kumar House Ward No. 3 (SH:- P/L Interlocking Tile at RD 0/00 to 0/027 (Deposit)	Rs. 99,320.00	Rs. 2,000.00	Two Months

11	Restoration of Rain damages on Dharamshala Yol Dadh Palampur road KM 15/00 to 27/00 (SW:- Hiring of JCB for removal of slips) (Deposit)	Rs. 98,900.00	Rs. 2,000.00	Two Months
12	Restoration of OFC damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road KM 33/000 to 40/500 (SW:- Providing and laying Interlocking Paver Block at RD 37/711 to 37/720)	Rs. 97,460.00	Rs. 2,000.00	Three Months
13	Steel Crash Barrier Sidhpur Sarkari link road steel Crash barrier (SW:- P/F "W" Metal beam Crash barrier at RD 3/750 to 3/773.20 (DC Deposit)	Rs. 99,470.00	Rs. 2,000.00	Two Months
14	Steel Crash Barrier Sidhpur Sarkari link road steel Crash barrier (SW:- P/F "W" Metal beam Crash barrier at RD 0/374 to 0/397.20 (DC Deposit)	Rs. 99,470.00	Rs. 2,000.00	Two Months
15	Additionality to C/o Sarai in Ward No. 1 GP Jia Khas (SW:- Providing and laying Vetrified Tiles) (VKVNY Deposit)	Rs. 97,614.00	Rs. 2,000.00	Two Months
16	Additionality to C/o Sarai in Ward No. 1 GP Jia Khas (SW:- P/L Grills, Vetrified Tiles, Flooring & Painting work (VKVNY Deposit)	Rs. 92,144.00	Rs. 1,900.00	Two Months
17	C/o link road from SC Community Awadi to Connect Draman to Jadiayala Mandir (Sungal to Matt) via Padiyarkhar Farm road KM 0/00 to 0/800 (SW:- P/L CC pavement at RD 0/00 to 0/026) (Deposit)	Rs. 99,828.00	Rs. 2,000.00	Three Months
18	C/o link road from SC Community Awadi to Connect Draman to Jadiayala Mandir (Sungal to Matt) via Padiyarkhar Farm road KM 0/00 to 0/800 (SW:- P/L CC pavement at RD 0/028 to 0/050) (Deposit)	Rs. 99,167.00	Rs. 2,000.00	Three Months
19	Jeepable road from Sh. Dhannu Ram S/o Sh. Gigga Ram house to Govt. Agri farm Ward No. 3 (SW:- C/o CC Pavement RD 0/035 to 0/040 & Grating on Kuhal Crossing) (Deposit)	Rs. 99,729.00	Rs. 2,000.00	Three Months
20	Additional Accommodation Govt. Senior Secondary School Kandwari (SW:- Providing Putty Ist Floor & 2 nd Floor Halls, Verandah etc (Deposit)	Rs. 96,316.00	Rs. 2,000.00	Three Months
21	Additional Accommodation Govt. Senior Secondary School Kandwari (SW:- Distempering and painting etc (Deposit)	Rs. 96,561.00	Rs. 2,000.00	Three Months
22	Restoration of rain damages on Lohna Surad road (SW:- Providing and laying Interlocking Concrete Block Pavement at RD 0/420 to 0/442 (DC Deposit)	Rs. 97,710.00	Rs. 2,000.00	Three Months
23	Restoration of Rain damages on Bindraban Sidhpur Sarkari Bharer road (SW:- Providing and laying Interlocking Concrete block Pavement at RD 0/650 to 0/672) (DC Deposit)	Rs. 98,094.00	Rs. 2,000.00	Three Months
24	Repair of Pot holes in Banuri to Odder road KM 0/00 to 3/500 (SW:- Repair of Pot holes at various RDs (MMSRRY)	Rs. 99,955.00	Rs. 2,000.00	Three Months
25	Strengthening of culvert in Ward No. 2 GP Lamlehar (SW:- Providing 1:3:6 under Flooring, RCC slab etc)	Rs. 74,455.00	Rs. 1,500.00	Three Months

26	Footpath from Main road to Smt. Subhi Devi house Ward No. 3 GP Chandropa (SW:- C/o B/Wall on both sides)	Rs. 99,641.00	Rs. 2,000.00	Three Months
27	C/o Concrete road from Main road to Bachiter Singh in Kand Gwaltkar (SW:- wearing II and Cement Concrete 1:2:4)	Rs. 99,288.00	Rs. 2,000.00	Three Months
28	Repair of Mahila Mandal Bhawan Jandera Saralu Ward No. 13 M.C. Tanda (SW:- Repair of Plaster, Flooring work etc)	Rs. 98,912.00	Rs. 2,000.00	Three Months
29	R/Wall to protect the land of Sh. Sanjay Kumar S/o Sh. Kalu Ram Village KhianPatt Chandropa (SW:- C/o R/Wall)	Rs. 99,533.00	Rs. 2,000.00	Three Months
30	Repair of Revenue Record Room in Tehsil Palampur Distt. Kangra (HP) (SW:- Providing and fixing Galvanized Steel Room Sheet roofing)	Rs. 99,775.00	Rs. 2,000.00	Three Months
31	R/Wall to protect the land of Sh. Sanjeev Kumar Village Dohal Mohal Chandropa (SW:- C/o R/Wall)	Rs. 74,259.00	Rs. 1,500.00	Three Months
32	Repair of Revenue Record Room in Tehsil Palampur Distt. Kangra (HP) (SW:- Steel work in built up sections, trusses work)	Rs. 99,064.00	Rs. 2,000.00	Three Months
33	Restoration of rain damages on link road Chachian to Darati via Mathred Km 0/00 to 3/900 (SW:- C/o R.C.C Slab Culvert (Kuhai Crossing) at RD 0/950)	Rs. 99,987.00	Rs. 2,000.00	Two Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand. Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Palampur Division
HPPWD Palampur

1

SCHEDULE OF QUANTITY

Name of work:- C/o Pucca Path alongwith Retaining wall from main road to Sh. Prakash Chand house ward No. 1 G.P Lahla. (SH:- C/o R/wall) Deposit 0.75 Lacs							Estimated cost Rs. 73420.00
							Earnest Money Rs. 1500.00
							Time Limits Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.20			Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	16.28			Per cubic metre.		
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	5.00			Each		
Total							

Executive Engineer,
Palampur Division
HP.PWD Palampur

(2)

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Parour Lahla Chachian road Km 0/00 to 10/00. (SH- C/o Edge wall at Rd 6/200 to 6/221).

6/200 to 6/221).							Estimated cost Rs.		99998.00		
							Earnest Money Rs.		2000.00		
							Time Limits		Two Months		
Description of Item							Quantity	Rate		Unit	Amount
								In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.						8.51			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.						22.05			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.						10.00			Each	
Total											

Executive Engineer,
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- Repair of road from Dharamshala Yol Dadh Palampur Chadhiyar Sandhole road
Sub Work :- Providing and fixing dual directional reflective speed breaker at RD 27/00 to 33/00 *C De Deposit*

Estimated Cost :- Rupees 98,400/-
Earnest Money :- Rupees 2000/-
Time limit : One Month.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and fixing dual directional reflective speed breaker/ rumble strips high impact resistant plastic body of sizes 275x150x32mm (Two hundred seventy five into one hundred fifty into thirty two millimetre) having six glass large 12mm (twelve millimetre) diameter reflector lenses to one side 12(Twelve) number on both side provided with two steel zink plated nails of 12mm(Twelve millimetre) and of length 120mm (One hundred twenty millimetre) for fixing to road by hammering make green/greenlite electera as per drawing and specifications including carriage of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in-charge.	82.00 Nos.	1300/-	one thousand three hundred	Each	
			Total:-			

Handwritten notes:
 1. Under Kewra Gas
 2. Cost 7214 x 82
 3. 60312
 4. 60312 (12)

Signature:
 Executive Engineer
 Palampur Division
 H.P.PWD Palampur

(4)

Schedule of Quantity

Name of Work :- Repair of road from ~~from~~ Dharamshala Yol Dadh Palampur Chadhiyar Sandhole road
Sub Work :- Providing and fixing dual directional reflective speed breaker at RD 33/00 to 38/00 (C De Deposit)

Estimated Cost :- Rupees 98,400/-
Earnest Money :- Rupees 2000/-
Time limit : One Month.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and fixing dual directional reflective speed breaker/ rumble strips high impact resistant plastic body of sizes 275x150x32mm (Two hundred seventy five into one hundred fifty into thirty two millimetre) having six glass large 12mm (twelve millimetre) diameter reflector lenses to one side 12(Twelve) number on both side provided with two steel zink plated nails of 12mm(Twelve millimetre) and of length 120mm (One hundred twenty millimetre) for fixing to road by hammering make green/greenlite etcetera as per drawing and specifications including carriage of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in-charge.	82.00 Nos.			Each	
			Total:-			

Executive Engineer
Palampur Division
H.P.PWD Palampur

(5)

SCHEDULE OF QUANTITY						
Name of work:- Restoration of Rain Damages on Rajnali Harizan Basti Dharer road Km 0/00 to 1/600. (SH:- C/o R/wall at Rd 0/630 to 0/645).				Estimated cost Rs.		97510.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time	8.10			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.00			Per cubic metre	
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.15			Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	10.00			Each	
Total						

Executive Engineer,
Palampur Division
HP PWD Palampur

6

SCHEDULE OF QUANTITY

Name of work:- R/O Link road from Dyala via ward No. 3 G.P. Badsar to Harizan Basti Km 0/00 to 1/500. (SH:- C/o R/wall at Rd 0/015 to 0/022) SDRF . (D.C. Deposit)							Estimated cost Rs.	88770.00
							Earnest Money Rs.	1800.00
							Time Limits	Two Months
Sr. No.	Description of Item	Quantity	In Figures	Rate		Unit	Amount	
					In Word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.40				Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	19.11				Per cubic metre.		
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.36				Per cubic metre		
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	7.00				Each		
Total								

Executive Engineer,
Palampur Division
HP, PWD Palampur

7

SCHEDULE OF QUANTITY						
Name of work:- C/o Link road to Bhagotla Dharer Rajnali road Km 0/00 to 5/00. (SH:- P/L Patch work on various Rd's between Km 0/00 to 5/00). Under MMSRRY				Estimated cost Rs.		99366.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying, spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Per cubic metre	
2	Reparing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10 (ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre. Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen Vg-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required fine grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	272.40			Per Square metre	

Executive Engineer
Palampur Division
HP PWD Palampur

88

SCHEDULE OF QUANTITY

Name of work:- C/o Lugri Bhatti Kandi to Rajnali road Km 0/00 to 2/00. (SH:- P/L Patch work on various Rd's between Km 0/00 to 2/00). Under MMSRRY				Estimated cost Rs.		99313.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.00			Per cubic metre	
2	Repairing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10 (ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre. Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	252.39			Per Square metre	

Executive Engineer,
Palampur Division
HP PWD Palampur.

SCHEDULE OF QUANTITY

Name of work:- R/O link road from Drognu Km 0/00 to 1/600. (SH:- P/L Patch work on varios Rd's between 1/220 to 1/295).
D.C. Deposit 0.90 Lacs

Name of work:- R/O link road from Drognu Km 0/00 to 1/600. (SH:- P/L Patch work on varios Rd's between 1/220 to 1/295).				Estimated cost Rs.		88936.00
				Earnest Money Rs.		1800.00
				Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17.16			Per cubic metre	
2	Providing and applying tack coat with Bitumen emulsion (RS-I) using emulsion pressure distributor at the rate of 0.275 kg. (zero point two seven five kilogram per Square metre on the prepared granular surface treated with primer and cleaned with hydraulic broom as per M.O.R.D. technical specifications clause 503 and as per the directions of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	228.75			Per square metre	
3	Providing, laying and rolling of open-graded premix carpet of 20 mm (Twenty millimetre) compacted thickness composed of Type-A 13.2 mm (Thirteen decimal two millimetre) to 5.6 mm (Five decimal six millimetre) aggregates at the rate of 0.27 Cum. (Zero point two seven Cubicmetres) mixed with penetration grade V.G-10 (Viscosity grade-Ten) Bitumen at the rate 14.6 Kg. (Fourteen point six Kilogram) per ten Square metres of road surface to required line, grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot mix Plant 30/40 (Thirty / Forty) Tonne per hour capacity, transporting mixed material with tipper and laying with paver finisher to the required grade and camber and rolling with a three wheel 80-100 (Eighty - Hundred)KN static road roller, finished to required level and grades to be followed by seal coat as per MORD Technical Specification Clause 506 by mechanical means and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	228.75			Per square metre	
					Total	

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Path from main road Ree to Sh. Vipin Kumar House Ward No. 3, (SH):- P/L interlocking tile at Rd 0/00 to 0/027). Deposit 1.00 Lacs					Estimated cost Rs.	
					2000.00	
					Two Months	
Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	74.25			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix. P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.81			Per cubic metre.	
Total						


 Executive Engineer
 Palampur Division
 HP PWD Palampur

11

SCHEDULE OF QUANTITY						
Name of work:- Restoration of Rain Damages on Dharamshala Yol Dadh Palampur road Km 15/00 to 27/00. (SH:- Hiring of JCB for removal of slips). Deposit						
Sr. No.	Description of Item	Quantity	Estimated cost Rs.		98900.00	
			Earnest Money Rs.		2000.00	
			Time Limits		Two Months	
			Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of JCB (Excavator-Cum-Loader) including P.O.L. charges shifting charges and other ancillary equipments as per required at site of work for removal of slips. The disposal of this un-serviceable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage intook place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	86.00			Per Hour	
				Total		

Executive Engineer,
Palampur Division
HP, PWD Palampur.

12

Work No.

Estimated Cost :- Rs. 97,460/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

Schedule of Quantity


Name of Work :- Restoration of OFC damages on Dharamshala Yol Dadh Holta Chadhiyar Sandhole road km. 33/000 to 40/500
(S. W. :- Providing and Laying interlocking Paver Block at RD 37/711 to 37/720)

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	4.81	Cubic metres		Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	64.24	Square Metre		Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203, including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.70	Cubic metres		Per Cubic metre.	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Steel Crash Barrier Sidhpur Sarkari Link road steel crash barrier.(SH:- P/F "W" metal beam crash barrier at Rd 3/750 to 3/773.20), D.C. Deposit				Estimated cost Rs.	
				Earnest Money Rs.	
				Time Limits	
Sr. No.	Description of item	Quantity	In Figures	Rate	
				In Word	Unit
					Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, (GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre.
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (Seventy Centimetre) above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 m (two metre) centre to centre, 1.80 m (one point eight zero metre) high, 1.10 m (One point one zero metre) below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, (one hundred fifty into seventy five into five millimetre) 330 mm (three hundred thirty millimetre long complete as per clause 810 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.20			Per running metre
Total					


 Executive Engineer
 Palampur Division
 HP PWD Palampur

SCHEDULE OF QUANTITY


Name of work:- Steel Crash Barrier Sidhpur Sarkari Link road steel crash barrier.(SH:- P/F "W" metal beam crash barrier at Rd 0/374 to 0/397.20) D.C. Deposit					Estimated cost Rs.	
					Earnest Money Rs.	
					Time Limits	
Sl. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 I and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19			Per cubic metre	
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (Seventy Centimetre) above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 m (two metre) centre to centre, 1.80 m (one point eight zero metre) high, 1.10 m (One point one zero metre) below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, (one hundred fifty into seventy five into five millimetre) 330 mm (three hundred thirty millimetre long complete as per clause 810 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.20			Per running metre	
Total						

 Executive Engineer
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Additionality to C/o Sarai in ward No. 1 G.P. Jia Khas. (SH:- Providing and Laying Vetrified tiles).
VKVNY Deposit 2.00 Lacs

Sr. No.	Description of Item	Quantity	Estimated cost Rs.		Earnest Money Rs.	
			Time Limits		Two Months	
			In Figures	Rate	In Word	Amount
1	Providing and laying 600x600 mm (six hundred millimetre) Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm (twelve millimetre) thick bed of cement mortar 1:3 (one cement: three coarse sand), jointing with grey cement slurry @ 3.3 (three point three) Per Kilogram/ Per Square Metre including grouting the joint with white cement & matching pigments etc. complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	67.32			Per square metre	
	Total					


 Executive Engineer,
 Palampur Division
 HP PWD Palampur

16

SCHEDULE OF QUANTITY									
Name of work:- Additionality to C/o Sarai in ward No. 1 G.P. Jia Khas. (SH:- P/F Grills, Vetrified tiles, Flooring & Painting work). VKVVY Deposit 2.00 Lacs				Estimated cost Rs.		92144.00			
				Earnest Money Rs.		1900.00			
				Time Limits		Two Months			
Sr No	Description of Item	Quantity	In Figures		Rate		Unit	Amount	
						In Word			
1	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	272.76					Per Kilogramme		
2	Providing and laying 600x600 mm (six hundred into six hundred millimetre) Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm (twelve millimetre) thick bed of cement mortar 1:3 (one cement: three coarse sand), jointing with grey cement slurry @ 3.3 (three point three) Per Kilogram/ Per Square Metre including grouting the joint with white cement & matching pigments etc. complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	31.89					Per square metre		
3	40mm thick Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) 20 mm nominal size finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete . The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	31.03					Per square metre		
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over and under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	38.90					Per square metre		
5	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi,royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	22.73					Per square metre		
Total									

Executive Engineer,
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work :- C/O link road from SC Community Awadi to connect Draman to Jadiyah Mandir (Sungal to Matt) via Padhiarkhar farm road km. 0/00 to 0/800.

Sub Work :- P/L CC Pavement at RD 0/00 to 0/026 (Deposit)

Estimate Cost :- Rs. 99,828/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.24	Cubic metres			Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	15.76	Cubic metres			Per Cubic metre.	
	Total :-						

Executive Engineer,
Palampur Division,
HPPWD Palampur

Name of Work :-C/O link road from SC Community Awadi to connect Draman to Jadyala Mandir (Sungal to Matt) via Padhiarkhar farm road km. 0/00 to 0/800.

Sub Work :- P/L CC Pavement at RD 0/028 to 0/050 (Deposit)

Schedule of Quantity

Estimate Cost :- Rs. 99,167/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.31	Cubic metres			Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203, including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	15.63	Cubic metres			Per Cubic metre.	
Total :-							

Executive Engineer,
Palampur Division,
HPPWD Palampur

79

Schedule of Quantity

Name of Work :- Jeepable road from Sh. Dhannu Ram S/O Sh. Giggam Ram house to Govt. agri farm ward No. 3
Sub Work :- C/O CC Pavement RD 0/035 to 0/040 & grating on kuhal crossing

Deposit

Estimated Cost : Rupees 99,729/-
Earnest Money : Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads,lifts and other incidentals by Manual Means.The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	1.12			Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix.P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	6.93			Per Cubic metre.	
3	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in-Charge.The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	595.00			Per Kilogram	
					Total:-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

20

Schedule of Quantity

Name of Work :- Additional Accommodation Govt. Senior Secondary School Kandwari

Sub Work :- Providing putty etc. 1st floor & 2nd floor halls, Verandah etc. (Deposit)

Estimated Cost : Rupees 96,316/-

Earnest Money : Rupees 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	1481.79	Square metres		Per Square metre	
				Total:-		

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Name of Work :- Additional Accomodation Govt. Senior Secondary School Kandwari

Sub Work :- Distempering and Painting etc. (Deposit)

Estimated Cost : Rupees 96,561/-

Earnest Money : Rupees 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	15.66	Square metre			Per Square metre	
2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	408.23	Square Metre			Per Square Metre	
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	518.85	Square metre			Per Square metre	
					Total:-		

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Name of Work :- Restoration of rain damages on Lohna Surad road

Sub Work :- Providing and Laying interlocking concrete block pavement at RD 0/420 to 0/442 (DC Deposit)

Estimated Cost :- Rupees 97,710/-

Earnest Money :- Rupees 2000/-

Time limit :- Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing and laying of interlocking Concrete Block Pavements having thickness 80 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	66.00	Square Metre			Per square metre	
2	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix .P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 & 1203 including carriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	2.10	Cubic metre			Per Cubic metre	
					Total:-		

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of Quantity

Name of Work :- Restoration of rain damages on Binderaban Sidhpur Sarkari Bharer road
Sub Work :- Providing and Laying interlocking concrete block pavement at RD 0/650 to 0/672 (DC Deposit)

Estimated Cost :- Rupees 98,094/-
Earnest Money :- Rupees 2000/-
Time limit :- Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and laying of interlocking Concrete Block Pavements having thickness 80 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	66.30			Per square metre	
2	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	2.10			Per Cubic metre	
					Total:-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

(24)

Work No.

Estimate Cost :-Rs. 99,955/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

Schedule of Quantity

Name of Work :- Repair of pot holes in Banuri to odder road km 0/00 to 3/500

Sub Work :- Repair of Pot Holes at various RDs (MMSRRY)

S. No.	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm(twenty millimetres) thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	286.68	Square metre			Per Square metre	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.08	Cubic metres			Per Cubic metre.	
Total :-							

Executive Engineer,
Palampur Division,
HPPWD Palampur

25

Work No.

Estimate Cost :- Rs. 74,455/-

Earnest Money :- Rs. 1500/-

Time Limit :- Three Months

Schedule of Quantity

Name of Work :- Strengthening of culvert in ward no. 2 GP Lamlehar

Sub Work :- Providing 1:3:6 under flooring, RCC slab etc.

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
		In figure	In Words -	In figure	In Words -		
1	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	0.45	Cubic metre			Per Cubic metre.	
2	Providing concrete for plain/reinforced concrete, in open foundations 1:1.5:3 (1cement:1.5 :3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate (20 mm nominal size) R.C.C. grade M- 25 (M-Twenty Five) complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	1.38	Cubic metres			Per Cubic metre	
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	48.30	Kilogram me			Per Kilogram me	
4	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	9.20	Cubic metres			Per Cubic metre.	
	Total:-						

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Name of Work :- Footpath from main road to Smt. Subhi Devi house ward no. 3 G.P. Chandropa
Sub Work :- C/o B/wall on both sides

Work No. 26

Estimate Cost :-Rs. 99,641/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rupees
			In figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	7.56			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	22.68			Per Cubic metre	
Total :-						

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Name of Work :- C/O Concrete road from main road to Bachitar Singh house in Kand Gwaltikar
Sub Work :- P/L wearing II and C.conc. 1:2:4

Work No. 27

Estimate Cost :-Rs. 99,288/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rupees
			In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads,lifts and other incidentals by Manual Means. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	9.24	Cubic metres		Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix.P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203, including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	12.46	Cubic metres		Per Cubic metre.	
Total :-						

Executive Engineer,
Palampur Division,
HPPWD Palampur

Name of Work :- Repair of Mahila Mandal Bhawan Jandera Saralu Ward No. 13 M.C. Tanda
Sub Work :- Repair of Plaster, Flooring work etc.

Schedule of Quantity

Work No.

Estimate Cost :-Rs. 98,912/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Providing and laying cement concrete wearing course M 30 grade including reinforcement complete as per drawing and technical specifications Clauses 800 and 1206.3 including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	5.04	Cubic metres			Per Cubic-metre.	
2	15mm Cement plaster Cement Mortar 1:4 (One Cement; four Sand).in single coat on the rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	235.00	Square metre			Per Square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	2.40	Cubic metres			Per Cubic-metre.	
Total :-							

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Name of Work :- R/wall to protect the land of Sh. Sanjay Kumar S/O sh. Kalu Ram village Khianpatt Chandropa
(S. W. :- C/O R/wall

Work No. 29

Estimated Cost :- Rs. 99,533/-

Earnest Money : 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	9.18			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	22.11			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	7.00			Each	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- Repair of Revenue Record room in Tehsil Palampur Distt. Kangra (H.P.)

Sub Work :- Providing & fixing Galvanised Steel sheet roofing

Work No. 30

Estimate Cost :-Rs. 99,775/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like including carriage of materials with in all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	65.00	Kilogram me			Per Kilogram me	
2	Providing and Fixing 0.60 mm (zero decimal six zero millimetre) thick prepainted polyster galvanised steel sheet of approved colour over steel trusses with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns of primer back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating fixed with prepainted J or L hooks, bolts and nuts 8mm (eight millimetre) dia bitumen and G.I. limpet washers filled with required colour and laid completed as per the Direction of Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	65.00	Square metre			Per Square metre	
				Total :-			

Executive Engineer,
Palampur Division,
HPPWD Palampur

Name of Work :- R/wall to protect the land of Sh. Sanjeev Kumar village Dohal Mohal Chandropa
(S. W. :- C/O R/wall)

Schedule of Quantity

Work No. 32

Estimated Cost :- Rs. 74,259/-

Earnest Money :- Rs. 1500/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	6.10	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	16.37	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	8.00	Numbers			Each	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- Repair of Revenue Record room in Tehsil Palampur Distt. Kangra (H.P.)

Sub Work :- Steel work in built up sections, trusses work

Work No. 32

Estimate Cost :-Rs. 99,064/-

Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like including carriage of materials with in all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	1165.46	Kilogram me			Per Kilogram me	
					Total :-		

Executive Engineer,
Palampur Division,
HPPWD Palampur

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road Chachian to Drati via Mathred Km 0/00 to 3/900. (SH:- C/o R.C.C. Slab culvert (Kuhel Crossing) at Rd 0/950).									
Estimated cost Rs.									
Earnest Money Rs.									
Time Limits									
Two Months									
Sr No.	Description of Item	Quantity	Rate		Unit	Amount			
			In Figures	In Word					
1	Demolishing Nominal cement concrete 1:3:6 or richer mix (i/e equivalent design mix) manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.95			Per cubic metre				
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.27			Per cubic metre				
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government	2.15			Per cubic metre.				
4	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogramme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.49			Per cubic metre				
5	Providing and laying M-25 (1:1.5:3) Plain/reinforced cement concrete in open foundation complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 ans 1204 and to the entire satisfaction and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.55			Per cubic metre				

33

6	Supplying fitting and placing HYSD bar reinforcement in super structures in slab complete as per drawings and MORTH technical specifications clause 1600 and 2300, including cutting bending, binding and placing in position complete in all respect including the cost of binding wire upto all heights / depths or as per the direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.26			Per Metric Tonne	
7	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.60			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur