

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO:-PW/TD/CB/TA/NIT /2025- 26-

4179

Dated- 23-7-2025

To

The Executive Engineer (IT Cell)
Nigam Vihar, Shimla-2,

Subject:- Tender Notice.

Dear Sir,

Enclosed Please find herewith the notice work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP. Letter No. PBW (B) A (3) 1/2021 dated 03-01.2025. As the work mentioned in the tender notice are urgent in nature and in public interest.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender and schedule of quantity.


Executive Engineer
Tanda Division
HP PWD Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, as called vide this office letter No.PW-TD-CB-TA 2025-26- 4180-99 dated 23-07-2025 are of urgent nature.


Executive Engineer
Tanda Division
HP PWD at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on 05-08.2025 up to 11:00 A.M. And the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on 04.08.2025 up to 4:00 P.M and the application for issue of tender form shall be received on 02.08.2025 up to 12:00 noon. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Restoration of rain damages on Jeepable link road to the residence of Anuradha, Pankaj and others in Tehsil Baroh Distt. Kangra HP (SH: Construction of Retaining wall at RD 0/060 to 0/069 (Under Deposit Head SDF/2024/1618).	99967.00	2000.00	Two Months
2	Construction of Sarai in Tikka Har in Distt. Kangra HP (SH: Constuction of Civil work etc, under SDP/2017/266).	97686.00	2000.00	Two Months
3	Construction of link road from Yol Dhaloon road to Dhaloon Society road in Distt. Kangra HP (SH: Construction of steel grating at various RD 2017/307/121).	96179.00	1950.00	Two Months
4	Special repair of Govt. Senior Secondary School Serathana in Tehsil Nagrota Bagwan, Distt. Kangra HP (SH: Providing and fixing preapainted sheet steel work etc). VKV/2018/1361).	99964.00	2000.00	Two Months
5	Annual repair and maintenance of Non- Residential Building at Dr. R.P. Govt. Medical College at tanda in Distt. Kangra HP Deposit. (SH: Painting work in Old sub- division building).	63660.00	1300.00	Two months
6	Balance work of Dr. Bheem Rao Ambedkar Mahila Mandal Bhawan Ward No.1 at Karahpura in Gram Panchayat Patiyalkar in Nagrota Bagwan Distt. Kangra H.P. (SH: Balance work of Brick work, wood work, Plastering etc, Deposit work VKV/2017/1664).	99186.00	2000.00	Two Months
7	Restoration of rain damagaes on link road Ramehar Tangroti Dhaloon km 0/00 to 6/00 in Distt. Kangra HP (SH: Construction of Breast wall at Rd 4/105 to 4/108 SO SDF/2024/1692).	41618.00	850.00	Two months
8	Balance work of Dr. Bheem Rao Ambedkar Mahila Mandal Bhawan Ward No.1 at Karahpura in Gram Panchayat Patiyalkar in Nagrota Bagwan Distt. Kangra H.P. (SH: Balance work of Plastering, painting and steel work etc, Deposit work VKV/2017/1664).	99860.00	2000.00	Two months

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender form.
6. Next tender will be issued only after completion of previous works in hand

HIMSUCHANA AVAM & JAN SAMPARK

No.PW/NBD/TA/Tender/NIT/2025-26- **4180-99** Dated/ **23-7-2025**
Copy to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Director, Information & Publications Department, H.P. Shimla.
3. The Executive Engineer IT Cell Shimla HP PWD Shimla.
4. The Superntending Engineer, 5th Circle, HPPWD, Palampur
5. The Deputy Commissioner, Kangra at Dharamshala
6. All the S.E.s/E.E.s under North Zone.
7. The Sub-Divisional Officer(C) Nagrota Bagwan.
8. All the Assistant Engineer under this Division.
9. The Drawing /Accounts Branch in this office.
10. Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan
(On behalf of Governor of Himachal Pradesh)

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99967.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on Jeepable link road to the residence of Anuradha, Pankaj and others in Tehsil Baroh, Distt. Kangra (H.P.).
 SUB HEAD:- Construction of Retaining wall at RD 0/060 to 0/069 (Under Deposit Head SDF/2024/1618).

Sr. No.	Description	Quantity	In fig.	Rate in words	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	3	4	5	6	7
2	Providing and laying in position cement concrete of specified grade including the cost of entering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	8.91 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	23.56 Cubic metres			Per cubic metre	
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	6.00 Running metres			Per running metre	
		4.77 Cubic metres			Per cubic metre	
TOTAL:-						


 Executive Engineer,
 H.P.P.W.D Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 97686.00
 EARNEST MONEY :- Rs. 2000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of Sarai in Tikka Har in Distt. Kangra (H.P.).
 SUB-HEAD :- Construction of Civil work etc; Under SDP/2017/266.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig 4	In words 5		
1	Excavation work by mechanical means (Hydraulic excavatory) manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and running of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	3 0.36 Cubic metres			6 Per cubic metre	7
2	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm (Five centimetre to twenty centimetre) nominal size in recharge pit, in the required thickness and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	1.80 Cubic metres			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering plain cement concrete 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	2.16 Cubic metres			Per cubic metre	
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of materials within all leads, lifts and other incidentals.	238.08 Kilogram			Per kilo gram	
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge.	491.40 Kilo grams			Per kilo gram	
6	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge.	27.30 Square metres			Per square metre	
TOTAL :-						


 Executive Engineer,
 HP PWD, Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 96179.00
 EARNEST MONEY :- ₹ 1950.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Construction link road from Yol Dhaloon road to Dhaloon Society road in Distt. Kangra (H.P.).
 SUB HEAD :- Construction of steel grating at various RDs. (2017-307-121)

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering plain cement concrete 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and H.P.W.D technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	3.15 Cubic metres			Per cubic metre	
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of materials within all leads, lifts and other incidentals.	738.99 Kilogram			Per kilo gram	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagavan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99964.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Special repair of Govt. Senior Secondary School Serahana in Tehsil Nagrota Bagawan, Distt. Kangra (H.P.)

SUB-HEAD :- Providing and fixing prepainted sheet steel work etc; VKV/2018/1361

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 0.60mm (Zero point Sixty millimeters) thick prepainted sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimeters) diameter with prepainted limpet and rubber washers complete with all accessories as required including carriage of materials within all leads, lifts and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	31.69 Square metres			Per square metre	
2	Providing and fixing ridges or hips 60 cm(Sixty centimeters) over all in 0.63mm(Zero decimal six three millimeters) thick plain galvanized iron G.I. sheet fixed with galvanized iron J or L hooks, bolts and nuts 8mm(Light millimetres) diameters G.I. limpet and bitumen washers including carriage of materials within all leads, lifts and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	15.20 Running metres			Per running metre	
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including entire carriage of materials within all leads, lifts and other incidentals	495.02 Kilogram			Per Kilo-gram	
TOTAL :-						


 Executive Engineer,
 Medical College Division,
 H.P.P.W.D. Tanda.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 63660.00
 EARNEST MONEY :- ₹ 1300.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Annual repair and maintenance of Non-Residential Building at Dr. R.P. Govt. Medical College at Tanda in Distt. Kangra (I.P.) (Deposit work)
 SUB-HEAD :- Painting work in Old Sub-Division Building.

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2 Providing and applying J.K./Birla white cement based wall care putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete, as directed by the Engineer-In-charge, including carriage of materials within all leads, lifts and other incidentals.	3 199.99 Square metres	4	5	6 Per square metre	7
2	Wall painting (two coats) with plastic emulsion paint of approved brand and manufacture on un-decorated wall surface to give an even shade including thoroughly brushing the surface clean of all dirt grease, loose pieces of scale and sand papered smooth including applying of putty as required for making the surface complete as per direction of Engineer-In-Charge, including carriage of material within all leads, lifts and other incidentals.	608.63 Square metres			Per square metre	
3	Painting one or more coats (excluding priming coat) on previously painted steel and other metal surface with enamel paint other than white brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications drawing, design and as directed by the Engineer-in-charge.	132.50 Square metres			Per square metre	
TOTAL :-						


 Executive Engineer,
 H.P.P. W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99186.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : TWO MONTHS

NAME OF WORK :- Balance work of Dr. Bheem Rao Ambedkar Mahila Mandal Bhawan Ward No.-1 at Karahpura in Gram Panchayat Patiyalkar in N/Bagwan, Distt. Kangra (H.P.)

SUB-HEAD :- Balance work of Brick work, Wood work, Plastering etc; (Deposit Work) VKV/2017/1664

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
		3	4	5	6	7
1	Brick work with common burnt clay F.P.S. (Non modular) building bricks of class designation 7.5 (Seven point five) in super-structure upto all floor level in cement mortar 1:4 (One cement isto Four sand) and euring complete including carriage of material within all leads, lifts and other incidentals as per approved specifications, drawing, design and as directed by the Engineer-in-charge.	6.14 Cubic metres			Per cubic metre	
2	Providing and fixing Sal wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) as per Architectural drawing, design and specifications and the like floor etcetera including carriage of material within all leads, lifts and other incidentals and as directed by the Engineer-in-charge.	0.04 Square metres			Per square metre	
3	Providing and fixing 35 mm thick shutters panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	1.89 Square metres			Per square metre	
4	Providing and fixing 300x16mm (Three hundred into sixty millimetres) anodized aluminium sliding door bolts anodized transparent or dyed to required colour and shade with necessary screws etc. complete and as per direction of Engineer-In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	1 Number			Each	
5	Providing and fixing 250x10mm (Two hundred fifty into ten millimetres) anodized aluminium tower bolts (barrel type anodized transparent or dyed to required shade and colour with screws etc. complete and as per direction of Engineer-In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each	
6	Providing and fixing 125mm (One hundred twenty five millimetres) anodized aluminium handles anodized transparent or dyed to required shade and colour with screws etc. complete and as per direction of Engineer-In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each	
7	6mm (Six millimetres) thick cement plaster to ceiling/slab in cement mortar 1:3 (One cement : Three sand) upto all floor levels complete including carriage of material within all leads, lifts and other incidentals as per approved specifications, drawing, design and as directed by the Engineer-in-charge.	75.88 Square metres			Per square metre	
8	15mm (Fifteen millimetres) thick cement plasters in single coat on rough side of brick/concrete/stone walls for interior plastering upto all floor level including arises, internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:4 (One cement : Four sand) upto any height as directed by the Engineer-in-Charge, including entire carriage of materials within all leads, lifts and other incidentals.	155.00 Square metres			Per square metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 41618.00
 EARNEST MONEY :- ₹ 850.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Restoration of rain damages on link road Ramehar Tangroti Dhaloon Km 0/000 to 6/000 in Distt. Kangra (H.P.)
SUB-HEAD :- Construction of Breast wall at RD 4/105 to 4/108.80 (SDF/2024/1692).

S. No.	Description of items	Quantity	In fig.	Rate		Unit	Amount
					In words		
1	2	3	4	5	6	7	
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads. lifts and other incidentals.	3.86 Cubic meters			Per cubic metre		
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	10.22 Cubic metres			Per cubic metre		
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	2.00 Running metre			Per running metre		
TOTAL :-							


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99860.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : TWO MONTHS

NAME OF WORK :- Balance work of Dr. Bhoom Rao Ambedkar Mahila Mandal Bhawan Ward No.-1 at Karahpura in Gram Panchayat Patiyalkar in N/Bagwan, Distt. Kangra (H.P.)

SUB-HEAD :- Balance work of Plastering, painting and steel work etc; (Deposit Work) VKV/2017/1664

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	15mm (Fifteen millimetres) thick cement plasters in single coat on rough side of brick/concrete/stone walls for interior plastering upto all floor level including arises, internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:4 (One cement : Four sand) upto any height as directed by the Engineer-in-Charge, including entire carriage of materials within all leads, lifts and other incidentals.	55.03 Square metres			Per square metre	
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete and as per direction of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals.	295.02 Square metres			Per square metre	
3	Finishing walls with 100% (One hundred percent) Premium acrylic emulsion paint (Two or more coats) having VOC less than 50 gm/litre (Fifty grams per litre) and UV resistance as per IS 15489:2004, Alkali & fungal resistance. dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives New work applied @ 1.43 litre/ 10 sqm (One point forty three litre per ten square metre) over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm (Zero point ninety litre per ten square metre) upto all floor level complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge.	128.75 Square metres			Per square metre	
4	Wall painting Two or more coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour as directed by the Engineer-In-charge, including carriage of materials within all leads, lifts and other incidentals.	185.11 Square metres			Per square metre	
5	Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required and as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	13.22 Square metres			Per square metre	
6	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including entire carriage of materials within all leads, lifts and other incidentals	238.85 Kilogram			Per Kilo-gram	
TOTAL :-						


Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.