

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO:-PW/TD/CB/TA/NIT /2025- 26-

3826

Dated- 18-7-2025

To

The Executive Engineer (IT Cell)
Nigam Vihar, Shimla-2,

Subject:- Tender Notice.

Dear Sir,

Enclosed Please find herewith the notice work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP. Letter No. PBW (B) A (3) 1/2021 dated 03-.01.2025. As the work mentioned in the tender notice are urgent in nature and in public interest.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender and schedule of quantity.


Executive Engineer
Tanda Division
HP PWD Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, as called vide this office letter No.PW-TD-CB-TA 2025-26- 3796- 8825 dated 18/07/2025 are of urgent nature.


Executive Engineer
Tanda Division
HP PWD at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **28-07.2025** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **26.07.2025** up to **4:00 P.M** and the application for issue of tender form shall be received on **25.07.2025** up to **12:00 noon**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Special Repair of Govt. Degree College at Nagrota Bagwan in Distt. Kangra H P Deposit Work (SH: Construction of brick work and tiles flooring etc).	98531.00	2000.00	Two Months
2	Special Repair of Govt. Degree College at Nagrota Bagwan in Distt. Kangra H P Deposit Work (SH: Providing and fixing aluminium work, Plastering and sanitary installation etc).	99981.00	2000.00	Two Months
3	Annual repair and maintenance of Kangra Tanda road km 0/00 to 4/00 in Distt. Kangra HP (SH: Providing and laying patch work in at Rd 1/540 to 2/340)	98669.00	1970.00	Two Months
4	Special Repair of Govt. Degree College at Nagrota Bagwan in Distt. Kangra HP Deposit work (SH: Providing and Granite work etc).	99720.00	2000.00	Two Months
5	Annual repair and maintenance of Kangra Tanda road km 0/00 to 4/00 in Distt. Kangra HP (SH: Providing and laying patch work in at Rd 2/340 to 2/770).	98399.00	1970.00	Two months
6	Special Repair of Govt. Degree College at Nagrota Bagwan in Distt. Kangra HP Deposit work (SH: Providing and laying Granite work, Painting, water supply and sanitary installation etc).	94845.00	1900.00	Two Months
7	Annual repair and maintenance of Kangra Tanda road km 0/00 to 4/00 in Distt. Kangra HP (SH: Providing and laying patch work in at Rd 2/770 to 2/880).	99964.00	2000.00	Two months
8	Special Repair of Govt. Degree College at Nagrota Bagwan in Distt. Kangra HP Deposit work (SH: Construction of cement concrete work, Granite work and glass panes etc).	98599.00	2000.00	Two Months
9	Annual repair and maintenance of Kangra Tanda road km 0/00 to 4/00 in Distt. Kangra HP (SH: Providing and laying patch work in at Rd 2/880 to 3/290).	96870.00	1940.00	Two months
10	Special Repair of Govt. Degree College at Nagrota Bagwan in Distt. Kangra HP Deposit work (SH: Providing and fixing Water supply and sanitary installation etc).	73902.00	1500.00	Two Months

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender form.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2025-26- **3796-3825** Dated/ **18-7-2025**

Copy to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Director, Information & Publications Department, H.P. Shimla.
3. The Executive Engineer IT Cell Shimla HP PWD Shimla.
4. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
5. The Deputy Commissioner, Kangra at Dharamshala.
6. All the S.E.s/E.E.s under North Zone.
7. The Sub-Divisional Officer(C) Nagrota Bagwan.
8. All the Assistant Engineer under this Division.
9. The Drawing /Accounts Branch in this office.
10. Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99984.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Special repair of Govt. Degree College at Nagrota Bagwan in Distt Kangra (H.P.). Deposit Work.
 SUB-HEAD :- Providing and fixing aluminium work, Plastering and sanitary installation etc;

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2 Providing and fixing anodised/colour coated aluminium work (Shampion shade colour coated) shutters for door, windows, ventilators and partitions with extruded built up standard tubular and other sections of approved make conforming to IS 733 and IS 1285 anodised transparent or dyed to required shade according to IS 1868. (Minimum anodic coating of grade AC 15) fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rustfree, straight, mitred and jointed mechanically where ever required including cleast angle, aluminium, snap beading for glazing/ panelling C.P. brass/stainless steel screws for shutters of doors windows & ventilators including providing and fixing hinges/pivots and making provisions for fixing of fittings where ever required including the cost of PVC/neoprene gaskets as required (fittings and glazing/panelling shall be paid for separately) all complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals	3 57.00 Kilograms	4	5	6 Per kilo-gram	7
2	Providing and fixing anodised/colour coated aluminium work (Shampion shade colour coated) frames for door, windows, ventilators and partitions with extruded built up standard tubular and other sections of approved make conforming to IS 733 and IS 1285 anodised transparent or dyed to required shade according to IS 1868. (Minimum anodic coating of grade AC 15) fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rustfree, straight, mitred and jointed mechanically where ever required including cleast angle, aluminium, snap beading for glazing/ panelling C.P. brass/stainless steel screws for frame of doors windows & ventilators including providing and fixing hinges/pivots and making provisions for fixing of fittings where ever required including the cost of PVC/neoprene gaskets as required (fittings and glazing/panelling shall be paid for separately) all complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals	97.12 Kilograms			Per kilo-gram	
3	Providing and fixing 12mm (Twelve millimetres) thick prelaminated board both side bwp phenol bonded exterior/interior grade panelled shutters including bright finished/black enamelled iron butt hinges with necessary screws complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	3.33 Square metres			Per square metre	
4	15mm (Fifteen millimetres) thick cement plasters in single coat on rough side of brick/concrete/stone walls for interior plastering including arises, internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:4 (One cement : Four sand) upto floor all levels including carriage of material within all leads, lifts and other incidentals, as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	41.05 Square metres			Per square metre	
5	Providing and fixing for 22.22 mm outer dia piperequired Stainless Steel Fitting of press fit design of grade AISI 304 conforming to JWVA G116 standard with V-profile or M-profile and with O-ring sealing gasket of EPDM material of required dia complete and as directed by the Engineer- Incharge, including entire carriage of materials within all leads, lifts and other incidentals.	50 Numbers			Each	
6	Providing and fixing for 22.22 mm outer dia piperequired Stainless Steel Fitting of press fit design of grade AISI 304 conforming to JWVA G116 standard with V-profile or M-profile and with O-ring sealing gasket of EPDM material of required dia complete and as directed by the Engineer- Incharge, including entire carriage of materials within all leads, lifts and other incidentals.	15 Numbers			Each	
7	Providing and fixing 100mm (One hundred millimetre) to inlet and 75mm (Seventy five millimetre) outlet trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : complete including entire carriage of materials within all leads lifts and other incidentals.	4 Numbers			Each	
TOTAL :-						


 Executive Engineer,
 H P P. W. D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98599.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Special repair of Govt. Degree College at Nagrota Bagwan in Distt Kangra (H.P.), Deposit Work.
SUB-HEAD :- Construction of cement concrete work, Granite work and glass panes etc;

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (One cement : One and half coarse sand) : Three graded stone aggregate 20mm (Twenty millimetre) nominal size nominal size complete and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals .	4.91 Cubic metres			Per cubic metre	
2	Steel reinforcement for reinforced cement concrete work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more complete including carriage of materials within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge.	343.70 Kilogram			Per cubic metre	
3	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre-moulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade Area of slab over 0.50 sqm complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	8.40 Square metres			Per square metre	
4	Supplying and fixing plain glass 4mm (Four millimetres) thick glass panes with putty and nails including removal of broken glass panes wherever necessary complete and as directed by the Engineer- Incharge, including entire carriage of materials within all leads, lifts and other incidentals.	1.92 Square metres			Per square metre	
5	Providing and fixing For 22.22 mm outer dia x 20 mm nominal dia threaded required Stainless Steel Fitting of press fit design of grade AISI 304 conforming to JWWA G116 standard with V-profile or M-profile and with O-ring sealing gasket of EPDM material of required dia complete and as directed by the Engineer- Incharge, including entire carriage of materials within all leads, lifts and other incidentals.	8 Numbers			Each	
TOTAL :-						


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99720.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Special repair of Govt. Degree College at Nagrota Bagwan in Distt Kangra (H.P.). Deposit Work.
 SUB-HEAD :- Providing and laying Granite work etc;

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2 Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for Kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment. epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade Area of slab over 0.50 sqm complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	3 28.09 Square metres	4	5	6 Per square metre	7
TOTAL :-						



 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98531.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Special repair of Govt. Degree College at Nagrota Bagwan in Distt Kangra (H.P.). Deposit Work.
SUB-HEAD :- Construction of brick work and tiles flooring etc

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2 Second class brick masonry using common burnt clay building bricks in super-structure upto all floor level in cement mortar 1:6 (One cement: Six sand) and curing complete including carriage of material within all leads, lifts and other incidentals as per approved specifications, drawing, design and as directed by the Engineer-in-charge.	3 3.06 Cubic metres	4	5	6 Per cubic metre	7
2	Half class brick masonry using common burnt clay building bricks in super-structure upto all floor level in cement mortar 1:4 (One cement : Four sand) and curing complete including carriage of material within all leads, lifts and other incidentals as per approved specifications, drawing, design and as directed by the Engineer-in-charge.	7.20 Cubic metres			Per cubic metre	
3	Providing and fixing first class ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (One cement : Three coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm (Three point three kilogram per square metre) including pointing in white cement mixed with pigment of matching shade complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications, entire satisfaction and as directed by the Engineer-in-charge.	98.10 Square metres			Per square metre.	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 94845.00
 EARNEST MONEY :- ₹ 1900.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Special repair of Govt. Degree College at Nagrota Bagwan in Distt Kangra (H.P.). Deposit Work.
 SUB-HEAD :- Providing and laying Granite work, painting, Water supply and sanitary installation etc;

S. No.	Description of Items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2 Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade Area of slab over 0.50 sqm complete and as per direction of Engineer- In-charge, including carriage of materials within all leads, lifts and other incidentals.	3 10.42 Square metres	4	5	6 Per square metre	7
2	Providing and applying white cement based putty of Birla / JK average thickness 1mm (One millimetres) thick, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete upto all floor level complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge.	186.06 Square metres			Per square metre	
3	Distempering with oil bound washable distemper of approved brand and manufacture to give aneven shade: New work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	186.06 Cubic metres			Per cubic metre	
4	Providing and fixing 20 mm dia nominal bore G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. complete including carriage of material within all leads, lifts and other incidentals as per approved specifications, drawing, design and as directed by the Engineer-in-charge.	114.00 Running metre			Per running metre	
5	Providing and fixing For 22.22 mm outer dia x 20 mm nominal dia threaded required Stainless Steel Fitting of press fit design of grade AISI 304 conforming to JWWA G116 standard with V-profile or M-profile and with O-ring sealing gasket of EPDM material of required dia complete and as directed by the Engineer- In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	8 Numbers			Each	
6	Providing 100mm sand cast iron grating for gully, floor or Nahnri trap complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	5 Numbers			Each	
7	Providing 32mm dia PVC waste pipe for wash basin or sink including necessary PVC fitting complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 73902.00
 EARNEST MONEY :- ₹ 1500.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Special repair of Govt. Degree College at Nagrota Bagwan in Distt Kangra (H.P.). **Deposit Work.**
SUB-HEAD :- Providing and fixing Water supply and sanitary Installation etc;

S. No.	Description of items	Quantity	In fig	Rate		Unit	Amount
					In words		
1	2	3	4	5	6	7	
1	Providing and fixing For 22.22 mm outer dia pipe required Stainless Steel Fitting of press fit design of grade AISI 304 conforming to JWWA G116 standard with V-profile and with O-ring sealing gasket of EPDM material of required dia complete and as per direction of Engineer-Incharge, including carriage of materials within all leads, lifts and other incidentals	25 Numbers			Each		
2	Providing and fixing 15 mm (Fifteen millimetre) nominal bore brass bib cock of approved quality complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each		
3	Providing 15mm (Fifteen millimetres) dia long body brass bib tap (Superior or heavy type) Cera, Jaquar and Hindware complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each		
4	Providing and fixing 550x400mm (Five thousand fifty into four hundred millimetre) size vitreous China wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and marking good the same but excluding fittings complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each		
5	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings complete and as directed by the Engineer- Incharge, including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each		
6	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each		
7	providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each		
8	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each		
9	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each		
10	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan White solid plastic seat with lid complete and as per direction of Engineer-Incharge, including carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each		

11	Providing and fixing 15 mm nominal bore with 45 cm length unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour complete and as per direction of Engineer- In-charge, including carriage of materials within all leads, lifts and other incidentals.	7 Numbers			Each
12	Providing and fixing 15mm nominal bore C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 complete and as directed by the Engineer- In-charge, including entire carriage of materials within all leads, lifts and other incidentals.	9 Numbers			Each
13	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each
14	Providing and fixing PTMT towel rail 450 mm long towel rail with total length of 495 mm, 78 mm wide and effective height of 88 mm, weighing not less than 170 gms complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each
15	Providing and fixing PTMT Waste Coupling for wash basin and sink Waste coupling 38 mm dia of 83 mm length and 77mm breadth, weighing not less than 60 gms of approved quality and colour. complete and as per direction of Engineer- In-charge, including carriage of materials within all leads, lifts and other incidentals.	4 Numbers			Each
16	Providing and fixing Rectangular shape 1500x450 mm mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing complete and as directed by the Engineer- In-charge. including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each
17	Providing and fixing 15 mm nominal bore, 125 mm long foam flow, weighing not less than 120 gms PTMT pillar cock of approved quality and colour complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each
18	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	24.00 Running metres			Per running metre
19	Providing and fixing 110x110x110 mm on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion complete and as per direction of Engineer- In-charge, including carriage of materials within all leads, lifts and other incidentals.	4 Numbers			Each
20	Providing and fixing 110 mm bend on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion complete and as per direction of Engineer- In-charge, including carriage of materials within all leads, lifts and other incidentals.	4 Numbers			Each
TOTAL :-					


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 98669.00
EARNEST MONEY :- ₹ 1980.00
TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Annual repair and maintenance of Kangra Tanda road Km 0/000 to 4/000 in Distt Kangra (H.P.).
SUB HEAD: - Providing and laying patch work in Km 1/540 to 2/340.

Sr. No.	Description	Quantity	In fig.	Rate	Unit	Amount
			4	in words 5		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	332.22 Square meters			Per square metre	7
TOTAL: -						


Executive Engineer,
H.P.P.W.D Division,
Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 98399.00
 EARNEST MONEY :- ₹ 1970.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Annual repair and maintenance of Kangra Tanda road Km 0/000 to 4/000 in Distt Kangra (H.P.).
 SUB HEAD: - Providing and laying patch work in Km 2/340 to 2/770.

Sr. No.	Description	Quantity	In fig.	Rate	Unit	Amount
			4	in words 5		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	331.31 Square meters			6 Per square metre	7
TOTAL: -						


 Executive Engineer,
 H.P.P.W.D Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 99964.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Annual repair and maintenance of Kangra Tanda road Km 0/000 to 4/000 in Distt Kangra (H.P.).
 SUB HEAD: - Providing and laying patch work in Km 2/770 to 2/880.

Sr. No.	Description	Quantity	In fig.	Rate	Unit	Amount
			4	in words 5		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	336.58 Square meters			6 Per square metre	7
TOTAL:-						-


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 96870.00
 EARNEST MONEY :- ₹ 1940.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Annual repair and maintenance of Kangra Tanda road Km 0/000 to 4/000 in Distt Kangra (H.P.).
 SUB HEAD: - Providing and laying patch work in Km 2/880 to 3/290.

Sr. No.	Description	Quantity	In fig.	Rate		Unit	Amount
					in words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	326.16 Square meters	4		5	6 Per square metre	7
TOTAL: -							


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagyan.