Office of

EXECUTIVE ENGINEER TAUNI DEVI DIVISION
H.P. Public Works Department, TAUNI DEVI 177023
Telephone. 01972-278422, e.mail: ee-tou-hp@nic.in

No. PW/TDD/GA/Tender/2025-26 4708-57 Dated: -21-07-2025

To

The Executive Engineer(IT Cell),
Nigam Vihar HP Shimla-171002.

Subject: - Publication of Tender Notice

Enclosed please find herewith the tender notice of various works as given in the Notice Inviting Tender . As per Notification Pr.Secy.(PW) to the Govt of Himachal Pradesh Letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th Jyly 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website

ECL: -Notice Inviting Tender/ Scheduled of Quantity and Certificate.

Yours faithfully,

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Copy forwarded to the following for information: -

1. The Engineer-in-Chief HPPWD., Shimla
2. The Chief Engineer (HZ), HP.PWD, Hamirpur
3. The Deputy Commissioner Hamirpur
4. The Superintending Engineer, 8th Circle HP.PWD, Hamirpur
5. The B.D.O Tauni Devi
6. All the Assistant Engineer working in this Division.
7. Notice Board.
8. AB & DB.

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Scanned with CamScanner

Office of
EXECUTIVE ENGINEER TAUNI DEVI DIVISION
H.P. Public Works Department, TAUNI DEVI 177023
Telephone. 01972-278422, e.mail: ee-tou-hp@nic.in

CERTIFICATE

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/ emergency in calling these tender without press vide this office letter No. No. PW/TDD/GA/Tender/2025-26 4708-57 dated 21-07-2025

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Scanned with CamScanner

Office of
EXECUTIVE ENGINEER TAUNI DEVI DIVISION
H.P. Public Works Department, TAUNI DEVI 177023
Telephone. 01972-278422, e.mail: ee-tou-hp@gov.in

Tender Notice

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Tauni Devi Division, H.P. PWD, Tauni Devi on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/firms enlisted in HP PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the HP General Sales Tax Act 1968 so as to reach in his office on or before **28.07.2025 up to 10.30 AM** And the same shall be opened on the same day at **11.00 AM** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) up to **26.07.2025** up **to 1.00 PM** and the application for issue of tender form shall be received up **26.07.2025 up to 5.00 PM** The earnest money in the shape of NSC/Time deposit account/saving account of the post office in HP duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S.No	Name of work	Estimated cost	Earnest money	Time
1	C/o link road Shiv Mandir towards Anil Kumar House in Village Bhatiana Km. 0/0 to 0/975 (SH:- C/o 5/7mtr,. Wide formation cutting at RD 0/500 to 0/561.75) Deposit work VKVMY MLALAD	1,99,966.00	4000.00	Two Months.
2	Construction of Additional room at Govt. High School Kanerar Tehsil Sujanpur Distt. Hamirpur. (SH:- Providing plaster interior side and exterior side along with painting on both side and providing kota stone, stone flooring and providing and fixing wire gauge door and other misc work). (Deposit work VKVMY MLALAD).	2,43,471.00	4900.00	Two Months.
3	Repair of toilet block in Govt. Senior Secondary School Chabutra Tehsil Sujanpur Distt. Hamirpur. (SH:- C/O septic tank for 50 users, soakpit). (Deposit work VKVMY MLALAD).	2,75,248.00	5500.00	Two Months.
4	C/O link road to Harizan Basti Chattruru km. 0/0 to 1/00.(SH:- C/O 5/7mtr. Wide formation cutting at RD. 0/00 to 0/034.70). (Deposit work VKVMY MLALAD).	1,90,107.00	4000.00	Two Months
5	C/O Danga (R/Wall) near house of Ramesh Chand village Rangar on Patlander Rangar road km. 0/0 to 6/00.(SH:- C/O R/Wall near above mentioned house at RD. 5/900 to 5/907) (Deposit work VKVMY MLALAD).	1,18,532.00	2400.00	Two Months.
6	Construction of link road from Kakriar to Kotlu km. 0/00 to 2/00. (SH:- C/O formation cutting and Hume pipe culvert at RD. 0/150). (Deposit work VKVMY MLALAD).	2,83,610.00	5700.00	Two Months.

Certifed that above works are of urgent nature and tenders are being called in exigency of works and in public interest.

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:-C/O link road Shiv Mandir towards Anil Kumar house in village Bhatiana km. 0/0 to 0/975.(SH:- C/O 5/7mtr. Wide formaction cutting at RD. 0/500 to 0/561.75). (Deposit work VKVMY MLALAD).

Estimated Cost:-	Rs. 199966.00
Earnest Money:-	Rs. 4000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical menus including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302,1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e.63.76/-cubic metre shall be made from the contractor @ Rs. 300/-(three hundred only per cubic metre) amounting to Rs. 19,128/- only.	562.62	355.42	Rupees three hundred fifty five and paise forty two only	Per cubic metre	199966.00
					Total	199966.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No 17 for the year 2025-26 duly approved for Rs. 1,99,966/-(Ninety three thousand twenty four) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Construction of Additional Room at Govt High School Kanerar Tehsil Sujanpur Distt. Hamirpur) (SH:- Providing plaster interior side and exterior side along with painting on both side and providing Kota stone , stone flooring and providing and fixing wire gauge door and other misc work)(Under VKVNY (MLALAD)(Deposit Work)	Estimated Cost:-	Rs.243471.00
	Earnest Money:-	Rs.4900.00
	Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	15mm(fifteen millimetre) cement lime plaster in single coat, on the rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises,internal rounded angles,chamfers and/or rounded angles not exceeding 80mm(eighteen millimetre) in girth and finished even and smooth in cement mortar 1:4(one cement : four sand)as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	250.45	196.45	Rupees one hundred ninety six and paise forty five only.	Per square metre	49201.00
2.00	6mm(six millimetre) cement plaster of mix 1:3(one cement : three sand)as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	76.86	125.00	Rupees one hundred ninety six and paise forty five only.	Per square metre	9608.00
3.00	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima Asian Paints) or its equarlied on undecorated wall surfaces (two coats) to give an even shade and final finish after throughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	125.23	140.00	Rupees one hundred forty and paise zero only.	Per square metre	17532.00
4.00	Finishing walls with Royal luxary emulsion paint(two coats) of required shade in intrior walls as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	202.08	100.00	Rupees one hundred and paise zero only.	Per square metre	20208.00
5.00	Kota stone slab flooring over 20 mm(twenty millimetre) (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (one cement : four coarse sand) :25mm(twenty five millimetre) thick upto all floor level as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royality, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	67.09	1215.70	Rupees one thousand two hundred fifteen and paise seventy only.	Per square metre	81561.00
6.00	Finishing with Deluxe Multi surface paint of **(Nerolac/Asisan/Dulux/Berger)**system for interiors and exteriors using Primer as per manufacturers specifications Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm(zero point ninety litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm(zero point seventy five litre per ten square metre) of approved brand and manufacture as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the	23.76	120.00	Rupees one hundred twenty and paise zero only.	Per square metre	2851.00

Scanned with CamScanner

7.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm (twenty millimetre)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	5.32	4800.00	Rupees four thousand eight hundred and paise zero only.	Per cubic metre	25531.00
8.00	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm(one point four millimetre) in both directions with wire of dia 0.63 mm (zero point sixty three millimetre), for doors, windows and clerestory windows with hinges and necessary screws with ISI marked M.S. pressed butt hinges bright finished of required size 35 mm(thirty five millimetre) thick shutters Second class deodar woood as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	7.38	3669.30	Rupees three thousand six hundred sixty nine and paise thirty only.	Per square metre	27079.00
9.00	Providing and fixing stainless steel door bolts, ISI marked transparent or dyed to required colour or shade, with nuts and screws etc. complete. 300x16mm (three hundred into sixteen millimetre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	4.00	385.00	Rupees three hundred eighty five and paise zero only.	Each	1540.00
10.00	Providing and fixing 150 mm(one hundred fifty millimetre) stainless steel, handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	8.00	65.00	Rupees sixty five and paise zero only.	Each	520.00
11.00	Structural steel work riveted, bolted or welded in built up sections(**TATA/SAIL Make**), trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint upto all floor level in all heights in trusses, purlins, rafters, grating, framed guard bars all complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royality, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	80.00	98.00	Rupees ninety eight and paise zero only.	Per kilogram	7840.00
					Total	**243471.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No.....21..... for the year 2025-26 duly approved for Rs. 2,43,471/-(Rupees two lacs forty three thousand four hundred seventy one only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Repair of toilet block in Govt. Senior Secondary School Chabutra Tehsil Sujanpur Distt. Hamirpur. (SH:- C/O septic tank for 50 users, soakpit).(Deposit work VKVMY MLALAD).

Estimated Cost:- Rs. 275248.00
Earnest Money:- Rs. 5500.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	76.87	290.00	Rupees two hundred ninety only	Per cubic metre	22292.00
2	Providing and laying cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement: four sand: eight graded stone aggregated 40mm (forty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	6.27	4600.00	Rupees four thousand six hundred only	Per Cubic metre	28842.00
3	Centering and shuttering including strutting, propping etc and removal of form work for as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.					
3.01	Vertical surface such as wall (any thickness) and the like including attached pilasters, buttersses plinth and string courses and the like.	3.84	411.15	Rupees four hundred eleven andpaise fifteen only	Per square metre	1579.00
3.02	Flat surfaces such as soffits of suspended floors, roofs, landings and the like floors etc. upto any thickness.	12.00	468.30	Rupees four hundred sixty eight and paise thirty only	Per square metre	5620.00
4	Coursed rubble masonry (second sort) with hard stone in foundation and plinth with cement mortar 1:6 (one cement: six course sand),as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	24.85	5360.00	Rupees five thousand three hundred sixty only	Per cubic metre	133196.00
5	Providing and laying in position machine batched and machine mixed design mix providing M-25 grade concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS 9103 to accelerate, ratard setting of concrete improve workability without impaining strength and durability as per direcion of Engineer-in-Charge Note - (cement content considered in M-25 is @ 330kg/cum)(three hundred thirty kilograme per cubic metre) All work upto any level,including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	3.48	7200.00	Rupees seven thousand two hundred only	Per cubic metre	25056.00
6	Steel reinforcement for RCC work including straightening, cutting, bending, placing in position and hinding all complete upto anly level thermo mechanically treated bars of grade Fe-500D or more,as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	417.60	95.70	Rupees ninety five and paise seventy only	Per kilogram	39964.00
7	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 110mm (one hundred ten millimeters) dia,as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	50.00	290.00	Rupees two hundred ninety only	Per running metre	14500.00
8	Providing and fixing 110mm (one hundred ten millimetre) dia PVC single equal branch with oval access door, ISI marked insertion rubber washer 3mm (three millimeter) thick bolts and nuts complete including fixing with approved adhesive etc completed as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	5.00	247.50	Rupees two hundred forty seven and paise fifty only	Each	1238.00
9	Providing and fixing 110mm (one hundred ten millimetre) dia PVC collar ISU marked including fixing with approved adhesive tec. Complete as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	2.00	180.65	Rupees one hundred eighty and paise sixty five only	Each	361.00
4	Supplying and fixing C.I. cover without frame for manholes 455x610mm (four hundred fifty five into six hundred ten millimeter) rectangular C.I. cover (light duty) the weight of the cover to be not less than 23 Kg (twenty three kilogram) as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	2.00	1300.00	Rupees one thousand three hundred only	Each	2600.00
					Total,	275248.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 22 for the year 2024-25 duly approved for Rs.2,75,248/- (Two lac. seventy five thousand two hundred forty eight) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Ta[illegible]

Scanned with CamScanner

Scanned with CamScanner

4

Draft Schedule of Quantity

NAME OF WORK:- C/O link road to Harizan Basti Chattruru km. 0/0 to 1/00.(SH:- C/O 5/7mtr. Wide formation cutting at RD. 0/00 to 0/034.70). (Deposit work VKVMY MLALAD).

Estimated Cost:-	**Rs. 190107.00**
Earnest Money:-	**Rs. 4000.00**
Time:-	**Two Months**

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical menus including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302,1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e.60.62/-cubic metre shall be made from the contractor @ Rs. 300/-(three hundred only per cubic metre) amounting to Rs. 18,186/- only.	534.88	355.42	Rupees three hundred fifty five and paise forty two only	Per cubic metre	190107.00
					Total	**190107.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No 23 for the year 2025-26 duly approved for Rs 1,90,107/-(One lac. ninety thousand one hundred seven) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Draft Schedule of Quantity

NAME OF WORK:- C/O Danga (R/Wall) nearr house of Ramesh Chand village Rangar on Patlander Rangar road km. 0/0 to 6/00.(SH:- C/O R/Wall near above mentioned house at RD. 5/900 to 5/907) (Deposit work VKVMY MLALAD).

Estimated Cost:-	Rs. 118532.00
Earnest Money:-	Rs. 2400.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	12.42	290.00	Rupees two hundred ninety only.	Per cubic metre	3602.00
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size). as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	26.89	4213.85	Rupees four thousand two hundred thirteen and paise eighty five only	Per Cubic metre	113310.00
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	6.00	270.00	Rupees two hundred seventy eight only	Each.	1620.00
					Total	**118532.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No....18..... for the year 2025-26 duly approved for Rs.1,18,532/-(One lac. eighteen thousand five hundred thirty two) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Construction of link road from Kakriar to Kotlu Km 0/00 to 2/00. (SH:- Construction of F/C & Hume pipe culvert at RD 0/150) (Deposit Work) (Under VKVNY) (MLALAD)

Estimated Cost:-	**Rs.283610.00**
Earnest Money:-	**Rs.5700.00**
Time:-	**Two Months**

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical menus including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302,1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts.	1077.93	184.20	Rupees one hundred eighty four and paise twenty only.	Per cubic metre	198555.00
2.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	21.12	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	6128.00
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : four coarse sand) : eight graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	1.45	4600.00	Rupees four thousand six hundred and paise zero only.	Per cubic metre	6670.00
4.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm (twenty millimetre)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	8.93	4900.00	Rupees four thousand nine hundred and paise zero only.	Per cubic metre	43757.00

Scanned with CamScanner

5.00	Providing and laying non-pressure NP2 class (light duty) reinforced cement concrete pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement : fine sand) including testing of joints etc. complete 900 mm(nine hundred millimetre) dia. reinforced cement concrete pipe as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	7.50	3800.00	Rupees three thousand eight hundred and paise zero only.	Per running metre	28500.00
					Total	**283610.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 9 for the year 2025-26 duly approved for Rs.2,83,610/-(Rupees two lacs eighty three thousand six hundred ten only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner