Himachal Pradesh
Public Works Department

NO/PW/TLD/Tender/2025:- 2726-35 Dated:- 16-07-2025

To

Executive Engineer IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject:- Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of HP letter No. PBW (B) 1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA: - NIT.

Executive Engineer,
Thalout Division, HPPWD,
Thalout.

Copy is forwarded to Superintending Engineer, 1st Circle, HPPWD Mandi for information please.

Copy to All the Assistant Engineers working under this Division.

Copy to AB/DB in this office.
Copy to Notice board.

Executive Engineer,
Thalout Division, HPPWD,
Thalout.

Scanned with CamScanner

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER "

Sealed item rate tender on form No. 6&8 for the following works detailed in the table below hereby invited by the Executive Engineer, Thalout Division, HPPWD, Thalout on behalf of Governor of Himachal Pradesh from the eligible contractors of appropriate Class registered in HPPWD as per revised enlistment rule so as to reach in his office on 28.07.2025 at 11.00 A.M. The tenders shall be opened on the same date at 11.30 A.M. in the presence of intending contractors or their authorized representative who wish to be present. The request for issuing tenders form along with earnest money must reach in his office up to 3.00 P.M. on 25.07.2025 and that tender documents can be had from his office on cash payment noted against each (Non-Refundable) on 26.07.2025 up to 5.00 P.M on any working day. Notice Inviting Tender and other specification and conditions of the tender can be seen by the contractor in the office of the Executive Engineer, Thalout Division, HPPWD, Thalout during office hour on any working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Cost of form	Time Period	Form No.	Eligibility of Contractors
1	Construction of Hanogi to Bandhi road km 0/0 to 15/0 (SH- C/O R/wall at RD 11/655.50 to 11/657).	99778	2,000	Rs. 350/-	One month	6&8	Class D enlisted in HPPWD
2	Removal of debries from GSSS Kholanal Tehsil Kholanal Tehsil Balichowki Distt. Mandi HP (SH- Removal of land slides, slips/boulders, muck/boulders, muck debries etc.) Job No.I	96905	2,000	Rs. 350/-	One month	6&8	-do-
3	C/O Pipludhar to Mata Shri Baglamukhi road km 0/0 to 2/0 (SH- C/O R/walls/Dry edging in stone masonery in various RDs between 1/714 to 1/724).	98502	2,000	Rs. 350/-	One month	6&8	-do-
4	RRD on various roads of Nagwain Section under Panarsa S/Divn (SH- Hiring of execvator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain section).	99600	2000	Rs. 350/-	One month	6&8	-do-
5	RRD on various roads of Panarsa S/Divn (SH- Hiring of excavator cum loader for removal of slips/clearance of berms, derbies etc. at various RDs under Nagwain Section).	99600	2,000	Rs. 350/-	One month	6&8	-do-
6	RRD on various roads of Panarsa S/Divn (SH- Hiring of excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Nagwain section).	99600	2,000	Rs. 350/-	One month	6&8	-do-
7	RRD on various roads of Panarsa S/Divn (SH— Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Nagwain section).	99600	2,000	Rs. 350/-	One month	6&8	-do-
8	RRD on various roads of Balichowki S/Divn (SH- Hiring of Excavator cum laoder for removal of slips/clearance of berms, debries etc. at various RDs under Balcihowki Section).	99600	2,000	Rs. 350/-	One month	6&8	-do-
9	RRD on various roads of Balichowki S/Divn (SH- Hiring of Excavator cum laoder for removal of slips/clearance of berms, debries etc. at various RDs under Panjain Section).	99600	2,000	Rs. 350/-	One month	6&8	-do-
10	C/O Upper Karthach to Lower Karthach road km 0/0 to 0/465 (SH- C/O wire crate in km 0/330 to 0/340).	77004	2,000	Rs. 350/-	One month	6&8	-do-
11	RRD on various roads of Balichowki S/Divn (SH- Hiring of Excavator cum laoder for removal of slips/clearance of berms, debries etc. at various RDs under Panjain Section).	99600	2,000	Rs. 350/-	One month	6&8	-do-
12	RRD on Shalla Nallah Shara Odidhar Dhraunli road km 0/0 to 8/0 (SH- Hiring of excavator cum laoder for removal of slips/debries/muck etc. at RD 0/0 to 4/0).	99600	2,000	Rs. 350/-	One month	6&8	-do-
13	RRD on Shalari Nallah to Mani road km 0/0 to 3/0 (SH- Removal of land slide, slips/boulders,muck debries etc at various RDs) DC Deposit	99211	2,000	Rs. 350/-	One month	6&8	-do-
14	Construcrtion of Hanogi to Bandhi road km 0/0 to 15/0 (SH- C/O R/wall at RD 11/657 to 11/660).	99905	2,000	Rs. 350/-	One month	6&8	-do-
15	RRD on Thatta to Rangcha road km 0/0 to 3/500 (SH- Removal of slips/boulders, muck debries etc. at	99462	2,000	Rs. 350/-	One month	6&8	-do-

Scanned with CamScanner

	various RDs).						
16	RRD on Thalout Panjain Thachi Shetadhar road km 0/0 to 40/0 (SH- Removal of slips/bouldres, muck debries etc. at RD 30/40).	99211	2,000	Rs. 350/-	One month	6&8	-do-
17	Maintenance of Pandoh Takoli Kullu by Pass road km 222/700 to 227/500 (SH- C/O crated R/wall at RD 227/455 to 227/459).	99138	2,000	Rs. 350/-	One month	6&8	-do-
18	RRD on road from Bali to Thachi km 0/0 to 25/0 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at RD 0/0 to 8/0).	99600	2,000	Rs. 350/-	One month	6&8	-do-
19	RRD on Shalla Nallah Shara Odidhar Dhraunli road km 0/0 to 9/0 (SH- Hiring of excavator cum laoder for removal of slips/debries/muck etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
20	RRD on road from Sarali to Dobha road km 0/0 to 5/0 (SH- Hiring of Excavotor cum loader for removal of slips/clearance of berms, debries etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
21	RRD on road from Thachi to Bijhar km 0/0 to 6/0 (SH- Hiring of excavator cum loader for removal of slips/clearance of berms, debries etc. at RD 0/0 to 3/0).	99600	2,000	Rs. 350/-	One month	6&8	-do-
22	RRD on road from Thalout Panjain Thachi Shetadhar km 0/0 to 39/360 (SH- Hiring of excavator cum laoder for removal of slips/clearance of berms, debries etc. at RD 30/0 to 39/390).	99600	2,000	Rs. 350/-	One month	6&8	-do-
23	Maintenance of Pandoh Takoli Kullu by Pass road km 222/700 to 227/500 (SH- C/O crated R/wall at RD 227/459 to 227/463).	99106	2,000	Rs. 350/-	One month	6&8	-do-

TERMS & CONDITIONS: -

1. The Tender form will not be issued to those contractors whose performance is not found satisfactory.
2. The Contractor whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to complete in tendering for four months.
3. The Contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only upto completion of work Satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.

4 The rates beyond the limit over +5% will be rejected besides this the Additional Performance security will have to borne @ 20 % & 30 % for unbalanced bid in case the rates is lower than 10 % but upto 20 % & lower than 20 % upto 30 % respectively. The tender will be accepted beyond the limit of -30 % also.

Executive Engineer,
Thalout Division,
HP.PWD Thalout

NO/PW/TLD/Tender/2025:- 2716-25 Dated: - 16.07.2025

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP.
3. The Sub Divisional Officer Balichowki, Distt. Mandi HP.
4. The Chief Engineer, (MZ) HPPWD Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD Mandi HP.
6. The Distt. Panchayat Officer Mandi HP.
7. All AEs under this Division.
8. The President of Contractor's Association.
9. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.

Executive Engineer,
Thalout Division,
HP.PWD Thalout.

Scanned with CamScanner

Certificate

Certified that the tender called vide this office letter NO. PW/TLD/Tender/2025- 2716-25 dated 16.07.2025 is emergent nature and in Public interest.

Executive Engineer,
Thalout Division, HPPWD,
Thalout.

Scanned with CamScanner

(D)

SCHEDULE OF QUANTITY

Name of work:- Construction of Hanogi to Bandhi road Km 0/00 to 15/00 (SH:- C/o R/wall at RD. 11/655.50 to 11/657).

Estimated Cost:-99778.00
Earnest Money :-2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	12.50	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	4978
2	Providing and laying dowel bar in foundation in hard rock including making holes for dowel bar and fixing 25mm dia for steel in cement slurry with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	3.00	794.55	Rs. Seven hundred ninety four and paise fifty five only	Each	2384
3	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty milimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	5.50	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	26904
4	Providing weepholes in brick masonary/stone masonary /plain reinfoirced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	2.00	391.20	Rs.Three hundred ninety one and paise Twenty only	Each	782
5	Providing and laying of Boulder upron laid in wire crates with 4 mm (four milimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred milimetre) mesh (woven) diagonally) including 10 (Ten persant) persent extra for laps and joints laid with stones boulders weighting not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	19.50	3254.70	Rs.Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	63467.00
6	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	1.00	1263.40	Rs.One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	1263
	Total					**99778.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout

Scanned with CamScanner

(2)

SCHEDULE OF QUANTITY

Name of work:- Removal of debries from GSSS Kholanal Tehsil Balichowki Distt Mandi H.P. (SH:- Removal of land slides, slips/boulders, muck debries etc.) Job No-I

Estimated Cost:- 96905.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in all kinds of soli in hilly area including ordinary rock not requiring blasting and boulders on rocky portion of slips (where blasting is required) by mechnical means including cutting and trimming of slops and disposal of cut material as per technical specification clause 302.3.3 including carriage of material and other incidentials with in all leads, lifts and as per the direction of the Engineer-in Charge.	774.62	125.10	Rs.One hundred twenty five and paise Ten only	Per cubic metre	96905.00
					Total	**96905.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division
HP PWD Thalout.

Scanned with CamScanner

(3)

SCHEDULE OF QUANTITY

Name of work:- C/o Pipludhar to Mata Shri Baglamukhi road Km 0/00 to 2/00 (SH: - C/o R/walls / Dry edging in stone masonery in various RDs between 1/714 to 1/724).

Estimated Cost:- 98502.00
Earnest Money : 2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawiing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with all kind of soil upto any depth including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	12.92	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	1811.00
2	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	8.03	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	3198
3	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub stuctur and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	21.66	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	81251.00
4	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	9.69	1263.40	Rs.One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	12242
	Total					**98502.00**
	Rate quoted by contractor +/-		Percent			
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout.

Scanned with CamScanner

(4)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Nagwain section under Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout

Scanned with CamScanner

5

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout

Scanned with CamScanner

(6)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(7)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout.

Scanned with CamScanner

(8)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Balichowki Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Balichowki Section).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(9)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Balichowki Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panjain Section).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms.Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

(10)

SCHEDULE OF QUANTITY

Name of work:- C/O Upper Karthach to Lower Karthach road km 0/0 to 0/465 (SH: - C/O wire crate in km 0/330 to 0/340).

Estimated Cost: 77004.00
Earnest Money :- 2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated ssuitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	5.18	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	2063.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 persent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	24.19	3098.00	Rs.Three thousand ninty eight and paise zero only	Per Cubic Metre	74941.00
	Total					**77004.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division
HP,PWD,Thalout

Scanned with CamScanner

(11)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Balichowki Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panjain Section).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

(12)

SCHEDULE OF QUANTITY

Name of work:- RRD on Shalla Nallah Shara Odidhar Dhraunli road km 0/0 to 8/00 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 0/0 to 4/00).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division
HP PWD Thalout.

Scanned with CamScanner

(1)

SCHEDULE OF QUANTITY

Name of work :- RRD on Shalari Nallah to Mani road km 0/0 to 3/0 Km. Removal of land slide, slips/boulders, muck debries etc. at various RDs) EPC (in Rs.+/-)

Estimated Cost : 99211.00
Earnest Money : 2000.00
Time : One Month

S. No.	Description of Item	Qty.	Rate in Figure	Rate in Words	Unit	Amount
1	Removal of land slide in all kinds of soil in hilly area including ordinary rock not requiring blasting and boulders or rocky portion of slope (where blasting is required) by mechanical means including cutting and trimming of slope and disposal of cut material as per technical specification clause 302.1.3 including carriage of material and other incidentals with in all leads, lifts and as per the direction of the Engineer in Charge.	792.00	125.10	Rs One hundred twenty five and paise Ten only	Per cubic metre	99211.00
					Total	99211.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer
Thatrot Division
HP PWD Thatrot

Scanned with CamScanner

(14)

SCHEDULE OF QUANTITY

Name of work:- Construction of Hanogi to Bandhi road Km 0/00 to 15/00 (SH:- C/o R/wall at RD. 11/657 to 11/660).

Estimated Cost:-99905.00
Earnest Money :-2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	12.50	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	4978
2	Providing and laying dowel bar in foundation in hard rock including making holes for dowel bar and fixing 25mm dia for steel in cement slurry with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	3.00	794.55	Rs. Seven hundred ninety four and paise fifty five only	Each	2384
3	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty milimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	5.50	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	26904
4	Providing weepholes in brick masonary/stone masonary /plain reinfoirced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	2.00	391.20	Rs.Three hundred ninety one and paise Twenty only	Each	782
5	Providing and laying of Boulder upron laid in wire crates with 4 mm (four milimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred milimetre) mesh (woven) diagonally) including 10 (Ten persant) persent extra for laps and joints laid with stones boulders weighting not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	19.50	3254.70	Rs.Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	63467.00
6	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	1.10	1263.40	Rs.One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	1390
	Total					**99905.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout.

Scanned with CamScanner

(15)

SCHEDULE OF QUANTITY

Name of work:- RRD on Thatta to Rangcha road km 0/0 to 3/500 (SH:- Removal of slips/boulders, muck debries etc. at various RDs)	Estimated Cost:- 99462.00
	Earnest Money:-2000.00
	Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in all kinds of soli in hilly area including ordinary rock not requiring blasting and boulders on rocky portion of slips (where blasting is required) by mechnical means including cutting and trimming of slops and disposal of cut material as per technical specification clause 302.3.3 including carriage of material and other incidentials with in all leads, lifts and as per the direction of the Engineer-in Charge.	795.06	125.10	Rs.One hundred twenty five and paise Ten only	Per cubic metre	99462.00
					Total	99462.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout.

Scanned with CamScanner

(16)

SCHEDULE OF QUANTITY						
Name of work:- RRD on Thalout Panjain Thachi Shetadhar road km 0/0 to 40/0 (SH:- Removal of slips/boulders, muck debries etc. at RD 30/0 to 40/0)				**Estimated Cost:- 99211.00**		
				Earnest Money:-2000.00		
				Time:- One Month		
S. No.	**Description of item**	**Qty.**	**Rate in**		**Unit**	**Amount**
			Figure	**Words**		
1	Removal of land slide in all kinds of soli in hilly area including ordinary rock not requiring blasting and boulders on rocky portion of slips (where blasting is required) by mechnical means including cutting and trimming of slops and disposal of cut material as per technical specification clause 302.3.3 including carriage of material and other incidentials with in all leads, lifts and as per the direction of the Engineer-in Charge.	793.05	125.10	Rs.One hundred twenty five and paise Ten only	Per cubic metre	99211.00
					Total	**99211.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(17)

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/500 (SH: - C/O crated R/wall at RD 227/455 to 227/459)

Estimated Cost: 99138.00
Earnest Money :- 2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing and laying of Boulder upron laid in wire crates with 4 mm (four milimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred milimetre) mesh (woven) diagonally) including 10 (Ten persant) persent extra for laps and joints laid with stones boulders weighting not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	30.46	3254.70	Rs.Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	99138.00
	Total in figures					**99138.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division
HP,PWD,Thalout

Scanned with CamScanner

(15)

SCHEDULE OF QUANTITY

Name of work:- RRD on road from Bali to Thachi Km 0/000 to 25/000 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at RD 8/000 to 16/000). 0/0 To 8/00

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout.

Scanned with CamScanner

(19)

SCHEDULE OF QUANTITY

Name of work:- R.R.D. on Shalla Nallah Shara Odidhar Dhraunli Bharshi road km 0/0 to 9/00 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(20)

SCHEDULE OF QUANTITY

Name of work:- RRD on road from Sarali to Dobha road Km 0/000 to 5/000. (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(21)

SCHEDULE OF QUANTITY

Name of work:- RRD on road from Thachi to Bijhar Km 0/000 to 6/000 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at RD 0/000 to 3/000).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout

Scanned with CamScanner

22

SCHEDULE OF QUANTITY

Name of work:- RRD on road from Thalout Panjain Thachi Shettadhar Km 0/000 to 39/360 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at RD 30/000 to 39/390).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout.

Scanned with CamScanner

23

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/500 (SH: - C/O crated R/wall at RD 227/459 to 227/463)

Estimated Cost: 99106.00
Earnest Money :- 2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing and laying of Boulder upron laid in wire crates with 4 mm (four milimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred milimetre) mesh (woven) diagonally) including 10 (Ten persant) persent extra for laps and joints laid with stones boulders weighting not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	30.45	3254.70	Rs.Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	99106.00
	Total in figures					**99106.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout

Scanned with CamScanner