Himachal Pradesh
Public Works Department

NO/PW/TLD/Tender/2025:- 2944-53 Dated:- 22/07/25

To

Executive Engineer IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject:- Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of HP letter No. PBW (B) 1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA: - NIT.

Executive Engineer,
Thalout Division, HPPWD,
Thalout.

Copy is forwarded to Superintending Engineer, 1st Circle, HPPWD Mandi for information please.

Copy to All the Assistant Engineers working under this Division.

Copy to AB/DB in this office.
Copy to Notice board.

Executive Engineer,
Thalout Division, HPPWD,
Thalout.

Scanned with CamScanner

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER "

Sealed item rate tender on form No. 6&8 for the following works detailed in the table below hereby invited by the Executive Engineer, Thalout Division, HPPWD, Thalout on behalf of Governor of Himachal Pradesh from the eligible contractors of appropriate Class registered in HPPWD as per revised enlistment rule so as to reach in his office on 06.08.2025 at 11.00 A.M. The tenders shall be opened on the same date at 11.30 A.M. in the presence of intending contractors or their authorized representative who wish to be present. The request for issuing tenders form along with earnest money must reach in his office up to 3.00 P.M. on 04.08.2025 and that tender documents can be had from his office on cash payment noted against each (Non-Refundable) on 05.08.2025 up to 5.00 P.M on any working day. Notice Inviting Tender and other specification and conditions of the tender can be seen by the contractor in the office of the Executive Engineer, Thalout Division, HPPWD, Thalout during office hour on any working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Cost of form	Time Period	Form No.	Eligibility of Contractors
1	RRD on various roads of Pandoh Sub Division (SH- Hiring of Excavator cum loader for removal of slips clearance of berms, debries etc. at various RDs under Pandoh Section-II).	99600	2,000	Rs. 350/-	One month	6&8	Class D enlisted in HPPWD
2	C/O road from Nauna to Sudharani km 0/0 to 14/0 (SH- C/O Toe wall for existing R/wall at RD 12/728.30 to 12/731.05)	99909	2,000	Rs. 350/-	One month	6&8	-do-
3	C/O Stage and Boundry wall of GSSS Ghaniar Tehsil Balichowki Distt. Mandi HP (SH- Providing and laying CC flooring).	99979	2,000	Rs. 350/-	One month	6&8	-do-
4	RRD on road from Nauna to Sudhrani km 0/0 to 14/0 (SH- C/O Toe wall for existing R/wall at RD 12/731.05 to 12/733.080)	99905	2000	Rs. 350/-	One month	6&8	-do-
5	RRD on various roads of Pandoh S/Divn (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Pandoh Section-I).	99600	2,000	Rs. 350/-	One month	6&8	-do-
6	C/O Masad to Binoul road km 0/0 to 4/500 (SH- Hiring of Excavator cumloader for removal of slips/debries/mucks etc. at RD 0/0 to 4/500).	99600	2,000	Rs. 350/-	One month	6&8	-do-
7	RRD on various roads of Balichowki S/Divn (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at varirous RDs under Thachi Section).	99600	2,000	Rs. 350/-	One month	6&8	-do-
8	C/O Thach to Khari road km 0/0 to 3/500 (SH- Hiring of Excavator cum loader for removal of slips/debries/mucks etc. at RD 0/0 to 3/500).	99600	2,000	Rs. 350/-	One month	6&8	-do-
9	RRD on road from Dhingli Gagan Tandi km 0/0 to 6/0 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at RD 0/0 to 6/0).	99600	2,000	Rs. 350/-	One month	6&8	-do-
10	RRD on road from Sudharani to Ghat km 0/0 to 12/0 (SH- Hiring of excavator cum loader for removal of slips/clearance of berms, debries etc. at RD 6/0 to 12/0).	99600	2,000	Rs. 350/-	One month	6&8	-do-
11	RRD on various road under Balichowki S/Divn (SH- Hiring of Tipper for carriage of muck/debries etc. at various RDs in Balichowki Section).	98000	2,000	Rs. 350/-	One month	6&8	-do-
12	RRD on Dhamu to Masar road km 0/0 to 4/500 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at RD 0/0 to 4/500	99600	2,000	Rs. 350/-	One month	6&8	-do-
13	Construction of Hanogi to Bandhi road km 0/0 to 15/0 (SH- C/O R/wall at RD 11/653 to 11/655.50).	99778	2,000	Rs. 350/-	One month	6&8	-do-
14	RRD on Dhamu to Deori road km 0/0 to 2/645 (SH- C/O R/walls Dry stones masonary at km 0/868 to 0/879).	99981	2,000	Rs. 350/-	One month	6&8	-do-
15	RRD on various roads of Pandoh S/Divn (SH- Hiring of Excavator cum loader ffor removal of slips/clearance of berms, debries etc. at various RDs under Pandoh-II Section) Job No.I	99600	2,000	Rs. 350/-	One month	6&8	-do-

Scanned with CamScanner

16	RRD on various roads of Pandoh S/Divn (SH- Hiring of Excavator cum loader ffor removal of slips/clearance of berms, debries etc. at various RDs under Pandoh-II Section) Job No.II	99600	2,000	Rs. 350/-	One month	6&8	-do-
17	Maintenance of Pandoh Takoli Kullu by pass road km 222/700 to 227/500 (SH- Hiring of Excavator cum loader for removal of slips, clearance of berms, debries etc. at various RDs) Job No.I	99600	2,000	Rs. 350/-	One month	6&8	-do-
18	RRD on various roads of Pandoh S/Divn (SH- Hiring of Excavator cum loader ffor removal of slips/clearance of berms, debries etc. at various RDs under Pandoh-II Section) Job No.I	99600	2,000	Rs. 350/-	One month	6&8	-do-
19	RRD on various roads under Panarsa S/Divn (SH- Hiring of Excavator cum loader for removal of slips/debries, muck etc. at various RDs of Nagwain Section).	99600	2,000	Rs. 350/-	One month	6&8	-do-
20	RRD on various roads of Pandoh S/Divn (SH- Hiring of Excavator cum loader ffor removal of slips/clearance of berms, debries etc. at various RDs under Pandoh-II Section) Job No.I	99600	2,000	Rs. 350/-	One month	6&8	-do-

TERMS & CONDITIONS: -

1. The Tender form will not be issued to those contractors whose performance is not found satisfactory.
2. The Contractor whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to complete in tendering for four months.
3. The Contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only upto completion of work Satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.

4 The rates beyond the limit over +5% will be rejected besides this the Additional Performance security will have to borne @ 20 % & 30 % for unbalanced bid in case the rates is lower than 10 % but upto 20 % & lower than 20 % upto 30 % respectively. The tender will be accepted beyond the limit of -30 % also.

Executive Engineer,
Thalout Division,
HP.PWD Thalout

NO/PW/TLD/Tender/2025:- 2934-43 Dated: - 22.07.2025

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP.
3. The Sub Divisional Officer Balichowki, Distt. Mandi HP.
4. The Chief Engineer, (MZ) HPPWD Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD Mandi HP.
6. The Distt. Panchayat Officer Mandi HP.
7. All AEs under this Division.
8. The President of Contractor's Association.
9. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.

Executive Engineer,
Thalout Division,
HP.PWD Thalout

Scanned with CamScanner

Certificate

Certified that the tender called vide this office letter NO. PW/TLD/Tender/2025- 2934-43 dated 22.07.2025 is emergent nature and in Public interest.

Executive Engineer,
Thalout Division, HPPWD,
Thalout.

Scanned with CamScanner

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-II).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(2)

SCHEDULE OF QUANTITY

Name of work:- C/O of road from Nauna to Sudhrani km 0/0 to 14/00 (SH:- C/O Toe wall for existing R/wall at TD 12/728.30 to 12/731.05)

Estimated Cost:- 99909.00
Earnest Money : 2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	15.39	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	6128.00
2	Stone masonry work in cement mortar 1:6 (One cement: six sand) in foundation complete as per drawing and technical specifications Clause 702,704,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	9.34	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	48542.00
3	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub stuctur and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	12.06	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	45239.00
	Total in figures					**99909.00**
	Rate quoted by contractor +/-		Percent			
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout.

Scanned with CamScanner

(3)

SCHEDULE OF QUANTITY

Name of work:- C/O stage and Boundary Wall of GSSS Ghaniyar, Tehsil Balichowki, Distt. Mandi (H.P.)
(SH: - Providing and laying CC flooring).

Estimated Cost:- 99979.00
Earnest Money :-2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Providing and fixing M.S. BP Sheet 1.66mm (one point sixty six milimetre) to 2mm (two milimetre) thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer completer as per the instruction of Engineer-in-Charge (Base members of steel work shall be measured & paid separtely) including carriage of material and other incidentials in all leads and lifts and as per the direction of the Engineer-in Charge.	25.87	2130.90	Rs. Three thousand five hundred ninety four and paise seventy only	Square Metre	55126.00
2	52 mm (fifty two millimetre) thick cement concrete flooring with concrete hardener toopping, under layar 40 mm (forty millimetre) thick cement concrete 1:2:3 (one cement : two coarse sand : four graded aggregate) 20 mm (twenty millimetre) nominal size and top layer 12 mm (twelve millimetre) thick cement hardener consisting of 1:2 (one cement hardener mix : two graded stone aggregate) 6 mm (six milimetre) nominal size by volume, hardening compound mixed @ 2 liter (two liter) per 50 kg (fifty kilogramme) of cement or as per manufacturer's specification. this includes cost of cement slurry, but excluding the cost of nosing of steps etc. including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	54.90	817.00	Rs. Three thousand five hundred ninety four and paise seventy only	Square Metre	44853.00
					Total	**99979.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout

Scanned with CamScanner

(4)

SCHEDULE OF QUANTITY

Name of work:- RRD on road from Nauna to Sudhrani km 0/0 to 14/00 (SH:- C/O Toe wall for existing R/wall at TD 12/731.05 to 12/733.80)

Estimated Cost:- 99905.00
Earnest Money : 2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deletanous material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	15.38	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	6124.00
2	Stone masonry work in cement mortar 1:6 (One cement: six sand) in foundation complete as per drawing and technical specifications Clause 702,704,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	9.34	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	48542.00
3	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub stuctur and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	12.06	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	45239.00
	Total in figures					99905.00
	Rate quoted by contractor +/-		Percent			
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout.

Scanned with CamScanner

(5)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-I).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(6)

SCHEDULE OF QUANTITY

Name of work:- C/O Masad to Binoul road km 0/0 to 4/500 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 0/00 to 4/500).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout.

Scanned with CamScanner

(7)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Balichowki Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Thachi Section).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

(8)

SCHEDULE OF QUANTITY

Name of work:- C/O Thach to Khari road km 0/0 to 3/500 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 0/0 to 3/500).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout.

Scanned with CamScanner

(9)

SCHEDULE OF QUANTITY

Name of work:- RRD on road from Dhingli Gagan Tandi Km 0/000 to 6/000 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at RD 0/000 to 6/000).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

(10)

SCHEDULE OF QUANTITY

Name of work:- RRD on road from Sudharani to Ghat Km 0/000 to 12/000 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at RD 6/000 to 12/000).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(11)

SCHEDULE OF QUANTITY

Name of work:- R.R.D. on various road under Balichowki Sub-Division. (SH: - Hiring of Tipper for carriage of muck/debris etc. at various RDs in Balichowki Section).

Estimated Cost:-98000.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Tipper in good condtion of minimum 5.50 (Five point fifty drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavaated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	28.00	3500.00	Rs. Three thousand five hundred and paise zero only	Per Hour	98000.00
	Total					**98000.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(12)

SCHEDULE OF QUANTITY

Name of work:- RRD onDhamu to Masar road km 0/0 to 4/500 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at RD at Km 0/0 to 4/500).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(13)

SCHEDULE OF QUANTITY

Name of work:- Construction of Hanogi to Bandhi road Km 0/00 to 15/00 (SH:- C/o R/wall at RD. 11/653 to 11/655.50).

Estimated Cost:-99778.00
Earnest Money :-2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	12.50	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	4978
2	Providing and laying dowel bar in foundation in hard rock including making holes for dowel bar and fixing 25mm dia for steel in cement slurry with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	3.00	794.55	Rs. Seven hundred ninety four and paise fifty five only	Each	2384
3	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty milimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	5.50	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	26904
4	Providing weepholes in brick masonary/stone masonary /plain reinfoirced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	2.00	391.20	Rs.Three hundred ninety one and paise Twenty only	Each	782
5	Providing and laying of Boulder upron laid in wire crates with 4 mm (four milimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred milimetre) mesh (woven) diagonally) including 10 (Ten persant) persent extra for laps and joints laid with stones boulders weighting not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	19.50	3254.70	Rs.Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	63467.00
6	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	1.00	1263.40	Rs.One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	1263
	Total					**99778.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout.

Scanned with CamScanner

(14)

SCHEDULE OF QUANTITY

Name of work:- RRD Damages on Dhamu to Deori road km 0/0 to 2/645 km. (Sub Head :- C/o R/Walls Dry stones masonary at km 0/868 to 0/879 km).

Estimated Cost: 99981.00
Earnest Money :- 2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated ssuitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	12.86	452.95	Rs. Four hundred fifty two and paise ninety five only	Per Cubic Metre	5825.00
	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub stuctur and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	24.09	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	90366.00
	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	3790.00
	Total					**99981.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout

Scanned with CamScanner

(15)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh-II Section).	Estimated Cost:-99600.00
	Earnest Money:-2000.00
	Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout

Scanned with CamScanner

(6)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh-II Section).	Estimated Cost:-99600.00
	Earnest Money:-2000.00
	Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

17

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/500 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs). Job-I

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(18)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh-I Section).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(19)

SCHEDULE OF QUANTITY

Name of work:- R.R.D. on various roads under Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs of Nagwain Section)

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

20

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-I).	Estimated Cost:-99600.00
	Earnest Money:-2000.00
	Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner