

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
No.PW-AD-EA-I-Tender-2025-26 3102-13

Dated:- 05/08/25

To

The Executive Engineer (IT Cell)  
H.P.P.W.D. Nigam Vihar Shimla-2.

**Subject:- Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

**Encl:-Copy of NIT**

Executive Engineer,  
Arki Division  
H.P.P.W.D. Arki  
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.

Executive Engineer,  
Arki Division  
H.P.P.W.D. Arki  
Ph. 01796-220714

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **13.08.2025 up to 11.30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **12.08.2025 up to 4:00 PM** and the application for issue of tender form shall be received on **12.08.2025 up to 5:00 PM.**


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

S.N o	Name of work	Estimated cost.	Earnest money	Form	Cost, of form	Time
1.	Restoration of rain damages on various roads under Arki Sub-Division Piplughat section(SH:-Hiring of JCB for removal of slips,dressing of roads, cleaning of drains etc.)Job No.1	99,000/-	2000/-	6&8	350/-	1Month s
2	Restoration of rain damages on various roads under Arki Sub-Division Arki section(SH:-Hiring of JCB for removal of slips,dressing of roads, cleaning of drains etc.)Job No.1	99,000/-	2000/-	6&8	350/-	1Month s
3	Restoration of rain damages on various roads under Arki Sub-Division Bhumti section(SH:-Hiring of JCB for removal of slips,dressing of roads, cleaning of drains etc.)Job No.1	99,000/-	2000/-	6&8	350/-	1Month

4	Restoration of rain damages on various roads under Darla Sub-Division, Mangal section(SH:- Hiring of JCB for removal of slips,dressing of roads, cleaning of drains etc.)Job No.1	99,000/-	2000/-	6&8	350/-	1Month
5	Restoration of rain damages on various roads under Darla Sub-Division, Navgaon section(SH:- Hiring of JCB for removal of slips,dressing of roads, cleaning of drains etc.)Job No.1	99,000/-	2000/-	6&8	350/-	1Month
6	Restoration of rain damages on various roads under Darla Sub-Division, Shalaghat section(SH:- Hiring of JCB for removal of slips,dressing of roads, cleaning of drains etc.)Job No.1	99,000/-	2000/-	6&8	350/-	1Month
7	Restoration of rain damages on various roads under Kunihar Sub-Division, Mann section(SH:- Hiring of JCB for removal of slips,dressing of roads, cleaning of drains etc.)Job No.1	99,000/-	2000/-	6&8	350/-	1Month
8	Restoration of rain damages on various roads under Kunihar Sub-Division, Kunihar section(SH:- Hiring of JCB for removal of slips,dressing of roads, cleaning of drains etc.)Job No.1	99,000/-	2000/-	6&8	350/-	1Month
9	Restoration of rain damages on various roads under Kunihar Sub-Division, Jainagar section(SH:- Hiring of JCB for removal of slips,dressing of roads, cleaning of drains etc.)Job No.1	99,000/-	2000/-	6&8	350/-	1Month
10	C/o link road Navi Karyan to village Navi G.P. Dadhogi(SH:-Formation cutting 5/7mtrs wide road in km. 0/0 to 0/095)	96564/-	2000/-	6&8	350/-	1Month

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


  
Executive Engineer  
Arki Division,  
H.P.P.W.D. Arki

No:PW/AD/EA-I/Tender/2025-26 3114-21

Dated:- 05/08/25


Copy forwarded for the following for information and necessary action to:-

1. The Superintending Engineer 3<sup>rd</sup> Circle HPPWD Solan.
2. The all Assistant Engineer working under this division for information and necessary action.
3. All the heads of the branches in this office.
4. Notice Board.

  
Executive Engineer  
Arki Division,  
H.P.P.W.D. Arki

**Certificate**

Certified that the tenders called vide this notice inviting tender for 10 (ten) jobs are due to exigencies/emergency of works in the larger public interest.

  
Executive Engineer  
Arki Division,  
H.P.P.W.D. Arki

### SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Arki Sub Division Piplughat Section (SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- I)						Estimated Cost: -Rs 99,000/- only	
						Earnest Money : Rs 2000 /-Only	
						Time -One Months	
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

  
 Executive Engineer  
 H.P.W.D (B&R)  
 Division Arki

### SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Arki Sub Division Arki Section (SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- I)						Estimated Cost: -Rs 99,000/- only	
						Earnest Money : Rs 2000 /-Only	
						Time -One Months	
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

  
 Executive Engineer.  
 H.R. PWD (B&R)  
 Division Arki

### SCHEDULE OF QUANTITY



Name of Work:- Restoration of rain damages on various roads under Arki Sub Division Bhumti Section (SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- I)					Estimated Cost: -Rs 99,000/- only		
					Earnest Money : Rs 2000 /-Only		
					Time -One Months		
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimmimg of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

  
 Executive Engineer  
 H.P.W.D (B&R)  
 Division Arki

### SCHEDULE OF QUANTITY



SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Darla Sub Division Mangal Section (SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- I)					Estimated Cost: -Rs 99,000/- only		
					Earnest Money : Rs 2000 /-Only		
					Time -One Months		
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

  
 Executive Engineer  
 Add Division, HPPWD  


### SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Darla Sub Division Navgaon Section (SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- I)					Estimated Cost: -Rs 99,000/- only		
					Earnest Money : Rs 2000 /-Only		
					Time -One Months		
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

  
 Executive Engineer:  
 And Division, HPPWD  




### SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Darla Sub Division Shallaghat Section (SH:- Hiring of JCB for removal of slips, dressing of roads, cleaning of drains etc.) ( Job No- I)						Estimated Cost: -Rs 99,000/- only	
						Earnest Money : Rs 2000 /-Only	
						Time -One Months	
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

*Enl*  
Executive Engineer  
A&S Division, HPWD  
*Enl*


### SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Kunihar Sub Division Mann Section (SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- I)					Estimated Cost: -Rs 99,000/- only		
					Earnest Money : Rs 2000 /-Only		
					Time -One Months		
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

  
 Executive Engineer  
 Add Division, HPPWD  




### SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Kunihar Sub Division Kunihar Section (SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- I)						Estimated Cost: -Rs 99,000/- only	
						Earnest Money : Rs 2000 /-Only	
						Time -One Months	
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimmimg of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

  
 Executive Engineer  
 Anti Division, HPPWD

### SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Kunihar Sub Division Jainagar Section (SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- I)						Estimated Cost: -Rs 99,000/- only	
						Earnest Money : Rs 2000 /-only	
						Time -One Months	
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

  
 Executive Engineer  
 HPP Division, HPPWD  


# SCHEDULE OF QUANTITY

Name of work:- Construction of link road Navi Karyah to Village Navi G.P Dadhogi (SH:- Formation cutting 5/7 mtr wide road in km 0/000 tp 0/095)

Estimated Cost: -Rs 96,564/- only

Earnest Money : Rs 2000 /-Only

Time -One Month

S.N o.		Sub head and items of work	Qty.		Rate		Unit	Amount
1	2		3		In figure	In words	6	7
1	Excavation in earthwork in hilly area all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of techanical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wodth including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrcted by the Engineer-in -Charge for smooth ridiiing. The recovery of useful stone that is <b>12.42 Cubic meter</b> in all cases falling which recovery @ <b>Rupees 300/-</b> only (Rupees three hundred only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	620.99	Cum	155.50	Rupees One Hundred Fifty Five and Paise Fifty Only	Per cubic metre.	96564.00	
							Total:-	96564.00

Quoted rate percentage in figures

Quoted rate percentage in words

  
Executive Engineer  
B&R Division H&PW  
