Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal **Pradesh Public works Department Baijnath-176125**
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

NO: PWD/BN/TA/NIT/2025-26/- 6599 — 6604 Dated:-**12.08.2025**

To

The Executive Engineer, (IT Cell),
Nirman Bhawan Nigam Vihar,
Shimla-2.

Subject:- Publication of Tender Notice on the Departmental website.

Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.

Encl: Notice Inviting Tender
& Schedule of Quantity.

Yours faithfully,

Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.

Copy forwarded for information to:-

1. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
2. All the Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **02.09.2025** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **01.09.2025 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **30.08.2025 up to 12.00 Noon.**

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O OBC Bhawan at Ghirtholi (2nd Part) Balance work (SH: Civil Work) (Deposit Work) VKV/2024/1189	2,31,048/-	4700/-	Rs.350/-	Two Months
2	C/O Mahila Mandal Bhawan at Gowal (First Floor) (SH: C/O Civil work) (Deposit work VKV/2024/1188)	2,91,075/-	5900/-	Rs.350/-	Two Months
3	C/O Mahila Mandal Bhawan Janehad (SH: P/F Door Shutter, Grill work, Plastering and Flooring work etc) (Deposit work SDP/2021/1145, VKV/2024/49)	1,21,827/-	2500/-	Rs.350/-	Two Months
4	C/O Road from Chaniyara to House of Hoshiar Singh Mehta at Chobin (SH: P/L interlocking paver block 60 mm concrete block in RD 0/136.30 to 0/183.56) (Deposit work VKV/2024/1175)	1,93,167/-	3900/-	Rs.350/-	Two Months
5	C/O Building work 2 rooms in GSSS Jandpur (SH: Civil work) (Deposit work SDP/2023/1141)	1,96,701/-	4000/-	Rs.350/-	Two Months
6	C/O Bridge at village Hartada (SH: Super structure) (Deposit work SDP/2023/379, SDP/2021/1137)	1,95,220/-	4000/-	Rs.350/-	One Month
7	C/O Gaziabad to Kholi km 0/00 to 0/520 (SH: C/O R/wall at RD 0/195 to 0/201.50 & P/L C.C pavement at RD 0/055 to 0/096.50) Deposit work VKV/2025/372	1,95,583/-	4000/-	Rs.350/-	One Month

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
3. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
4. Only two tenders form will be issued to the contractor/firm which may be noted.
5. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
6. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
7. The contractor shall have all required machinery such as Truck/Tipper,Mixture,water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
8. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
9. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
10. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.
For & On behalf of the governor of H.P.

(1)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O OBC Bhawan at Ghirtholi (2nd Part) Balance work
(SH:- Civil work) (DEPOSIT WORK) VKV/2024/1158

Estimate Cost: 2,31,048.00
Earnest Money:4,700.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Providing tor steel reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all respects as per drawing and design in all floor levels including the cost of binding wire as per PWD specification and approved design. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royality, GST, toll tax. Sale Tax or other taxes imposed by the government.	773.25	Per kilo gram	96.00	Rupees Ninety Six Only	74232.00
2	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.43	Per cubic metre	7,500.00	Rupees Seven Thousand Five Hundred Only	18,225.00
3	Providing and laying of Kota stone slab flooring 20mm (average) thick base of cement mortor 1:4 laid over slury mixed with pigment match the shade of slab 20 mm . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.20	Per square metre	1450.00	Rupees One Thousand Four Hundred & Fifty Only	7,540.00
4	Providing and laying of Kota stone slab flooring 20mm (average) thick base of cement mortor 1:4 laid over slury mixed with pigment match the shade of slab 20 mm . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	90.38	Per square metre	1450.00	Rupees One Thousand Four Hundred & Fifty Only	1,31,051.00
						2,31,048.00

D.N.I.T. Checked and approved for Rs. 2,31,048.00 only
Rupees Two Lakh(s) Thirty One Thousand Forty Eight Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Mahila Mandal Bhawan at Gowal (First floor)
(sh:- C/O Civil work) (Deposit work VKV/2024/1188)

Estimate Cost: 2,91,075.00
Earnest Money: 5,900.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Providing form work with steel plates 3.15mm.thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centring, shuutering, strutting and propping etc with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: Sides and soffits of beams,beam haunchings, cantilevers,bressumers and lintels not exceeding 1 Mtr. in depth in all heights from floor.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	16.44	Per Square metre	375.00	Rupees Three Hundred & Seventy Five Only	6,165.00
2	Providing form work with steel plates 3.15mm(three point fifteen).thick welded with angle iron in frame 30x30x5mm (thirty inti thirty into five) . so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 (four) Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in Square, rectangular or polygonal in plan column pillar posts and sturts The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government	31.32	Sqm	475.00	Rupees Four Hundred & Seventy Five Only	14,877.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering in **column pillar posts and sturts** level :1:2:4 (One Cement : Two coarse sand) Four graded stone aggregate 20 mm (twenty millimeter) nominal size The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.11	Per cubic metre	6,950.00	Rupees Six Thousand Nine Hundred & Fifty Only	14,665.00
4	Providing and laying mechanically mixed and vibrated reinforced cement concrete work grade M-20 design mix to obtain the minimum compressive strength of M-20 N/mm2 with cement contents not less than of 320kg/m3 (three hundred twenty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in suspended floor, roofs, landing and shelves and their support balconies beams girders bressumers and cantilevers upto floor all level and curing complete The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.38	Per cubic metre	7000.00	Rupees Seven Thousand Only	2,660.00
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete work grade M-20 design mix to obtain the minimum compressive strength of M-20 N/mm2 with cement contents not less than of 320kg/m3 (three hundred twenty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in stair cases (except spiral stair cases) excluding landing but including preparing of top surface and finishing of nosing upto all floor level and curing complete including carriage of material within all leads, lifts and other incidental charges complete in all respect as per direction of Engineer-in-Charge.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government	1.32	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	9,372.00
6	Providing mild steel/Tor steel reinforcement for R C C work including bending, binding and placing in position complete upto floor two level Tor Steel The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	544.80	KG	95.00	Rupees Ninety Five Only	51,756.00
7	Providing and fixing 0.60mm (zero point sixty millimeter) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (five) microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm (six millimeter dia metre with prepainted limpet and rubber washers complete with all accesorices as required as per the direction of Engineer-in-charge.The rate including of octroi, royality, Malkata, tolltax, Sale Tax or other taxes imposed by the government	20.65	Sqm	1600.00	Rupees One Thousand Six Hundred Only	33,040.00

(2)(b)

8	Providing and fixing pre-painted sheet ridge or hips 60cm (sixty centimetre) over all of kotar metal skin trapezoidal profiled sheeting 0.60mm (zero point sixty centimetre) cover with over all width 1126mm (one thousand one hundred twenty six) 28mm (twenty eight) crest depth at 353mm (three hundred fifty three) 2mm (two millimetre) C/C crest distance. There will be two ribs at the centre for stiffening heaving crest depth of 2.50mm (two point five millimetre) the main crest with at top zinc waiting top coat with regular modified polyster coating of approved shade and balancing reverse coat 5.5mm (five decimal five millimetre) dia and 55mm (fifty five millimetre) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government	24.50	Per running metre	900.00	Rupees Nine Hundred Only	22.050.00
9	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat ofapproved steel primer all complete.The rate including of octroi, royality, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1252.20	Per Kilogram	109.00	Rupees One Hundred & Nine Only	1,36,490.00
						2,91,075.00

D.N.I.T. Checked and approved for Rs. 2,91,075.00 only
Rupees Two Lakh(s) Ninety One Thousand Seventy Five Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

(3)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Mahila Mandal Bhawan Janehad .
(Sh:- P/F Door Shutter , Grill work , Plastering and Flooring work etc) (Deposit work SDP/2021/1145 , VKV/2024/49)

Estimate Cost: 1,21,827.00
Earnest Money: 2,500.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Providing and fixing 12mm (Twelve millimetre) Thick Prelaminated board in matt finished ISI marked NO 12823 as per approved shade of viromica / kit ply / nona pan / green ply both side BWP phenol bonded exterior / interior grade panelled shutter with frame of first class Deodar wood including bright finished black enameled butt hinges with necessary screws 40 mm (Forty millimetre) thick shutter as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	2.76	Per square metre	2,657.80	Rupees Two Thousand Six Hundred & Fifty Seven - Paise Eighty Only	7,336.00
2	Providing and fixing M.S. grills of required pattern in frames of windows etc with M S flats, square or round bars etc. including priming coat with approved steel primer all complete Fixed to openings /wooden frames with rawl plugs screws etc.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	89.04	kg	120.10	Rupees One Hundred & Twenty - Paise Ten Only	10,694.00
3	15 mm (Fifteen) cement plaster in single coat on rough side of brick/ stone masonry for interior plaserting upto floor two level with Cm 1:6 as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government	56.27	Sqm	375.00	Rupees Three Hundred & Seventy Five Only	21,101.00
4	15 mm (Fifteen) cement plaster in single coat on fair side of brick/ stone masonry for outer plaserting upto floor two level with Cm 1:6 as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government	74.09	Sqm	320.00	Rupees Three Hundred & Twenty Only	23.709.00
5	6mm (six millimeter) cement plaster 1:3 (One Three) in ceiling as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government	49.17	Sqm	275.00	Rupees Two Hundred & Seventy Five Only	13,522.00
6	Providing and fixing 10mm(ten milimeter) thick anti skid water proof stain and impect resistent heavy duty vetrified tiles Nitco or equivalant 600x600mmx10mm (Six hundred into six hundred into ten milimeter) manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (one cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government	34.99	Per square metre	1268.10	Rupees One Thousand Two Hundred & Sixty Eight - Paise Ten Only	44371.00
7	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS 1868), transparent or dyed to required colour or shade, with nuts and screws etc complete 250x16 mm (two fifty into sixteen millimetre) The rate including of octroi, royality, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each	214.20	Rupees Two Hundred & Fourteen - Paise Twenty Only	214.00
8	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS 1868) transparent or dyed to required colour or shade, with necessary screws etc complete 250x10 mm (two hundred fifty into ten millimeter) The rate including of octroi, royality, Malkana, tolltax, Sale Tax or other taxes imposed by the government	4.00	Each	125.00	Rupees One Hundred & Twenty Five Only	500.00
9	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS . 1868) transparent or dyed to required colour or shade, with necessary screws etc complete 150 mm (One twenty five millimetre)The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	4.00	Each	95.00	Rupees Ninety Five Only	380.00
						1,21,827.00

Estimate Checked and approved for Rs. 1,21,827.00 only
Rupees One Lakh(s) Twenty One Thousand Eight Hundred Twenty Seven Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

(4)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Road from Chaniyara to House of Hoshiar Singh Mehta at chobin (SH:- P/L interlocking paver block 60 mm concrete block in RD 0/136.30 to 0/183.56) (Deposit Work VKV/2024/1175)	**Estimate Cost: 1,93,167.00/-** **Earnest Money: 3,900.00/-** **Time Limit :Two months**

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilogramms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royality, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.66	Per Cubic metre	6,950.00	Rupees Six Thousand Nine Hundred & Fifty Only	4,587.00
2	Providing and Laying of Interlocking Concrete Blcok Pavements having thickness 60 mm as per drawing and Technical Specification Clause 1504 entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate shall include all lead, lift and proper stacking complete in all respect as per the direction of the Engineer-in-charge. 60 mm	134.70	Per Square metre	1400.00	Rupees One Thousand Four Hundred Only	188580.00
						1,93,167.00
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

D.N.I.T. Checked and approved for Rs. 1,93,167.00 only
Rupees One Lakh(s) Ninety Three Thousand One Hundred Sixty Seven Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

Condition :-

1. **Rate should be quoted for all heights including all leads and lifts**
2. **Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards**

(5)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :-C/O Building work 2 rooms in GSSS Jandpur
(Sh:- Civil Work) (Deposit work SDP/2023/1141)

Estimate Cost: 1,96,701.00
Earnest Money:4,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing form work with steel plates 3.15mm.thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centring, shuutering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: Sides and soffits of beams,beam haunchings, cantilevers,bressumers and lintels not exceeding 1 Mtr. in depth in all heights from floor.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	34.60	SQM	295.00	Rupees Two Hundred & Ninety Five Only	10,207.00
2	Providing and fixing angle iron door, window, clerestory window frame manufactured from M.S. Angle iron section of 50*50*6mm . thickness including hinges jamb, lock jamb, beed and if required angle thrashold ofmild steel angle 50*25 mm welded or rigidly fixed by mechanical means and applying a coat of approved steel primer after preteatment of the surface as directed by Engineer-in-charge.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	63.80	RMT	400.00	Rupees Four Hundred Only	25,520.00
3	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	8.35	CUM	7400.00	Rupees Seven Thousand Four Hundred Only	61,790.00
4	Square rubble masonry coursed with hard stone of approved quality in foundation and plinth including racking out joints in cement mortar 1:6 (one cement : six sand) and curing complete including carriage of materials within all leads and lifts complete in all respect as per the direction of Engineer-in-Charge.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.47	CUM	5400.00	Rupees Five Thousand Four Hundred Only	18,738.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level .1.2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.19	CUM	6950.00	Rupees Six Thousand Nine Hundred & Fifty Only	36,071.00
6	Providing tor steel reinforcement for RCC work including bending, binding and placing in position complete upto floor two level.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	467.10	KG	95.00	Rupees Ninety Five Only	44,375.00
						1,96,701.00

D.N.I.T. Checked and approved for Rs. 1,96,701.00 only
Rupees One Lakh(s) Ninety Six Thousand Seven Hundred One Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O Bridge at Village Hartada (Sh:- Super structure) (Deposit work SDP/2023/379 , SDP/2021/1137)				Estimate Cost: 1,95,220.00 Earnest Money:4,000.00 Time Limit : One Month		
Sr.n	**Description of work**	**No.or Qty.**	**Unit**	**Rate**		**AMOUNT**
				Figures	**Words**	**Rs. P**
1	Providing tor steel reinforcement for RCC work including bending binding and placing in position complete.as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals. as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi. royality. GST. toll tax. Sale Tax or other taxes imposed by the government.	2270.00	Kg	86.00	Rupees Eighty Six Only	1,95,220.00
						1,95,220.00

D.N.I.T. Checked and approved for Rs. 1,95,220.00 only

Rupees One Lakh(s) Ninety Five Thousand Two Hundred Twenty Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

(7)(a)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Gaziabad to kholi km 0/00 to 0/520 (SH:-C/O R/wall at RD 0/195 to 0/201.50 & P/L C C pavement at RD 0/055 to 0/096.50) Deposit work VKV/2025/372	Estimate Cost: 1,95,583.00/- Earnest Money: 4,000.00/- Time Limit :One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	2.08	Per Cum	290.00	Rupees Two Hundred & Ninety Only	603.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 &1200 for nominal mix 1:5:10 (one cement five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	8.10	Per Cum	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	40,095.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	2.73	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	2,703.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	5.00	Each	290.00	Rupees Two Hundred & Ninety Only	1,450.00
5	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the intersitices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	9.03	Per Cubic Metre	2,800.00	Rupees Two Thousand Eight Hundred Only	25,284.00

6	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilogramms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royality, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	18.05	Per Cubic metre	6,950.00	Rupees Six Thousand Nine Hundred & Fifty Only	1,25,448.00
	Total					**1,95,583.00**
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

Dnit Checked and approved for Rs. 1,95,583.00 only
Rupees One Lakh(s) Ninety Five Thousand Five Hundred Eighty Three Only

Executive Engineer
Baijnath Division
HPPWD Baijnath