

OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS
DEPARTMENT BANGANA

No:- PW-BGN-CB/T-1/2025-26-
To

4278-87

Dated:- 19-08-2025


The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.
ee-pwd-hp@nic.in.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.


Executive Engineer
Bangana Division
HPPWD Bangana

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD, Una.
4. The Assistant Engineer, Sub Division, HPPWD Bangana and Basal.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.


Executive Engineer
Bangana Division
HPPWD Bangana.

Handwritten text at the top of the page, possibly a title or header.

Handwritten text, possibly a date or reference number.

Handwritten text, possibly a paragraph or list of items.

Handwritten text, possibly a signature or name.

Handwritten text, possibly a signature or name.

Handwritten text, possibly a signature or name.

**OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS
DEPARTMENT BANGANA**

NOTICE INVITING TENDER.

Sealed percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Bangana Division HPPWD Bangana on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **25-08-2025 up to 10.30 A.M** and same will be opened on the same day at 11.00 AM in presence of the interested contractors or their authorized representative. The application will be received in this office on at **22-08-2025 upto 04.00 PM**. The tender form can be had from the office of Executive Engineer Bangana Division HPPWD Bangana on cash payment (Non-refundable) on **23-08-2025** during office Hours **up to 5.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Bangana Division HPPWD Bangana cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The tender document fee shall also be deposited by the applicant/ contractor with at the time of application in the shape of Demand Draft or Cash (Non-Refundable) otherwise tender documents/ Forms shall not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period	Eligible of Class
1	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Teuri Section)	99750.00	2000.00	Two Month	C& D
2	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Teuri Section)	99750.00	2000.00	Two Month	C& D
3	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Teuri Section)	99750.00	2000.00	Two Month	C& D
4	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Teuri Section)	99750.00	2000.00	Two Month	C& D
5	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Dhamandri Section)	99750.00	2000.00	Two Month	C& D
6	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Dhamandri Section)	99750.00	2000.00	Two Month	C& D
7	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Dhamandri Section)	99750.00	2000.00	Two Month	C& D
8	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Dhamandri Section)	99750.00	2000.00	Two Month	C& D
9	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Khurwain Section)	99750.00	2000.00	Two Month	C& D
10	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms	99750.00	2000.00	Two Month	C& D


12	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hiring of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Khurwain Section)	99750.00	2000.00	Two Month	C& D
13	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hiring of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Chattara Section)	99750.00	2000.00	Two Month	C& D
14	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hiring of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Chattara Section)	99750.00	2000.00	Two Month	C& D
15	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hiring of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Chattara Section)	99750.00	2000.00	Two Month	C& D
16	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hiring of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Chattara Section)	99750.00	2000.00	Two Month	C& D
17	C/o Office Accommodation for Joint Commissioner State Taxes & Excise, Central Enforcement Zone Una (Samoor Kalan) Tehsil & Distt. Una (H.P.) (SH: C/o Embankment in front of main Building)	99839.00	2000.00	Two Month	C& D
18	C/o Office Accommodation for Joint Commissioner State Taxes & Excise, Central Enforcement Zone Una (Samoor Kalan) Tehsil & Distt. Una (H.P.) (SH: C/o Embankment in back side of main Building)	95165.00	2000.00	Two Month	C& D
19	Restoration of Rain Damages on Mohalla Batian in G.P. Panoh (SH: Balance work for P/L Interlocking paver Block flooring in Km 0/068 to 0/082.80)	99887.00	2000.00	Two Month	C& D
20	Restoration of Rain Damages on Mohalla Batian in G.P. Panoh (SH: Balance work for P/L Interlocking paver Block flooring in Km 0/082.80 to 0/097.60)	99887.00	2000.00	Two Month	C& D
21	Restoration of Rain Damages on Mohalla Batian in G.P. Panoh (SH: P/L Interlocking paver Block flooring in Km 0/097.60 to 0/112.60)	99776.00	2000.00	Two Month	C& D
22	Restoration of Rain Damages on Mohalla Batian in G.P. Panoh (SH: P/L Interlocking paver Block flooring in Km 0/112.60 to 0/127.20)	99776.00	2000.00	Two Month	C& D
23	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Khurwain Section)	99630.00	2000.00	Two Month	C& D
24	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Khurwain Section)	99630.00	2000.00	Two Month	C& D
25	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Khurwain Section)	99630.00	2000.00	Two Month	C& D
26	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Chattara Section)	99630.00	2000.00	Two Month	C& D
27	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Chattara Section)	99909.00	2000.00	Two Month	C& D
28	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Chattara Section)	99736.00	2000.00	Two Month	C& D
29	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Teuri Section)	99960.00	2000.00	Two Month	C& D
30	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Teuri Section)	99960.00	2000.00	Two Month	C& D
31	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in	99960.00	2000.00	Two Month	C& D

D
D
D
D
D
D

radesh.

32	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Dhamandri Section)	99960.00	2000.00	Two Month	C& D
33	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Dhamandri Section)	99960.00	2000.00	Two Month	C& D
33	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Dhamandri Section)	99960.00	2000.00	Two Month	C& D
34	Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hiring of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Teuri Section)	99750.00	2000.00	Two Month	C& D
35	Stock Storage at HPPWD Sub Division Dera Baba Rudru Basal (SH:- Supply & Stacking 600mm Dia RCC Hume Pipe)	75000.00	1500.00	Two Months	C& D

HIM SUCHANA AVAM JAN SAMPARK.


 Executive Engineer
 Bangana Division
 HPPWD Bangana.
 On behalf of Governor of Himachal Pradesh.

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hiring of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Teuri Section)	Estimated Cost Rs	99750.00
	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	Two Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B.(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Anil Kumar
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana

Estimated Cost
Rs 99750.00Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH:
Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Teuri Section)Earnest Money
Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: Two Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

NAME of Works: Restoration of various road under Dera Baba Farid Road-Bylan 651:
Location of work: On the corner of shops Road side Dera, Shahr-e Bera and road surface in 1st section
Duration of work: 10 days

NAME OF TRADER / TRADING FIRM / COMPANY:

1995年5月11日

(The word template must not be modified or placed in the footer and the name should be changed after changing the research community, else the matter is more to be reported to your research community.)

DESCRIPTION OF SITE

[illegible]

2000

[illegible][illegible]

Food in 1990s

Control Ratio in Equities

Notes (4)

1.0000

00'02.00

2000
 2001
 2002
 2003
 2004
 2005
 2006
 2007
 2008
 2009
 2010
 2011
 2012
 2013
 2014
 2015
 2016
 2017
 2018
 2019
 2020
 2021
 2022
 2023
 2024
 2025
 2026
 2027
 2028
 2029
 2030
 2031
 2032
 2033
 2034
 2035
 2036
 2037
 2038
 2039
 2040
 2041
 2042
 2043
 2044
 2045
 2046
 2047
 2048
 2049
 2050
 2051
 2052
 2053
 2054
 2055
 2056
 2057
 2058
 2059
 2060
 2061
 2062
 2063
 2064
 2065
 2066
 2067
 2068
 2069
 2070
 2071
 2072
 2073
 2074
 2075
 2076
 2077
 2078
 2079
 2080
 2081
 2082
 2083
 2084
 2085
 2086
 2087
 2088
 2089
 2090
 2091
 2092
 2093
 2094
 2095
 2096
 2097
 2098
 2099
 2100
 2101
 2102
 2103
 2104
 2105
 2106
 2107
 2108
 2109
 2110
 2111
 2112
 2113
 2114
 2115
 2116
 2117
 2118
 2119
 2120
 2121
 2122
 2123
 2124
 2125
 2126
 2127
 2128
 2129
 2130
 2131
 2132
 2133
 2134
 2135
 2136
 2137
 2138
 2139
 2140
 2141
 2142
 2143
 2144
 2145
 2146
 2147
 2148
 2149
 2150
 2151
 2152
 2153
 2154
 2155
 2156
 2157
 2158
 2159
 2160
 2161
 2162
 2163
 2164
 2165
 2166
 2167
 2168
 2169
 2170
 2171
 2172
 2173
 2174
 2175
 2176
 2177
 2178
 2179
 2180
 2181
 2182
 2183
 2184
 2185
 2186
 2187
 2188
 2189
 2190
 2191
 2192
 2193
 2194
 2195
 2196
 2197
 2198
 2199
 2200
 2201
 2202
 2203
 2204
 2205
 2206
 2207
 2208
 2209
 2210
 2211
 2212
 2213
 2214
 2215
 2216
 2217
 2218
 2219
 2220
 2221
 2222
 2223
 2224
 2225
 2226
 2227
 2228
 2229
 2230
 2231
 2232
 2233
 2234
 2235
 2236
 2237
 2238
 2239
 2240
 2241
 2242
 2243
 2244
 2245
 2246
 2247
 2248
 2249
 2250
 2251
 2252
 2253
 2254
 2255
 2256
 2257
 2258
 2259
 2260
 2261
 2262
 2263
 2264
 2265
 2266
 2267
 2268
 2269
 2270
 2271
 2272
 2273
 2274
 2275
 2276
 2277
 2278
 2279
 2280
 2281
 2282
 2283
 2284
 2285
 2286
 2287
 2288
 2289
 2290
 2291
 2292
 2293
 2294
 2295
 2296
 2297
 2298
 2299
 2300
 2301
 2302
 2303
 2304
 2305
 2306
 2307
 2308
 2309
 2310
 2311
 2312
 2313
 2314
 2315
 2316
 2317
 2318
 2319
 2320
 2321
 2322
 2323
 2324
 2325
 2326
 2327
 2328
 2329
 2330
 2331
 2332
 2333
 2334
 2335
 2336
 2337
 2338
 2339
 2340
 2341
 2342
 2343
 2344
 2345
 2346
 2347
 2348
 2349
 2350
 2351
 2352
 2353
 2354
 2355
 2356
 2357
 2358
 2359
 2360
 2361
 2362
 2363
 2364
 2365
 2366
 2367
 2368
 2369
 2370
 2371
 2372
 2373
 2374
 2375
 2376
 2377
 2378
 2379
 2380
 2381
 2382
 2383
 2384
 2385
 2386
 2387
 2388
 2389
 2390
 2391
 2392
 2393
 2394
 2395
 2396
 2397
 2398
 2399
 2400
 2401
 2402
 2403
 2404
 2405
 2406
 2407
 2408
 2409
 2410
 2411
 2412
 2413
 2414
 2415
 2416
 2417
 2418
 2419
 2420
 2421
 2422
 2423
 2424
 2425
 2426
 2427
 2428
 2429
 2430
 2431
 2432
 2433
 2434
 2435
 2436
 2437
 2438
 2439
 2440
 2441
 2442
 2443
 2444
 2445
 2446
 2447
 2448
 2449
 2450
 2451
 2452
 2453
 2454

Topic

[illegible]

44444444 444 444444

[illegible]

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Teuri Section)

Estimated Cost
Rs 99750.00

Earnest Money
Rs 2000.00


Time Limit: Two Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana

Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Dhamandri Section)

Estimated Cost Rs 99750.00

Earnest Money Rs 2000.00

Time Limit: Two Month

Name of Bidder/ Bidding Firm/ Company :-

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the

PRICE SCHEDULE


Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B.(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged-material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				

Amal Chandra
Executive Engineer
Bangana Division
HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99750.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Dhamandri Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Exceccutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99750.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Dhamandri Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures				Excess (+)		
				Less (-)		


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99750.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Dhamandri Section)					Earnest Money Rs	2000.00
					Time Limit:	Two Month
Name of Bidder/ Bidding Firm/ Company :-						
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures				Excess (+)		
				Less (-)		


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99750.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Khurwain Section)					Earnest Money Rs	2000.00
					Time Limit:	Two Month
Name of Bidder/ Bidding Firm/ Company :-						
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana

Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Khurwain Section)

Estimated Cost
Rs 99750.00

Earnest Money
Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: Two Month

PRICE SCHEDULE


(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				

A. M. Chaur
Executive Engineer
Bangana Division
HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99750.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Khurwain Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Percentage BOQ					Estimated Cost Rs	99750.00
Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Earnest Money Rs	2000.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Khurwain Section)					Time Limit:	Two Month
Name of Bidder/ Bidding Firm/ Company :-						
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99750.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Chattara Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99750.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Chattara Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ


Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Chattara Section)	Estimated Cost Rs	99750.00
Name of Bidder/ Bidding Firm/ Company :-	Earnest Money Rs	2000.00
	Time Limit:	Two Month

PRICE SCHEDULE


(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99750.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Hirirng of J.C.B. for removal of slips, Road side Drain, Shoulder berms and road surface in Chattara Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L. (Petrol Oil Lubricant) charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation if necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road berms. Minimum 25 cubic meter of earth work shall be done by machine in one hour, otherwise number of hours shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	95.00	Per Hours	1050.00	99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Total in Figures					99750.00	Rupees Ninety Nine Thousand Seven Hundred & Fifty Only
Qouted Rate in Figures				Excess (+)		
				Less (-)		


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Exceecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99839.00
Name of Work: C/o Office Accommodation for Joint Commissioner State Taxes & Excise, Central Enforcement Zone Una (Samoor Kalan) Tehsil & Distt. Una (H.P.) (SH: C/o Embankment in front of main Building)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 303 upto any lead as per MORD 2014 Technical Specification Clause 303 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	317.25	Per Cubic metre	314.70	99839.00	Rupees Ninety Nine Thousand Eight Hundred & Thirty Nine Only
Total in Figures					99839.00	Rupees Ninety Nine Thousand Eight Hundred & Thirty Nine Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	95165.00
Name of Work: C/o Office Accommodation for Joint Commissioner State Taxes & Excise, Central Enforcement Zone Una (Samoor Kalan) Tehsil & Distt. Una (H.P.) (SH: C/o Embankment in back side of main Building)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 303 upto any lead as per MORD 2014 Technical Specification Clause 303 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	302.40	Per Cubic metre	314.70	95165.00	Rupees Ninety Five Thousand One Hundred & Sixty Five Only
Total in Figures					95165.00	Rupees Ninety Five Thousand One Hundred & Sixty Five Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division,
 HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana				Estimated Cost Rs	99887.00	
Name of work:- Restoration of Rain Damages on Mohalla Batian in G.P. Panoh (SH: Balance work for P/L Interlocking paver Block flooring in Km 0/068 to 0/082.80)				Earnest Money Rs	2000.00	
				Time Limit:	Two Month	
Name of Bidder/ Bidding Firm/ Company :-				PRICE SCHEDULE		
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.10	Per cubic metre	384.00	2726.00	Rupees Two Thousand Seven Hundred & Twenty Six Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.44	Per Cubic metre	3932.00	17458.00	Rupees Seventeen Thousand Four Hundred & Fifty Eight Only
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge). including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	66.60	Per Square metre	1150.00	76590.00	Rupees Seventy Six Thousand Five Hundred & Ninety Only
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)) nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.59	Per Square metre	5276.00	3113.00	Rupees Three Thousand One Hundred & Thirteen Only
Total in Figures					99887.00	Rupees Ninety Nine Thousand Eight Hundred & Eighty
Excess (+)						
Qouted Rate in Figures				Less (-)		


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Exceecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99887.00
Name of work:- Restoration of Rain Damages on Mohalla Batian in G.P. Panoh (SH: Balance work for P/L Interlocking paver Block flooring in Km 0/082.80 to 0/097.60)					Earnest Money Rs	2000.00
					Time Limit:	Two Month
Name of Bidder/ Bidding Firm/ Company :-						
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.10	Per cubic metre	384.00	2726.00	Rupees Two Thousand Seven Hundred & Twenty Six Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.44	Per Cubic metre	3932.00	17458.00	Rupees Seventeen Thousand Four Hundred & Fifty Eight Only
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge). including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	66.60	Per Square metre	1150.00	76590.00	Rupees Seventy Six Thousand Five Hundred & Ninety Only
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.59	Per Square metre	5276.00	3113.00	Rupees Three Thousand One Hundred & Thirteen Only
Total in Figures					99887.00	Rupees Ninety Nine Thousand Eight Hundred & Eighty
Excess (+)						
Qouted Rate in Figures					Less (-)	


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Tender Inviting Authority:- Exceecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99776.00
Name of work:- Restoration of Rain Damages on Mohalla Batian in G.P. Panoh (SH: P/L Interlocking paver Block flooring in Km 0/097.60 to 0/112.60)					Earnest Money Rs	2000.00
					Time Limit:	Two Month
Name of Bidder/ Bidding Firm/ Company :-						
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	6.81	Per cubic metre	384.00	2615.00	Rupees Two Thousand Six Hundred & Fifteen Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.44	Per Cubic metre	3932.00	17458.00	Rupees Seventeen Thousand Four Hundred & Fifty Eight Only
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi. royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	66.60	Per Square metre	1150.00	76590.00	Rupees Seventy Six Thousand Five Hundred & Ninety Only
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)) nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in- Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.59	Per Square metre	5276.00	3113.00	Rupees Three Thousand One Hundred & Thirteen Only
Total in Figures					99776.00	Rupees Ninety Nine Thousand Seven Hundred & Seventy Six
Qouted Rate in Figures					Excess (+)	
					Less (-)	



 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Exceecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99776.00	
Name of work:- Restoration of Rain Damages on Mohalla Batian in G.P. Panoh (SH: P/L Interlocking paver Block flooring in Km 0/112.60 to 0/127.20)					Earnest Money Rs	2000.00	
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)							
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	6.81	Per cubic metre	384.00	2615.00	Rupees Two Thousand Six Hundred & Fifteen Only	
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.44	Per Cubic metre	3932.00	17458.00	Rupees Seventeen Thousand Four Hundred & Fifty Eight Only	
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	66.60	Per Square metre	1150.00	76590.00	Rupees Seventy Six Thousand Five Hundred & Ninety Only	
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.59	Per Square metre	5276.00	3113.00	Rupees Three Thousand One Hundred & Thirteen Only	
Total in Figures						99776.00	Rupees Ninety Nine Thousand Seven Hundred & Seventy Six
Qouted Rate in Figures					Excess (+)		
					Less (-)		


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana					Estimated Cost Rs	99630.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Khurwain Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour capacity, transporting mixed material with tipper and laying manually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2, 503 and 508.1, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	293.03	Per Square Metre	340.00	99630.00	Rupees Ninety Nine Thousand Six Hundred & Thirty Only
Total in Figures					99630.00	Rupees Ninety Nine Thousand Six Hundred & Thirty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Exceecutive Engineer HPPWD Division Bangana				Estimated Cost Rs	99630.00	
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Khurwain Section)				Earnest Money Rs	2000.00	
Name of Bidder/ Bidding Firm/ Company :-				Time Limit:	Two Month	
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour capacity, transporting mixed material with tipper and laying mannualy to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	293.03	Per Square Metre	340.00	99630.00	Rupees Ninety Nine Thousand Six Hundred & Thirty Only
Total in Figures					99630.00	Rupees Ninety Nine Thousand Six Hundred & Thirty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99630.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Khurwain Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty).Tonne per hour capacity, transporting mixed material with tipper and laying manually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	293.03	Per Square Metre	340.00	99630.00	Rupees Ninety Nine Thousand Six Hundred & Thirty Only
Total in Figures					99630.00	Rupees Ninety Nine Thousand Six Hundred & Thirty Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99630.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Chattara Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour caperty, transporting mixed material with tipper and laying manually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	293.03	Per Square Metre	340.00	99630.00	Rupees Ninety Nine Thousand Six Hundred & Thirty Only
Total in Figures					99630.00	Rupees Ninety Nine Thousand Six Hundred & Thirty Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99909.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Chattara Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour capcity, transporting mixed material with tipper and laying mannually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	293.85	Per Square Metre	340.00	99909.00	Rupees Ninety Nine Thousand Nine Hundred & Nine Only
Total in Figures					99909.00	Rupees Ninety Nine Thousand Nine Hundred & Nine Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD.Bangana

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Chattara Section)	Estimated Cost Rs	99736.00
	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	Two Month

PRICE SCHEDULE


(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre. 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilogramme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour capacity, transporting mixed material with tipper and laying manually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	293.34	Per Square Metre	340.00	99736.00	Rupees Ninety Nine Thousand Seven Hundred & Thirty Six Only
Total in Figures					99736.00	Rupees Ninety Nine Thousand Seven Hundred & Thirty Six Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Anil Kumar
Executive Engineer
Bangana Division
HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99960.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Teuri Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour capcity, transporting mixed material with tipper and laying manually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	294.00	Per Square Metre	340.00	99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Total in Figures					99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99960.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Teuri Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour capcity, transporting mixed material with tipper and laying manually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	294.00	Per Square Metre	340.00	99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Total in Figures					99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana					Estimated Cost Rs	99960.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Teuri Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour capacity, transporting mixed material with tipper and laying manually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	294.00	Per Square Metre	340.00	99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Total in Figures					99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana					Estimated Cost Rs	99960.00
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Dhamandri Section)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	Two Month
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender.Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour capacity, transporting mixed material with tipper and laying manually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	294.00	Per Square Metre	340.00	99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Total in Figures					99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				



 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana				Estimated Cost Rs	99960.00	
Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Dhamandri Section)				Earnest Money Rs	2000.00	
				Time Limit:	Two Month	
Name of Bidder/ Bidding Firm/ Company :-						
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour capcity, transporting mixed material with tipper and laying mannually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0 006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	294.00	Per Square Metre	340.00	99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Total in Figures					99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only
Qouted Rate in Figures				Excess (+)		
				Less (-)		


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Name of Work: Restoration of Rain Damages on various road under Dera Baba Rudru Sub-Division (SH: Patch work in Dhamandri Section)						Estimated Cost Rs	22200.00
Name of Bidder/ Bidding Firm/ Company :-						Earnest Money Rs	2000.00
						Time Limit:	Two Month
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words	
1.00	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30Kg (zero decimal three zero kilogramme) per square metre, 20 mm (twenty millimeter) compacted thickness, composed of crushed stone aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre aggregate at rate of 0.27 cum (zero point two seven cubic metres), mixed with Bitumen VG-10 at the rate 1.46 Kg (one point four six kilograme) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour capacity, transporting mixed material with tipper and laying manually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2,503 and 508.1, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	294.00	Per Square Metre	340.00	99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only	
Total in Figures					99960.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Only	
Quoted Rate in Figures		Excess (+)					
		Less (-)					


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana						Estimated Cost Rs	75000.00
Name of work:- Stock Storage at HP.PWD Sub-Division Dera Baba Rudru-Basal (SH: Supply and stacking 600mm dia & 900mm dia RCC Hume pipes)						Earnest Money Rs	1500.00
Name of Bidder/ Bidding Firm/ Company :-						Time Limit:	Two Month
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words	
1.00	Supply and Stacking RCC 900mm dia Hume pipes NP-2 (2.50 mtr length each pipe) i/c collar approved brand/ISI marked including loading & unloading and stacking properly at site, including carriage of materials within all leads and lifts and including all incidentals and as per drawings and technical specification as per the direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	6.00	Each	7000.00	42000.00	Rupees Fourty Two Thousand Only	
2.00	Supply and Stacking RCC 600mm dia Hume pipes NP-2 (2.50 mtr length each pipe) i/c collar approved brand/ISI marked including loading & unloading and stacking properly at site, including carriage of materials within all leads and lifts and including all incidentals and as per drawings and technical specification as per the direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	6.00	Each	5500.00	33000.00	Rupees Thirty Three Thousand Only	
Total in Figures					75000.00	Rupees Seventy Five Thousand Only	
Qouted Rate in Figures					Excess (+)		
					Less (-)		

Executive Engineer
Bangana Division
HP.PWD.Bangana