



**Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in**

“NOTICE INVITING TENDERS”

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **07-08-2025** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **06-08-2025** up to **4.00 P.M** and the application for issue of tender form shall be received on **06-08-2025** up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

| Sr. No. | Name of Work | Estimated Cost | Earnest Money | Time Limit | Cost of Tender form |
|---------|---|----------------|---------------|------------|---------------------|
| 1 | Restoration of rain damages on Dheera Kahanpat road km. 0/00 to 13/00 (SH:- C/O R/wall Wire crate at RD. 1/905 to 1/910) | 89,189/- | 1800/- | One Month | 350/- |
| 2 | Restoration of rain damages on Dheera Kahanpat road km. 0/00 to 13/00 (SH:- C/O R/wall Wire crate at RD. 1/900 to 1/905) | 89,882/- | 1800/- | One Month | 350/- |

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

Bal
Executive Engineer
Bhawarna Division
HPPWD Bhawarna
(On behalf of Governor of Himachal Pradesh)



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

Dated:- 11/8/2025

No. PWD/BWD/TA/NIT/2025-26/

4423-82

Copy is forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief, HPPWD. Shimla.
2. The Chief Engineer (KZ), HPPWD, Dharmsala.
3. The Superintending Engineer, 5thCircle, HPPWD.,Palampur.
4. The Deputy Commissioner, Kangra at Dharamshala.
5. The Sub-Divisional Officer (Civil) Palampur/Dheera.
6. All the S.E.s under Kangra Zone.
7. All the E.E.s under 5thCircle, HPPWD.,Palampur.
8. All the Assistant Engineers under this Division.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
10. The Drawing /Accounts Branch in this office.
11. Notice Board.

[Signature]
Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-
4423- 82 dated: 01-08-2025.

[Signature]
Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.

Draft Schedule of quantity

Name of Work :- Restoration of rain damages on Dheera Kahanpatt road Km 0/00 to 13/00

(SW:- Clo Wire crate R/wall at RD 1/905 to 1/910)

| S. No | Description of Item | Quantity | Rate | | Time Limit :- One Month | Unit | Amount Rs. |
|-------|---------------------|----------|-----------|----------|-------------------------|------|---------------|
| | | | In figure | In Words | | | |

| | | | | | | |
|---|---|-------|---------|--------------------------------------|-----------------|----------|
| 1 | Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etc in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 12.20 | 250.00 | Rupees Two Hundred Fifty Only | Per Cubic metre | 3050.00 |
| 2 | Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 150mm x150mm (One Hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 31.25 | 2600.00 | Rupees Two Thousand Six Hundred Only | Per Cubic metre | 81250.00 |
| 3 | Construction of embankment for road way with approved materials from borrowpits , or other sources in layers of suitable thickness not exceeding 200mm (Two hundred millimeter) thick each layers and compacted with 80-100 (Eighty - Hundred) K N static/ vibratory road roller to meet the requirement of table 300.1 and 300.2 of technical specifications to lines, grades, levels and cross sections as per Drawings or direction of the Engineer-in-Charge to Technical specification clause 301 and other relevant clauses including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water where ever required including handling of material for construction of embankments within all leads and lifts. The rate shall include carriage of machineries, equipments, tools and materials and safety measures payment of all taxes, octroi royalty GST and other incidentals necessary to complete the work in all respects. The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government. | 13.70 | 220.00 | Rupees Two Hundred Twenty Only | Per Cubic metre | 3014.00 |

| | | | | | |
|--|------|--------|--------------------------|-----------------|----------|
| Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 3.75 | 500.00 | Rupees Five Hundred Only | Per Cubic metre | 1875.00 |
| | | | | Total:- | 89189.00 |
| Quoted rates percentage in figures | | | | | |
| Quoted rates percentage in words | | | | | |

b/w
Executive Engineer
Bhawarna *b/w* Division
HP PWD Bhawarna

Schedule of quantity

Work :- Restoration of rain damages on Dheera Kahanpatt road Km 0/00 to 13/00

No Wire crate R/wall at RD 11900 to 11905)

Estimate Cost :- 89,882/-
Earnest Money :- 1800/-
Time Limit :- One Month

| Description of Item | Quantity | In figure | In Words | Rate | Unit | Amount |
|--|-----------------|------------------|--------------------------------------|-----------------|-------------|---------------|
| 1 Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapet's etc/tra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 12.20 | 250.00 | Rupees Two Hundred Fifty Only | Per Cubic metre | 3050.00 | |
| 2 Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 150mm x150mm (One Hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 31.25 | 2600.00 | Rupees Two Thousand Six Hundred Only | Per Cubic metre | 81250.00 | |
| 3 Construction of embankment for road way with approved materials from borrowpits , or other sources in layers of suitable thickness not exceeding 200mm (Two hundred millimeter) thick each layers and compacted with 80-100 (Eighty - Hundred) K.N static/ vibratory road roller to meet the requirement of table 300.1 and 300.2 of technical specifications to lines, grades, levels and cross sections as per Drawings or direction of the Engineer-in-Charge to Technical specification clause 301 and other relevant clauses including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water where ever required including handling of material for construction of embankments within all leads and lifts. The rate shall include carriage of machineries, equipments, tools and materials and safety measures payment of all taxes, octroi royalty GST and other incidentals necessary to complete the work in all respects.The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 16.85 | 220.00 | Rupees Two Hundred Twenty Only | Per Cubic metre | 3707.00 | |

back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.

| | | | | | | |
|------------------------------------|--|------|--------|--------------------------|-----------------|----------|
| Quoted rates percentage in figures | | 3.75 | 500.00 | Rupees Five Hundred Only | Per Cubic metre | 1675.00 |
| Quoted rates percentage in words | | | | | Total:- | 89882.00 |


Executive Engineer
Bhawarna Division
HP PWD Bhawarna