

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Scaled item rate / percentage rate tender are hereby invited on Form No. 6 & 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 06-09-2025 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 06-09-2025 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 08-09-2025 at 10.30 AM.
4. Date of opening of Tender:- 08-09-2025 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	R/R damages on Chhoun to Dharyara road Km 0/00 to 2/750 (SH:- C/O B/wall at RD 1/420 to 1/429)	99753/-	2000/-	Two Months	Rs. 350/-	Class D
2	A/R & M/O Una Aghar Mandi road (SH:- Providing & installation of Crash barrier at RD 77/055 & 77/170)	93600/-	2000/-	Two Months	Rs. 350/-	Class D
3	A/R & M/O Non Residential Building HPPWD Bhoranj (SH:- P/F Inverter including Battery and all other Accessories in Division office.	99500/-	2000/-	Two Months	Rs. 350/-	Class D
4	A/R & M/O Non Residential Building HPPWD Bhoranj (SH:- Supply of Computer in Division office Building)	99500/-	2000/-	Two Months	Rs. 350/-	Class D
5	C/O link road Jeevan Dutt House to Sulgwan Jahu via Hour road in Tehsil Bhoranj Distt Hamirpur (HP) (SH:- P/L Interlocking paver block at RD 0/00 to 0/59) (VKV/2025/125)	4,83,682/-	10000/-	Two Months	Rs. 350/-	Class D
6	C/O link road Una - Aghar Mandi to Om furniture Factory in Tehsil Bhoranj Distt Hamirpur (HP) (SH:- P/L interlocking paverblock at RD 0/00 to 0/59) (VKV/2025/124)	4,82,312/-	10000/-	Two Months	Rs. 350/-	Class D
7	C/O link road to Dimple shop to Dohag Km 0/00 to 1/00 (SH:- P/L GSB, CC Pavement at RD 0/250 to 0/375) VKV/2025/123)	4,76,774/-	10000/-	Two Months	Rs. 350/-	Class D
8	C/O Community Hall at Beharwin (SH:- C/O B/wall back side of proposed Building) VKV/2023/732	1,96,170/-	4000/-	Two Months	Rs. 350/-	Class D

9	C/O link road to village Doh to Doh km 2/00 to 2/360 (Extended portion) (SH:- C/O R/wall at RD 0/320 to 0/335 & PCC at RD 2/305 to 2/340) (VKV/ 2025/128 & 129)	2,86,772/-	6000/-	Two Months	Rs. 350/-	Class-D
10	A/R & M/O various road under Bhoranj Sub Division (Section Jahu) (SH:- Painting and writing of sign board Km stone and village board etc.	99,961/-	2000/-	Two Months	Rs. 350/-	Class-D
11	R/M of Una - Aghar - Mandi road Km 79/00 to 91/00 (SH:- Maintenance of earthen shoulder at various RD's)	99,913/-	2000/-	Two Months	Rs. 350/-	Class-D
12	R/M of Tikker Khatrian to Kulehra Bajwal Km 0/00 to 2/500 (SH:- Maintenance of earthen shoulder, unlined surface drain and removal of slips)	99,028/-	2000/-	Two Months	Rs. 350/-	Class-D
13	R/R damages on Manoh to lagmanwin road Km 0/00 to 2/600 (SH:- P/L CC pavement at RD 0/970 to 1/005)	99,680/-	2000/-	Two Months	Rs. 350/-	Class-D
14	R/R damages on Manoh to Lagmanwin road Km 0/00 to 2/600 (SH:- P/L CC pavement at RD 0/900 to 0/935)	99,680/-	2000/-	Two Months	Rs. 350/-	Class-D
15	A/R & M/O on various roads under Samirpur Sub Division (SH:- Repair of pot hole at various RDs) (Chamboh Section)	99,900/-	2000/-	Two Months	Rs. 350/-	Class-D
16	A/R & M/O on various roads under Samirpur Sub Division (SH:- Repair of pot hole at various RDs) (Chamboh Section)	99,563/-	2000/-	Two Months	Rs. 350/-	Class-D
17	R/M of various roads under Samirpur Sub Division HPPWD Division Bhoranj (Section Dho) (SH:- Repair & Maintenance of earthen shoulder , unlined surface drain at various RDs and Removal of slip)	99550/-	2000/-	Two Months	Rs. 350/-	Class-D
18	Repair and maintenance on Bassi -Tikker road (SH:-C/O V-shape drain at RD 2/650 to 2/705.50)	99977/-	2000/-	Two Months	Rs. 350/-	Class-D
19	R/M of various roads under Samirpur Sub Division HPPWD Bhroanj (Section Dho) (SH:- Repair & Maintenance of earthen shoulder, unlined surface drain at various RDs and Removal of slip)	99454/-	2000/-	Two Months	Rs. 350/-	Class-D
20	A/R & M/O various roads under Bhoranj Sub Division (SH:- Painting & writing letters of information sign boards, Km stone and other road side furniture etc) (Section Bhareri)	98203/-	2000/-	Two Months	Rs. 350/-	Class-D
21	Repair and maintenance on Bassi - Tikker road (SH:- C/O V-shape drain at RD 2/705.50 to 2/761)	99977/-	2000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj
For and on behalf of Governor of HP.

No:-PW/BHD/TA/NIT/2025-

7060-84

Dated:- 28-08-2025

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj, Various Contractors/ Firms.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

Job-1

NAME OF WORK:- R/R Damages on Chhoun to Dharyara Road km. 0/00 to 2/750.(SH:- C/O B/Wall at RD 1/420 to 1/429)

Estimated Cost
Earnest Money
Time

Rs 99753/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	10.00	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	22.21	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.00	Each			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoran] Division
HQ PWD Bhoran]

SCHEDULE OF QUANTITY

Job-2

NAME OF WORK:- A/R & M/O Una-Aghar-Mandi road.(Providing & Installation of crash barrier at RD 77/055 & 77/170)

Estimated Cost
Earnest Money
Time

Rs 93600/-
Rs.2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size i/c erecting W metal beam crash barrier comprising 3 mm thick corrugated sheet metal beam rail 70 cm (seventy centimeter) above the ground level fixed on ISMC series channel vertical post 150x75x5 mm spaced 2 mtr Centre to centre 1.80 mtr. Height 1.010 meter below ground/road level and steel parts or fitment to be galvenised by hot dip process , all fitting to confirm to IS 1367 , metal beam rail to be fixed on the vertical posts with a spacer of channel section 150x75x5 mm 330 m long complete as per clause 810 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	24.00	Per running metre			
	Total					

Terms and Condition:-

1 Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

Job-3

NAME OF WORK:- A/R & M/O Non Residential Building HPPWD Bhoranj.(SH:- P/F Inverter including Battery and all other Accessories in Division office Building).

Estimated Cost
Earnest Money
Time
Rs. 99,500/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Microtek UPS Jumbo inverter 3.6 KVA as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1	Each			
2	Microtek 150 Ah Battery advanced Dura core for long life Heavy duty Tubular battery for longer power backup as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2	Each			
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

Job-4

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O Non Residential Building HPPWD Bhoranj.(SH:- supply of Computer in Division office Building).

Estimated Cost
Earnest Money
Time

Rs 99,500/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	All in One make with Intel Core i5/R5-Processor,, 16 GB, 1TB SSD, 23" LED Color display with FHD (1920x1080), Integrated HD Graphics & 5 MP pull up webcam with Integrated Dual array and digital microphone, 2xUSB 3.0, 2xUSB 2.0, Audio jack/VGA/HDMI/DP Port, 10/100/1000M compliant LAN, WiFi 6 with Bluetooth 5.0, Wireless Keyboard & Mouse, Internal Speaker connectivity: 802.11 b/g/n/ac, PL- Windows 11 64 bit OS:- with Three years onsite warranty.as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1	Each			
2	Canon make MFP Model 3010 with Print including wifi function, Scan and Copy facility (A4 size Printer) : Prints upto 30ppm, 64MB RAM, 250 Pages input Tray capacity, High speed USB Port, Wi-fi with One Year Warranty.as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1	Each			
3	1000VA Offline UPS System with 12V*7Ah*2 Nos. (168VAH) SMF batttries to provide 15-20 min backup (03 Years warranty on UPS & 12 months on batteries from deliver date).as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1	Each			
<u>Terms and Condition:-</u>						

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

Job-5

OF WORK:- C/O link road Jeevan Dutt House to Sulgwan jahu via Hour Road in Teh. Bhoranj Distt. Hamirpur (H.P). (SH:- P/L Interlocking block at RD 0/00 to 0/59.) (VKV/2025/125)


Estimated Cost
Earnest Money
Time

Rs 483682/-
Rs. 10000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Providing and laying cement concrete 1:4:8 (1cement :4:sand : 8 graded stone aggregates 40mm nominal size) and curing complete including cost of form work in foundation and plinth.as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	24.78	Per Cubic Meter			
2	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (n.t.c or its equilant ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government	236.00	Per square meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2.36	Per Cubic Meter			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

Jul-6

WORK:- C/O link road Una-Aghar-Mandi to Om Furniture Factory in Teh. Bhoranj Distt. Hamirpur (H.P). (SH:- P/L Interlocking paverblock at to 0/59.) (VKV/2025/124)


Estimated Cost
Earnest Money
Time

Rs 482312/-
Rs. 10000/-
2Months

	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Providing and laying cement concrete 1:4:8 (1cement :4:sand : 8 graded stone aggregates 40mm nominal size) and curing complete including cost of form work in foundation and plinth.as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.00	Per Cubic Meter			
2	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (n.t.c or its equilant ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government	299.00	Per square meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.52	Per Cubic Meter			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 H.P.WD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O link road to Dimple Shop to Dohag km. 0/00 to 1/00. (SH:- P/L GSB, C.C.Pavement at RD 0/250 to 0/375.) (VKV/2025/123)

Estimated Cost
Earnest Money
Time

Rs 476774/-
Rs. 10000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularation on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	437.50	Per square metre			
2	P/L granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-ChargeWith material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	38.12	Per cubic Meter			
3	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M-ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	38.12	Per cubic meter			
4	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	28.59	Per Cubic Meter			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR PWD Bhoranj

Job-8

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O Community Hall at Beharwin (S.H :- C/o B/wall back side of proposed Building) VKV/2023/732

Estimated Cost
Earnest Money
Time

Rs 1,96,170/-
Rs. 4000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includinmg dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.16	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cment:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may anse at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	43.00	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	19.00	Each			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Job-9

SCHEDULE OF QUANTITY

OF WORK:- C/O link road to village Doh to Doh km. 2/00 to 2/360(Extended Portion).(SH:- C/O R/Wall at RD 0/320 to 0/335 & PCC at RD 2/305 to (VKV/2025/128 & 129).


Estimated Cost
Earnest Money
Time

Rs 286772/-
Rs. 6000/-
2 month

	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	23.54	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	31.60	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	12.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.75	Per Cubic Meter			
5	Providing , laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical paver finisher in sub base/base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, completed as per specification and directions of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.	11.00	Per Cubic Meter			

Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.00	Per cubic meter			
Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	11.00	Per Cubic Meter			
Total					
Terms and Condition:-					

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 H.P.W.D Bhoranj

26-9

Job - 10

SCHEDULE OF QUANTITY


NAME OF WORK:- A/R & M/O various road under Bhoranj Sub- Division (Section Jahu) (SH:- Painting and writing of sign board Km. Stone and village board etc.).

Estimated Cost
Earnest Money

Rs 99961/-
Rs. 2000/-

Sr No	Description of Items	Quantity	Unit	Rate	Time	2 Months
					Rates in Words	Amount
1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One or more coats on old work as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	77.20	Per Square Meter			
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	39.96	Per Square Meter			
3	Re-lettering with black Japan paint of approved brand and manufacture as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	23650.00	Per letter/Per cm ht.			
Terms and Condition:-						

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HP PWD Bhoranj

Job-11

SCHEDULE OF QUANTITY

NAME OF WORK:-R/M of Una-Aghar-Mandi road. Km 79/00 To 91/00
(SH:- Maintenance of earthen shoulder at various RD's.)

Estimated Cost Rs. 99913
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1198.00	Per square metre			
	Total					

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

Job-12

NAME OF WORK:- R/M of Tikker Khatrian to Kulehra Bajwal km. 0/00 to 2/500.
Maintenance of earthen shoulder , unlined surface drain and Removal of Slips.)

Estimated Cost
Earnest Money
Time
Rs. 99028/-
Rs. 2000/-
2Months

Sl. No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	807.50	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	510.00	Per Running Mtr			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	133.50	Per cubic metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification

Executive Engineer
 Bhoranj Division
 HP PWD Bhoranj

Job-13

SCHEDULE OF QUANTITY

AE OF WORK:- R/R damages on Manoh to Lagmanwin road km. 0/00 to 2/600. (SH:- P/L C.C.Pavement at RD 0/970 to 1/005.)

Estimated Cost
Earnest Money
Time

Rs 99,680/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Providing and laying cement concrete 1:4:8 (1cement :4:sand : 8 graded stone aggregates 40mm nominal size) and curing complete including cost of form work in foundation and plinth.as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	11.20	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.40	Per Cubic Meter			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR PWD Bhoranj

Job-14

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on Manoh to Lagmanwin road km. 0/00 to 2/600. (SH:- P/L C.C.Pavement at RD 0/900 TO 0/935.)


Estimated Cost
Earnest Money
Time

Rs 99,680/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Providing and laying cement concrete 1:4:8 (1cement :4:sand : 8 graded stone aggregates 40mm nominal size) and curing complete including cost of form work in foundation and plinth,as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	11.20	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.40	Per Cubic Meter			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HRPWD Bhoranj

SCHEDULE OF QUANTITY

Job-15

DESCRIPTION OF WORK:- A/R & M/O on various roads under samirpur Sub-Division . (SH:- Repair of Pot Hole at various RDs.) (Chamboh Section)

Estimated Cost
Earnest Money
Time

Rs 99900/-
Rs. 2000/-
2Months

No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-30 bitumen specification clause 1904-2,503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	190.00	Per square metre			
2	Providing Laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone scseening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	14.00	Per cubic meter			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

Job-16

DESCRIPTION OF WORK:- A/R & M/O on various roads under samirpur Sub-Division . (SH:- Repair of Pot Hole at various RDs.) (Chamboh Section)


Estimated Cost
Earnest Money
Time

Rs 99563/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-30 bitumen specification clause 1904-2,503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	200.00	Per square metre			
2	Providing Laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone scseening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	12.25	Per cubic meter			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 H.P. PWD Bhoranj

Job-17

SCHEDULE OF QUANTITY


NAME OF WORK:- R/M of Various roads under Samirpur Sub Division HPPWD Division Bhoranj (Section Dho) (SH:- Repair & Maintenance of earthen shoulder, Unlined Surface drain at Various RDs and Removal of Slip)

Estimated Cost
Earnest Money
Time

Rs 99,550/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	926.25	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	255.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	118.43	Per Cubic metre			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HPPWD Bhoranj

Job-18

SCHEDULE OF QUANTITY

OF WORK:- Repair and Maintenance on Bassi - Tikker road .(SH:-C/O V-shape drain at RD 2/650 to 2/705.50.)

Estimated Cost
Earnest Money
Time

Rs 99977/-
Rs. 2000/-
2 month

No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP:PWD., specification 100mm(one hundred millimeters) spread thickness (finished work including materials and labour) in all leads and lifts and dressing of sides and bottom and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	14.00	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	16.09	Per cubic meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HR PWD Bhoranj

Job-19

SCHEDULE OF QUANTITY


NAME OF WORK:- R/M of Various roads under Samirpur Sub Division HPPWD Division Bhoranj (Section Dho) (SH:- Repair & Maintenance of earthen shoulder, Unlined Surface drain at Various RDs and Removal of Slip)

Estimated Cost
Earnest Money
Time

Rs 99,454/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	842.50	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	320.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	158.25	Per Cubic metre			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HPPWD Bhoranj

Job-20

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK:-A/R & M/O Various roads under Bhoranj Sub division. (SH:- Painting & writing letters of information sign boards, km Stone and other road side furniture etc.) (Section Bhareri)

Estimated Cost
Earnest Money

Rs 98203/-
Rs 2000/-

Time

2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Painting with synthetic ename paint of approved brand and manufacture of required colour to give an even shade 13.99.1 one or more coat on old works.including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	55	Per sqm	89.40	Rupees eighty nine and paise forty only	4917.00
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade 13.62.1 Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	60	Per Sqm	125.80	Rupees one hundred twenty five and paise eighty only	7548.00
3	Wall painting road side kerv stone with acrylic cement emulsion approved brand and manufacture of required colour to give an even shade Two or more coats .including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	120	Per Sqm	128.65	Rupees one hundred thirty nine only	15438.00
4	Re-lettering with black Japan paint of approved brand and manufacture.including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	19000	Per letter. Per cm ht.	3.70	Rupees three and paise seventy only	70300.00
Total						98203.00

Terms and Condition:-

DNIT . NO:- 586 for the year 2024-25 recommended for approval for Rs 98203/-(Rupees Ninety eight thousand two hundred three only.)

1. Work shall be executed as per PWD specification.




Executive Engineer
Bhoranj Division
HR PWD Bhoranj

Job-21

SCHEDULE OF QUANTITY

DESCRIPTION OF WORK:- Repair and Maintenance on Bassi - Tikker road .(SH:-C/O V-shape drain at RD 2/705.50 to 2/761.00.)

Estimated Cost
Earnest Money
Time

Rs 99977/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP:PWD., specification 100mm(one hundred millimeters) spread thickness (finished work including materials and labour) in all leads and lifts and dressing of sides and bottom and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	14.00	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	16.09	Per cubic meter			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D. Bhoranj