

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

***NOTICE INVITING TENDER**

Engineer, Bilaspur Division No.II, HP. PWD., Bilaspur (H.P) from the eligible contractors of the appropriate class registered in HP.PWD., as per revised enlistment rules so as to reach in the office undersigned on 02.09.2025 upto 10.30AM and will be opened on the same day at 11.00AM in the presence of intending contractors. The tender application will be received in this office alongwith cash payment on account of cost of tender form and the tender form can be had from this office on any working day upto 2.00 PM. On dated 01.09.2025. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued to contractor on production of proof of enlistment, GST and Pan No etc. Conditional tender and tender received without earnest money will be rejected straightway. The offer of the tender shall be kept open for 45 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

| S. No. | Name of work | Estimated of cost | Earnest Money | Cost of form | Time limit |
|--------|---|-------------------|---------------|--------------|--------------|
| 1 | Restoration of Rain Damages on Kutehla Kiyarian Bagchhal road Km.0/00 to 10/815(SH:-Hiring of Excavator cum rock breaker for removal of rocks at various RDs) for the year 2025-26 Job No.4 | Rs.99,648/- | Rs.2,000/- | Rs.350/- | One Month |
| 2 | Restoration of Rain Damages on Deoth Lagghat Jamli road Km.0/00 to 13/180(SH:-Hiring of Excavator cum rock breaker for removal of rocks at various RDs) for the year 2025-26 Job No.6 | Rs.99,648/- | Rs.2,000/- | Rs.350/- | One Month |
| 3 | Balance work of link road NH-21 Jamli to Neri Km.(G.P Chharol) Km.0/00 to 2/150(SH:-Providing and Laying correction Layer G-III in Km.1/195 to 1/720) | Rs.98,490/- | Rs.2,000/- | Rs.350/- | One Month |
| 4 | Restoration of Rain Damages on link road Swarghat to Village Bag Km.0/00 to 2/000(SH:-Construction of R/Wall at RD.0/044.00 to 0/048.60) | Rs.97,483/- | Rs.2,000/- | Rs.350/- | Three Months |
| 5 | Restoration of Rain Damages on Kutehla Kiyarian Bagchhal road Km.0/00 to 10/815(SH:-Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms,clearance of drain at various RDs.5/00 to 10/815) for the year 2025-26 Job No.3 | Rs.99,708/- | Rs.2,000/- | Rs.350/- | One Month |
| 6 | Restoration of Rain Damages on link road to Village Mayoht Km.0/00 to 6/930(SH:-Hiring of Excavator cum loader /JCB for removal of slips and dressing of berms, clearance of drain at various RDs) for the year 2025-26 Job No.2 | Rs.99,708/- | Rs.2,000/- | Rs.350/- | One Month |

Certified that tenders are being called for due to exigencies of works in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No.II, HP.PWD, Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate of each item both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

No.PW/NBT/CB/Tender-State/EA-1/2025-

5893-5900

Dated:-

25/08/2025

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HP.PWD., Hamirpur.
3. The Superintending Engineers, 10th Circle, HP. PWD., Bilaspur.
4. The Executive Engineers (IT) O/o Engineer-in-Chief, HP.PWD., Shimla through [email-eeict-pwd-shi@hp.gov.in](mailto:eeict-pwd-shi@hp.gov.in) & cc-pwd-hp@nic.in for uploading the same on HP.PWD web portal.
5. The Assistant Engineer, HP.PWD., Sub-Division No.III Bilaspur/ Swarghat .
6. Drawing Branch in this office/ Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

| | | | |
|--------------|-------------|-----------|-------|
| Rs. 97,483/- | Rs. 2,000/- | Rs. 350/- | Month |
| Rs. 99,708/- | | | |

1.1.2.946 1-7-18

| | | |
|--|--|-------------------------------------|
| SCHEDULE OF QUANTITY. | | Estimated Cost:- Rs.=99,648 /-Only. |
| | | Earnest Money:- Rs.= 2,000/-Only. |
| | | Time:- One Month. |
| Name of work :- Restoration of Rain Damages on kutehla Kiyarian Bagchhal road km 0/00 to 10/815 (SH):- Hiring of Excavator cum rock breaker for removal of rocks at various Rds) For the Year 2025-26 Job No.-4 | | |

| Sr No. | Description of items. | Quantity | | Rate In | | Unit | Amount |
|------------------------------|---|----------|-------|-----------|-----------|-----------|--------|
| | | 3 | 4 | In Figure | In words. | | |
| 1 | 2 Hiring of Excavator cum rock breaker for removal of rocks in all kind of rocks such as soft or hard rock complete as per direction Engineer -in -Charge i/c P.O.L charges and other establishment requaied at site i.e operator. cleaner and staff and incidental charges i/c stacking of seviceable material and disposal of un serviceable material in all lead and lifts as per direction and instruction of Engineer-in- charge.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 48.00 | Hours | | | Per Hours | |
| Terms and Condition:- | | | | | | | |
| 1 | The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge | | | | | | |
| 2 | The one number Exacavator cum rock breaker will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery | | | | | | |
| 3 | No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period | | | | | | |
| 4 | The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work | | | | | | |
| Total | | | | | | | |


 For the Engineer
 District Engineer
 H.P.P.W.D.

SCHEDULE OF QUANTITY.

Estimated Cost:- Rs.=99,648 /-Only.

Earnest Money:- Rs.= 2,000/-Only.

Time:- One Month.

Name of work :- Restoration of Rain Damages on Deoth Lagghat Jamli road km 0/00 to 13/180(SH:- Hiring of Excavator cum rock breaker for removal of rocks at various Rds) For the Year 2025-26 Job No.-6

| Sr No. | Description of items. | Quantity | | Rate In | | Unit | Amount |
|------------------------------|--|-----------|-----------|---------|---|-----------|--------|
| | | In Figure | In words. | | | | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| 1 | Hiring of Excavator cum rock breaker for removal of rocks in all kind of rocks such as soft or hard rock complete as per direction Engineer -in -Charge i/c P.O.L charges and other establishment requaied at site i.e operator, cleaner and staff and incidental charges i/c stacking of seviceable material and disposal of un serviceable material in all lead and lifts as per direction and instruction of Engineer-in- charge.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 48.00 | Hours | | | Per Hours | |
| Terms and Condition:- | | | | | | | |
| 1 | The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge | | | | | | |
| 2 | The one number Excavator cum rock breaker will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery | | | | | | |
| 3 | No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period | | | | | | |
| 4 | The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work | | | | | | |
| Total | | | | | | | |

Engineer,
H.P.P.W.D.

6

| SCHEDULE OF QUANTITY. | | | | Estimated cost:- Rs.98,490/-Only. | | | |
|---|--|----------|-------|-----------------------------------|--------|-----------------------|--------|
| | | | | Earnest Money :- Rs.2,000/- | | | |
| | | | | Time:- One Month. | | | |
| NAME OF WORK:- Balance work of link road NH-21 Jamli to Neri km (G.P Chharol) km 0/00 to 2/150 (SH:- Providing and Laying correction Layer G-III in km 1/195 to 1/720) | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rates in | | Unit | Amount |
| | | | | Figure. | Words. | | |
| | | 3 | | 4 | 5 | 6 | 7 |
| 1 | 2 | 42.00 | Cubic | | | Per Cubic metre | |
| 1 | Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge..The rates includes octroi,royalty ,Malkana toll tax ,goods and service ,building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | | | | | |
| Total:- | | | | | | | |


 ENGINEER
 DISTRICT
 ROAD
 BHILAI

SCHEDULE OF QUANTITY

Estimated cost - Rs 97,483/- Only

Earnest Money - Rs 2,000/-

Time - Three Months

NAME OF WORK:- Restoration of R in Damages on Link road Swarghat to village Bag km 0/00 to 2/000 (SH:- Construction of R/wall at Rd 0/044 00 to 0/048 60)

| Sr No. | Description of items | Quantity | Rates in | | Unit | Amount |
|---------|---|----------|-------------|-------|-----------------|--------|
| | | | Figure | Words | | |
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge ordinary road including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same | 6.72 | Cubic metre | | Per Cubic metre | |
| 2 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement, Five coarse sand, Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same | 19.09 | Cubic metre | | Per Cubic metre | |
| 3 | Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same | 5.43 | Cubic metre | | Per Cubic Metre | |
| 4 | Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same | 8.00 | Nos | | Each | |
| Total:- | | | | | | |

| | | | | | | | |
|---|--|----------|-------|--------------------------------------|----------|-----------|--------|
| SCHEDULE OF QUANTITY. | | | | Estimated Cost :- Rs =99,708 /-Only. | | | |
| | | | | Earnest Money :- Rs = 2,000/-Only. | | | |
| | | | | Time :- One Month | | | |
| Name of work :- Restoration of Rain Damages on kutehla Kiyarian Bagchhal road km 0/00 to 10/815 (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various Rd 5/00 to 10/815) For the Year 2025-26 Job No.-3 | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rate In | | Unit | Amount |
| | | | | In Figure | In words | | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| 1 | Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip The rate includes octon, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same | 84.00 | Hours | | | Per Hours | |
| Terms and Condition:- | | | | | | | |
| 1 | The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge | | | | | | |
| 2 | The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery | | | | | | |
| 3 | No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period | | | | | | |
| 4 | The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work | | | | | | |
| Total | | | | | | | |


 Date: _____
 Place: _____

| SCHEDULE OF QUANTITY. | | Estimated Cost:- Rs.=99,708 /-Only. | | | | | |
|---|--|-------------------------------------|-----------|---------|---|-----------|--------|
| | | Earnest Money:- Rs.= 2,000/-Only. | | | | | |
| | | Time:- One Month. | | | | | |
| Name of work :- Restoration of Rain Damages on link road to village Mayooh km 0/00 to 6/930 (SH:- Hiring of Excavator cum loader/JCB for removal of slips and dressing of berms, clearance of drain at various Rds) For the Year 2025-26 Job No.-2 | | | | | | | |
| Sr No. | Description of items. | Quantity | | Rate In | | Unit | Amount |
| | | In Figure | In words. | | | | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| 1 | Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 84.00 | Hours | | | Per Hours | |
| Terms and Condition:- | | | | | | | |
| 1 | The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge | | | | | | |
| 2 | The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery | | | | | | |
| 3 | No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period | | | | | | |
| 4 | The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work | | | | | | |
| Total | | | | | | | |


 For work done
 Date: 20/05/2025
 H.R. P. W. D.

