



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Tel.01899-299219.

cepwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2025-26-

To

3495-97

Dated:- 19/8/2025

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

(Signature)
Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Certificate

Certified that the tenders called vide this office letter No. PWD-CHW/Tender
/2025-26 3495-97 dated 18.8.21 is emergent nature and in Public interest.

21-8/01
FP-2018
Executive Engineer,
Chowari Division,
HPPWD, Chowari.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons: -

1 Date of issued/sale of tender form against

25.08.2025

Cash payment (nonrefundable).

2 Date of open of tender

26.08.2025

The tender shall be received upto **11.00 AM** on **26.08.2025** and will be opened on the day of **26.08.2025 at 12.00 PM** in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Nonrefundable) during the working hours on **25.08.2025**.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons: -

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	Restoration of Rain damage on Bad-Draman to Banoli road Km. 0/0 to 3/500 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 3/500).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
2	Restoration of Rain damage on Dugred Pukhred Naloh road Km. 0/0 to 6/210 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 6/210).	51540.00	1100.00	Rs. 350/-	One Month	Class-D & C
3	Restoration of Rain damage on Thulel to Anai road Km. 0/0 to 2/400 (SH:- Hiring of Excavator cum loader & Tipper for removal of slips in between Km. 0/0 to 2/400)	99150.00	2000.00	Rs. 350/-	One Month	Class-D & C
4	Restoration of Rain damage on Motla Gola Kathla road Km. 0/0 to 7/00 (SH:- Hiring of Excavator cum loader & Tipper for removal of slips in between Km. 3/0 to 7/000)	99150.00	2000.00	Rs. 350/-	One Month	Class-D & C
5	Restoration of Rain damage on Shahpur Sihunta Chowari road Km. 0/0 to 24/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 5/0 to 7/950).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C

6	Restoration of Rain damage on Samote Dramnala road Km. 0/0 to 12/435 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 4/930).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
7	Restoration of Rain damage on Dukhar Morthu road Km. 0/0 to 8/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 2/950).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
8	Restoration of Rain damage on Balana to Gola road Km. 0/0 to 8/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 3/0).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
9	Restoration of Rain damage on link road to village Nahana Km. 0/0 to 4/100 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 2/0)	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
10	Restoration of Rain damage on Patka to Hathidar road Km. 0/0 to 10/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 3/890).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
11	Restoration of Rain damage on Patka to Dadriyada road Km. 0/0 to 14/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 3/810).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
12	Restoration of Rain damage on Motla Sukhiyad road Km. 0/0 to 9/0 (SH:- Hiring of Excavator cum loader & Tipper for removal of slips in between Km. 0/0 to 3/0)	99510.00	2000.00	Rs. 350/-	One Month	Class-D & C
13	Restoration of Rain damage on Shahpur Sihunta Chowari road Km. 0/0 to 24/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 12/330 to 15/940).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
14	Restoration of Rain damage on Motla Sukhiyad road Km. 0/0 to 9/0 (SH:- Hiring of Excavator cum loader & Tipper for removal of slips in between Km. 5/500 to 8/0)	99510.00	2000.00	Rs. 350/-	One Month	Class-D & C
15	Restoration of Rain damage on Balana to Gola road Km. 0/0 to 8/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 5/150 to 7/0).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
16	Restoration of Rain damage on Patka to Dadriyada road Km. 0/0 to 14/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 4/050 to 6/915).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C

17	Restoration of Rain damage on Link road to village Dangari Km. 0/0 to 5/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 3/00 to 5/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
18	Restoration of Rain damage on Link road to village Dangari Km. 0/0 to 5/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 1/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
19	Restoration of Rain damage on Link road to village Dangari Km. 0/0 to 5/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 1/200 to 3/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
20	Restoration of Rain damage on Chowari Mandhiar Baloh Fagot road Km. 0/0 to 8/700 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 2/500).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
21.	Restoration of Rain damage on Chowari Mandhiar Baloh Fagot road Km. 0/0 to 8/700 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 2/700 to 6/500).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
22	Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 17/100 to 21/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
23	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 22/100 to 25/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
24.	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 18/500 to 22/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
25	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 15/390 to 18/105).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
26.	Restoration of Rain damage on Link road to Village Fakrodu Km. 0/00 to 2/700 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 1/500).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C

27	Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 1/00 to 2/00).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
28.	Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 7/00 to 14).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
29	Restoration of Rain damage on Chowari Mandhiar Baloh Fagot road Km. 0/0 to 8/700 (SH:- Hiring of Tipper for shifting of muck / debris in between Km. 0/00 to 2/500).	97680.00	2000.00	Rs. 350/-	One Month	Class-D & C
30	Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00 (SH:- Hiring of Tipper for shifting of muck / debris in between Km. 16/00 to 21/00).	99900.00	2000.00	Rs. 350/-	One Month	Class-D & C
31.	Restoration of Rain damage on Ghatasani Pull to Bhalog road Km. 0/0 to 7/360 (SH:- Supplying and Stacking of Stone Boulders at RD. 0/195).	99098.00	2000.00	Rs. 350/-	One Month	Class-D & C
32.	Restoration of Rain damage on Shahpur Sihunta Chowari Jot Chamba road Km. 40/0 to 53/00 (SH:- Providing and Laying Wire crate for protection of Toe At RD. 49/800 to 49/809.50).	99519.00	2000.00	Rs. 350/-	One Month	Class-D & C
33	Restoration of Rain damage on Dukhai to Morthu road Km. 0/00 to 8/00 (SH:- Construction of R-wall at RD. 0/515.10 to 0/517.60).	97066.00	2000.00	Rs. 350/-	One Month	Class-D & C
34	Restoration of Rain damage on various road under Chowari Sub Division (SH:- Hiring of Excavator cum loader for removal of slips in various reaches).	94500.00	1900.00	Rs. 350/-	One Month	Class-D & C
35	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 25/00 to 40/810 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 30/00 to 32/00).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
36	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 25/00 to 40/810 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 34/00 to 36/00).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
37	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 25/00 to 40/810 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 36/00 to 40/810).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C

38	Restoration of Rain damage on Patka to Dalhousie road Km. 45/0 to 67/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 45/500 to 50/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
39	Restoration of Rain damage on Nanikhad to Samleu road Km. 0/0 to 30/585 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 20/00 to 23/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
40	Restoration of Rain damage on Nagali to Sanjap road Km. 0/0 to 8/450 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 5/00 to 7/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
41	Construction of link road Bagdhar to Chhuuni Km 0/0 to 3/350 (SH:- C/o R/wall with Pustha at RD 2/542.50 to 2/545.10).	99247.00	2000.00	Rs. 350/-	One Month	Class-D & C

- 3 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- 4 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
- 5 GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.

(Signature)
Executive Engineer,
Chowari Division,
HPPWD, Chowari.

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Bad-Draman to Banoli road Km. 0/0 to 3/500 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 3/500).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
					Total: -	

(Signature)
 Executive Engineer
 Chowari Division
 HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 51450.00
 Earnest Money :- Rs. 1100.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Dugred Pukhred Naloh road Km. 0/0 to 6/210 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 6/210).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royality ,malkana toll tax sale tax or any other taxes imposed by the Government.	49.00			Per Hours	
Total:-						

(Signature)
 Executive Engineer
 Chowari Division
 HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99150.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Thulel to Anai road Km. 0/0 to 2/400 (SH:- Hiring of Excavator cum loader & Tipper for removal of slips in between Km. 0/0 to 2/400)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	68.00			Per Hours	
2	Hiring of tipper having capacity 5.50 (Five decimal five Zero) cubic metre for carriage of all type material up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge.	50.00			Per Hours	
					Total:-	

(Signature)
Executive Engineer
Chowari Division
HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99150.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Motta Gola Kathla road Km. 0/0 to 7/00 (SH:- Hiring of Excavator cum loader & Tipper for removal of slips in between Km. 3/0 to 7/000)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	68.00			Per Hours	
2	Hiring of tipper having capacity 5.50 (Five decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	50.00			Per Hours	
					Total: -	

(Signature)
Executive Engineer
Chowari Division
HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Shahpur Shuunta Chowari road Km. 0/0 to 24/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 5/0 to 7/950).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
Total: -						


 Executive Engineer
 Chowari Division
 HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Samote Dramnala road Km. 0/0 to 12/435 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 4/930).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
Total: -						

Executive Engineer
Chowari Division
HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Dukhar Morthu road Km. 0/0 to 8/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 2/950).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
Total: -						

(Signature)
 Executive Engineer
 Chowari Division
 HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Balana to Gola road Km. 0/0 to 8/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 3/0).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
					Total: -	


 Executive Engineer
 Chowari Division
 HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on link road to village Nahana Km. 0/0 to 4/100 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 2/0)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
					Total:-	

(Signature)
 Executive Engineer
 Chowari Division
 HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Hahidar road Km. 0/0 to 10/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 3/890).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	0.00
Total: -						0.00

(Signature)
Executive Engineer
Chowari Division
HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dadriyada road Km. 0/0 to 14/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 3/810).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
Total: -						

(Signature)
Executive Engineer
Chowari Division
HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99510.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Motta Sukhiyad road Km. 0/0 to 9/0 (SH:- Hiring of Excavator cum loader & Tipper for removal of slips in between Km. 0/0 to 3/0)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	62.00			Per Hours	
2	Hiring of tipper having capacity 5.50 (five decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge.	62.00			Per Hours	
Total: -						

(Signature)
Executive Engineer
Chowari Division
HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Shahpur Sihunta Chowari road Km. 0/0 to 24/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 12/330 to 15/940).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	#NAME?	Per Hours	99750.00
Total: -						99750.00

(Signature)
Executive Engineer
Chowari Division
HPPWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Modla Sukhiyad road Km. 0/0 to 9/0 (SH:- Hiring of Excavator cum loader & Tipper for removal of slips in between Km. 5/500 to 8/0)

Estimated Cost: - Rs. 99510.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	62.00			Per Hours	
2	Hiring of tipper having capacity 5.50 (Five decimal five Zero) cubic metre for carriage of all type material up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge.	62.00			Per Hours	
Total: -						

(Signature)
Executive Engineer
Chowari Division
HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Balana to Gola road Km. 0/0 to 8/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 5/150 to 7/0).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
					Total:-	

(Signature)
Executive Engineer
Chowari Division
HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dadriyada road Km. 0/0 to 14/0 SH:- Hiring of Excavator cum loader for removal of slips in between Km. 4/050 to 6/915).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,makana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
Total: -						

(Signature)
Executive Engineer
Chowari Division
HPPWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Link road to village Dangari Km. 0/0 to 5/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 3/00 to 5/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
					Total:-	

(Signature)
Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 98700.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Link road to village Dangari Km. 0/0 to 5/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 1/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-in-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
					Total:-	


 Executive Engineer
 Chowari Division
 HP PWD Chowari

Estimated Cost: - Rs. 98700.00
Estimated Cost: - Rs. 2000.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Link road to village Dangari Km. 0/0 to 5/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 1/200 to 3/00).																																										
--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--


Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Chowari Mandhiar Baloh Fagot road Km. 0/0 to 8/700 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 2/500).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
Total: -						



Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Chowari Mandhiar Baloh Fagot road Km. 0/0 to 8/700 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 2/700 to 6/500).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
					Total: -	


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 17/100 to 21/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
					Total: -	


Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 22/100 to 25/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
					Total:-	



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 18/500 to 22/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
					Total: -	


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 15/390 to 18/105).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
Total: -						

(Signature)
Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Link road to Village Fakrodu Km. 0/00 to 2/700 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 1/500).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
Total: -						


(Signature)
Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 1/00 to 2/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
					Total: -	


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY


Estimated Cost:- Rs. 98700.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 7/00 to 14/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
Total:-						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 97680.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Chowari Mandhiar Baloh Fagot road Km. 0/0 to 8/700 (SH:- Hiring of Tipper for shifting of muck / debris in between Km. 0/00 to 2/500).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of tipper having capacity 10.50 (ten decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	88.00			Per Hours	
Total: -						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99900.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00(SH:- Hiring of Tipper for shifting of muck / debris in between Km. 16/00 to 21/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of tipper having capacity 10.50 (ten decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases . The fuel and operational staff for truck will be provided by the owner . The repair and spare , watch & ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site , which should be duly verified by the Engineer -in-Charge.	90.00			Per Hours	
					Total: -	

(Signature)
 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99098.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Chatasani Pull to Bhalog road Km. 0/0 to 7/360 (SH:- Supplying and Stacking of Stone Boulders at RD. 0/195).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Supply and Stacking of 150 to 300mm (one hundred fifty millimetre to three hundred millimetre) size stone boulder and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	86.00			Per Cubic Metre	
					Total: -	



 Executive Engineer
 Chowari Division
 HP PWD Chowari

D.N.I.T

Estimated Cost: - Rs. 99519.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work: - Restoration of Rain damage on Shahpur Sihunta Chowari Jot Chamba road Km. 40/0 to 53/00 (SH:- Providing and Laying Wire crate for protection of Toe At RD. 49/800 to 49/809.50).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	3.90			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 Kg (twenty five kilogramme) each as per drawing technical specifications Clause 1301 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	29.69			Per Cubic Metre	
					Total: -	


Executive Engineer
Chowari Division
HP PWD Chowari


SCHEDULE OF QTY

Estimated Cost :- Rs.97066.00
Earnest Money :- Rs. 2000/-
Time Limit :- Two Months.

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON DUKHAR TO MORTHU ROAD KM 0/00 TO 8/00(SH:- C/O
R/WALL AT RD 0/515.10 to 0/517.60)

Sr.No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	12.08			Per Cubic Metre	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.53			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	1.13			Per Cubic Metre	

4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters. PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.00			Each	
					Total: -	


 Executive Engineer
 Chowari Division
 HPPWD Chowz

SCHEDULE OF QUANTITY


Estimated Cost:- Rs. 94500.00

Earnest Money :- Rs. 1900.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on various road under Chowari Sub Division (SH:- Hiring of Excavator cum loader for removal of slips in various reaches).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	90.00			Per Hours	
					Total:-	


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY


Estimated Cost: - Rs. 99750.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 25/00 to 40/810 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 30/00 to 32/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
Total: -						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 25/00 to 40/810 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 34/00 to 36/00).


Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malhana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
Total:-						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 25/00 to 40/810 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 36/00 to 40/810).		Estimated Cost:- Rs. 98700.00
		Earnest Money :- Rs. 2000.00
		Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
Total:-						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dalhousie road Km. 45/0 to 67/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 45/500 to 50/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
Total: -						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY


Estimated Cost: - Rs. 98700.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nanikhad to Samleu road Km. 0/0 to 30/585 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 20/00 to 23/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
Total: -						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nagali to Sanjap road Km. 0/0 to 8/450 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 5/00 to 7/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
Total: -						

(Signature)
Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QTY

Estimated Cost: - Rs.99247.00
Earnest Money :- Rs. 2000/-
Time Limit :- Two Months.

NAME OF WORK :- CONSTRUCTION OF LINK ROAD BAGDHAR TO CHHUNUI KM 0.00 TO 3/350(SH:- C/O R/WALL WITH PUSHITA AT RD 2/542.60 TO 2/545.10)

Sr.No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	3.64			Per Cubic Metre	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.59			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	4.07			Per Cubic Metre	

4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.00				Each	
						Total:-	

G. K. Sharma
 Executive Engineer
 Chowari Division
 HPBWD Chowari