

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Offline

No. PWD-Dal/TA/Tender /2025-26 **3382-84**  
To

Dated: - **28.08.2025**


The Executive Engineer (IT Cell)  
Nigam Bihar Shimla-2

**Subject: - Publishing of Tender Notice.**

Dear Sir,


Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

Copy forwarded to the Superintending Engineer, 7<sup>th</sup> Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie

**"NOTICE INVITING TENDERS"**

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

1. Date of receipt of application for the tender Form a /w requisite documents:- 02.09.2025 onward (between 2:00 p.m.to 4:30.p.m.)

2. Date of issue/sale of tender form against Cash payment (non refundable). 02.09.2025.

The tender shall be received up to 3:00 PM on 03.09.2025 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender will be sold by this office against cash payment as shown below (Non refundable) during the working hours on 02.09.2025

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie a must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Removal of Slips in Km. 0/0 to 10/00).	98156.00	2000.00	350.00	One Month	D & C
2.	Restoration of rain damage on Dalhousie Jandrihat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Removal of Slips in Km. 0/0 to 11/040).	99692.00	2000.00	350.00	One Month	D & C
3	Restoration of rain damage on Banikhet Dalhousie Khajjiar road Km. 15/600 to 27/00 (SH: - Removal of Slips in Km. 16/0 to 27/000).	99305.00	2000.00	350.00	One Month	D & C
4	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Removal of Slips in Km. 17/00 to 21/500).	98964.00	2000.00	350.00	One Month	D & C
5	Restoration of rain damage on Orumour to Sherpur road Km. 0/0 to 3/750 (SH: - Removal of Slips in Km. 0/0 to 3/750).	99217.00	2000.00	350.00	One Month	D & C
6	Restoration of rain damage on Gandohra road Km. 0/0 to 5/510 (SH: - Removal of Slips in Km. 0/0 to 5/510).	98341.00	2000.00	350.00	One Month	D & C
7	Restoration of rain damage on Patka Chowari Dalhousie road Km. 67/00 to 73/00 (SH: - Removal of Slips in Km. 67/00 to 73/00).	98587.00	2000.00	350.00	One Month	D & C
8	Restoration of rain damage on Link road to village Ruliyani Km. 0/0 to 3/020 & Link road Dalhousie Cantt to Bathri road Km. 0/0 to 4/700 (SH: - Removal of Slips on Link road to village Ruliyani)	98805.00	2000.00	350.00	One Month	D & C

	Km. 0/0 to 3/020 & Link road Dalhousie Cantt to Bathri road Km. 0/0 to 4/700 ).					
9	Restoration of rain damage on Bounkharimour to Nagali road Km. 0/0 to 6/00 (SH: - Removal of Slips oin Km. 0/0 to 6/00 ).	98582.00	2000.00	350.00	One Month	D & C
10	Patch work on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Patch work with 20mm thick Mix Seal Surfacing at RD. 0/0 to 1/00	98999.00	2000.00	350.00	<del>Two</del> Month	D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory. .
2. GST No. Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
3. Application without all documents will not be entertained.
4. Proxy application will not be entertained.

Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

No. PWD/TA/Tender /2025-26 3385 -3435

Dated:- 28.08.2025

Copy forwarded to the following for information and necessary action please:-


- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.

Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie




### Certificate

Certified that the tenders called vide this office letter No. PWD-  
/TA/Tender /2025-26:-3382-84 dated 28.08.2025 is emergent nature and in Public  
interest.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

### Certificate

Certified that the tenders called vide this office letter No. PWD-  
/TA/Tender /2025-26:-3382-84 dated 28.08.2025 is emergent nature and in Public  
interest.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

## Schedule of Qty.

Job No. 01 TS 35

Estimated Cost :- Rs.	98156.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

**Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH:- Removal of Slips in Km. 0/0 to 10/00 ).**

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	786.00			Per Cubic Metre	
					Total:-	

  
**Executive Engineer**  
**Dalabeste Division**  
**H. P. W. D. Dababeste**


**Schedule of Qty.**

Estimated Cost :- Rs. 99692.00  
 Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: Restoration of rain damage on Dalhousie Jandirghat Chamba via Kohlar road Km. 0/0 to 11/040 (SH:- Removal of Slips in Km. 0/0 to 11/040).

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611, or as directed by Engineer-in-Charge. The rate including the octroi, royalty, Mahana, Toll tax, sale tax GST or any other taxes imposed by the Government.	798.30			Per Cubic Metre	
Total:-						

  
 J. P. W. D. Dalhousie  
 Dalhousie Division

Schedule of Qty.


Estimated Cost: - Rs. 99305.00

Earnest Money: - Rs. 2000.00

Time Limit: - One Month

Name of work: - Restoration of rain damage on Bankhet Dalhousie Khajjiar road Km. 15/600 to 27/00 (Slit: - Removal of Slips in Km. 15/600 to 27/00).

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611, or as directed by Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	795.20			Per Cubic Metre	
					Total:-	

  
 D. P. Singh  
 District Engineer  
 District Engineer  
 District Engineer

**Schedule of QTY.**

Estimated Cost - Rs.	9896.400
Estimated Wherry - Rs.	2000.00
Time Limit :-	One Month

Name of work: Restoration of rain damage on Brangal V. signal Standard road Km. 00 to 20/400 (S.R.) - Removal of slips in Km. 17.000 to 21.500 k.

Sr. No	Description of Item	Qty.	Rate		Unit	Amount
			for fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all lands and hills as per technical specification 302.3.3 and 1611 or as directed by Engineer in Charge. The rate including the material, machinery, Manpower, Fuel tax, sale tax CST or any other taxes imposed by the Government.	792.47			per Cubic Metre	
					Total	

  
 District Engineer  
 17/7/2019




**Schedule of Qty.**

Estimated Cost: - Rs.	99217.00
Earnest Money :- Rs.	2000.00

Time Limit :- One Month

Name of work: -Restoration of rain damage on Orumour to Sherpur road Km. 0/0 to 3/750 (SH: - Removal of Slips in Km. 0/0 to 3/750 ).

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	794.50			Per Cubic Metre	
Total:-						

  
 H.P.W.D. Dalbenda  
 Dalbenda Division  
 Dalbenda

**Schedule of Qty.**


Estimated Cost: - Rs. 98341.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of rain damage on Gandohra road Km. 0/0 to 5/510 (SH: - Removal of Slips in Km. 0/0 to 5/510 ).

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	787.48			Per Cubic Metre	
Total:-						

  
 EXECUTIVE ENGINEER  
 Dalbenda Division  
 M. P. W. D. Dalbenda


Schedule of Qty.

Estimated Cost: - Rs. 98587.00  
 Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: - Restoration of rain damage on Patka Chowari Dalhousie road Km. 67/00 to 73/00 (Stt:- Removal of Slips in Km. 67/00 to 73/00 ).

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	789.45			Per Cubic Metre	
Total:-						

  
 Executive Engineer  
 Dalhousie Division  
 A.P.W.D. Dalhousie

**Schedule of Qty.**

Estimated Cost: - Rs. 98805.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of rain damage on Link road to village Ruliyani Km. 0/0 to 3/020 & Link road Dathousie Cantt to Bathri road Km. 0/0 to 4/700  
(SH: - Removal of Slips on Link road to village Ruliyani Km. 0/0 to 3/020 & Link road Dathousie Cantt to Bathri road Km. 0/0 to 4/700 ).

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana. Toll tax, sale tax GST or any other taxes imposed by the Government.	791.20			Per Cubic Metre	
Total:-						

  
 EXECUTIVE ENGINEER  
 Dathousie Division  
 E. J. P. W. D. Dathousie



**Schedule of Qty.**

Estimated Cost: - Rs. 98582.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: - Restoration of rain damage on Bounkharimour to Nagali road Km. 0/0 to 6/00 (SH: - Removal of Slips in Km. 0/0 to 6/00 ).

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty, Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	789.41			Per Cubic Metre	
Total:-						

  
 H.P.W.D. Dalbouda  
 Dalbouda Division


## Schedule of Qty.

Name of work: - Patch work on Dallhousie Jandrihat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Patch work with 20mm thick Mix Seal Surfacing at RD. 0/0 to 1/00 ).

Job No. 10 TS 44

Estimated Cost: - Rs.	98999.00
Earnest Money :- Rs.	2000.00
Time Limit :-	Type Month

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion pressure distributor at the rate of 0.275 kg (zero point two seven five killograme) per sqm on prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 or as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	274.80			Per Square Metre	
	Providing . Laying and rolling of close graded Mix seal surfacing , surfacing material of 20mm (Twenty millimeter) thickness composed of 11.2 mm (Eleven point two millimeter) to 0.09 mm (Zero point zero nine millimeter) crushed stone aggregate (Type-A) per ten square meter aggregates using penetration grade bitumen (VG-10) (viscosity grade ten) 22 kg (twenty two killogram) per ten square metre and level to serve as wearing course on previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kn static roller and finishing to required level and grades as per Technical specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. and other incidentals the rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	274.80			Per Square Metre	
Total:-						

  
 M. P. W. D. Dalhousie  
 Dalhousie Division