

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DPD/CB-Tender/2023- 2557-58
To


Dated:- 23-08-2025

✓
The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publishing of tender Notice.
Sir,

Enclosed please find herewith tender notice of work as given in the Notice inviting Tender along with Schedule of Quantities for uploading the same on department website as per Notification No. Pr. Secy. (PW) to the Govt. of HP letter No. PBW (B) A(3) 1/2024 dated Shimla-2, the 03.01.2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ As above.


Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

Copy along with its enclosures is forwarded to the Superintending Engineer, 15th Circle, HPPWD Una for information please.

✓
Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed **Percentage rates** tenders on form 6 & 7 are hereby invited by the Executive Engineer Daulatpur Chowk Division, HPPWD, Daulatpur Chowk on behalf of Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office and opened as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tenders.


| | |
|--|------------------------------------|
| Date and time of receipt of applications for the tender form | : 01.09.2025 up to 12.30 PM |
| Date and time of issue/Sale of tender forms against cash Payment | : 01.09.2025 (04.00 PM to 5.00 PM) |
| Date and time of receipt of tenders | : 02.09.2025 up to 11.00 AM |
| Date and time of opening of tenders | : 02.09.2025 at 11.30 AM |

The tender forms will be issued against cash payment (non-refundable). The earnest money in the shape of NSC/Time Deposit/FDR of nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

| Sr. No. | Name of Work | Estimated Cost | Earnest money | Time Limit | Cost of Form | Eligible Class of Contractor |
|---------|---|----------------|---------------|-------------|--------------|------------------------------|
| 1 | Repair & Restoration of Rain Damages on Gagret Daulatpur Road Km 0/0 to 13/400. (SH: Maintenance of Earthen shoulder, Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD,s) | 98891.00 | 2000.00 | One Month | 350- | C & D |
| 2 | Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-II. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide) | 98771.00 | 2000.00 | One Month | 350- | C & D |
| 3 | Repair & Restoration of Rain Damages on various roads in Gagret Sub Division, Section Gagret-I. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide) | 99291.00 | 2000.00 | One Month | 350- | C & D |
| 4 | SDP/2024/250, C/O (Construction of) Playground in Govt. High School Thaplan in G.P. Oel Tehsil Ghanari Distt. Una (H.P) Under SDP | 70210.00 | 1400.00 | Three Month | 350- | C & D |
| 5 | Repair & Restoration of Rain Damages on link Road Gram Panchayat Nangal Jarialan Harijan Basti, (SH- Construction of embankment for roadway Km. 1/850 to 1/930 and Back filling behind Retaining wall at Km. 1/900 to 1/920) | 48642.00 | 1000.00 | Three Month | 350- | C & D |
| 6 | Repair & Restoration of Rain Damages on link road Daulatpur Bhera road km. 0/0 to 4/425 Km 0/0 to 1/350, (SH:- C/O wire crate wall D/S of Culvert at RD 0/750 to 0/760) | 99680.00 | 2000.00 | Three Month | 350- | C & D |



TE35RMS AND CONDITIONS: -

- The contractor should produce a copy of enlistment/renewal letter at the time of application.
- The contractor/firm shall have his registration and GST No. and copy of the same be attached with the application.
- The earnest money for the above works should be submitted duly pledged in favour of Executive Engineer, Daulatpur Chowk Division, HPPWD Daulatpur chowk with the application for the purchase of tender forms. The application received without earnest money shall be summarily rejected.
- The contractor/firms are required to insert the rate in words as well as in figures failing which Executive Engineer reserves the right to accept/rejects any or all tenders.
- If any of the date mentioned above happens to be Local/Gazetted Holidays the same shall be process on next date.
- The tender form will be issued to those contractors who have relevant machinery and equipment, list of which may be attached with their application along with proof of ownership of machinery/legal tie up.
- The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.


 Executive Engineer,
 Daulatpur Chowk Division

CERTIFICATE

Certified that tenders called vide this office letter No. PWD/DPD/CB-Tender/2025-2550-56 dated 23-08-2025 are required to be carried out immediately being emergent nature of work in the public interest.



Executive Engineer,
Daulatpur chowk Division,
HPPWD Daulatpur Chowk.


DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 98891/-
Earnest Money: Rs.2000/-
Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on Gagret Daultapur Road Km 0/0 to 13/400. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD,s)

| Sr. No. | Sub-Head and Items of work | Quantity | Rates in | | Unit | Amount |
|----------------------------|--|----------------------|-----------------------|--|-------------------|-----------------|
| | | | Figures | Words | | |
| 1 | Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 972.00 Square metre | 16.10 | Rupees Sixteen And Paise Ten Only | Per Square metre | 15649.00 |
| 2 | Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 880.00 Square metre | 38.50 | Rupees Thirty Eight And Paise Fifty Only | Per Square metre | 33,880.00 |
| 3 | Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 543.00 Running metre | 30.50 | Rupees Thirty And Paise Fifty Only | Per running metre | 16,562.00 |
| 4 | Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 410.00 Square metre | 80.00 | Rupees Eighty Only | Per Square metre | 32800.00 |
| Total Amount in Rs. | | | | % above/below | | 98891.00 |
| | | | Quoted Rate in Figure | | | |
| | | | Quoted Rate in Words | | | |



Executive Engineer,
HPPWD Division,
Daultapur Chowk.

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 98771/-
 Earnest Money: Rs.2000/-
 Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-II. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)

| Sr. No. | Sub-Head and Items of work | Quantity | Rates in | | Unit | Amount |
|-----------------------|---|----------------------|----------|--|-------------------|-----------|
| | | | Figures | Words | | |
| 1 | Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 972.00 Square metre | 16.10 | Rupees Sixteen And Paise Ten Only | Per Square metre | 15649.00 |
| 2 | Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC, upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 880.00 Square metre | 38.50 | Rupees Thirty Eight And Paise Fifty Only | Per Square metre | 33,880.00 |
| 3 | Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 543.00 Running metre | 30.50 | Rupees Thirty And Paise Fifty Only | Per running metre | 16,562.00 |
| 4 | Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 408.50 Square metre | 80.00 | Rupees Eighty Only | Per Square metre | 32680.00 |
| Total Amount in Rs. | | | | | | 98771.00 |
| Quoted Rate in Figure | | | | | | |
| Quoted Rate in Words | | | | | | |
| % above/below | | | | | | |


 Executive Engineer,
 HPPWD Division,
 Daulatpur Chowk

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99291/-
 Earnest Money: Rs. 2000/-
 Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on various roads in Gagret Sub Division, Section Gagret-I. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)

| Sr. No. | Sub-Head and Items of work | Quantity | Rates in | | Unit | Amount |
|---------------------|--|-----------------------|---------------|--|-------------------|-----------|
| | | | Figures | Words | | |
| 1 | Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 972.00 Square metre | 16.10 | Rupees Sixteen And Paise Ten Only | Per Square metre | 15649.00 |
| 2 | Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 880.00 Square metre | 38.50 | Rupees Thirty Eight And Paise Fifty Only | Per Square metre | 33,880.00 |
| 3 | Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 543.00 Running metre | 30.50 | Rupees Thirty And Paise Fifty Only | Per running metre | 16,562.00 |
| 4 | Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government. | 415.00 Square metre | 80.00 | Rupees Eighty Only | Per Square metre | 33200.00 |
| Total Amount in Rs. | | | | | | 99291.00 |
| | | Quoted Rate in Figure | % above/below | | | |
| | | Quoted Rate in Words | | | | |

Executive Engineer,
 HPPWD Division,
 Daultapur Chowk

DRAFT BILL OF QUANTITY

Job-4

Estimate Cost :- Rs. 70210/-
Earnest Money :-Rs. 1400/-
Time Limit :- Three Month.

Name of Work:- SDP/2024/250, C/O (Construction of) Playground in Govt. High School Thaplan in G.P. Oel Tehsil Ghanari Distt. Una (H.P) Under SDP

| Sr. No. | Description of Item | Quantity | Rate in | | Unit | Amount |
|-----------------------|---|--------------------|---------|--|-----------------|----------|
| | | | Figures | Words | | |
| 1 | Construction of embankment with approved materials deposited at site obtained from roadway cutting and excavation from drains and foundation of all other structures or other sources, or obtained from borrow pits within all leads and lifts, graded and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor-Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 of MORD technical specification section 300 and 1600 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, toll tax, goods service tax, labour cess or any other taxes imposed by the Government. | 61.88 Cubic metre. | 240.00 | Rupees Two Hundred Forty Only | Per cubic metre | 14851.00 |
| 2 | Loosening, Levelling and Compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve minimum dry density as given in Tables 300.1 and 300.2 for embankment construction as per Technical Specification Clause 301.4 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, toll tax, goods service tax, labour cess or any other taxes imposed by the Government. | 45.00 Cubic metre. | 135.00 | Rupees One Hundred Thirty Five Only | Per cubic metre | 6075.00 |
| 3 | Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depts on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depts and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government. | 13.32 Cubic metre. | 3700.00 | Rupees Three Thousand Seven Hundred Only | Per cubic metre | 49284.00 |
| TOTAL | | | | | | 70210.00 |
| Quoted Rate in Figure | | % above/below | | | | |
| Quoted Rate in Words | | | | | | |

Executive Engineer,
HPPWD Division,
Daultpur Chh...

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 48642/-
 Earnest Money: Rs. 1000/-
 Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages on link Road Link road Gram Panchyat Nangal Jarialan Harijan Basti, (SH- Construction of embankment for roadway Km 1/850 to 1/930 and Back filling behind Retaining wall at Km 1/900 to 1/920)

| Sr. No. | Sub-Head and Items of work | Quantity | Rates in | | Unit | Amount |
|---------|---|-----------------------|----------|---------------------------------|-----------------|-----------------|
| | | | Figures | Words | | |
| 1 | Construction of embankment for roadway with approved material obtained from borrow pits and laid in layers of suitable thickness not exceeding 200mm (two hundred millimetres) spreading to required slope and compacted with three wheel 80-100 KN static/ vibratory road roller to meet the requirements of Tables 300.1 and 300.2 as per MORTH technical specifications section 300 as per drawings or directions of the Engineer-in-charge including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water wherever required including hauling of materials for construction of embankment within all leads and lifts. The rate shall include carriage of machineries, equipment, tools and materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects and per direction of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government. | 153.60 Cubic metre | 220.00 | Rupees Two Hundred Twenty Only | Per cubic metre | 33792.00 |
| 2 | Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government. | 19.80 Cubic metre | 750.00 | Rupees Seven Hundred Fifty Only | Per cubic metre | 14850.00 |
| | | TOTAL | | | | 48642.00 |
| | | Quoted Rate in Figure | | | | |
| | | Quoted Rate in Words | | | | |
| | | | | % above/below | | |


 Executive Engineer,
 HPPWD Division,
 Daulatpur Chowk

BILL OF QUANTITY

Estimate Cost :- Rs.99680/-
 Earnest Money :-Rs.2000/-
 Time Limit :- Three Month.

Name of Work:- Repair & Restoration of Rain Damages on link road Daulatpur Bhera road Km. 0/0 to 4/425 Km 0/0 to 1/350, (SH:- C/O wire crate wall D/S of Culvert at RD 0/750 to 0/760)

| Sr. No. | Description of Item | Quantity | Rate in | | Unit | Amount |
|-----------------------|--|-------------------|---------|---------------------------------------|-----------------|-----------------|
| | | | Figures | Words | | |
| 1 | Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government. | 12.80 Cubic metre | 175.00 | Rupees One Hundred Seventy Five Only | Per cubic metre | 2240.00 |
| 3 | Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10 (ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each as per drawing and technical specifications Clause 1301 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government. | 33.60 Cubic metre | 2900.00 | Rupees Two Thousand Nine Hundred Only | Per cubic metre | 97,440.00 |
| TOTAL | | | | | | 99680.00 |
| Quoted Rate in Figure | | | | | | |
| Quoted Rate in Words | | | | | | |
| | | % above/below | | | | |

Executive Engineer,
 HPPWD Division,
 Daulatpur Chowk.