

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DEH/CB/TENDER/2024-25-
To

5345-69

DATED: 23/08/25

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :- Tender Notice.

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above


Executive Engineer,
HPPWD Division,
Dehra.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President MC Dehra.
9. The BDO Dehra /Pragpur/ Nagrota Surian.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Dehra Division.


Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

H. P. P.W.D. TENDER

Sealed item percentage tenders on the form 6&8 are invited by the **Executive Engineer Dehra Division HPPWD., Dehra** on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.


TENDER SCHEDULE:

- | | |
|---|----------------------------|
| 1. Date and time of receipt of application for tender form: | 30.08.2025 upto 12.00 Noon |
| 2. Date and time of issue of tender form: | 01.09.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 02.09.2025 upto 10.30AM |
| 4. Date and time of opening of tenders: | 02.09.2025 at 11.00 AM |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
01	Construction of Pucca Path from Manohar Lal House to Handpump Ward No. 07 (G.P. Nandpur Bhatoli) (SH: P/L Hume Pipe 600mm dia, 60mm thick Paver Block & Edge Wall) SDP/2023/755	Rs. 79,678.00	Rs.2,000/-	One Month	Rs.350/-
02	Construction of Jeepable Road from Main Road to the House of Kamlesh Kumari Ward No. 01 (SH: C/o Cement Concrete Pavement at RD 0/0 to 0/058) VKV/2023/1324	Rs. 99,878.00	Rs.2,000/-	One Month	Rs.350/-
03	Construction of Pucca Path from Main Road to Rashpal Kumar, Pardeep Kumar, Kamal Kumar, Tilak Raj etc. Houses in Ward No. 01 Village Dhanotu Moahl (SH: C/o Protection Wall and Cement Concrete Pavement at RD 0/00 to 0/058) SDP/2023/751	Rs. 99,910.00	Rs.2,000/-	One Month	Rs.350/-
04	Repair of Bankhandi to Sameli via Kallar Gujrera Road KM 0/0 to 3/185 (SH: C/o B/Wall at RD 3/090 to 3/100 and V-Shape Drain at RD 3/070 to 3/090) SDF/2023/445	Rs. 99,520.00	Rs.2,000/-	One Month	Rs.350/-
05	Reapir of Sapru to Pansal Road KM 0/0 to 0/440 (SH: C/o R/Wall at RD 0/00 to 0/006) SDF/2023/436	Rs. 97,546.00	Rs.2,000/-	One Month	Rs.350/-
06	Restoration of Rain Damages on Govt. Sr. Sec. School Serabari Khas, Dhiman Basti, Harizan Basti to Dehra Jawali Raja-Ka-Talab Road KM 0/0 to 1/500 (SH: C/o B/Wall at RD 0/410 to 0/435).	Rs. 98,476.00	Rs.2,000/-	One Month	Rs.350/-
07	Repair & Maintenance of Sr. Division Judge Residence at Dehra in District Kangra (H.P.) (SH: P/L ACP Sheet, Steel Work etc.).	Rs. 83,564.00	Rs.1,700/-	One Month	Rs.350/-
08	Construction of Harar to Khabli via Jalandhar Lahar Road (SH: Formation Cutting at RD 0/100 to 0/200).	Rs. 85,768.00	Rs.2,000/-	One Month	Rs.350/-
09	Construction of Harar to Khabli via Jalandhar Lahar Road (SH: Formation Cutting at RD 0/200 to 0/300).	Rs. 85,768.00	Rs.2,000/-	One Month	Rs.350/-
10	Restoration of Rain Damages on Bankhandi to Bassa via Mehwa Gurard Hut Road KM 0/0 to 12/155 (SH: C/o Wire Crate Wall at RD 8/500 to 8/508 on RHS).	Rs. 96,509.00	Rs.2,000/-	Two Months	Rs.350/-
11	Restoration of Rain Damages on Harpukhar to Chanouta Road KM 0/0 to 3/00 (SH: C/o R/Wall at RD 2/750 to 2/755).	Rs. 99,816.00	Rs.2,000/-	One Month	Rs.350/-

12	Restoration of Rain Damages on Harpukhar to Chanouta Road KM 0/0 to 3/00 (SH: C/o R/Wall at RD 2/755 to 2/760).	Rs. 99,816.00	Rs.2,000/-	One Month	Rs.350/-
13	Restoration of Rain Damages on Diara Bara Road KM 0/0 to 2/750 (SH: Deployment of Excavator-Cum-Loader for Removal of Slips/Clearance of Drains at Various RD's) Section: Dhaliara	Rs. 99,000.00	Rs.2,000/-	One Month	Rs.350/-
1	The contractors/firms should possess the following documents (Photocopy to be attached): (i) Latest renewal of enlistment. (ii) PAN (Permanent Account No.) (iii) Registration under HP GST/ (TIN No.). (iv) EPF (Employee Provident Fund Account No.)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.				
4	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
5	The Contractor will have to submit affidavit alongwith application for issue of tender that he has not more than two works in hand.				
6	The next tender will be issued only after completion of previous works in hand.				
7	The offer of the tender shall remain valid upto 30 days after the opening.				



 Executive Engineer
 HPPWD Division Dehra
 Distt Kangra H.P
 on behalf of Governor of Himachal Pradesh

Exigency Certificate

It is certified that the tenders invited vide this office NIT
No.....5345-69...dated...23/08/25... are of emergent nature of work and in public
interest.

Place:

Dated:


Executive Engineer,
HPPWD Division,
Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- 79,678.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Months.

Name of work:- Construction of Pucca path from Manohar Lal House to Handpump Ward No.7(GP Nandpur Bhatoli) (SH:-Providing and Laying Hume pipe 600 mm dia, 60 mm thick paver block & Edge wall).SDP/2023/755.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.35 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	392.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.15 Cubic metre	4050.00	Rupees Four Thousand Fifty only	Per Cubic metre	24,908.00
3	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	31.50 Square metre	900.00	Rupees Nine Hundred Only	Per Square metre	28,350.00

Bill of quantity checked and approved
for Rs. 79678/- only.

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

ESTIMATED COST: - Rs. 99,878.00
 EARNEST MONEY Rs. 2,000.00
 TIME LIMIT : One month

Name of Work :-Construction of Jeepeable road from main road to the house of Kamlesh Kumari Ward No. 1 (SH:-Construction of Cement concrete pavement RD 0/00 to 0/058)VKV/2023/1324.

Sr No.	Description of item	Quantity	Rate		Units	Amount
			In figures	In words		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications.and as directed by the Engineer-in-Charge complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	145.00 Sqm	1.50	Rupees One And Paise Fifty Only	Per Square Meter	218.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405. as directed by the Engineer-in-Charge including complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	10.88 Cum	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per Cubic Meter	19040.00
3	Providing and laying 1:2:4 concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as directed by the Engineer-in-Charge including complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	13.90 Cum	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic Meter	80620.00
Total Amount						99,878.00
TOTAL :-						
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

*Bill of Materials checked and approved
for Rs 99,878.00 only.*

Executive Engineer,
Dehra Division,
HP.PWD., Dehra

PERCENTAGE BILL OF QUANTITY

ESTIMATED COST: - Rs. 99,910.00
EARNEST MONEY Rs. 2,000.00
TIME LIMIT : One month

Name of Work :-Construction of Pucca path from main road to Rashpal Kumar , Pardeep Kumar, Kamal Kumar , Tilak Raj & etc. house Ward No. 1 Village Dhanotu Mohal (SH:- Construction of Protection wall & Cement concrete pavement RD 0/00 to 0/058)SDP/2023/751.

Sr .No	Description of item	Quantity	Rate		Units	Amount
			In figures	In words		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications.and as directed by the Engineer-in-Charge complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	166.75 Sqm	1.50	Rupees One And Paise Fifty Only	Per Square Meter	250.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405. as directed by the Engineer-in-Charge including complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	10.88 Cum	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per Cubic Meter	19040.00
3	Providing and laying 1:2:4 concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203.and as directed by the Engineer-in-Charge including complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	13.90 Cum	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic Meter	80620.00
	Total Amount					99,910.00
	TOTAL :-					
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Rs 99,910/- as per bill of material and approved

Executive Engineer,
Dehra Division,
HP.PWD., Dehra

166

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99520.00

Earnest Money :-Rs 2000.00

Time Limit :- One month.

Name of work :- Repair of Bankhandi to Sameli via Kallar Gujrera road Km 0/000 to 3/185. (SH:- C/O Breast wall from RD 3/090 to 3/100 & V-shape drain from RD 3/070 to 3/090).SDF/2023/445						
Sr. No.	Description of Item	Qty.	Figures	Rate in words	Unit	Amount
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	11.50	Cubic Meter 290.00	Rupees two Hundred Ninety Only	Per Cubic Meter	3335.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	8.10	Cubic Meter 4050.00	Rupees Four Thousand Fifty Only	Per Cubic Meter	32805.00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax,GST or any other taxes imposed by the Government.	13.20	Cubic Meter 4650.00	Rupees Four Thousand Six Hundred Fifty Only	Per Cubic Meter	61380.00

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 97546.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- one month.

Name of work:- Repair of Sapru To Pansal road km 0/00 to 0/440,(S.H.-: C/o Retaining wall at Rd 0/000 to 0/006) SDF/2023/436

Sr. No.	Description of Item	Qty.	Rate in		Unit	Amount
			Figures	words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	12.96	290.00	Rupees Two Hundred Ninety only	Per Cubic Meter	3758.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	21.43	4050.00	Rupees Four Thosand Fifty Only	Per Cubic Meter	86792.00

Sr. No.	Description of Item	Qty.	Rate in		Unit	Amount
			Figures	words		
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	10.00	Numbers	Rupees Two Hundred Fifty only	Each	2500.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing & Technical Specification Clause-1204.3.8 Granular material completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	4.86	Cubic Meter	Rupees Nine Hundred Twenty Five Only	Per Cubic Meter	4496.00
	Total=					97546.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 97546.00 only

[Signature]
Executive Engineer
Dehra Division
HP.PWD. Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 98476.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain Damages on Govt. Senior Secondary School Serabari Bari Khas Dhiman Basti Harizan Basti to Dehra Jawali Raja Ka Talab road in Km 0/0 to 1/500 (SH:- C/o B/wall at RD.0/410 to 0/435)

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	12.25 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	3,553.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depts and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	22.45 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	90,923.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	16.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	4,000.00
	Total					98,476.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

BLU 9 quantity checked for approval

for Rs 98476/-

Executive Engineer,
Debra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 83,564.00
 Earnest Money :- Rs. 1,700.00
 Time Limit :- One Month.

Name of work:--Repair & Maintenance of Sr. Div. Judge Residence at Dehra Distt. Kangra (H.P.) (S.H.: P/F ACP sheet, steel work etc.)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and fixing 6 mm thick commercial ply wood ceiling of approved quality with butt jointing and nails/framework and cover fillets to be paid for separately/complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royalty, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	12.33 Square metre	600.00	Rupees Six Hundred Only	Per Square metre	7,398.00
2	Providing corrugated G.I sheet roofing fixed with galvanised iron J or L, hooks bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers filled with white lead complete excluding the cost of purlines referters and trusses complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royalty, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	23.75 Square metre	1200.00	Rupees One Thousand Two Hundred Only	Per Square metre	28,500.00
3	Steel work welded in built up sections, framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royalty, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	442.89 Square metre	105.00	Rupees One Hundred Five Only	Per Kilogram me	46,503.00
4	Painting wood work with Deluxe Multi Surface Paint to give an even shade Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture completed and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	12.33 Square metre	94.30	Rupees Ninety Four and Thirty Paise Only	Per Square metre	1,163.00
						83,564.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Bill of quantity by client's order approved for Rs 83,564/- only.

Executive Engineer,
 Dehra Division,
 HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.85768.00
 Earnest Money :-Rs.2000.00
 Time Limit :- Two Months.
 Name of work:- Construction of Harar to Khabli via Jalandhar Lahar road (SH:- Formation cutting at RD 0/100 to 0/200).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by the engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shungla, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 39.55cum (five hundred fifty four decimal five five cubic metres) quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected nfrom the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	263.90	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic meter	85,768.00
	Total					85,768.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 85768.00 only

Executive Engineer,
 Dehra Division,
 HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. ~~2,57,280.00~~ **85,768.00**
 Earnest Money :- Rs. ~~2,000.00~~
 Time Limit :- Two Months.

Name of work:- Construction of Harar to Khabli via Jalandhar Lahar road (SH:- Formation cutting at RD 0/200 to 0/300).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by the engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 39.55 cum (five hundred fifty four decimal five five cubic metres) quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	263.90 Cubic meter	325 00	Rupees Three Hundred Twenty Five Only	Per Cubic meter	85,768.00
	Total					85,768.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs 85,768 only.

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.96509.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- Two Months.

Name of work:- Restoration of rain damages on Bankhandi to Bassa via Mehwa Guard Hut Road in Km 0/0 to 12/155 (SH:- C/o Wire Crate R/wall at RD 8/500 to 8/508 RHS).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	25.92 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	7,517.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS 280 and IS-4826 in 100 mmx100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders/ with cut stones weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	30.24 Cubic meter	2800.00	Rupees Two Thousand Eight Hundred Only	Per Cubic meter	84,672.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	5.76 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	4,320.00
	Total					96,509.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 96,509.00 only

[Signature]
Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 99816.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.
 Name of work:- Restoration of Rain Damages on Road Harpukhar to Chanota km 0/00 to 3/00 (SH:- C/o R/wall at RD.2/750 to 2/755)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	18.00 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	5,220.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing*complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	20.41 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	82,661.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709.1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	16.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	4,000.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	10.58 Cubic meter	750.00	Rupees Seven Hundred Fifty Only	Per Cubic meter	7,935.00
Total						99,816.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 99816.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain Damages on Road Harpukhar to Chanota km 0/00 to 3/00 (SH:- C/o R/wall at RD.2/755 to 2/760

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	18.00 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	5,220.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	20.41 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	82,661.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	16.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	4,000.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	10.58 Cubic meter	750.00	Rupees Seven Hundred Fifty Only	Per Cubic meter	7,935.00
	Total					99,816.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99000.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:-Restoration of rain damages on Diara Bara Road Km.0/00 to 2/225. (SH:- Deployment of Excavator Cum Loader for Removal of slips/
 Clearance of drain in various RD;s).(Under Dhaliara Section) SDF/2025/528

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Deployment of excavator cum loader on through rate basis for removal of slips and removal of formation deficiency in all kinds of soil from road formation, removal of slips, berms dressing, clearing of drains etc. complete in all respect as per direction of the Engineer-in-Charge including all leads lifts. The cost of lubricant diesel etc be borne by the contractor.	90.00 Hours	1100.00	Rupees One Thousand One Hundred Only	Per Hours	99,000.00
	Total					99,000.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Team & Conditions:-

- 1 Hire charges shall be quoted per hour rate.
- 2 Hire charges shall be include all expenses including fuel lubricat establishment major and repair over hauling replacement of equipment if required.
Hire charges also including insurance of machinery and department shall not be responsible for 3 and fatal and non fatal accident.
- 4 Hire charges shall be include local and other taxes including tax if any imposed by the Govt.
- 5 for drain and 1.20cum side cutting (0.75x0.80%)+(6.00x20%).

*Percentage Bill of Quantity checked
 & approved for Rs 99,000/-*

(Signature)
 Executive Engineer,
 Dehra Division,
 CHPPWD Dehra.