

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-SRDD-CB-CTR-NIT-2025-26- 7178-7202

Dated:- 28-08-2025

To

The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) A (3)1/2024 dated Shimla-2 the 03-01-2024 as the works mentioned in the tender Notice are urgent in nature and in public interest.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhani
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhani
Ph. 0177-2790534

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dhami on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **08.09.2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **06.09.2025 up to 4.30 PM** and the application for issue of tender form shall be received on **05.0.2025 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhami must be accompanied with the application for tender documents. Please not any exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	C/O Jawahar Lal govt. College of fine Arts at Loharav, Distt. Shimla (SH: Providing fixing steel sink & water supply installation for canteen for students).	20834/-	400/-	One month	Rs.350 -
2	C/O link road from Daud to Neen Km. 0/00 to 1/00 (SH: Formation cutting 5/7 mtr. Wide at Rd. 0/490 to 0/535)	99631/-	2000/-	One Month	Rs.350 -
3	R/R damages on Tara Devi Gamber road Km. 0/00 to 11/550 (SH: Removal of slips at various Rds.between Km. 0/00 to 5/00)	99844/-	2000/-	One Month	Rs.350 -
4	R/R damages on Tara Devi Gamber road Km. 0/00 to 11/550 (SH: Removal of slips at various Rds.between Km. 5/00 to 11/550).	99844/-	2000/-	One Month	Rs.350 -
5	A/R & M/O on Tutikandi Sheelgoan via Kiari road Km. 0/00 to 3/870 (SH: P/L correction layer G-III, SS-I in between Km. 1/00 to 1/345)	99905/-	2000/-	One Month	Rs.350 -
6	Special repair to residential accommodation of govt. Ayurvedic health Centre at thaila Tehsil Duni Distt. Shimla H.P (SH: Repair of tiles work thereof).	99799/-	2000/-	One Month	Rs.350 -
7	A/R & M/O on Tutikandi Sheelgoan via Kiari road Km. 0/00 to 3/870 (SH: P/L correction layer G-III, SS-I in between Km. 0/00 to 1/00).	99778/-	2000/-	One Month	Rs.350 -

8	Special repair to H.P. printing press at Ghora Chowki Shimla (SH: Dismantling of chowked sewerage line and provision of PVC line and P/F WS & SI works thereof).	58826/-	1500/-	One Month	Rs.350/-
9	Preparation forest diversion case under F.C.A. 1980 for (i) Construction of link road Lagha to Bog Km. 0/00 to 0/500).	65000/-	2000/-	One Month	Rs.350/-
10	Special repair to HP Printing Press at Ghora Chowki Shimla (SH: Dismantling toilet & Bathroom floor tile works for flooring and WS & SI works thereof (Set No. 1) Type IV Quarters).	99031/-	2000/-	One Month	Rs.350/-
11	Special repair to HP Printing Press at Ghora Chowki Shimla (SH: Dismantling toilet & Bathroom floor tile works for flooring and WS & SI works thereof (Set No. 2) Type IV Quarters).	99031/-	2000/-	One Month	Rs.350/-
12	C/O link road from Jood to Khunara, Distt. Shimla H.P Km. 0/00 to 0/900 (SH: Preparation of FRA case in all respect).	70000/-	2000/-	One Month	Rs.350/-
13	A/R & M/O on link road to village Garkhan Km. 0/00 to 3/00 (SH: Maintenance of earth shoulder, Trimming of grass, Maintenance of drain and Maintenance of hume pipe culvert in Km. 0/00 to 3/00)	99840/-	2000/-	One Month	Rs.350/-
14	C/O link road from Jalog Himri to village Jhutnu Km. 0/00 to 1/150 (SH: C/O R/Wall at Rd. 0/495 to 0/499.30) Under BASP Head.	99085/-	2000/-	One Month	Rs.350/-
15	C/O link road from Jalog Gadheri to village Kandharti Ojdu Shaw seri Km. 0/00 to 1/330 (SH: C/O R/Wall at Rd. 0/240 to 0/244.90) Under BASP Head.	99398/-	2000/-	One Month	Rs.350/-
16	A/R & M/O on 16 Mile to Sedan road Km. 0/00 to 2/660 (SH: Maintenance of earthen shoulder, Trimming of grass, Maintenance of drain and Maintenance of hume pipe culvert in Km. 0/00 to 2/660).	99080/-	2000/-	One Month	Rs.350/-
17	A/R & M/O on Pakki Bawari Shakrah Sedan road Km. 0/00 to 5/700 (SH: Maintenance of earthen shoulder, Trimming of grass, Maintenance of drain and Maintenance of hume pipe culvert in Km. 0/00 to 2/800).	99840/-	2000/-	One Month	Rs.350/-
18	Repair & Maintenance of Shimla Rural Division office building at Dhami (SH: Establishment of departmental lab).	99085/-	2000/-	One Month	Rs.350/-
19	A/R & M/O on link road to village Khatnol Km. 0/00 to 10/00 (SH: Maintenance of earth shoulder, Trimming of grass, Maintenance of drain and Maintenance of hume pipe culvert in Km. 5/00 to 10/00)	98090/-	2000/-	One Month	Rs.350/-
20	R/R damages on Shimla Mandi road Km. 22/00 to 52/300 (SH: Hiring of JCB for removal of slips in Km. 39/00 to 52/300)	99645/-	2000/-	One Month	Rs.350/-
21	R/R damages on Shimla Mandi road Km. 22/00 to 52/300 (SH: Hiring of JCB for removal of slips in Km. 22/00 to 33/00)	99645/-	2000/-	One Month	Rs.350/-
22	R/R damages on Karyali to Shara road Km. 0/00 to 2/555 (SH: Hiring of JCB for removal of slips in Km. 0/00 to 2/555)	99645/-	2000/-	One Month	Rs.350/-
23	R/R damages on link road from Mandorghat to village Anu in Km.0/00 to 5/00 (SH: Hiring of JCB for removal of slips in Km. 0/00 to 5/00).	99645/-	2000/-	One Month	Rs.350/-
24	R/R damages on Shoghi Mehli road Km. 0/00 to 12/375 (SH: Removal of slips at various Rds.)	99796/-	2000/-	One Month	Rs.350/-
25	R/R damages on Shoghi Mehli road Km. 0/00 to 12/375 (SH: Removal of slips at Rds. 6/375 to 6/405).	83115/-	2000/-	One Month	Rs.350/-

26	R/R damages on Shoghi Mehli road Km. 0/00 to 12/375 (SH: Removal of slips at various Rds.)	99931/-	2000/-	One Month	Rs.350/-
27	R/R damages on Kawara Chowki to Thalak Dhar road Km. 0/00 to 2/200 (SH: Removal of slips at various Rds.)	99666/-	2000/-	One Month	Rs.350/-
28	A/R & M/O on Shoghi Mehli road Km. 0/00 to 12/375 (SH: P/F precast RCC drain covers between Km. 11/00 to 11/100).	97730/-	2000/-	One Month	Rs.350/-
29	A/R & M/O on Shoghi Mehli road Km. 0/00 to 12/375 (SH: P/F precast RCC drain covers between Km. 11/100 to 11/200).	97730/-	2000/-	One Month	Rs.350/-
30	A/R & M/O Hiranagar Dhamoon road Km. 0/00 to 8/00 (SH: Repair of earthen shoulder, Trimming of grass and clearing of drain in Km. 0/00 to 2/00).	99500/-	2000/-	One Month	Rs.350/-
31	A/R & M/O on Tara Mata temple road Km. 0/00 to 2/200 (SH: Maintenance of earthen shoulder and white washing in Km. 0/00 to 2/200).	99648/-	2000/-	One Month	Rs.350/-
32	A/R & M/O on Tara Mata temple road Km. 0/00 to 2/200 (SH: Painting on steel railing).	98800/-	2000/-	One Month	Rs.350/-
33	A/R & M/O on Taradevi Gamber road Km. 0/00 to 11/550 (SH: Maintenance of drain, trimming of grass, earthen shoulder and white washing in Km. 7/00 to 9/00 and A/R & M/O Shakoh to Hanuman Mandir road Km. 0/00 to 1/250 (SH: Maintenance of drain, trimming of grass, earthen shoulder and white washing in Km.0/00 to 1/250).	99887/-	2000/-	One Month	Rs.350/-
34	A/R & M/O Rest House at Tara Devi (SH: Supply of drinking water in rest House at Tara Devi).	99400/-	2000/-	One month	Rs.350/-

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhani

Certificate

Certified that the tenders called vide this notice inviting tender for 34 (Thirty four) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhani

SCHEDULE OF QUANTITY
Name of Work:- Construction of Jawahar Lal Govt. College of Fine Arts at Loharav, District Shimla (Sh. Providing fixing Steel sink & water supply installation for canteen for students)

Estimated Cost :- Rs 20834/- only
Earnest Money :- Rs. 400/-only
Time :- One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS-13983 with C.I brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required carriage of material in all leads and lifts as per direction of the Engineer in Charge 610x460 mm bowl depth 200mm.	1.00	No.	2985 90	2986 00
2	Providing and fixing G.I pipes complete with G.I fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall, 15 mm nominal bore including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	26.00	Rmt.	310 00	8060 00
3	Providing and fixing G.I Union in G.I pipe including cutting and threading the pipe and making long screws etc. complete (New work) 15 mm nominal bore including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	No.	162 30	649 00
4	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour including carriage of material in all leads and lifts as per direction of the Engineer in Charge 15 mm nominal bore with 45 cm length	2.00	No.	112 45	225 00
5	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms 15 mm nominal bore including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	1.00	No.	1054 00	1054 00
6	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS 8931 15 mm nominal bore including carriage of material within all leads and lifts as per direction of Engineer-in-charge	2.00	No.	475 13	950 00
7	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 110mm dia.	15.00	Rmt	372 00	5580 00
8	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion: PVC Door bend 110 mm bend including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	2.00	No.	364 00	728 00
9	Providing and fixing PVC floor traps ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of materials within all leads and lifts-110mm x 90mm	1.00	No.	402 40	402 00

10	Providing & fixing 110mm dia C.P. grating for floor or nahani / gully / floor trap including carriage of material within all leads and lifts.	1.00	No.	80.00	Rupees Eighty Only	Each	80.00
11	Providing and fixing PVC waist pipe 32 mm including carriage of materials within all leads and lifts:- 110mm x 90mm	1.00	No.	120.00	Rupees One Hundred Twenty Only	Each	120.00
0					Total:		20834.00

Amount Quoted by the Contractor in Percentage	Rs.	
---	-----	--

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division,
HPPWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 99,631.00	
Name of Work :- C/o Link road from Daud to Neen km. 0/00 to 1/00 (SH:- Formation Cutting 5/7 mtr wide at Rd. 0/490 to 0/535)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). The cost of all useful materials such as stones, shingles, aggregates, and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of the jumper work and one sixth of ballasting work (soft rock) one third of blasting work (Hard rock) 39.77 cum qty. which shall be proportionately increases/decreases as the antity of earth work increase/decrease in all cases recovered from the contractor at the rate of Rupees 300/- (Three hundred only) per cubic meter shall be effected, any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	397.73	Cum	250.50	Rupees Two Hundred Fifty and Paise Fifty Only	Per cubic metre	99631
Total Rs.							99631
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dham

Schedule Of Quantity						Estimated Cost:- 99,844.00	
Name of Work :- R/R Damages on Tara Devi Gamber road km. 0/00 to 11/550 (SH:- Removal of slips <i>in various Rds between km. 9/00 to 5/00</i>)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	1109.38	Cum	90.00	Rupees Ninety Only	Per Cubic Metre	99844
	Total Rs.						99844
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi. *2/3/21*

Schedule Of Quantity						Estimated Cost:- 99,844.00	
Name of Work :- R/R Damages on Tara Devi Gamber road km. 0/00 to 11/550 (SH:- Removal of slips at various Rds. <i>between km. 5/00 to 11/550</i>)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	1109.38	Cum	90.00	Rupees Ninety Only	Per Cubic Metre	99844
Total Rs.							99844
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi. *[Signature]*

Schedule Of Quantity						Estimated Cost:- 99,905.00	
Name of Work :- A/R & M/O on Tutikandi Sheelgoan via Kiari road km. 0/00 to 3/870 (SH:- Providing and Laying correction layer G-III, and SS-I, in between km. 1/00 to 1/345)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 22mm to 45mm(twenty two millimetre to forty five millimetre) grading- III 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 kN (Eighty to hundred) static roller in stages to proper grade and camber, applying and brooming, crushable screening type -B of size 11.2 mm (eleven point two millimetre) nominal size at the rate 0.20 cum.(Zero point twenty cubic metre) and binding materials at the rate 0.06cum. (zero point zero six cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading as per MORD Technical specification Clause 405.. By manual means and as per intire satisfaction or the Engineer-In-Charge. including carriage of materials within all leads and lifts.	30.83	Cum	2410.00	Rupees Two Thousand Four Hundred Ten Only	Per Cubic Metre	74300
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning the road surface with hydralic broom and spraying primer at ther ate 1.05 kg (one point zero five kilogramme) per square metre using mechanical means as per Technical Specifictions Clause 502 including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	411.00	Sqm	62.30	Rupees Sixty Two and Paise Thirty Only	Per Square metre	25605
Total Rs.							99905
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 99,799.00	
Name of Work :- Special Repair to Residential accomodation of Govt. Ayurvedic Health Centre at Thaila Tehsil Suni Distt Shimla HP (SH:- Repair of Tiles work thereof)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	White glazed tiles 6 mm thick in skirting risers of steps and dado 12 mm thick cement mortar 1:3 (1 cement:3 sand) and jointed with cement slurry. (30X45 cm) with 7cm wide border/listed at top	59.76	Sqm	1670.00	Rupees One Thousand Six Hundred Seventy Only	Per Square metre	99799
Total Rs.							99799
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 99,778.00	
Name of Work :- A/R & M/O on Tutikandi Sheelgoan via Kiari road km. 0/00 to 3/870 (SH:- Providing and Laying correction layer G-III, and SS-I, in km. 0/00 to 1/00)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 22mm to 45mm(twenty two millimetre to forty five millimetre) grading- III 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 kN (Eighty to hundred) static roller in stages to proper grade and camber, applying and brooming, crushable screening type -B of size 11.2 mm (eleven point two millimetre) nominal size at the rate 0.20 cum.(Zero point twenty cubic metre) and binding materials at the rate 0.06cum. (zero point zero six cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading as per MORD Technical specification Clause 405.. By manual means and as per intire satisfaction or the Engineer-In-Charge including carriage of materials within all leads and lifts.	30.79	Cum	2410.00	Rupees Two Thousand Four Hundred Ten Only	Per Cubic Metre	74204
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning the road surface with hydralic broom and spraying primer at ther ate 1.05 kg (one point zero five kilogramme) per square metre using mechanical means as per Technical Specifictions Clause 502 including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	410.50	Sqm	62.30	Rupees Sixty Two and Paise Thirty Only	Per Square metre	25574
Total Rs.							99778
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi.

Schedule Of Quantity

Estimated Cost:- 58,826.00


**Name Of Work :- Special Repair to H.P. Printing press at Ghora Chowki Shimla (SH:-
Dismantling of Chocked Sewerage line and provision of PVC line & P/F WS & SI. works Thereof)**

Earnest Money:- 1500.00

Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Dismantling C.I pipe i/c excavation and ceiling trenches a/w including stacking materials within 50 meters lead complete including carriage of materials within all leads and lifts	45.00	Rmt	186.50	Rupees One Hundred Eighty Six and Paise Fifty Only	Per running Metre	8393
2	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fitting with approved adhesive etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.:-150mm dia.	45.00	Rmt	620.00	Rupees Six Hundred Twenty Only	Per running Metre	27900
3	Providing and fixing 150 mm (one hundred ten millimetre) dia PVC door bend with oval access door insertion rubber washer 3 mm Three millimetre) thick bolts and nuts ISI market complete including fixing with approved adhesive etc. complete as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals	4.00	No	330.45	Rupees Three Hundred Thirty and Paise Forty Five Only	Each	1322
4	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. complete as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportion within all leads and lifts and as per direction of Engineer-in- Charge.150 mm dia.	4.00	No	216.75	Rupees Two Hundred Sixteen and Paise Seventy Five Only	Each	867
5	Providing and fixing 150 mm (one hundred ten millimetre) dia PVC single equal branch with oval access door, ISI marked insertion rubber washer 3 mm (three millimetre) thick bolts and nuts complete /including fixing with approved adhesive etc. complete as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals	3.00	No	386.65	Rupees Three Hundred Eighty Six and Paise Sixty Five Only	Each	1160
6	Providing and fixing 110 mm (one hundred ten millimetre) dia PVC Collar ISI marked including fixing with approved adhesive etc. complete as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals	16.00	No	156.55	Rupees One Hundred Fifty Six and Paise Fifty Five Only	Each	2505

7	Constructing brick masonry chamber for underground C.I. inspection chamber and bends with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) C.I. cover with frame (light duty) 455mm x 610mm internal dimensions, total weight of cover with frame to be not less than 38kg (weight of cover 23kg and weight of frame 15 kg), R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 Fine sand : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size), inside plastering 12mm thick with cement mortar 1:3 (1 cement : 3 coarse sand), finished smooth with a floating coat of neat cement on walls and bed concrete etc. complete as per standard design including carriage of material in all leads and lifts as per direction of the Engineer in Charge.: - Inside dimensions 455mm x 610mm and 45cm deep for single pipe line : With common burnt clay F.P.S. (non modular) bricks of class designation 7.50. including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.00	No	4170.00	Rupees Four Thousand One Hundred Seventy Only	Each	16680
Total Rs.							58826
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhama. 

Schedule Of Quantity						Estimated Cost:- 65,000.00	
Name Of Work :- Preparation of Forest Diversion case under F.C.A 1980 for (i) Construction of link road Lagha to Bog km. 0/00 to 0/500)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Preparation of Forest Deversion case Under Forest Conservation Act-1980 including preparation of revenue papers of land falling on the road alignment and collection of other field date. All relevant documents/formats mandatory required would be attached with the case as per latest requirement of Ministry of Environment and forest conservation Govt. of India after getting the joint inspection/ site including computer typing in 6 copies, binding complete and getting it through from HP, PWD Sub Division Shoghi HP, PWD Division Dhami office of range Officer Mashobra , office of DFO Shimla Conservator of Forest Department Shimla including attending all the observations, if raise, at many time by any office and to prepare the same by neatly and accurately filling in all the formats/Documents complete in all respect as per direction and complete satisfaction of HP, PWD and Forest Department.	1.00	Per Case	65000.00	Rupees Sixty Five Thousand Only	Per Case	65000
Total Rs.							65000
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami.

SCHEDULE OF QUANTITY

Name Of Work :- Special repair to HP Printing Press at Ghoar Chowki Shimla (SH:- Dismantling toilet & Bathroom Floor tile works for flooring and WS & SI works thereof (Set No. 1)Type IV Quarters)

Estimated Cost: - Rs 99031 /- only

Earnest Money : - Rs. 2000 /-only

Time: - One Month

S No	Sub head and items of work	Qty.		Rate figures		Unit	Amount
1	2	3	4	5	6	7	
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within Sometres lead-For thickness of tiles 10 mm to 25 mm complete including carriage of materials within all leads and lifts.	42.39	Sqm	48.30	Rupees Forty Eight and Paise Thirty Only	Per Square Metre	2047.00
2	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete (1) Size of Tile 300 x 450 mm	35.08	Sqm	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square Metre	39991.00
3	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. (i) Size of Tile 300x300 mm	7.31	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Metre	9869.00
4	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required: Kitchen sink without drain board (i)610x510 mm bowl depth 200 mm	1.00	No.	2500.00	Rupees Two Thousand Five Hundred Only	Each	2500.00
5	Providing and fixing P.V.C. waste pipe for sink or wash basin Including P.V.C. waste fittings complete. Semi rigid pipe 32 mm dia including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No.	311.46	Rupees Three Hundred Eleven and Paise Forty Six Only	Each	311.00
6	Providing and fixing C.P. grating of approved quality and colour.Circular type (i) 100 mm nominal dia including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	3.00	No.	120.00	Rupees One Hundred Twenty Only	Each	360.00
7	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 93 gms. (i) 15 mm nominal bore including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	2.00	No.	585.74	Rupees Five Hundred Eighty Five and Paise Seventy Four Only	Each	1171.00
8	Providing and fixing 15mm nominal bore C.P. brass angle cock of approved quality conforming to IS:8931 complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	7.00	No.	426.36	Rupees Four Hundred Twenty Six and Paise Thirty Six Only	Each	2985.00
9	Providing and rising 30 cm length uplasticised PVC connection pipe with brass unions 15 mm nominal bore complete including camage of materials upto all leads and lifts and as directed by the Engineer in Charge	6.00	No.	128.04	Rupees One Hundred Twenty Eight and Paise Four Only	Each	768.00
10	Providing and fixing GI pipes complete with G.I. fittings including trenching and refilling etc. 15 mm nominal bore including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	20.00	Rmt	329.10	Rupees Three Hundred Twenty Nine and Paise Ten Only	Per Running Metre	6582.00
11	Providing and fixing PVC (Finolex) floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (i)110mm X 90mm size.	5.00	No.	400.26	Rupees Four Hundred and Paise Twenty Six Only	Each	2001.00

SCHEDULE OF QUANTITY

Name Of Work :- Special repair to HP Printing Press at Ghoar Chowki Shimla (SH):- Dismantling toilet & Bathroom Floor tile works for flooring and WS & SI works thereof (Set No. 1)Type IV Quarters)

Estimated Cost: - Rs 99031 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S No	Sub head and items of work	Qty.		Rate figures		Unit	Amount
				4	5		
1	2	3				6	7
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within Sometres lead-For thickness of tiles 10 mm to 25 mm complete including carriage of materials within all leads and lifts.	42.39	Sqm	48 30	Rupees Forty Eight and Paise Thirty Only	Per Square Metre	2047 00
2	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete (1) Size of Tile 300 x 450 mm	35.08	Sqm	1140 00	Rupees One Thousand One Hundred Forty Only	Per Square Metre	39991 00
3	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. (i) Size of Tile 300x300 mm	7.31	Sqm	1350 00	Rupees One Thousand Three Hundred Fifty Only	Per Square Metre	9869 00
4	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required: Kitchen sink without drain board (i)610x510 mm bowl depth 200 mm	1.00	Sqm	2500 00	Rupees Two Thousand Five Hundred Only	Per Square Metre	2500 00
5	Providing and fixing P.V.C. waste pipe for sink or wash basin Including P.V.C. waste fittings complete. Semi rigid pipe 32 mm dia including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	Sqm	311.46	Rupees Three Hundred Eleven and Paise Forty Six Only	Per Square Metre	311 00
6	Providing and fixing C.P. grating of approved quality and colour.Circular type (i) 100 mm nominal dia including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	3.00	Sqm	120 00	Rupees One Hundred Twenty Only	Per Square Metre	360 00
7	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 93 gms. (i) 15 mm nominal bore including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	2.00	Sqm	585.74	Rupees Five Hundred Eighty Five and Paise Seventy Four Only	Per Square Metre	1171 00
8	Providing and fixing 15mm nominal bore C.P. brass angle cock of approved quality conforming to IS:8931 complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	7.00	No	426.36	Rupees Four Hundred Twenty Six and Paise Thirty Six Only	Each	2985 00
9	Providing and rising 30 cm length uplasticised PVC connection pipe with brass unions 15 mm nominal bore complete including camage of materials upto all leads and lifts and as directed by the Engineer in Charge	6.00	No	128 04	Rupees One Hundred Twenty Eight and Paise Four Only	Each	768 00
10	Providing and fixing GI pipes complete with G.I. fittings including trenching and refilling etc. 15 mm nominal bore including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	20.00	Rmt	329.10	Rupees Three Hundred Twenty Nine and Paise Ten Only	Per Running Metre	6582 00
11	Providing and fixing PVC (Finolex) floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (i)110mm X 90mm size.	5.00	No	400.26	Rupees Four Hundred and Paise Twenty Six Only	Each	2001 00

12	Providing and fixing 110 mm dia PVC Finolex Plain Bend type-B ISI marked including fixing with approved adhesive etc. complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (1) 110mm Nominal Dia	10.00	No	180.00	Rupees One Hundred Eighty Only	Each	1800.00
13	Providing and fuong PVC collars ISI marked including fixing with approved adhesive etc. complete in all respect including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. 110 mm dia	10.00	No	160.00	Rupees One Hundred Sixty Only	Each	1600.00
14	Providing and fixing high pressure PVC finolex Type B spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc, complete, including Carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge. 110mm Dia	24.00	Rmt.	409.30	Rupees Four Hundred Nine and Paise Thirty Only	Per Running Metre	9823.00
15	Providing and fixing two hole basin mixing Faucet, 15 mm Dia including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (S.S.)	3.00	No	2500.00	Rupees Two Thousand Five Hundred Only	Each	7500.00
16	Providing and fixing C.P. Brass pillar tap with capstan head 15mm dia, including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (S.S.)	2.00	No	650.00	Rupees Six Hundred Fifty Only	Each	1300.00
17	Providing and fixing 8 mm dia C.P./S.S. Jet with flexible tube upto 1 metre long with S.S triangular plate to European type W.C. of quality and make as approved by Engineer - in charge including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No	723.15	Rupees Seven Hundred Twenty Three and Paise Fifteen Only	Each	723.00
18	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS: 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No	3500.00	Rupees Three Thousand Five Hundred Only	Each	3500.00
19	Providing & fixing White vitreous china water closet squatting pan (Indian type) along with "S" or "P" trap including dismantling of old WC seat and "S" or "P" trap at site complete with all operations including all necessary materials, labour and disposal of dismantled material l/c malba, all complete as per the direction of Engineer-in charge.	1.00	No	2500.00	Rupees Two Thousand Five Hundred Only	Each	2500.00
20	Providing and fixing 10.00 ltr. (ten litre) capacity PVC low level flushing cistern Hind ware sleek ultra design No 186575 size 42 X 39 X 14 cm (forty two into thirty nine into fourteen centimetre) or equivalent with a pair of brackets with fittings such as lead valve, syphon, 15mm nominal size PVC ball valve with polythene float, with push button, couplings for connections with Inlet, outlet and overflow pipe, 40mm (forty milimetre) dia C.P. flush bend including cutting holes in walls and making good the same and connecting the flush bend with cistern and closet (overflow) pipe to be measured and paid for separately including carriage of materials within all leads and lifts:	1.00	No	1700.00	Rupees One Thousand Seven Hundred Only	Each	1700.00
0						Total:	99031.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhama

SCHEDULE OF QUANTITY

Name Of Work :- Special repair to HP Printing Press at Ghoar Chowki Shimla (SH:- Dismantling toilet & Bathroom Floor tile works for flooring and WS & SI works thereof(Set No.2)Type IV Quarters)

Estimated Cost: - Rs 99031 /- only

Earnest Money : - Rs. 2000 /-only

Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			4	5		
1	2	3		figures	6	7
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within Sometres lead-For thickness of tiles 10 mm to 25 mm complete including carriage of materials within all leads and lifts.	42.39 Sqm	48.30	Rupees Forty Eight and Paise Thirty Only	Per Square Metre	2047.00
2	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete (1) Size of Tile 300 x 450 mm	35.08 Sqm	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square Metre	39991.00
3	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. (i) Size of Tile 300x300 mm	7.31 Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Metre	9869.00
4	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required: Kitchen sink without drain board (i)610x510 mm bowl depth 200 mm	1.00 No.	2500.00	Rupees Two Thousand Five Hundred Only	Each	2500.00
5	Providing and fixing P.V.C. waste pipe for sink or wash basin Including P.V.C. waste fittings complete. Semi rigid pipe 32 mm dia including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00 No.	311.46	Rupees Three Hundred Eleven and Paise Forty Six Only	Each	311.00
6	Providing and fixing C.P. grating of approved quality and colour.Circular type (i) 100 mm nominal dia including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	3.00 No.	120.00	Rupees One Hundred Twenty Only	Each	360.00
7	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 93 gms. (i) 15 mm nominal bore including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	2.00 No.	585.74	Rupees Five Hundred Eighty Five and Paise Seventy Four Only	Each	1171.00
8	Providing and fixing 15mm nominal bore C.P. brass angle cock of approved quality conforming to IS:8931 complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	7.00 No	426.36	Rupees Four Hundred Twenty Six and Paise Thirty Six Only	Each	2985.00
9	Providing and rising 30 cm length uplasticised PVC connection pipe with brass unions 15 mm nominal bore complete including camage of materials upto all leads and lifts and as directed by the Engineer in Charge	6.00 No	128.04	Rupees One Hundred Twenty Eight and Paise Four Only	Each	768.00
10	Providing and fixing GI pipes complete with G.I. fittings including trenching and refilling etc. 15 mm nominal bore including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	20.00 Rmt	329.10	Rupees Three Hundred Twenty Nine and Paise Ten Only	Per Running Metre	6582.00

11	Providing and fixing PVC (Finolex) floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (i) 110mm X 90mm size.	5.00	No	400.26	Rupees Four Hundred and Paise Twenty Six Only	Each	2001.00
12	Providing and fixing 110 mm dia PVC Finolex Plain Bend type-B ISI marked including fixing with approved adhesive etc. complete including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (1) 110mm Nominal Dia	10.00	No	180.00	Rupees One Hundred Eighty Only	Each	1800.00
13	Providing and fuong PVC collars ISI marked including fixing with approved adhesive etc. complete in all respect including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. 110 mm dia	10.00	No	160.00	Rupees One Hundred Sixty Only	Each	1600.00
14	Providing and fixing high pressure PVC finolex Type B spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc, complete, including Carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge. 110mm Dia	24.00	Rmt.	409.30	Rupees Four Hundred Nine and Paise Thirty Only	Per Running Metre	9823.00
15	Providing and fixing two hole basin mixing Faucet, 15 mm Dia including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (S.S.)	3.00	No	2500.00	Rupees Two Thousand Five Hundred Only	Each	7500.00
16	Providing and fixing C.P. Brass pillar tap with capstan head 15mm dia, including carriage of material upto all leads and lifts as per the direction of Engineer in Charge. (S.S.)	2.00	No	650.00	Rupees Six Hundred Fifty Only	Each	1300.00
17	Providing and fixing 8 mm dia C.P./S.S. Jet with flexible tube upto 1 metre long with S.S triangular plate to Eureka type W.C. of quality and make as approved by Engineer - in charge including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No	723.15	Rupees Seven Hundred Twenty Three and Paise Fifteen Only	Each	723.00
18	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS: 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	1.00	No	3500.00	Rupees Three Thousand Five Hundred Only	Each	3500.00
19	Providing & fixing White vitreous china water closet squatting pan (Indian type) along with "S" or "P" trap including dismantling of old WC seat and "S" or "P" trap at site complete with all operations including all necessary materials, labour and disposal of dismantled material l/c malba, all complete as per the direction of Engineer-in charge.	1.00	No	2500.00	Rupees Two Thousand Five Hundred Only	Each	2500.00
20	Providing and fixing 10.00 ltr. (ten litre) capacity PVC low level flushing cistern Hind ware sleek ultra design No 186575 size 42 X 39 X 14 cm (forty two into thirty nine into fourteen centimetre) or equivalent with a pair of brackets with fittings such as lead valve, syphon, 15mm nominal size PVC ball valve with polythene float, with push button, couplings for connections with Inlet, outlet and overflow pipe, 40mm (forty milimetre) dia C.P. flush bend including cutting holes in walls and making good the same and connecting the flush bend with cistern and closet (overflow) pipe to be measured and paid for separately including carriage of materials within all leads and lifts:	1.00	No	1700.00	Rupees One Thousand Seven Hundred Only	Each	1700.00
0						Total:	99031.00

Amount Quoted by the Contractor in Percentage	Rs.
---	-----

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 70,000.00	
Name of Work :- Construction of Link road from Jood to Khunara, Distt. Shimla (H.P.) km 0/00 to 0/900 (SH:- Preperation of FRA case in all respect)						Earnest Money:- 2000.00	
						Time:- One Month.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Preparation of Geo refrence digital map and Collecting the data from proposed site including fild visits Preparation of Kml file, Geo coordinates along with making of Habitations to be benefited by construction of project and dumping area of proposed site. Making The alignment in soft copy and submission in hard copy.Preperation of Forest case(FRA) proposed road in Dhami Sub Division.Preperation of Folders complete in all respect and submit to the department as per the direction of Engineer- in- charge.	1.00	Job	70000.00	Rupees Seventy Thousand Only	Per Job	70000
Total Rs.							70000
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

Schedule Of Quantity						Estimated Cost:- 99,840.00	
Name of Work :- A/R & M/O on Link road to Village Garkhan km. 0/00 to 3/00 (SH:- Maintenance of earth shoulder, Trimming of grass, Maintenance of earth shoulder, Maintenance Of Drain, and Maintenance of Hume pipe Culvert in km. 0/00 to 3/00)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2860.00	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	12870
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2860.00	Sqm	24.50	Rupees Twenty Four and Paise Fifty Only	Per Square metre	70070
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2200.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per Running Metre	9900
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	4.00	No.	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Each	7000
	Total Rs.						99840
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhamsi. *[Signature]*

Schedule Of Quantity						Estimated Cost:- 99,085.00	
Name of Work :- C/O road from Jalog Himri to village Jhutnu km. 0/00 to 1/150 (SH:- Construction of Retaining wall at Rd. 0/495 to 0/499.30) Under BASP Head						Earnest Money:- 2000.00	
						Time:- One Months.	
						Unit	Amount
S.No	Description of Work	No. of Qty.		Rate			
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	6.19	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	1232
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	0.99	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	353
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.45	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	92250
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	12.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2280
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	2.97	Per cum	1000.00	Rupees One Thousand Only	Per cubic metre	2970
Total Rs.							99085
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhama. *dm*

Schedule Of Quantity						Estimated Cost:- 99,398.00	
Name of Work :- C/O road from Jalog Gadheri to village Kandharti Ojdu Shaw seri km. 0/00 to 1/330 (SH:-						Earnest Money:- 2000.00	
Construction of Retaining wall at Rd. 0/240 to 0/244.90) Under BASP Head						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	8.92	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	1775
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth	1.13	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	403
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.77	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	93850
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	10.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	1900
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD . specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	1.47	Per cum	1000.00	Rupees One Thousand Only	Per cubic metre	1470
	Total Rs.						99398
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhama. *[Signature]*

Schedule Of Quantity						Estimated Cost:- 99,080.00	
Name of Work :- A/R & M/O on 16 Mile to Sedan Road km. 0/00 to 2/660 (SH:- Maintenance of earth shoulder, Trimming of grass, Maintenance of earth shoulder, Maintenance Of Drain, and Maintenance of Hume pipe Culvert in km. 0/00 to 2/660)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In-Charge .	3080.00	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	13860.00
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2860.00	Sqm	24.50	Rupees Twenty Four and Paise Fifty Only	Per Square metre	70070.00
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2200.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per Running Metre	9900.00
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	3.00	No.	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Each	5250.00
Total Rs.							99080
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhani.

Schedule Of Quantity						Estimated Cost:- 99,840.00	
Name of Work :- A/R & M/O Pakki Bawari Shakrah Sedan Road km. 0/00 to 5/700 (SH:- Maintenance of earth shoulder, Triming of grass,Maintenance of earth shoulder, Maintenance Of Drain, and Maintenance of Hume pipe Culvert in km. 0/00 to 2/800)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In-Charge .	2860.00	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	12870.00
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2860.00	Sqm	24.50	Rupees Twenty Four and Paise Fifty Only	Per Square metre	70070.00
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2200.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per Running Metre	9900.00
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	4.00	No.	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Each	7000.00
Total Rs.							99840
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharni.

SCHEDULE OF QUANTITY
Name of Work:- Repair & Maintenance of Shimla Rural Division office Building at Dhami (Sh: Establishment of departmental Lab)

Estimated Cost: - Rs 96235 /- only
 Earnest Money : - Rs. 2000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure in Cement mortar 1:4 (1 cement: 4 coarse sand) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	6.97 Sqm	975.00	Rupees Nine Hundred Seventy Five Only	Per Cubic Metre 6796.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 Cement: 2 coarse sand): 4 graded stone aggregate 20 mm nominal size) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	0.14 Cum	6950.00	Rupees Six Thousand Nine Hundred Fifty Only	Per Cubic Metre 1001.00
4	Reinforced cement concrete work in beams, suspended floors, roofs landings, balconies, shelves, chajjas, lintels, bands plain window sills, above plinth level up to floor five level, including the cost of centering, shuttering finishing and reinforcement with 1:1.5:3 (1) cement: 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	0.03 Cum	8250.00	Rupees Eight Thousand Two Hundred Fifty Only	Per Cubic Metre 248.00
4	Providing Mild Steel/tor steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto two level, including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	6.00 Kg.	95.00	Rupees Ninety Five Only	Per Kilogramme 570.00
5	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). 2nd class D/wood or Sal wood.	0.13 Cum	126000.00	Rupees One Lakh Twenty Six Thousand Only	Per Cubic Metre 16380.00
4	Providing and fixing panelled or panelled and glazed shutters for windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, /nails including fixing 4.00 mm thick glass with necessary screws, corners/mouldings complete in all respect and as per direction and satisfaction of Engineer in-charge. 2nd class deodar	4.30 Sqm	4150.00	Rupees Four Thousand One Hundred Fifty Only	Per Square Metre 17845.00
7	Providing and fixing aluminium sliding door bolts (Barrel type) anodized transparent or dyed to required shade and colour with bolts and nuts etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.: 300 X 16 mm	1.00 No.	350.00	Rupees Three Hundred Fifty Only	Each 350.00
8	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.: 250mm x 10mm.	6.00 No.	85.00	Rupees Eighty Five Only	Each 510.00
4	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge. :125mm.	6.00 No.	70.00	Rupees Seventy Only	Each 420.00

10	Providing and fixing 19 mm thick commercial board water proof in shelves, lining, box for cup boards with butt joints fixed with nails and screws etc complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	17.76	Sqm	1476.00	Rupees One Thousand Four Hundred Seventy Six Only	Per Square Metre	26214.00
11	Providing and fixing 19 mm thick commercial board water proof shutter for cup boards including fixing with nickel plated piano hinges with screws etc. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	4.80	Sqm	1690.00	Rupees One Thousand Six Hundred Ninety Only	Per Square Metre	8112.00
12	Providing and fixing 0.80 mm thick coloured or plain laminated sheet (sunmica) on boards ply wood sheets with approved adhesive and nails complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	9.60	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square Metre	8160.00
4	Providing and fixing square edged cover fillets (beading) 19 x 6 mm section including mitring at junction with wooden screws/nails etc complete of hard wood including carriage of material in all leads and lifts.	20.00	Rmt.	65.00	Rupees Sixty Five Only	Per Running Metre	1300.00
14	15 mm cement plaster on the rough side of single or half brick wall of mix: 1:6 (1 cement: 6 fine sand) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	13.94	Sqm	250.00	Rupees Two Hundred Fifty Only	Per Square Metre	3485.00
15	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	9.05	Sqm	150.00	Rupees One Hundred Fifty Only	Per Square Metre	1358.00
16	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	13.94	Sqm	75.00	Rupees Seventy Five Only	Per Square Metre	1046.00
17	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	13.94	Sqm	175.00	Rupees One Hundred Seventy Five Only	Per Square Metre	2440.00
0							
						Total:	96235.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Shimla

Schedule Of Quantity						Estimated Cost:- 98,090.00	
Name of Work :- A/R & M/O on Link road to Village Khatnol km. 0/00 to 10/00 (SH:- Maintenance of earth shoulder, Trimming of grass, Maintenance of earth shoulder, Maintenance Of Drain, and Maintenance of Hume pipe Culvert in km. 5/00 to 10/00)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2860.00	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	12870
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2860.00	Sqm	24.50	Rupees Twenty Four and Paise Fifty Only	Per Square metre	70070
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2200.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per Running Metre	9900
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	3.00	No.	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Each	5250
Total Rs.							98090
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhama. *[Signature]*

Schedule Of Quantity						Estimated Cost:- 99,645.00	
Name of Work :- Restoration of rain Damages on Shimla Mandi road km. 22/00 to 52/300 (SH:- Hiring of JCB for removal of slips in km. 39/00 to 52/300)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost .including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645
Total Rs.							99645
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

Schedule Of Quantity						Estimated Cost:- 99,645.00	
Name of Work :- Restoration of rain Damages on Shimla Mandi road km. 22/00 to 52/300 (SH:- Hiring of JCB for removal of slips in km. 22/00 to 33/00)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost .including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645
Total Rs.							99645
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharmu

Schedule Of Quantity						Estimated Cost:- 99,645.00	
Name of Work :- Restoration of rain Damages on Karyali to Shara in km. 0/00 to 2/555 (SH:- Hiring of JCB for removal of slips in km. 0/00 to 2/555)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost .including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645
Total Rs.							99645
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhani.


Schedule Of Quantity						Estimated Cost:- 99,645.00	
Name of Work :- Restoration of rain Damages on Link road from Mandorghat to Village Anu in km. 0/00 to 5/00 (SH:- Hiring of JCB for removal of slips in km. 0/00 to 5/00)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost .including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow/,slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645
Total Rs.							99645
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhami

Schedule Of Quantity						Estimated Cost:- 99,796.00	
Name of Work :- R/R Damages on Shoghi Mehli road km. 0/00 to 12/375 (SH:- Removal of slips at various Rds.)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	1108.84	Cum	90.00	Rupees Ninety Only	Per Cubic Metre	99796
Total Rs.							99796
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 83115.00	
Name Of Work :- Restoration of rain damages on Shoghi Mehli road km. 0/00 to 12/375 (SH:- Removal of Slips at Rd. 6/375 to 6/405)						Earnest Money:- 1700.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	923.50	Per cum	90.00	Rupees Ninety Only	Per cubic metre	83115
Total Rs.							83115
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi. 

Schedule Of Quantity							Estimated Cost:- 99,931.00
Name of Work :- R/R Damages on Shoghi Mehli road km. 0/00 to 12/375 (SH:- Removal of slips at various Rds.)							Earnest Money:- 2000.00
							Time:- One Months.
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	1110.34	Cum	90.00	Rupees Ninety Only	Per Cubic Metre	99931
Total Rs.							99931
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharmi. *Sm*

Schedule Of Quantity						Estimated Cost:- 99,666.00	
Name of Work :- R/R Damages on Kawara Chowki to Thalak Dhar road km. 0/00 to 2/200 (SH:- Removal of slips at various Rds.)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	1107.40	Cum	90.00	Rupees Ninety Only	Per Cubic Metre	99666
Total Rs.							99666
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 97,730.00	
Name of Work :- A/R & M/O on Shoghi Mehli road km. 0/00 to 12/375 (SH:- Providing and Fixing Precast RCC drain covers between km. 11/00 to 11/100)						Earnest Money:- 2000.00	
						Time:- One Month.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words	7	8
1	Providing and fixing in position pre- cast R.C.C. Manhole cover of required shape and approved quality Rectangular shape 900 mm x 600 mm size) including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	9.00	No	10858.90	Rupees Ten Thousand Eight Hundred Fifty Eight and Paise Ninety Only	Each	97730
Total Rs.							97730
Amount Quoted by the Contractor in Percentage							
Note :- All the material will be procured by the contractor himself							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dham

Schedule Of Quantity						Estimated Cost:- 97,730.00	
Name of Work :- A/R & M/O on Shoghi Mehli road km. 0/00 to 12/375 (SH:- Providing and Fixing Precast RCC drain covers between km. 11/100 to 11/200)						Earnest Money:- 2000.00	
						Time:- One Month.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2	3	4	5	6	7	8
1	Providing and fixing in position pre- cast R.C.C. Manhole cover of required shape and approved quality Rectangular shape 900 mm x 600 mm size) including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	9.00	No	10858.90	Rupees Ten Thousand Eight Hundred Fifty Eight and Paise Ninety Only	Each	97730
Total Rs.							97730
Amount Quoted by the Contractor in Percentage							
Note :- All the material will be procured by the contractor himself							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dham

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance of Hirnagar Dhamoon Road Km. 0/00 to 8/00 (Sh: Repair of Earthen Shoulder, Trimming of Grass and clearing of Drain in Km. 0/00 to 2/000)

Estimated Cost: - Rs 99500 /- only

Earnest Money : - Rs. 2000 /-only

Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			4	5		
1	2	3	4	5	6	7
1	Maintenance of Earthen shoulder (stripping of excess soil) , Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 as per the direction of Engineer-in-Charge.	3000.00 Sqm	16.50	Rupees Sixteen and Paise Fifty Only	Per Square Meter	49500.00
2	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of material upto all leads and lifts as per the direction of Engineer-in-charge.	500.00 Rmt.	4.00	Rupees Four Only	Per Running Meter	2000.00
3	Trimming of grass and weeds from shoulder / berms and disposing off the same to suitable locations as per technical specifications clause 1914 including carriage of material within all leads and lifts as per the directions of Engineer-in-charge.	12000.00 Sqm	4.00	Rupees Four Only	Per Square Meter	48000.00
0					Total:	99500.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 99,648.00	
Name Of Work :- Annual Repair & Maintenance on Tara Mata Temple road km. 0/00 to 2/200 (SH:- Maintenance of earthen shoulder & white washing in km. 0/00 to 2/200)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Maintenance of earthen shoulder (Filling with fresh soil) making up loss of material/ irregularities on shoulder to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead 1000m per tonne, as per drawings and Technical Specification Clause 1903 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	4000.00	Sqm	24.00	Rupees Twenty Four Only	Per Square Metre	96000
2	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	114.00	Sqm	32.00	Rupees Thirty Two Only	Per Square Metre	3648
Total Rs.							99648
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 98,800.00	
Name of Work :- Annual Repair & Maintenance on Tara Mata Temple road km. 0/00 to 2/200 (SH:- painting on steel Railing)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture. including carriage of materials with in all leads, lifts and other incidentals.	1520	Sqm	65.00	Rupees Sixty Five Only	Per Square metre	98800
Total Rs							98800
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 99,887.00	
Name of Work :- A/R & M/O Taradevi Gamber road km. 0/00 to 11/550 (SH:- Maintenance of drain, Trimming of Grass, Earthen Shoulder & white washing in km. 7/00 to 9/00) & A/R & M/o Shakoh to Hanuman mandir road km. 0/00 to 1/250 (SH:- Maintenance of drain, Trimming of Grass, Earthen Shoulder & white washing in km. 0/00 to 1/250)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	3229	Rmt	4.50	Rupees Four and Paise Fifty Only	Per running metre	14530.5
2	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	3412.50	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	15356
3	Maintenance of Earthen Shoulder (filling with fresh soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per tonne.including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2050.00	Sqm	24.00	Rupees Twenty Four Only	Per Square metre	49200
4	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	650.00	Sqm	32.00	Rupees Thirty Two Only	Per Square metre	20800
Total Rs.							99887
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhama. *Am*

Schedule Of Quantity						Estimated Cost:- 99,400.00	
Name of Work :- Annual Repair and maintenance of HPPWD Rest House at Tara Devi Distt. Shimla (HP) (SH:- Supplying of drinking water in rest House at Tara devi)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Supply of drinking water for Circuit house / Rest house / Old Rest House and office at Tara devi Rest house shoghi . The water Should be clean , free from impurities for drinking purpose as per entire satisfaction and direction of Engineer - in - Charge . i/c Carriage of Materials labour equipments and materiaks to various locations , Through all modes of transportion in all leads and lifts and all incidental Charges .	142000.00	Liters	0.70	Rupees NIL and Paise Seventy Only	Per Liters	99400
	Total Rs						99400
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi.