



Office of the
Executive Engineer
Electrical Division, HP PWD Una
Tel: +911975223484, Fax: +911975223484
E-mail: ee-eleu-hp@nic.in

4-8-2025

No.PW/EDU/CB//TA/Tender/2025-26/-

2877 - 2907

Dated

To

✓ The Executive Engineer (IT) Cell,
Nirman Bhawan, Nigam Vihar
Shimla-171002

Subject: - Regarding publication of Tenders Notice.

Sir,

“JAI HIND”


Enclosed please find herewith Tenders Notice along with Schedule of Quantities for uploading the same on Departmental website as per Notification no. PBW-(B)1/2020 dated 16.07.2021 as the work mentioned in the Tender Notice are urgent in nature and in Public interest. This is for your kind information and necessary action at your end please.

DA:-As above.


Executive Engineer,
Electrical Division,
HPPWD, Una.

Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer, 2nd Electrical Circle, HPPWD, Dharamshala.
2. The Assistant Engineer, Electrical Sub Division, HP PWD Una/Hamirpur & Bilaspur.
3. All the contractors working under the control of this Division.
4. All the Head of Branches in this office.
5. Notice Board.


Executive Engineer,
Electrical Division
HPPWD, Una



Office of the
Executive Engineer
Electrical Division, HP PWD Una
Tel: +911975223484, Fax: +911975223484
E-mail: ee-eleu-hp@nic.in

NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited by the Executive Engineer Electrical Division HPPWD Una, in form No.6 & 8 on behalf of Governor of H.P. for the following works from the contractors of appropriate class enlisted with HPPWD (Electrical). The tenders shall be opened on dated **18/08/2025** in the presence of contractors/firms or their authorized representative who wish to be present.

The copy of **Valid enlistment** and renewal certificate along with GST No., PAN No., and EPF No. shall be attached with application form. The offer of the tender shall remain open **75 days** from the date of opening of the tenders. The undersigned reserves the right to reject/cancel the tenders without assigning any reason. The tender form will be issued to only those contractors who qualify the criteria after the scrutiny of application forms by the committee constituted for the purpose.

TIME SCHEDULE OF TENDER

- | | | | |
|----|-------------------------------------|----|-----------------------------|
| 1. | Last date of receipt of application | :- | 14/08/2025 up to 1.00 P.M. |
| 2. | Date of sale of tenders | :- | 14/08/2025 up to 5.00 P.M. |
| 3. | Last date of receipt of bids | :- | 18/08/2025 up to 11.30 A.M. |
| 4. | Date of bid opening | :- | 18/08/2025 up to 1.00 P.M. |

Sr. No.	Name of work	Estimated Cost (In Rs.)	Earnest Money (In Rs.)	Cost of form (In Rs.)	Time Limit	Eligible Class of Contract
1	Replacement of damaged accessories and E.I. in various Govt. NR building i.e. Rest House Taun Bharari in first floor VIP suit, sitting & suit No. 03 under ESD Hamirpur (Barsar Section) Distt. Hamirpur (HP)	99,837/-	2,000/-	350/-	One month	Class D,C
2	A/R & M/O of different capacity Air conditioning installed in various N/R building under ESD Hamirpur (Barsar section) for 2025-26 (w.e.f. One year from awarded date)	96,222/-	2,000/-	350/-	One year	Specialize Job
3	Supplying, installation, Testing and Commissioning of Split type Air Conditioner in Mechanical Sub-Division HPPWD, Hamirpur Distt. Hamirpur (H.P)	72,586/-	1,500/-	350/-	Six months	Specialize Job
4	Special repair of Air Conditioner in the office of Deputy Commissioner (DC) and the Additional Deputy Commissioner (ADC) Una (H.P)	61,423/-	1,250/-	350/-	One month	Specialize Job
5	Repair and Maintenance of E.I. in various Government N.R. building under ESD HPPWD, Una (SH:- Providing repair & rewiring of E.I. thereof in Una HP)	77,041/-	1,500/-	350/-	Six months	Class-D,C
6	Repair and Maintenance of E.I. in various Government N.R. buildings under ESD	85,176/-	1,700/-	350/-	Six months	Class-D,C

	HPPWD, Una (SH:- Providing repair & rewiring of E.I. in the accountant in Electrical Division HPPWD, Una (HP)					
7	Running and Maintenance of E.I. in various Govt. N.R. buildings in Distt. Una (H.P) (SH:- Engagement of T-mate/Helper under ESd HPPWD, Una Distt. Una (H.P) (W.e.f. for 04 (Four) months from awarded date)	91,744/-	1,800/-	350/-	Four Months	Class-D,C

GENERAL TERMS AND CONDITIONS:-

1. The earnest money in the shape of NATIONAL Saving Certificate time deposit account in any of the post office in HP/FDR or any bank duly pledged in favour of Executive Engineer, HPPWD., Electrical Division Una accompanied with the application for receipt of tender form along with cost of form.
2. The Contractor/Firm should be submitted the all above-mentioned documents (photocopy to be self-attested) with the application for obtaining the tender documents.
3. In case office happens to be closed on any of the above mentioned dates, the bids will be opened on the next working day at same time and venue.
4. The contractors/firms are required to quote their rates clearly both in words as well as in figures, failing which tenders are likely to be rejected.
5. No Person/persons shall be allowed to give the documents with regard to tender unless he/they hold/holds the power of attorney duly registered under law.
6. The tender of those contractors who are registered under H.P. Central Sales Tax Act 1969, GST and who have been cleared all the dues on account of tax will be entertained.
7. The competent authority on behalf of Governor of H.P. reserves the right to reject any or all the tenders received without assigning any reason.
8. The eligible Contractors/Firm should performance certificate for specialized jobs as required.
9. The tendered amount should be within the limit of (+) 5% to (-) 30% as per notification No. PBW(B)A(3)1/2020-1 dated 07.10.2021 shall be applicable for Bid price lower than-10% and more than + 5%. If the Contractors/Firms has quoted bid price lower than 10% the performance guarantee will be deposited before the award of work as per terms & condition of above said notification.

“HIM SUCHANA AVAM JANSAMPARK”


**Executive Engineer,
 Electrical Division
 HPPWD, Una**

DRAFT SCHEDULE OF QUANTITY

216 No. 01

Estimated Cost Rs	Rs	99837/-
Earnest Money Deposit Rs	Rs	2000/-
Time Limit		One Month

NAME OF WORK:- Replacement of damaged accessories and E.I. in various Govt. NR Building i.e. Rest House Taun Bharari in First Floor VIP Suit, Sitting & Suit No 3 under ESD Hamirpur (Barsar Section) Dist. Hamirpur (HP)

S.No.	Description of Items	Qty.	Unit	Rate	Rate in words	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVCConduit as required.					0
1.01	S&D 3 X 1.5 sq. mm wire	80	each	100	Rs. One hundred only	8000
2	Supplying and fixing of following sizes of PVC conduit Heavy duty ISI marked minimum thickness 2.0 mm along with accessories insurface/recess including painting in case of surface conduit, or cutting the walland making good the same in case of recessed conduit as required. Make:- Diplas/BEC/Polyfit/Polyplas/AKG as approved by Engineer-in-charge.					
2.02	25 mm. dia	55	each	99	Rs. Ninety Nine only	5445
3	Supply and fixing of LED COB Pro spot light 12 W recessed mounted with aluminium housing and Polycarbonate diffuser, minimum system efficacy of 100lm/W with P.F.>0.95 with THD<10%, CCT5700 K, CRI 80, Surge Protection 4 KV. The LED with Useful life of 35000 Hrs @ L70. The Input voltage range shall be 150V to 360V. Make:- PHILIPS/WIPRO//AQUAR/LEKSA as approved by Engineer-in-Charge with five year warranty.	28	each	1865	Rs. One Thousand Eight Hundred sixty Five only	52220
4	Supplying and fixing LED strip 6.6 watt per metre, 3000K, with five year warranty. and it should be compatible with specification i.e. Power Factor > .9, Harmonic Distortion<10% and efficacy >100 Lumens per watt, suitable for input voltage: AC 220-240 V, 50/60Hz, complete with all accessories, connections, testing and commissioning etc. Make:- Jaquar /Philips/Wipro/Crompton as approved by Engineer-in-Charge.	56	each	286	Rs. Two Hundred Eighty Six only	16016
5	Supplying and fixing of LED panel driver 120 watt, 12 volt, 10 amp, 30K burning hours with connector including connections, testing and commissioning as required. Make:- Jaquar /Philips/Wipro/Crompton as approved by Engineer-in-Charge.	6	each	1526	Rs. One Thousand Five Hundred Twenty Six only	9156
6	Dismentalling, shifting and reinstalation of existing Split type 1.5 Ton A.C. connections, testing & commissioning etc. as required complete in all respect.	3	each	3000	Rs. Three Thousandsd only	9000
	Total					99837
	Total					750
	Total					99087

DMIT No. 184 for the years 2025-26 has been checked for Rs. 99837/- only. (Repaired Ninety nine thousand Eighty Seven only).

Assistant Engineer

**Executive Engineer
Electrical Division
M.P.W.D. Una-174308**

**Electrical Sub Division
HP, PWD, Hamirpur**

DRAFT SCHEDULE OF QUANTITY

Job No 02

Estimated Cost	Rs.	96222/-
Earnest Money/Rs.		2000/-
Time Limit		one year

Name of work :- A/R & M/O of different capacity Air Conditioning installed in various N/R building under ESD Hamirpur (Barsar section) for 2025-2026
(W.E.F. One year from Awarded date)

S.No	Description of items	Qty.	Unit	Rate	Rate in words	Amount
1	Annual Repair and maintenance (Routine and preventive) of various make type and different capacity split A.C with 4 No Mandatory quarterly service and all emergency break down service as when required from time to time as per the best satisfaction of engineer in charge.					
i	The AMC include the following.					
ii	Compressor, Thermostat, Over Load Relays, fan motors, timers, heaters, air damper, ice maker temprature sensor, evaporator, condenser, refrigerant charging, driers, capillary blowers, fan blade, control box, magnetron, Electrical switch, transformer, diode, capacitor, wire harness, wash and spin motor gear box clutch assembly drum, inner belws bear & lip seal (drain motor pump) electrical bulb buzzer suspension key members remote PCB including cost of their replacement.					
iii	All defective component shall be replaced with compatible working parts and defective part shall be company /firm /contractor property.					
iv	(i) Split type (H&C) A.C. 1.5/2.0 Ton capacity	21	each	4582	Rs. Four thousand five hundred eighty two only	96222
	Total					96222

*DNIT No. 188 for the year 2025-26 has been checked for Rs. 96222/- only.
(Rupees Ninety Six thousand two hundred twenty two only).*

Executive Engineer
Electrical Division
H.P.P.W.D. Ura-174303

[Signature]
Assistant Engineer
Electrical Sub-Division
HP, PWD, Hamirpur

DRAFT SCHEDULE OF QUANTITY

Abhishek


Estimated Cost:- Rs. 72,586/-
Earnest money:- Rs. 1500/-
Time Limit:- Six months.

Name of work:- Supplying, Installation, Testing and Commissioning of Split type Air Conditioner in Mechanical Sub-Division,
HP.PWD., Hamirpur Distt. Hamirpur (H.P.).

S. No.	Description of Items.	Quantity		Rate In Fig.	In Words.	Unit	Amount
1	Supplying and fixing 1.5 ton inverter split type air conditioner Hot and Cold with advanced filter , E saver mode , quit mode, dual display ,auto clean ,anti bacteria filter jet Cool on/off timer sleep mode compressor cord less remote complete in all respect as per comprising to ISI with latest amendment suitable to operate on 230 volt /240 volt \pm 10 % AC supply capable to perform the function of cooling dehumidification air circulation ventilation and fitting in size of nominal cooling capacity with as per company standard copper pipe with insulation tape, drain pipe, power cable, control cable, two nos free services in one year including carriage of material within all leads and lifts. 3 STAR Make:- Daikin/O General/ Mitsubsi as approved by the Engineer-In-Charge. Warranty on product one year, on PCB fiuve year & on compressor 10 year.	1	Number	61125	Rupees Sixty one thousand one hundred twenty five only.	Each	61125
2	Installation charges of split A C 1.5 TR Unit as required complete in all respect.	1	Number	1415	Rupees One thousand four hundred fifteen only.	Each	1415

7	Wiring for Circuit/Sub-main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed heavy class 2.0mm wall thickness conduit as required. Make:- KEI/Finolex/Polycab as approved by Engineer-In-Charge.							
7.01	2x4 Sq.mm + 1x4Sq.mm. earth wire.	10	Metres	311	Rupees Three hundred eleven only.	P/Mtr.	3110	
8	Supplying and fixing 5Amp to 32Amp, 240/415 volts, 10 KA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Make:- L&T/Hager/ABB as approved by the Engineer-In-Charge(five year warranty).							
8.01	Single pole.	1	Each	239	Rupees Two hundred thirty nine only.	Each	239	
Total:-							72586	

DMIT No. 183 for the year 2025-26 has been checked for Rs. 72586/- only. (Rupees Seventy two thousand five hundred & Eighty six only).


 Executive Engineer,
 Electrical Division,
 HP.PWD., Una.

DRAFT SCHEDULE OF QUANTITY

Job No. 04

Estimated cost:- Rs. 61,423/-
 Earnest money:- Rs. 1,250/-
 Time Limit:- One month.

NAME OF WORK:- Special Repair of Air Conditioner in the office of Deputy Commissioner (DC) and the Additional Deputy Commissioner (ADC) Una H.P.

S. No.	Description of Items	Quantity	Unit	Rate In Figure	In Words.	Amount
1	Supply, Installation, Testing and Commissioning of Y/T/Multi Joints & Valve caps of One-quarter inch by one-half inch size in Outdoor unit of the Air conditioner.	3	Each	475	Rupees Four hundred seventy five only.	1425
2	Supply, Installation, testing and commissioning including vaccumization, leak testing and Nitrogen testing of soft/hard drawn copper refrigerant piping for VRV/VRF system for Suction and Liquid lines, all accessories as per specifications etc. as required to the best satisfaction of the Engineer in Charge.	3	Each	3000	Rupees Three thousand only.	9000
3	Refrigerant gas R-32 for top up required For the complete split type Air conditioner unit as required complete in all respects and as per direction and satisfaction of Engineer in charge so as to maintain suitable pressure at standstill with complete minor overhauling and servicing etc. Make: Dupont/ Godrej/ Totaline	3	Each	3950	Rupees Three thousand nine hundred fifty only.	11850
4	Replacement of Printed Circuit Board of Single way VRV/VRF Cassette Type Indoor ceiling mounted unit of 2.0 ton capacity along with all allied electronics complete in all respects and as per direction and satisfaction of Engineer in charge. Make Mitsubishi Electric /OEM only.	1	Each	11800	Rupees Eleven thousand eight hundred only.	11800
5	Repair of Printed Circuit Board of Split type Air Conditioner unit of 1.5 ton capacity along with all allied electronics complete in all respects and as per direction and satisfaction of Engineer in charge. Make Voltas /OEM only.	2	Each	4200	Rupees Four thousand two hundred only.	8400
6	Providing, laying and fixing of 3 core 2.5 sqmm PVC Insulated & PVC Sheathed Industrial Round Multicore Flexible Cable Copper Conductor 1100 Volts, as required complete in all respect from indoor unit to stabilizer & Outdoor unit of Air Conditioner. Make :- Plaza/ Havells/ Polycab/ KEI/ Finolex.	25	Meter	222	Rupees Two hundred twenty two only.	5550

7	Supplying and fixing of 5 KVA voltage stabilizer upto 2.0 ton A.C. having specifications of Input voltage range 130-300V or better, with LED indicator, Digital display, Under voltage Protection, Over voltage protection including connections, testing and commissioning as required with three year warranty. Make:-Microtek Pearl EM 5130+ / Voltas VA5130/IFB IVS 1455A	1	Each	6198	Rupees Six thousand one hundred ninety eight only.	6198
8	Service and testing of 1.5 ton//2.0 ton Air Conditione split type. Cleaning the filters and testing of gas pressure and other electrical parts etc Make: Voltas make.	9	Each	800	Rupees Eight hundred only.	7200
TOTAL						61423

*Certified that work is of emergent nature of impublic interest.
DNIT Recommended for approval.*

ASSISTANT ENGINEER
Electrical Sub Division
H.P.P.W.D. UNA

*DNIT No. for the year 2025-26 has
been checked for Rs. 61423/- only
(Rupees Sixty one Thousand four
hundred twenty three only)*

Executive Engineer
Electrical Division,
H.P.P.W.D. Una (H.P.)

DRAFT SCHEDULE OF QUANTITY

Job No 05

Estimated cost:- Rs. 77,041/-

Earnest money:- Rs. 1,500/-

Time Limit:- Six months.

NAME OF WORK:- Repair and Maintenance of EI in various Government Non Residential buildings under ESD HPPWD Ura.

S. No.	Description of Items	Quantity	Unit	Rate In Figure	In Words.	Amount
1	Supplying and fixing following plano type switch/ socket on the existing switch box/ cover including connections etc. as required. Make:Anchor (Roma classic)/L&T(Entice)/Legrand (Myrius) as approved by Engineer-in-charge.					
I	5/6 amp Plano switch	3	Each	42	Rupees Forty two only.	126
II	5 pin 5/6 amp socket outletPlano type	3	Each	57	Rupees Fifty seven only.	171
2	Supplying and fixing metal box of 150mm X 75mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in FRLSont including providing and fixing 3 pin 5/6 amps socket outlet and 5/6 amps plano type switch, connection, painting etc. as required. (For light plugs to be used in non residential buildings).Make: Anchor/L&T/SSK/Legrand as approved by Engineer-in-charge.	3	Each	265	Rupees Two hundred sixty five only.	795
3	Supplying and fixing metal box of 180mm X 100mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in FRLSont including providing and fixing 6 pin 5/6 & 15/16 amps socket outlet and 15/16 amps plano type switch, connection, painting etc. as required and approved by Engineer-in-charge Make:- Anchor/L&T/SSK Legrand.	4	Each	406	Rupees Four hundred six only.	1624
4	Supplying and fixing batten/ angle holder including connection etc. as required. Make :- Anchor (Roma classic)/L&T(Entice)/Legrand (Myrius) as approved by Engineer-in-charge.	1	Each	88	Rupees Eighty eight only.	88
5	Providing and installation of Wall mounting fan of 400 mm sizes i/e hang the same in position on the wall, connections, testing and commissioning etc. as required with best satisfaction of Engineer in charge :Make:- Usha(MIST AIR DUSOS/ICV)/Bajaj/Crompton as approved by Engineer-in-charge.	1	Each	3041	Rupees Three thousand forty one only.	3041

6	Supplying and fixing Ding Dong bell suitable for single phase, 230 V, complete as required Make :-Anchor (Roma classic)/L&T(Entice)/Legrand (Myrius) as approved by Engineer-in-charge.	1	Each	206	Rupees Two hundred six only.	206
7	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required and as approved by the Engineer-in-charge Make:- Anchor/L&T/ Legrand.	9	Each	422	Rupees Four hundred twenty two only.	3798
8	Providing and installation exhaust fan of 300 mm sizes in the existing opening, including making the hole to suit the size of the above fan, making good the damages, connections, testing and commissioning etc. as required: Make:- Usha/Bajaj/Crompton or as approved by Engineer-in-charge.					
i	EXHAUST Fan Light duty 300 mm sweep	3	Each	2567	Rupees Two thousand five hundred sixty seven only.	7701
9	Supplying and fixing Recess mounting 2'x2' size LED solution suitable for surface application with the use of the latest technology 36 Watt (3600 lumen) 5700K and it should be compatible with specifications i.e. power factor \geq 0.9, harmonic distortion \leq 10% and efficacy \geq 100 lumens per watt, CRI > 80, suitable for input voltage AC 220-240V, 50/60 Hz complete with all accessories, connections, testing and commissioning etc. as required.. Including five years warranty as required.					
i	Cat No: Wipro(CRICO10R036HP57GL1-36W)/Panasonic/Bajaj	4	Each	3397	Rupees Three thousand three hundred ninety seven only.	13588
10	Providing and Fixing of IP20 LED fixture of 12 watt +/- 1 W LED Surface Mounted Downlighter Round Shape with minimum system lumen efficacy of 100 lm/W with Polycarbonate housing, pressure die cast heat sink and P.F.>0.95 with THD<10%,CRI 80. The LED shall be tested with LM80-08 standard with Useful life of 50000 Hrs at L70. The LEDs used in the luminaire shall have CCT of ANSI Bin 5700 K with CRI of minimum 80.The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects.					
i	LED Surface mounting round downlighter 12 watt Makes:- Panasonic,/Wipro/C&S	3	Each	1458	Rupees One thousand four hundred fifty eight only.	4374

11	Supplying and fixing of sub main wiring with 6 sq.mm. weather proof twin core aluminium conductor cable on the G.I. bearer wire etc.as required.	26	Meter	40	Rupees Forty only.	1040
12	Supplying and fixing LED Street Light 60 Watt (2500 lumens), 5700 K CCT and it should be compatible with specifications i.e. power factor ≥ 0.95 , harmonic distortion $\leq 10\%$ and efficacy ≥ 100 lumens per watt, CRI > 45 , suitable for input voltage AC 220-240V, 50/60 Hz, minimum 2.5 kv built in surge protection IP 66 & IK-07 of rating. complete with all accessories, connections, with angle iron frame testing and commissioning etc.Including five years warranty as required.Make:- Wipro/HPL/Panasonic	6	Each	6409	Rupees Six thousand four hundred nine only.	38454
13	Supplying and fixing Computer board comprising metal box 200 mmx150 mmx75 mm for 3 nos 5 amp piano type switches and 3 Nos 5 amp sockets comprising 3 mm thick phenolic laminated sheet cover. for metal box, including connections etc as required.	1	Each	615	Rupees Six hundred fifteen only.	615
14	Supplying and drawing LAN cable CAT 6, solid copper conductor protected with PVC sheath in the existing surface / recessed, steel / PVC conduit as required. Make:- KEI/ D-link/Havell.	10	Meter	73	Rupees Seventy three only.	730
15	Supplying and drawing following pair of Fire Retardant, PVC insulated 0.5 sq.mm. (FR-Flexible) copper conductor, flat, unarmoured, telephone cable in existing surface / recessed, steel / PVC conduit as required.-Make:- KEI/D-link/Havell.	15	Meter	46	Rupees Forty six only.	690
TOTAL						77041

*Certified that work is of emergent nature & in impublic interest.
DNIT Recommended for approval.*

DNIT No. for the year 2025-26 has been checked for Rs. 77041/- only. (Rupees Seventy Seven thousand Fourty one only)

ASSISTANT ENGINEER
Electrical Sub Division
H.P.P.W.D. BHNA

Executive Engineer
Electrical Division,
H.P.P.W.D. Una (H.P.)

DRAFT SCHEDULE OF QUANTITY

205 No. 06

Estimated cost:- Rs. 85,176/-
 Earnest money:- Rs. 1,700/-
 Time Limit:- Six months.

NAME OF WORK:- Repair and Maintenance of EI in various Government Non Residential buildings under ESD HPPWD Una (SH:- Providing Repair & Rewiring of EI in the accountant office in Electrical Division HPPWD Una Distt. Una (HP)

S. No.	Description of Items	Quantity	Unit	Rate In Figure	In Words.	Amount
1	Wiring for light point / fan point / exhaust fan / call bell point with 1.5 Sq. tmm. PVC insulated heat resistant flame retardant (HRFR) and low smoke single core (flexible) copper conductor cable in surface/recessed steel conduit with modular switch, modular plates, suitable. G.I. box and earthing the light point with 1.5 Sq.mm. HRFRLS/PVC insulated single core copper conductor cable as required. (Make:- Legrand (Myrius)/L&T(Oris/Entice)/Anchor (Roma plus))					
i	Group C	11	Each	1650	Rupees One thousand six hundred fifty only.	18150
2	Wiring for power plug with 2x4 Sq. mm. PVC insulated heat resistant flame retardant (HRFR) and low smoke single core (flexible) copper conductor cable in surface/recessed steel conduit along with 1 No.4 Sq.mm. HRFRLS/PVC insulated single core copper conductor cable for earthing as required. (Make:- KEI/Anchor/SSK/Plaza)	30	Meter	395	Rupees Three hundred ninety five only.	11850
3	Wiring for power plug with 4x4 Sq. mm. PVC insulated heat resistant flame retardant (HRFR) and low smoke single core (flexible) copper conductor cable in surface/recessed steel conduit along with 2 No.4 Sq.mm. HRFRLS/PVC insulated single core copper conductor cable for earthing as required. (Make:- KEI/Anchor/SSK/Plaza)	15	Meter	732	Rupees Seven hundred thirty two only.	10980
4	Wiring for circuit/sub-main with following size PVC insulated heat resistant flame retardant (HRFR) and low smoke single core (flexible) copper conductor cable in surface/recessed steel conduit along with 1 No.HRFRLS/PVC insulated single core copper conductor cable of same size for earthing as required. (Make:- KEI/Anchor/SSK/Plaza)					

i	2x1.5 Sq. mm.	50	Meter	282	Rupees Two hundred eighty two only.	14100
ii	2x2.5 Sq. mm.	35	Meter	332	Rupees Three hundred thirty two only.	11620
iii	2x10 Sq. mm.	6	Meter	696	Rupees Six hundred ninety six only.	4176
5	Supplying and drawing following size of PVC insulated, heat resistant, flame retardant (HRRFR) and low smoke single core (flexible) copper conductor cable in existing surface / recessed, Steel/PVC conduit as required. (Make:- KEI/Anchor/SSK/Plaza)					
i	3x2.5 Sq. mm.	20	Meter	151	Rupees One hundred fifty one only.	3020
6	Providing and Fixing of IP20 LED fixture of 18 watt +/- 1 W LED Surface Mounted Downlighter Round Shape with minimum system lumen efficacy of 100 lm/W with Polycarbonate housing, pressure die cast heat sink and P.F.>0.95 with THD<10%, CRI 80. The LED shall be tested with LM80-08 standard with Useful life of 50000 Hrs at L70 The LEDs used in the luminaire shall have CCT of ANSI Bin 5700 K with CRI of minimum 80. The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects.					
i	LED Surface mounting round downlighter 18 watt Makes:- Panasonic./Wipro/C&S	6	Each	1880	Rupees One thousand eight hundred eighty only.	11280
TOTAL						85176

Certified that work is of emergent nature & in public interest.
DNIT Recommended for approval.

DNIT No. for the year 2025-26
has been checked for Rs 85176/- only
(Rupees Eighty five thousand one hundred
Seventy Six only.)

ASSISTANT ENGINEER
Electrical Sub Division
H.P.P.W.D. UNA

Executive Engineer
Electrical Division,
H.P.P.W.D. Una (H.P.)


DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 91,744/-
 Earnest money:- Rs. 1,800/-
 Time Limit:- Four Months.

Name of work:- Running and Maintenance of E.I. in various Govt. Non-Residential buildings in Distt. Una (H.P) (S.H:- Engagement of T-mate/Helper Under ESD HPPWD
 Una Distt. Una (HP) (w.e.f. for Four months from awarded date)

Sr. No.	Description	Quantity	Rate In fig.	In Words.	Unit	Amount
1	Engagement of T-mate/Helper for various Govt. NR building in Distt. Una as per instruction of Engineer-in-charge.	4 Months 122 days	752	Rupees Seven Hundred Fifty Two Only.	P/Day	91744
	TOTAL					91744


 ASSISTANT ENGINEER
 Electrical Sub Division
 H.P.P.W.D. UNA


 Executive Engineer
 Electrical Division,
 H.P.P.W.D. Una (H.P.)