

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2025:-
To,

4374-84

Dated:-

26/8/2025

The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of HP letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 02.09.2025 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 02.09.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 04.09.2025 upto 11.00AM |
| 4. Date and time of opening of tenders: | 04.09.2025 at 11.30 AM |


The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contractor
1	Construction of path from Sadak to Ramesh Chand house Village Mohli GP Samlet Under MLALAD Deposit Work (SH:- Providing and laying cement concrete pavement at RD 0/0 to 0/040)	Rs. 94952/-	Rs. 1900/-	One Month	350/-	Class D&C
2	Repair of Mahil Mandal Bhawan at Ward No. 3 Jagnoli Under MLALAD Deposit Work (SH:- Dismantling door and windows, wood work, repair of plaster and painting work.)	Rs. 95000/-	Rs. 1900/-	One Month	350/-	Class D&C
3	Construction of culvert near the house of Kishori Lal to Gagan Singh House Ward No. 1 GP Sunet Under MLALAD Deposit work (SH:- Construction of 900mm dia hume pipe culvert.)	Rs. 93312/-	Rs. 1900/-	One Month	350/-	Class D&C
4	Construction of path from Narsingh Gali to Kiran House ward No. 3 GP Fatehpur Under MLALAD Deposit work(SH:- Providing and laying interlocking concrete block pavements at RD 0/0 to 0/018)	Rs. 48741/-	Rs. 1000/-	One Month	350/-	Class D&C
5	Construction of pucca path road from Chatral Aghar road to Village Badal km 0/0 to 1/500 Under SDP Deposit work Construction of retaining wall at RD 0/150 to 0/158)	Rs. 68484/-	Rs. 1400/-	One Month	350/-	Class D&C
6	Construction of pucca path road from Chatral Aghar road to Village Badal Km 0/0 to 1/500 Under SDP Deposit Work (SH:- Construction of retaining wall at RD 0/160 to 0/168)	Rs. 67934/-	Rs. 1400/-	One Month	350/-	Class D&C

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. **Only two tenders form will be issued to the contractor/ firms which may be noted.**
6. **The Contractor complete the work with in stipulated period if fail do the work will be rescinded and E/money be forfeited without any notice**
7. The intending contractors are requested to see the site of the work before submitting the tender.
8. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
9. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
10. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur

On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Name of work:- Construction of path from Sadak to Ramesh Chand house village Mohli G.P. Samlet Under (MLALAD) Deposit work (SH:- Providing and laying cement concrete pavement at R.D. 0/0 to 0/040)

Estimated cost:- Rs.94952/- only
Earnest Money : Rs.1900/- only
Time limit:- One month

Sr.No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete laying and fixing of 125 (one hundred twenty five) micron thick polythine film for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.00 Cubic meter.	5275.10	Rupees Five Thousand Two Hundred Seventy Five And Paise Ten Only	Per cubic meter	94952.00
					Total:-	94952.00
	Amount quoted by the contractor in % Above/Below					

[Signature]
Executive Engineer
Fatehpur Division HF/MD
Fatehpur, (Kangra) H.P.

SCHEDULE OF QUANTITY

Name of work:- Repair of Mahila Mandal Bhawan at Ward No.3 Jagnoli Under (MLALAD) Deposit Work (SH:- Dismantling doors and windows, wood work, repair of plaster and painting work)

Estimated cost:- Rs.95000/- only

Earnest money Rs.1900/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Demolishing cement concrete manually/By mechanical means including disposal of material within 50 (fifty) metres lead as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	0.21 cubic meter	1004.15	Rupees One Thousand Four And Paise Fifteen Only	Per cubic meter	211.00
2	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 (fifty) metres of area 3 sq. (three square meter) and below including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	4.00 Numbers	156.25	Rupees One Hundred Fifty Six And Paise Twenty Five Only	Each	625.00
3	Repairs to plaster of thickness 12mm to 20mm (twelve millimeter to twenty millimeter) in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joint sand preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge With cement mortar 1:4 (one cement isto four fine sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	29.32 square meter	256.10	Rupees Two Hundred Fifty Six And Paise Ten Only	Per square meter	7509.00
4	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia and length (hold fast lugisor dash fastener shall be paid for separately). Sal wood including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	0.207 cubic meter	89500.00	Rupees Eighty Nine Thousand Five Hundred Only	Per cubic meter	18527.00
5	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion in side grooves or rebates to be measured).Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm (twenty five millimeter to forty millimeter) thick for door including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	6.42 square meter	2450.50	Rupees Two Thousand Four Hundred Fifty And Paise Fifty Only	Per square meter	15732.00

6	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion in side grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm (twenty five millimeter to forty millimeter) 5mm (five millimeter) thick glass for windows including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	3.00 square meter	1565.70	Rupees One Thousand Five Hundred Sixty Five And Paise Seventy Only	Per square meter	4697.00
7	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm (one point four millimeter) in both directions with wire of dia 0.63 mm (zero point sixty three millimeter) , for doors, windows and clerestory windows with hinges and necessary screws including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	3.00 square meter	2204.60	Rupees Two Thousand Two Hundred Four And Paise Sixty Only	Per square meter	6614.00
8	18 mm (eighteen millimeter) cement plaster in two coats under layer 12 mm (twelve millimeter) thick cement plaster 1:5 (one cement isto five coarse sand) finished with a top layer 6 mm (six millimeter) thick cement plaster 1:6 (one cement isto six fine sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	36.72 square meter	255.50	Rupees Two Hundred Fifty Five And Paise Fifty Only	Per square meter	9382.00
9	52mm (fifty two millimeter) thick cement concrete flooring with concrete hardener topping, under layer 40mm (forty millimeter) thick cement concrete 1:2:4 (one cement isto two coarse sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size) and top layer 12 mm (twelve millimeter) thick cement hardener consisting of mix 1:2 (one cement hardener mix isto two graded stone aggregate 6mm (six millimeter) nominal size) by volume, hardening compound mixed @ 2 (two) litre per 50kg (fifty killogramme) of cement or as per manufacturer's specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete. including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	12.08 square meter	579.07	Rupees Five Hundred Seventy Nine And Paise Seven Only	Per square meter	6995.00
10	Providing and fixing 200x10mm (two hundred into ten millimeter) ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	4.00 Numbers	56.50	Rupees Fifty Six And Paise Fifty Only	Each	226.00
10	Providing and fixing 150x10mm (one hundred fifty into ten millimeter) ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	18.00 Numbers	48.45	Rupees Forty Eight And Paise Forty Five Only	Each	872.00

11	Providing and fixing ISI marked oxidised M.S. handles conforming to IS: 4992 with necessary screws etc. complete including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	14.00 Numbers	25.50	Rupees Twenty Five And Paise Fifty Only	Each	357.00
12	Providing and fixing 300x16mm (three hundred into sixteen millimeter) aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868), transparent or dyed to required colour or shade, with nuts and screws etc. including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	2.00 Numbers	173.10	Rupees One Hundred Seventy Three And Paise Ten Only	Each	346.00
13	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content With ready mixed pink or grey primer on wood work (hard and soft wood) having VOC content less than 50 (fifty) grams/ litre including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	15.40 square meter	38.90	Rupees Thirty Eight And Paise Ninety Only	Per square meter	599.00
14	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point ninety litre/ten square meter) over an under coat of primer applied @0.75 ltr/10 sqm (zero point seventy five litre/ten square meter of approved brand and manufacture including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	15.40 square meter	94.30	Rupees Ninety Four And Paise Thirty Only	Per square meter	1452.00
15	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (zero point ninety litre/ten square meter) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (Zero point eighty litre/ten square meter) of approved brand and manufacture including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	6.00 square meter	89.20	Rupees Eighty Nine And Paise Twenty Only	Per square meter	535.00
16	Providing and applying white cement based putty of average thickness 1 mm (one millimetre) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	36.72 square meter	85.10	Rupees Eighty Five And Paise Ten Only	Per square meter	3125.00

17	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content With ready mixed pink or grey primer on with water thinnable cement primer on wall surface having VOC content less than 50 (fifty) grams/ litre including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	36.72	37.40	Rupees Thirty Seven And Paise Forty Only	Per square meter	1373.00
18	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade two or more coats on new work including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	165.77	86.15	Rupees Eighty Six And Paise Fifteen Only	Per square meter	14281.00
19	Providing and fixing 110mm (One hundred ten millimeter) dia ISI marked high pressure PVC (finolex waste and ventilating pipes with collar including fixing with approved adhesive etc. including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	6.00	257.00	Rupees Two Hundred Fifty Seven Only	Per Running meter	1542.00
					Total:-	95000.00
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 PWD Division HPPWD
 Fatehpur Distt. Kangra (R)

SCHEDULE OF QUANTITY

Name of work:- Construction of culvert near the house of Kishori Lal to Gagan Singh House Ward No.1 G.P. Sunet Under MLALAD) Deposit work (SH:- Construction of 900mm dia hume pipe culvert)				Estimated cost:- Rs.93312/- only Earnest Money : Rs.1900/- only Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	19.31 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	6556.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	9.38 Cubic meter.	3950.40	Rupees Three Thousand Nine Hundred Fifty And Paise Forty Only	Per cubic meter	37055.00
3	Providing and laying (to level or slope) 900mm dia (Nine hundred millimeter) diameter reinforced cement concreté light duty non pressure pipes IS Class NP-2 for culverts on first class bedding in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1106 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.00 Running meter	4350.50	Rupees Four Thousand Three Hundred Fifty And Paise Fifty Only	Per Running meter	21753.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.10 Cubic meter.	3450.40	Rupees Three Thousand Four Hundred Fifty And Paise Forty Only	Per cubic meter	27948.00
					Total:-	93312.00
Amount quoted by the contractor in % Above/Below						

Executive Engineer

Fatehpur Division HPPWD

Fatehpur (Kangra) H.P.

Job-4

SCHEDULE OF QUANTITY

Name of work:- Construction of path from Narsingh Gali to Kiran house Ward No.3 G.P. Fatehpur Under (MLALAD) Deposit work (SH):-
 Providing and laying Interlocking concrete block pavements at R.D. 0/00 to 0/018).

Estimated cost:- Rs.48741/- only
 Earnest Money : Rs.1000/- only
 Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	5.94 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2017.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	2.97 Cubic meter.	3990.55	Rupees Three Thousand Nine Hundred Ninety And Paise Fifty Five Only	Per cubic meter	11852.00
3	Providing and laying of interlocking concrete block pavement having thickness 60mm (sixty millimeters) in grey and coloured shade APT or equivalent make over sand base as per drawing and technical specification clause 1504 complete approved by HPPWD and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, GST, sale tax or any other taxes imposed by the Government.	39.60 Square meter	880.60	Rupees Eight Hundred Eighty And Paise Sixty Only	Per Square meter.	34872.00
					Total:-	48741.00
	Amount quoted by the contractor in % Above/Below					

Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of pucca path road from Chattral Aghar road to village Badal km. 0/0 to 1/500 (Under SDP) Deposit work (SH:- Construction of Retaining wall at R.D. 0/150 to 0/158).

Estimated cost:- Rs.68484/- only
Earnest Money : Rs. 1400/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In -meter. Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge.	7.20 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2444.00
2	Including carriage of materials within all leads and lifts and other incidental . Including carrying of materials within all leads and lifts and other incidental for all type of structure complete of 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including carriage of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	17.28 cubic meter	3520.75	Rupees Three Thousand Five Hundred Twenty And Paise Seventy Five Only	Per cubic meter	60839.00
3	Back filling behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 Granular material and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	3.84 cubic meter	780.20	Rupees Seven Hundred Eighty And Paise Twenty Only	Per cubic meter	2996.00
4	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.00 Numbers	315.00	Rupees Three Hundred Fifteen Only	Each	2205.00
	Amount quoted by the contractor in % Above/Below					68484.00


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of pucca path road from Chatral Aghar road to village Badal km. 0/0 to 1/500 (Under SDP) Deposit work (SH:- Construction of Retaining wall at R.D. 0/160 to 0/168).				Estimated cost:- Rs.67934/- only		Earnest Money : Rs.1400/- only		Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount			
			In words	In figures					
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	7.20 Cubic meter.	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2444.00			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in-open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter)nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in parapet including the cost of form work as per drawing and M.O.R.D technical specification as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	17.28 cubic meter	3495.00	Rupees Three Thousand Four Hundred Ninety Five Only	Per cubic meter	60394.00			
3	Back filling behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 Granular material and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	3.84 cubic meter	780.20	Rupees Seven Hundred Eighty And Paise Twenty Only	Per cubic meter	2996.00			
4	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.00 Numbers	300.00	Rupees Three Hundred Only	Each	2100.00			
						67934.00			
Amount quoted by the contractor in % Above/Below									

Executive Engineer
Fatehpur Division HPP/WD
Fatehpur, (Kangra) H.P.