

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NO.PW- GHD-EA-I- /Tender/2024- **5386-91** Dated:- **23-08-2025**
To

The Executive Engineer (IT-Cell),
Nirman Bhawan Nigam Vihar Shimla-2
Himachal Pradesh Shimla -2.
Email:-ee-pwd-hp@nic.in

SUBJECT: - Publication of Tender Notice.

Sir,

Jai Hind

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary(PW) to the GOVT of HP vide No. PBW(B)A(3)1/2024 Dated 03/01/2025 as the matter is of urgent nature and in public interest , you are requested to kindly get it published on departmental website before 23.08.2025.

DA:-As above.

Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin
On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Chief Engineer (HZ) HP.PWD., Hamirpur.
2. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
3. All the Assistant Engineer, working under this Division
4. Notice Board of this office.

DA:- One No.

Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin.
On behalf of Governor of Himachal Pradesh

***NOTICE INVITING TENDER**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Ghumarwin Division HP.PWD. Ghumarwin on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **29-08-2025 up to 11.00 AM.** and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender form/documents can be had from his office against cash payment (Non refundable) on 28-08-2025 up to 4.00 P.M and the application for issue of tender form shall be **received on 28-08-2025 up to 1.00 PM.** The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons. The offer of the tender shall be kept open for 75 days.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost form	Time limit
1.	Restoration of rain damages on Bhager Panol Sunhani road in km 0/00 to 7/00(SH:- Removal of slips at various Rd's).	Rs.98000/-	Rs.2000/-	Rs.350/-	One Month
2.	Restoration of rain damages on various road in respect of Ghumarwin Sub -division (SH:- Removal of slips at various Rd's).	Rs.96380/-	Rs.2000/-	Rs.350/-	One Month
3.	Restoration of rain damages on various road in respect of Ghumarwin Sub -division (SH:- Removal of slips at various Rd's).	Rs.96000/-	Rs.2000/-	Rs.350/-	One Month
4.	Restoration of rain damages on Badhaghat to Sohni Devi via Kotla road km 0/00 to 5/500(SH: C/o of R/wall at RD 2/870 to 2/878.	Rs.99326/-	Rs.2000/-	Rs.350/-	One Month
5.	Restoration of rain damages on Bum Dipper Hatwar road km 0/00 to 3/00 (SH: C/o R/wall at RD 0/980 to 0/987.60	Rs.95406/-	Rs.2000/-	Rs.350/-	One Month
6.	Restoration of rain damages on link road Barota to Thana km 0/00 to 2/00 (SH: P/L Cement Concrete 1:1.5:3).	Rs.99095/-	Rs.2000/-	Rs.350/-	One Month
7.	Restoration of rain damages on Sumari to lower Bhapral road in km 0/00 to 9/200 (SH: Removal of slips, maintenance of earthen shoulder and maintenance of unlined drains at various Rd's).	Rs.98992/-	Rs.2000/-	Rs.350/-	One Month

Certified that tenders are being called for due to exigencies of works (landslide and road singking) in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Ghumarwin Division , HP.PWD, Ghumarwin and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate in percentage only both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.

Executive Engineer,
Ghumarwin Division,
HP.PWD, Ghumarwin

Schedule of Quantity

Estimated Cost:- Rs. 98,000.00

Earnest Money:- Rs. 2,000.00

Time :- One month

Name of Work:- Restoration of rain damages on Bhager Panol Sunhani road in km 0/00 to 7/00 (SH:- Removal of slips at various Rd's). (CRF).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Providing Excavator cum loader for removal of slips/debries with rock breakers including breaking rock, loading in tippers and, trimming bottom and side slopes in accordance with requirements of lines, grades and cross- sections. The owner shall bear to expensive of P.O.L charges, repair of machineries and pay of driver etc. any accidents and other damages to private and Govt. property occur during the working hour is the whole responsibility of the owner and disposal of earth /soil and the direction of Engineer-in-Charges. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	49.00	Per Hour	2000.00	Rupees Two Thousand Only	98000.00
	Total					98000
	Quote in Percentage		Above/below		%	

Executive Engineer,
Arwin Division
V.D. Ghuma

[Signature]

Schedule of Quantity

Estimated Cost:- Rs. 96,380.00
 Earnest Money:- Rs. 2,000.00
 Time:- One Month

Name of Work:- Restoration of rain damages on various road in respect of Ghumarwin Sub-division (SH:- Removal of slips at various Rd.s). (C&F)

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Providing of Tipper 5.5 cum capacity (4 trips per hour) for disposal of cut material with in all lead and lift as per technical specification 302.3.5 and 1611 as per requirement rate including travelling of vehicle upto site of work P.O.L. charges and other establishment required at site i.e. driver cleaner and other staff and other incidental charges complete as per the direction of Engineer-in- Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	158	Per Hours	610	Rupees Six Hundred Ten Only	96380.00
Quote in Percentage		Total:-		Above/below	%	96,380.00

Executive Engineer,
 Ghumarwin Division
 H.P.P.W.D. Ghumarwin
 R

Schedule of Quantity

Schedule of Quantity			Estimated Cost:- Rs. 96,000.00			
			Earnest Money:- Rs. 2,000.00			
			Time :- One month			
Name of Work:-Restoration of rain damages on various road in respect of Ghumarwin Sub -division (SH:- Removal of slips at various Rd's). (CRF) .						
Sr. No.	Description Item	Quantity	Unit	Rates		Amount
1	Providing Excavator cum loader for removal of slips/debris with rock breakers including breaking rock, loading in tippers and , trimming bottom and side slopes in accordance with requirements of lines, grades and cross- sections. The owner shall bear to expensive of P.O.L charges, repair of machineries and pay of driver etc. any accidents and other damages to private and Govt. property occur during the working hour is the whole responsibility of the owner and disposal of earth /soil and the direction of Engineer-in-Charges. The rate includes, octroi, Malkhana, Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	48.00	Per Hour	In figure 2000.00	In words Rupees Two Thousand Only	96000.00
	Total					96000
	Quote in Percentage		Above/below		%	

Executive Engineer
Ghumarwin Division
H.P. P.W.D. Ghumarwin

for

Draft Schedule of Quantity				Estimated Cost:- Rs.		99,326.00
				Earnest Money:- Rs.		2,000.00
				Time :-		One Month
Name of Work:- Restoration of rain damages on Badhaghat to Sohni Devi via Kotla road km 0/00 to 5/500 (SH:- Construction of R/wall at Rd 2/870 to 2/878).						
Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead .All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.89	Per cubic metre	250.00	Rupees Two Hundred Fifty Only	1973.00
2	Providing and Laying cement concrete 1:5:10 nominal mix (One Cement : five Sand : Ten graded crushed stone aggregate.) 40mm (forty millimetre) nominal size with minimum cement contents 130 kg (One hundred thirty kilogram) per cubic metre and curring complete . including cost of form work for plain /reinforce concrete in retaining walls, breast wall as per drawing and MORD tecnical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts ,shoring and shuttering and curring complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material ,tools equipment safety measures and other incidentals as per the direction of Engineer-in Charge.The rate includes, octroi, royalty Malkhana, Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.80	Per cubic metre	4500.00	Rupees Four Thousand Five Hundred Only	84600.00
3	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 .as per direction of Engineer-In-Charge.The rate includes, octroi, Malkhana, Toll tax , Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00	Each	365.00	Rupees Three Hundred Sixty Five Only	2190.00
4	Back filling behind abutment , wing walls return wall complete as per drawings and technical specification clause 1204.3.8 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.45	Per cubic metre	1250.00	Rupees One Thousand Two Hundred Fifty Only	10563.00
Total						99326

Draft Schedule of Quantity No 154 for
the year 2025-26 approved for Rs 99326/- only

(Executive Engineer,
Ghumanwin Division,
HP, FWD, Ghumanwin.)

Schedule of Quantity


Name of Work:- Restoration of rain damages on Bum Dipper Hatwar road km 0/00 to 3/00 (SH:- Construction of R/wall at Rd 0/980 to 0/987.60).	Estimated Cost:- Rs.	95,406.00
	Earnest Money:- Rs.	2,000.00
	Time :-	One Month

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.01	Per cubic metre	275.00	Rupees Two Hundred Seventy Five Only	2203.00
2	Providing and Laying cement concrete 1:5:10 nominal mix (One Cement : five Sand : Ten graded crushed stone aggregate.) 40mm (forty milimetre) nominal size with minimum cement contents 130 kg (One hundred thirty kilogram) per cubic metre and curring complete . including cost of form work for plain /reinforce concrete in retaining walls, breast wall as per drawing and MORD tecnical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts ,shoring and shuttering and curring complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material ,tools equipment safety measures and other incidentals as per the direction of Engineer-in Charge.The rate includes, octroi, royalty Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess Government shall not entertain any claim whatsoever in this respect of the same.	18.38	Per cubic metre	4550.00	Rupees Four Thousand Five Hundred Fifty Only	83629.00
3	Back filling behind abutment, wing walls return wall complete as per drawings and technical specification clause 1204.3.8 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.19	Per cubic metre	1250.00	Rupees One Thousand Two Hundred Fifty Only	7738
4	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 .as per direction of Engineer-In-Charge.The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00	Each	367.20	Rupees Three Hundred Sixty Seven and Twenty Paise	1836.00
Total						95406
Quote in Percentage			Above/below		%	

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin.

Draft Schedule of Quantity					Estimated Cost:- Rs.	99,095.00
					Earnest Money:- Rs.	2,000.00
					Time :-	One Month
Name of Work:- Restoration of rain damages on link road Barota to Thana km 0/00 to 2/00 (SH:- Providing and laying cement concrete 1:1.5:3).						
Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour)The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.27	Per cubic metre	1550.00	Rupees One Thousand Five Hundred Fifty Only	20569.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5 :3(One cement : one point five coarse sand : three graded stone aggregate 20 mm (twenty milimetre) nominal size.The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.06	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	78526.00
Total:-						99,095.00

Draft Schedule of Quantity No 145-pr
 The year 2025-26 approved for Rs 99095/-only

Executive Engineer,
 Ghumania Division,
 HP, P.V.


Draft Schedule of Quantity

Name of Work:- Restoration of Rain damage on Sumari to Lower Bhapral road in km 0/00 to 9/200(SH:- Removal of slips, maintenance of Earthen shoulder and maintenance of unlined drains at various Rd's).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Removal of land slide/slips in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 mtrs and lead upto 5000 mtrs/soil with in all leads and lifts as per technical specification 302.3.5 and 1611 and as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	542.00	Per cubic metre	120.00	Rupees One Hundred Twenty Only	65040
2	Maintenance of earthen shoulder (Stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and Technical Specification Clause 1903 and as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	688.00	Per square metre	22.00	Rupees Twenty Two Only	15136
3	The maintenance of unline drains include erosion, repair, clearing cleaning, reshaping, regarding, deepening of side drains as well as catch water drains as per technical specification clause 1907 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1568.00	Per Running Metre	12.00	Rupees Twelve Only	18816
Total:-						98,992.00

Draft Schedule of Quantity No. 156 for the year 2025-26 approved for Rs. 98,992/- only

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin.