

Himachal Pradesh
Public Works Department

No. PWH/HD/CB/T-I/2025-26
To

2511-13

Dated: - 28/07/2025

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publication of Notice inviting tender.

Sir,

Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above

Executive Engineer,
HPPWD Division Haroli,
Distt Una HP).

Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.

Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).

Certificate

Certified that the tenders for the works called vide this office letter No. PWH/HD/CB/T-1/2024
2743 dated 28.07.25 are required to be carried out immediately being emergent nature of work
in public interest.


Executive Engineer,
Haroli Division, HPPWD
Haroli, Distt.Una HP).

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

“ NOTICE INVITING TENDERS ”

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/firms enlisted in the PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any or all tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: - 04/08/2025 up to 10.30 (AM).
2. Date of issue/sale of tender forms against cash payment(non-refundable): - 04/08/2025 up to 3.00 PM
3. Date of receipt of tenders: - 05/08/2025 up to 10.30 AM
4. Date of opening of tenders: - 05/08/2025 at 11.00 AM

Sr. No.	Name of work	Estimate d cost	EMD	Time Limit	Cost of tender	Eligible class of contract or
1	2	3	4	5	6	7
1	C/o link road Nagnoli to SC Basti Chaperian Gour Bagirian Chotti Khad Gujiran Tarkhana Nainan Mohalla (SH: C/o protection wall RD 0/924.50 to 0/950) DW	98376.00	2000/-	One Month	350/-	Class- C & D
2	Restoration of Gramin Sampark from the H/O sh. Surinder Singh to Shahib Baba Mandir Ward No. 2 GP Palkwah, (Deposit Work) (SH:-P/L CC Pavement at RD. 0/00 to 0/023.90)	99570.00	2000/-	One Month	350/-	Class- C & D
3	Restoration of rain damage on Panjwar Bathri road to Ispur Pathak Mohalla Kayalia road Km 0/0 to 1/900 (SH: C/o B.wall in RD 1/273.50 to 1/282 RHS)	99808.00	2000/-	One month	350/-	Class- C & D
4	C/o link road from Baba Bankhandi road to Dalit Basti WNO.7 GP Haroli (SH C/o R/wall on Rest house haroli baba bankhandi mandir road 0/327.30 tom 324.60 LHS) under MMSY	99826.00	2000/-	One month	350/-	Class- C & D
5	A/R & M/O on Luluwal Gondpur road Km 0/0 to 6/315 (SH Painting of road side parapet, B/wall etc. between RD 3/400 to 6/315)	99436.00	2000/-	One Month	350/-	Class- C & D
6	Restoration of rain damage on link road Nayian Basti Baliwal Km 0/0 to 1/500 (SH: C/o R/wall at RD 0/0 to 0/007.80 LHS)	99115.00	2000/-	One Month	350/-	Class- C & D
7	Restoration of link road from Lalpuri Vishnu Dham Kutia upto CHC Beetan in GP Beetan (SH: C/o CC Pavement RD 0/083.20 to 0/113.50) DW (Balance work)	99990.00	2000/-	One Month	350/-	Class- C & D
8	Restoration of Rain damage on link road Old Haroli road Gugga Mandir upto Paijal Yojna Haroli km. 0/00 to 2/140-RHS(SH:-C/O U-shape drain at RD. 2/040 to 2/070-RHS)	99444.00	2000/-	One Month	350/-	Class- C & D
9	C/O Levelling work in Playground near GSSS Nangal Khurd Mohalla Thai Nangal Khurd(Phase-I) Deposit Work	99897.00	2000/-	One Month	350/-	Class- C & D
10	Improvement & widening of road from Gondpur Behli to Bathu Gurplah i/c bridge over Gondpur Jaichand Khad km. 0/0 to 8/655 (SH:-Preparation of working estimate and DNIT including submission of Hard and soft copies) under NABARD	85000.00	1700/-	15 day	350/-	Class- C & D
11	C/o link road Nagnoli to SC Basti Chaperian Gour Bagirian Chotti Khad Gujiran Tarkhana Nainan Mohalla (SH: C/o protection wall RD 0/900 to 0/924.50) DW	98365.00	2000/-	One Month	350/-	Class- C & D

12	Restoration of Gramin Sampark from the H/O sh. Surinder Singh to Shahib Baba Mandir Ward No. 2 GP Palkwah, (Deposit Work) (SH:-P/L CC Pavement at RD. 0/047.70 to 0/071.30)	98320.00	2000/-	One Month	350/-	Class- & D
13	Upgradation of link Umrali Dhilwan Heeran-Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-Preparation of working estimate and DNIT including submission of Hard and soft copies) under OTMNP	85000.00	1700/-	15 day	350/-	Class- & D
14	Restoration of link road from Lalpuri Vishnu Dham Kutia upto CHC Beetan in GP Beetan (SH: C/o CC Pavement RD 0/113.50 to 0/136) DW (Balance work)	74250.00	2000/-	One Month	350/-	Class- & D
15	Restoration of rain damages on link road to village Bhoolgarh Km 0/0 to 2/600 (SH: C/o B/wall at RD 2/509.50 to 519.10 RHS)	98632.00	2000/-	One Month	350/-	Class- & D
16	Restoration of Gramin Sampark from the H/O sh. Surinder Singh to Shahib Baba Mandir Ward No. 2 GP Palkwah, (Deposit Work) (SH:-C/O 900 mm dia Hume pipe culvert at RD. 0/200)	82971.00	2000/-	One Month	350/-	Class- & D
17	Restoration of rain damages on link road to village Bhoolgarh Km 0/0 to 2/600 (SH: C/o B/wall at RD 2/519.10 to 528.70 RHS)	98972.00	2000/-	One Month	350/-	Class- & D
18	Restoration of rain damage on link road Nayian Basti Baliwal Km 0/0 to 1/500 (SH: C/o R/wall at RD 0/007.80 to 0/015.60 LHS)	99365.00	2000/-	One Month	350/-	Class- & D
19	Restoration of rain damage on Panjwar Bathri road to Ispur Pathak Mohalla Kayalia road Km 0/0 to 1/900 (SH: C/o B.wall in RD 1/265 to 1/273.50 RHS)	99968.00	2000/-	One Month	350/-	Class- & D
20	A/R & M/O on Laluwal Gondpur road Km 0/0 to 6/315 (SH Painting of road side parapet, B/wall etc. between RD 0/0 to 3/400)	99307.00	2000/-	One Month	350/-	Class- & D
21	Upgradation of link Umrali Dhilwan Heeran-Thara Pubowal to Polian via Kuthar Beet km. 3/400 to 6/500(SH:-Preparation of working estimate and DNIT including submission of Hard and soft copies) under OTMNP	85000.00	1700/-	15 days	350/-	Class- & D
22	A/R & M/O on Tahliwal Garshankar (HP Boundary) MDR-41 from Km 0/0 to 7/800 (SH: Painting of solid concrete crash barrier RD in between 6/750 to 7/233)	60536.00	2000/-	One Month	350/-	Class- & D
23	C/o link road from Baba Bankhandi road to Dalit Basti WNO.7 GP Haroli (SH C/o R/wall on Rest house haroli baba bankhandi mandjr road 0/320 tom 327.30 LHS) under MMSY	99506.00	2000/-	One Month	350/-	Class- & D
24	Restoration of rain damage on link road Nayian Basti Baliwal Km 0/0 to 1/500 (SH: C/o R/wall at RD 0/023.40 to 0/031.20 LHS)	99676.00	2000/-	One Month	350/-	Class- & D
25	C/o link road Nagnoli to SC Basti Chaperian Gour Bagirian Chotti Khad Gujiran Tarkhana Nainan Mohalla (SH: C/o CC Pavement RD 0/179 to 0/200.50 approach road to Baba Sidhcharno Temple) DW	99220.00	2000/-	One Month	350/-	Class- & D
26	A/R & M/O on Tahliwal Garshankar (HP Boundary) MDR-41 from Km 0/0 to 7/800 (SH: P/L Thermoplastic paint at RD 5/500 to 6/160)	99000.00	2000/-	One Month	350/-	Class- & D
27	Restoration of rain damage on link road Nayian Basti Baliwal Km 0/0 to 1/500 (SH: C/o R/wall at RD 0/015.60 to 0/023.40 LHS)	99127.00	2000/-	One Month	350/-	Class- & D
28	Restoration of Gramin Sampark from main road to house of Major Dhalbir Singh WNO.5,6 GP Heera Nangar (SH: C/o CC pavement at RD 0/00 to 0/009 along with toe wall) Deposit work	99842.00	2000/-	One Month	350/-	Class- & D
29	C/o link road Nagnoli to SC Basti Chaperian Gour Bagirian Chotti Khad Gujiran Tarkhana Nainan Mohalla (SH: C/o Protection wall at RD 0/700 to 0/724.20) DW	98431.00	2000/-	One Month	350/-	Class- & D
30	Restoration of Gramin Sampark from main road to Kumhar Basti WNO.4,5 GP Heera Nagar (SH: C/o CC pavement at RD 0/169 to 0/195.50) DW	99149.00	2000/-	One Month	350/-	Class- & D

31	Restoration of rain damages on link road to village Kangar Km 0/00 to 1/700 (SH: C/O R/wall at RD 0/762.10 to 0/768.30 RHS) Phase-I	99462.00	2000/-	One Month	350/-	Class- & D
32	A/R & M/O PWD NR building at Haroli (SH: P/L All in one HP-PC with 15.12h Gen Processor 8GB Ram & 512 SSD with Microsoft office & window and Brother Printer DCP-B7640DW) in newly created Khad Sub Divn office)	99500.00	2000/-	One Month	350/-	Class- & D
33	Restoration of Gramin Sampark from main road to house of Major Dhalbir Singh WNO.5,6 GP Heera Nangar (SH: C/o CC pavement at RD 0/036 to 0/045 along with toe wall) Deposit work	~~99842.00~~ 98738.00	2000/-	One Month	350/-	Class- & D
34	Balance work for the C/o Community Park, Outdoor open gym at WNo.2 & 4 GP Dulehar Tehsil Haroli Distt.Una (SH: Hill side cutting for extended portion of park RD 0/012 to 0/016) Deposit work	99400.00	2000/-	One Month	350/-	Class- & D
35	Restoration of rain damages on link road to village Kangar Km 0/00 to 1/700 (SH: C/O R/wall at RD 0/756.10 to 0/762.10 RHS) Phase-II	98356.00	2000/-	One Month	350/-	Class- & D

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FD Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender r accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration N Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

1. The contractor should produce a copy of valid enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
3. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HP with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
4. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be postponed on next date.
5. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
6. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
7. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220
Email: ee-harolli-hp@hp.gov.in
On behalf of Governor of Himachal Pradesh.

SCHEDULE OF QUANTITY

Name of work :C/O Link road Nagnoli to SC Basti Chaparian Gour Bagirian Chotti Khad Gujran Tarkhana Nainan Mohalla (SH: C/o protection wall RD 0/924.50 to 0/950) - Deposit work

S. No.	Description of work	Quantity	Unit	Figures	RATE In		AMOUNT
					Words	Time limit	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,makhana ,toll tax,sale tax,GST labour cess or other taxes imposed by the Government.	8.82	Per cubic metre	160 00	Rupees One hundred sixty only		1411
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental The rate includes sale tax octroi , royalty,makhana ,toll tax,GST labour cess or other taxes imposed by the Government.	25.97	Per cubic metre	3300 00	Rupees three thousand three hundred only		85701
3	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material, within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,makhana ,toll tax,GST labour cess or other taxes imposed by the Government.	13.62	Per cubic metre	550 00	Rupees Five hundred fifty only		7491
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) with cement contents not less than 250kg/m ³ (two hundred fifty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water	0.98	Per cubic metre	3850 00	Rupees three thousand eight hundred fifty only		3773
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(1712/0212 dated 7.8.2018				Total:		98376
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(31/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
	Percentage quoted rate in Figures						
	Percentage quoted rate in words						
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						

Executive Engineer
Haroli Division
HP.PWD.,Haroli

2

Schedule of quantity

Name of work :Restoration of Gramin Sampark from the H/O Sh. Surinder Singh to Shahid Baba Mandir Ward No. 2 GP Palkwah. (Deposit work)					Estimated Cost: Rs	
(SH: P/L CC Pavement at Rd. 0/00 to 0/023.90)					Time:-	
S.NO					Earnest Money:-	
DESCRIPTION					Rate in words	
					Amount	
					2000	
					Rupees One Hundred Sixty Only	
					3442.00	
					Rupees One Hundred Forty Only	
					3814.00	
					Rupees One Hundred Only	
					3585.00	

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of material within all leads . The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	21.51	Cum.	160.00	Rupees One Hundred Sixty Only	3442.00
2	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	27.25	Cum.	140.00	Rupees One Hundred Forty Only	3814.00
3	Construction of Embankment with Material Obtained from Roadway Cutting Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	35.85	Cum.	100.00	Rupees One Hundred Only	3585.00

4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401.. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5.38	Cum.	1100.00	Rupees One Thousand One Hundred Only	5915.00
5	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.17	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	23661.00
6	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.76	Cum.	5500.00	Rupees Five Thousand Five Hundred Only	59153.00
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99570
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY									
Name of work: -Restoration of rain damage on Panjawar Bathri Road To Ispur Pathak Mohalla Kayalia Road KM 0/0 TO 1/900 (SH: C/o Breast wall in RD 1/273.50 to 1/282 RHS)									
		Estimated Cost	99808/-						
		Earnest Money	2000/-						
		Time limit	One month						
Sl. No.	Description of work	Quantity	Unit	Figures	Words	AMOUNT			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octori, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	11.22	cum	160.00	Rupees one hundred sixty only	1795			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	29.41	cum	3300.00	Rupees three thousand three hundred only	97053			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204 3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.00	Each	160.00	Rupees one hundred sixty only	960			
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018						Total:	99808		
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(31)/2020 dated 22.07.20									
Percentage quoted rate in Figures									
Percentage quoted rate in words									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

153

SCHEDULE OF QUANTITY

Name of work: C/O Link road from Baba Bankhandi road to Dalit Basti Ward No 7 G.P. Haroli (SH:-C/O R/Wall on Rest house Haroli Baba Bankhandi Mandir road 0/327.30 to 0/324.60 LHS)Under-MMSY

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.25	Per cubic metre	160.00	Rupees one hundred sixty only	1320
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (twenty millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	29.05	Per cubic metre	3300.00	Rupees three thousand three hundred only	95865
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.00	Each	160.00	Rupees one hundred sixty only	1920
4	Providing Back Filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.31	Per cubic metre	550.00	Rupees five hundred Fifty only	721
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)©(17)2/0212 dated 7.8.2018				Total:	99826
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

155

5

SCHEDULE OF QUANTITY

Name of Work: A/R & M/O on Laluwal Gondpur road km. 0/0 to 6/315 (SH: Painting of road side parapet, Breast wall etc. between Rd. 3/400 to 6/315)									
S. No.	Description of work	Quantity	Unit	Rates		Estimated cost	Earnest money	Time limit	One month
				Figures	Words				
1	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete and direction of Engineer in charge. including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, toll tax, sale tax other taxes imposed by the Govt.	801.90	Per Square metre	124.00	Rupees one hundred twenty four only	99436	2000		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@ (17)2/0212 dated 7.8.2018				G. Total	99436			
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021								
	Percentage quoted rate in Figures								
	Percentage quoted rate in words								
	Note:- Rate quoted in figures & words are mandatory by the contractoe , otherwise the tender will be rejected.								


 Executive Engineer ,
 Haroli Divn. HPWD.,
 Haroli

7

Schedule of quantity

Name of work:- Restoration of link road from Lalpuri Vishnu Dham Kutia upto CHC Beetan in G.P. Beetan (Sh: C/O CC Pavement Rd. 0/083.20 to 0/113.50). Deposit work (Balance work)						
Estimated Cost: Rs				Time:-		
One month				2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	Amount
1	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundation of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of material within all leads . The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	18.18	cum	5500.00	Rupees Five Thousand Five Hundred Only	99990
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	99990
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

52

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damage on link road Old Haroli road Gugga Mandir upto Pajjal Vojna Haroli Km 0/00 to 2/140-RHS (SH: C/O U shape drain at RD2/040 to 2/070- RHS)

Estimates cost:- 9944/-
Earnest Money:- Rs. 2000/-
Time Limit:- One Month.

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms. Lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	38.25	Per Cubic metre	160.00	Rupees one hundred sixty only	6120
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation: for all type structure complete of plain cement concrete nominal max 1:3:6 (One cement three sand six graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental The rate includes sale tax octroi, royalty, malkhana toll tax, GST labour cess or other taxes imposed by the Government	21.38	Per Cubic metre	3850.00	Rupees three thousand eight hundred fifty only	82294
3	Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type structure complete of reinforced cement concrete standard concrete design max of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205 4 and 1205 5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST labour cess or other taxes imposed by the Government.	0.90	Per cubic metre	5500.00	Rupees five thousand five hundred only	4950
4	Providing and laying mild steel medium tensile steel bars for steel (approved make) reinforcement for reinforced cement concrete work including bending, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	64	Per Kg	95.00	Rupees Ninety five only	6080
Note:- 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt of HP vide letter No PBW(B)(17/20212 dated 7 8 2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No PBW(B) A(3)/2020 dated 22 7 2020 & Govt of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7 10 2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected						
Total:-						99444

Executive Engineer,
H.P.P.W.D. Division Haroli

Tenderer with seal

SCHEDULE OF QUANTITY

Name of work:- C/O Levelling work in playground near GSSS Nangal Khurd Mohalla Thai Nangal Khurd (Phase-I)- Deposit work

Estimated Cost 99897
Earnest Money 2000/-
Time limit One month

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil/ jumper work and their intermediate classification of soil . setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the technical specification MORD 2014 section 300 of clause and 1600 1 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials ,tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetera shall be sorted out. A recovery of 22.05cum stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item. including carriage of material with in all leads and lifts and other incidentals . The rate includes sale tax octroi, royalty, malikhana ,toll tax ,GST ,labour cess or other taxes imposed by the Government	441.00	Per cubic metre	155.00	Rupees one hundred fifty five only	68355
2	Construction of embankment with approved material obtained at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with a lead upto 1000 metre as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014 . The rate includes sale tax octroi, royalty, malikhana ,toll tax ,GST ,labour cess or other taxes imposed by the Government.	300.40	Per cubic metre	105.00	Rupees one hundred five only	31542
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@/17/2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20				Total	99897
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division, Haroli
Distt. Una (Raj.)

(37)

Schedule of Quantity

(10)

Name of Work : Improvement & widening of road from Gondpur Behli to Bathu Gurplah i/c bridge over Gondpur Jaichand Khad Km.0/0 to 8/655 (SH: Preparation of working estimate and DNIT including submission of Hard and soft copies)- under NABARD

Estimated cost : 85000
Earnest Money : 1700
Time Limit : 15 day

S. No.	Description of item	Qty.	Unit	Rate (Rs.)	Rate in words	Amount (Rs.)
1	Preparation and approval of working estimate and Drafts Schedule of quantity from higher authority including submission of 5 (Five) set of estimate and soft copy of estimate .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1	Each	85000	Rupees Eighty five thousand only	85000
	1) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(3)1/2020 dated 22.07.20				Total =	85000
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					


Executive Engineer
Haroli Division
HPPWD Haroli.

137

SCHEDULE OF QUANTITY

Name of work :C/O Link road Nagnoli to SC Basti Chaparian Gour Bagirian Chotti Khad Gujran Tarkhana Nainan Mohalla (SH: C/o protection wall RD 0/900 to 0/924.50) - Deposit work

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.82	Per cubic metre	160.00	Rupees One hundred sixty only	1411
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of Plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 40mm (forty millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	25.97	Per cubic metre	3300.00	Rupees three thousand three hundred only	85701
3	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	13.60	Per cubic metre	550.00	Rupees Five hundred fifty only	7480
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M:Ten) with cement contents not less than 250Kg (Two hundred fifty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water	0.98	Per cubic metre	3850.00	Rupees three thousand eight hundred fifty only	3773
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					Total:	98365
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(31)/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer
Haroli Division
HP.PWD.,Haroli


125

12

Schedule of quantity

Name of work :Restoration of Gramin Sampark from the H/O Sh. Surinder Singh to Shahid Baba Mandir Ward No. 2 GP Palkwah. (Deposit work)						Estimated Cost: Rs	₹ 98,320
(SH: P/L CC Pavement at Rd. 0/047.70 to 0/071.30)						Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Earnest Money:-	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of material within all leads . The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	21.24	Cum.	160.00	Rupees One Hundred Sixty Only		3398.00
2	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	26.90	Cum.	140.00	Rupees One Hundred Forty Only		3767.00
3	Construction of Embankment with Material Obtained from Roadway Cutting Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	35.40	Cum.	100.00	Rupees One Hundred Only		3540.00
4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.31	Cum.	1100.00	Rupees One Thousand One Hundred Only		5841.00
5	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.08	Cum.	3300.00	Rupees Three Thousand Three Hundred Only		23364.00

6	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.62	Cum.	5500.00	Rupees Five Thousand Five Hundred Only	58410.00
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021				Total	98320
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of Quantity

Name of Work :

Upgradation of link Umralli Dhilwan Heeran-Thara Pubowal to Polian via Kuthar Beet Km 0/00 to 3/400 (SH: Preparation of working estimate and DNIT including submission of Hard and soft copies)- under OTMNP

Estimated cost : 85000
Earnest Money : 1700
Time Limit : 15 day

S. No.	Description of item	Qty.	Unit	Rate (Rs.)	Rate in words	Amount (Rs.)
1	Preparation and approval of working estimate and Drafts Schedule of quantity from higher authority including submission of 5-set of estimate and soft copy of estimate .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1	Each	85000	Rupees Eighty five thousand only	85000
	1) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20			Total =		85000
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					

Executive Engineer
Haroli Division
HPPWD Haroli

138

74

Schedule of quantity

Name of work:- Restoration of link road from Lalpuri Vishnu Dham Kutia upto CHC Beetan in G.P. Beetan						Estimated Cost: Rs	₹ 74,250
(Sh: C/O CC Pavement Rd. 0/113.50 to 0/136). Deposit work (Balance work)							
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:- Rate in words	Time:- One month 2000	Amount
1	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundation of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of material within all leads . The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	13.50	cum	5500.00	Rupees Five Thousand Five Hundred Only		74250
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total		74250
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

53

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.R.)

15

Draft Schedule of quantity

Name of Work:- Restoration of rain damages on Link road to Village Boolgarh km. 0/00 to 2/600					Estimated Cost: Rs		Amount	
(SH: C/O Breast wall at RD. 2/509.50 to 0/519.10 RH5)					Time:-		One month	
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	Amount	98632	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	8.64	Cum.	160.00	Rupees One Hundred Sixty Only	1382		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.50	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	94050		
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.00	nos	160.00	Rupees One Hundred Sixty Only	3200		
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018							
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021							
	Percentage quoted rate in figures				Total	98632		
	Percentage quoted rate in words							
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							

139

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY	
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42
43	43
44	44
45	45
46	46
47	47
48	48
49	49
50	50
51	51
52	52
53	53
54	54
55	55
56	56
57	57
58	58
59	59
60	60
61	61
62	62
63	63
64	64
65	65
66	66
67	67
68	68
69	69
70	70
71	71
72	72
73	73
74	74
75	75
76	76
77	77
78	78
79	79
80	80
81	81
82	82
83	83
84	84
85	85
86	86
87	87
88	88
89	89
90	90
91	91
92	92
93	93
94	94
95	95
96	96
97	97
98	98
99	99
100	100

88

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

17

Draft Schedule of quantity

(SH: C/O Breast wall at RD. 2/519.10 to 2/528.70 RHS)

Name of Work:- Restoration of rain damages on Link road to Village Boolgarh km. 0/00 to 2/600					Estimated Cost: Rs		Amount
					Time:-		One month
					Earnest Money:-		2000
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words		Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.64	Cum.	160.00	Rupees One Hundred Sixty Only		1382
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.70	Cum.	3300.00	Rupees Three Thousand Three Hundred Only		94710
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.00	nos	160.00	Rupees One Hundred Sixty Only		2880
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					Total		98972
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A(31)/2020-1 Dated 07.10.2021							
Percentage quoted rate in figures							
Percentage quoted rate in words							
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							

138

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

18

SCHEDULE OF QUANTITY

Name of work: Rest. of rain damage on link road Nayian Basti Baliwal km 0/00 to 1/500 (SH:C/O R/wall at RD 0/007.80 to 0/15.60 LHS)

Estimated Cost 99365/-
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material inclusive octroi, royalty, malkhana, toll tax sale tax GST labour cess or other taxes imposed by the Government.	6.24	Per cubic metre	160.00	Rupees One hundred sixty only	998
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand eight graded crushed /broken stone aggregate 40mm (twenty Millimeter) nominal size in or under water ground complete laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.70	Per cubic metre	3300.00	Rupees three thousand three hundred only	94710
3	Providing weepholes in brick masonry/ stone masonry plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204 3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax GST labour cess or other taxes imposed by the Government.	10.00	Each	160.00	Rupees One hundred fifty only	1600
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	3.74	Per cubic metre	550.00	Rupees five hundred fifty only	2057
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(1712/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20				Total:	99365
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY	
1	...
2	...
3	...
4	...
5	...
6	...
7	...
8	...
9	...
10	...
11	...
12	...
13	...
14	...
15	...
16	...
17	...
18	...
19	...
20	...
21	...
22	...
23	...
24	...
25	...
26	...
27	...
28	...
29	...
30	...
31	...
32	...
33	...
34	...
35	...
36	...
37	...
38	...
39	...
40	...
41	...
42	...
43	...
44	...
45	...
46	...
47	...
48	...
49	...
50	...
51	...
52	...
53	...
54	...
55	...
56	...
57	...
58	...
59	...
60	...
61	...
62	...
63	...
64	...
65	...
66	...
67	...
68	...
69	...
70	...
71	...
72	...
73	...
74	...
75	...
76	...
77	...
78	...
79	...
80	...
81	...
82	...
83	...
84	...
85	...
86	...
87	...
88	...
89	...
90	...
91	...
92	...
93	...
94	...
95	...
96	...
97	...
98	...
99	...
100	...

Name of work:- Restoration of rain damage on Panjagar Bathri Road To Ispur Pathak Mohalla Kayalia Road KM 0/0 TO 1/900 (SH: C/o Breast wall in RD 1/265 to 1/273.50 RHS)						
Sl. No.	Description of work	Quantity	Unit	Figures	Words	Estimated Cost Earnest Money Time limit One month
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	11.22	cum	160.00	Rupees one hundred sixty only	1795
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (twenty millimeter) nominal size in or under water or ground complete including pumping or bailing out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government..	29.41	cum	3300.00	Rupees three thousand three hundred only	97053
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)/dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204 3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government..	7.00	Each	160.00	Rupees one hundred sixty only	1120
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018				Total:	99968
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(31/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

52

SCHEDULE OF QUANTITY

Name of Work: A/R & M/O on Lalulal Gondpur road km. 0/0 to 6/315 (SH: Painting of road side parapet, Breast wall etc. between Rd. ~~3/400 to 6/315~~) 0/0 to 3(400)							Estimated cost	99307
							Earnest money	2000
							Time limit	One month
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)		
				Figures	Words			
1	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete and direction of Engineer in charge. including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, toll tax, sale tax other taxes imposed by the Govt.	800.86	Per Square metre	124.00	Rupees one hundred twenty four only	99307		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	99307		
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
	Percentage quoted rate in Figures							
	Percentage quoted rate in words							
	Note:- Rate quoted in figures & words are mandatory by the contractoe , otherwise the tender will be rejected.							

Executive Engineer ,
Haroli Divn. PWD.,
Haroli

78

Schedule of Quantity

Name of Work :

Upgradation of link Umralli Dhilwan Heeran-Thara Pubowal to Polian via Kuthar Beet Km 3/400 to 6/500 (SH: Preparation of working estimate and DNIT including submission of Hard and soft copies)- under OTMNP

Estimated cost : 85000
Earnest Money : 1700
Time Limit : 15 day

S. No.	Description of item	Qty.	Unit	Rate (Rs.)	Rate in words	Amount (Rs.)
1	Preparation and approval of working estimate and Drafts Schedule of quantity from higher authority including submission of 5-set of estimate and soft copy of estimate .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1	Each	85000	Rupees Eighty five thousand only	85000
	1) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(3)/2020 dated 22.07.20			Total =		85000
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					

Executive Engineer
Haroli Division
HPPWD Haroli.

135

Name of Work: A/R & M/O on Tahliwal Garshankar (HP Boundary) MDR-41 from km. 0/0 to 7/800 (SH; Painting of solid concrete crash barrier Rd. in between 6/750 to 7/233)						
Schedule of quantity				Estimated Cost: Rs		₹ 60,536
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	One month 2000 Amount
1	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete and direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. THE rate including octroi, royalty, Malkhana, toll tax sale tax r other taxes imposed by the Govt.	496.20	Sqm	122.00	Rupees One Hundred Twenty Two Only	60536
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021				Total	60536
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

144

SCHEDULE OF QUANTITY

Name of work: C/O Link road from Baba Bankhandi road to Dalit Basti Ward No 7 G.P.Haroli (SH:-C/O R/Wall on Rest house Haroli Baba Bankhandi Mandir road 0/320 to 0/327.30 LHS)Under-MMSY

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.25	Per cubic metre	160.00	Rupees one hundred sixty only	1320
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	29.05	Per cubic metre	3300.00	Rupees three thousand three hundred only	95865
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.00	Each	160.00	Rupees one hundred sixty only	1600
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.31	Per cubic metre	550.00	Rupees five hundred Fifty only	721
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@ (17/2/2012 dated 7.8.2018				Total:	99506
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)A(31)/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.R.)

154

24

SCHEDULE OF QUANTITY

Name of work: Rest. of rain damage on link road Nayian Basti Baliwal km 0/00 to 1/500 (SH-C/O R/wall at RD 0/023.40 to 0/031.20 LHS)

Estimated Cost 99676
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.25	Per cubic metre	160.00	Rupees One hundred sixty only	1000
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed/ broken stone aggregate 40mm (twenty millimeter) nominal size in or under water/ ground complete including pumping or bailing out water/ dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.80	Per cubic metre	3300.00	Rupees three thousand three hundred only	95040
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(V) 20(H) (one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204 3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.80	Each	160.00	Rupees One hundred fifty only	1568
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.76	Per cubic metre	550.00	Rupees five hundred fifty only	2068
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)(17)2/0212 dated 7.8.2018				Total:	99676
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

				Estimated Cost		99220	
				Earnest Money	Time limit	2000/-	One month
Name of work :C/O Link road Nagnoli to SC Basti Chaperian Gour Bagirian Chotti Khad Gujran Tarkhana Nainan Mohalla (SH: C/o CC pavement RD 0/179 to 0/200.50 approach road to Baba Sidhcharno Temple)- Deposit work							
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty, malikana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	8.60	Per cubic metre	3300.00	Rupees three thousand three hundred only	28380	
3	Providing and laying reinforcement cement concrete work of grade M-25 (M-twenty five) with minimum cement content of 400 kg (Four hundred kilogramme) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in open foundation including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty, malikana ,toll tax,GST,labour cess or other taxes imposed by the Government.	12.88	Per cubic metre	5500.00	Rupees Five thousand five hundred only	70840	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:		99220	
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
Percentage quoted rate in Figures							
Percentage quoted rate in words							
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.							

Executive Engineer
Haroli Division
HP.PWD.,Haroli

119

Schedule of quantity

Name of Work: A/R & M/O on Tahilwal Garshankar (HP Boundary) MDR-41 from km. 0/0 to 7/800

(SH) P/L Thermoplastic paint at Rd. 5/500 to 6/160)

Estimated Cost: Rs					₹ 99,000
Time:-					One month
Earnest Money:-					2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Amount
1	Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetre)thick including reflectorising glass beads @ 250 gms (at the rate of two hundred fifty gram per square metre)per sqm area, thickness of 2.5 mm(two point five millimetre) is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	165.00	Sqm	600.00	99000
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018			Total	99000
	PW to the Govt. of Hp vide letter no. PBW (B)A(3)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)/2020-1 Dated 07.10.2021				
	Percentage quoted rate in figures				
	Percentage quoted rate in words				
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected				

143

**Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)**

SCHEDULE OF QUANTITY

Name of work: Rest. of rain damage on link road Nayian Basti Baliwal km 0/00 to 1/500 (SH:C/O R/wall at RD 015.60 to 0/023.40 LHS)

Estimated Cost 99127/-
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax sale tax GST, labour cess or other taxes imposed by the Government.	6.25	Per cubic metre	160.00	Rupees One hundred sixty only	1000
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (twenty Millimeter) nominal size in or under water or ground complete laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in- charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	28.70	Per cubic metre	3300.00	Rupees three thousand three hundred only	94710
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204 3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.50	Each	160.00	Rupees One hundred fifty only	1360
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3 8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.74	Per cubic metre	550.00	Rupees five hundred fifty only	2057
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	99127
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

189

SCHEDULE OF QUANTITY

Name of work:- Restoration of Gramin Sampark from main road to the house of Major Dhalbir Singh ward No 5,6 GP Heeran Nagar (Estimated Cost SH: C/O C.C pavement at RD 0/00 to 0/009 alongwith toe wall) - Deposit work

Estimates cost:- 99842
Earnest Money:- Rs. 2000/-
Time Limit:- One Month,

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains including dressing of sides and ranning of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.10	Per Cubic metre.	160.00	Rupees one hundred sixty only	1136
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water/ ground complete including pumping or hauling out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	21.38	Per Cubic metre.	3300.00	Rupees three thousand three hundred only	70554
3	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 metre. transporting to site, spreading, grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with all leads as per Technical Specification Clause 301.5 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	17.40	Per Cubic metre.	250.00	Rupees two hundred fifty only	4350
4	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface mixing by mix in place method with rotavator at OMC and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading material including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	2.03	Per Cubic metre.	1050.00	Rupees one thousand fifty only	2132
5	Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	3.94	Per Cubic metre.	5500.00	Rupees five thousand five hundred only	21670
Note:- NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)(17/02/12 dated 7.8.2018						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						
Total:-						99842

SCHEDULE OF QUANTITY

Name of work :C/O Link road Nagnoli to SC Basti Chaperian Gour Bagirian Chotti Khad Gujran Tarkhana Nainan Mohalla (SH: 99300 412434)
C/o protection wall RD 0700 to 0724.50 - Deposit work

S. No.	Description of work	Quantity	Unit	Figures	RATE IN		Estimated Cost Earnest Money	One month
					Words	AMOUNT		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.82	Per cubic metre	160.00	Rupees One hundred sixty only	1411		
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed broken stone aggregate 40mm (forty millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	25.97	Per cubic metre	3300.00	Rupees three thousand three hundred only	85701		
3	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	13.72	Per cubic metre	550.00	Rupees Five hundred fifty only	7546		
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) with cement contents not less than 250kg (Two hundred fifty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.98	Per cubic metre	3850.00	Rupees three thousand eight hundred fifty only	3773		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@17/2/0212 dated 7.8.2018								
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B) A(31)/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(31)/2020-1 dated 7.10.2021								
Percentage quoted rate in Figures								
Percentage quoted rate in words								
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.								
Total:							98431	

Executive Engineer
Haroli Division
HP.PWD, Haroli

124

[illegible]

Sl.	D
pavement RD 0/169 to 0/195.50)- Deposit work	

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work :- Restoration of rain damages on link road to Village Kangar km. 0/00 to 1/700						
(SH: C/O Retaining wall at RD. 0/750 to 0/756.30 R.H.S) - 0/762.10 to 0/768.30 R.H.S)						
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil upto 3 m depth. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.81	cum	160.00	Rupees One Hundred Sixty Only	1250
2	Providing & Laying Cement Concrete 1:4:8 (1Cement :4 Sand :8Graded stone aggregate 40 mm nominal size) with including cost of form work plain/reinforced concrete in retaining wall /Breast wall, as per Drawing and H.P.P.W.D. technical Specification. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	29.02	cum	3300.00	Rupees Three Thousand Three Hundred Only	95753
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.00	Nos	160.00	Rupees One Hundred Sixty Only	1120
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.98	cum	450.00	Rupees Four Hundred Fifty Only	1339
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	99462
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

32

SCHEDULE OF QUANTITY

Estimated cost 99500/-
Earnest money 2000/-
Time limit One month

Name of work :- A/R & M/O PWD Non Residential building at Haroli (SH: P/F All in one HP-PC with 15. 12h Gen Processor 8 GB Ram & 512 GB SSD with Microsoft office & window and Brother printer DCP- B7640DW) in Newly created Khad Sub Division office

SCHEDULE OF WORK / ITEM(S)

S.No	Description of Work / Item(s)	Qty	Unit	Figures	Words	Amount
1	Providing and fixing commercial All in one HP make computer system with inspiron 24" Intel i5 12Th Gen Processor 8 GB Ram & 512TB SSD with Microsoft office & Window 11/12 Wi, fi, & Bluetooth 4.0 M.2/keyboard & optical mouse (3 year warranty provided by the manufacturer from date of purchase) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	1.00	Each	74500.00	Rupees Seventy four thousand five hundred only	74500
2	Providing and fixing Brother printer DCP-B7640DW with wifi technology. (1 year warranty provided by the manufacturer from date of purchase) including carriage of material with in all leads and lifts and other incidentals the rate includes sale tax octroi royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	1.00	Each	25000.00	Rupees Twenty five thousand only	25000
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)/@/17/2/0212 dated 7.8.2018				Total	99500
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer
Haroli Division
HP.PWD.,Haroli

79

33 **SCHEDULE OF QUANTITY**

Name of work:- Restoration of Gramin Sampark from main road to the house of Major Dhalbir Singh ward No 5,6 GP Heeran Nagar (Estimated Cost SH: C/O C.C pavement at RD 0/036 to 0/045 alongwith toe wall) - Deposit work						
Estimates cost:- 98738/- Earnest Money:- Rs. 2000/- Time Limit:- One Month.						
S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains including dressing of sides and ramming of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	7.12	Per Cubic metre.	160.00	Rupees one hundred sixty only	1139
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 40mm forty Millimeter nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights, depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	21.34	Per Cubic metre	3300.00	Rupees three thousand three hundred only	70422
3	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 metre, transporting to site, spreading, grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with all leads within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	17.46	Per Cubic metre.	250.00	Rupees two hundred fifty only	4365
4	Construction of Granular Sub Base by providing well graded material, spreading to uniform layers with tractor mount roller to achieve the desired density complete as per technical specification clause for grading 1 material including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government	2.04	Per Cubic metre	1050.00	Rupees one thousand fifty only	2142
5	Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights: depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government	3.94	Per Cubic metre	5500.00	Rupees five thousand five hundred only	21670
Note:- NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW/B/17/20212 dated 7.8.2018 Percentage quoted rate in Figures Percentage quoted rate in words Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						
Total:-						99738

Name of work:- Balance work for the C/O Community Park, Outdoor open gym at ward no. 2 & 4 G.P. Dulehar Tehsil Haroli Distt Una
HP. (Deposit work)
(SH: Hill side cutting for extended portion of park Rd. 0/012 to 0/016)

Schedule of quantity					Estimated Cost: Rs	One month
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:- Rate in words	2000 Amount
1	Earth work in excavation in hilly area in all heights and depths and in all kind of soil by mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification 2014 clause 302, 1603 in association with other clauses. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	710.00	Cum.	140.00	Rupees One Hundred Fourty Only	99400
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	99400
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

Name of work :- Restoration of rain damages on link road to Village Kangar km. 0/00 to 1/700						
(SH: C/O Retaining wall at RD. 0/750 to 0/756.10 Rms) — 0/756.10 to 0/762.10 Rms						
Schedule of quantity						
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Estimated Cost: Rs	
					Time:-	One month
Earnest Money:-						
					Rate in words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil Upto 3 m depth. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	7.69	cum	160.00	Rupees One Hundred Sixty Only	1230
2	Providing & Laying Cement Concrete 1:4:8 (1Cement :4 Sand :8Graded stone aggregate 40 mm nominal size) with including cost of form work plain/reinforced concrete in retaining wall /Breast wall, as per Drawing and H.P.P.W.D. technical Specification. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	28.55	cum	3300.00	Rupees Three Thousand Three Hundred Only	94208
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	10.00	Nos	160.00	Rupees One Hundred Sixty Only	1600
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	2.93	cum	450.00	Rupees Four Hundred Fifty Only	1318
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					Total	98356
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)(31)/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						