

Himachal Pradesh
Public Works Department

No. PWH/HD/CB/T-I/2025-26
To

3139-41

Dated: -

08/08/2025


The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publication of Notice inviting tender.

Sir,


Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above


Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).


Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.


Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).

Certificate

313241 dated 08/08/2025 Certified that the tenders for the works called vide this office letter No. PWH/HD/CB/T-1/2024- are required to be carried out immediately being emergent nature of work in public interest.


Executive Engineer,
Haroli Division, HPPWD
Haroli (Distt. Una HP).

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

" NOTICE INVITING TENDERS "

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Division H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/firms enlisting with PWD Department as per latest instructions. so as to reach and open in his office as per time schedule given below. The opening of the tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any tender without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: - 13-06-2025 up to 10.30 (AM)
2. Date of issue/sale of tender forms against cash payment(non-refundable): - 14-06-2025 up to 3.00 (PM)
3. Date of receipt of tenders: - 18-06-2025 up to 10.30 AM
4. Date of opening of tenders: - 18-06-2025 at 11.00 AM

Sr. No.	Name of work	Estimated cost	EMD	Time Limit	Cost of tender	Eligible class of contractor
1	2	3	4	5	6	7
1	C/O link road Nagnoli to SC Basti Chaperian Gour Bagirian Chotti Khad Gujran Tarkhana Nainan Mohalla (SH: C/o CC Pavement RD. 0/136 to 0/157.50 approach road to Baba Sidhcharno Temple) Deposit Work	99330	2000/-	One Month	350/-	Class & D
2	Restoration of rain damage Old Saloh Bhadouri road km. 0/00 to 9/615 (SH:-P/L CC Overlay on existing Cause way at RD. 7/510.10 to 7/530.30)	99456	2000/-	One Month	350/-	Class & D
3	Restoration of Gramin Sampark from the H/O sh. Surinder Singh to Shahib Baba Mandir Ward No. 2 GP Palkwah, (Deposit Work) (SH:-P/L CC Pavement at RD. 0/071.30 to 0/094)	94571	2000/-	One month	350/-	Class & D
4	Restoration of rain damage on link road Panjwar Bathri road km. 0/00 to 34/00 (SH: C/o U-shape drain at RD 4/721 to 4/740- RHS)	99458	2000/-	One month	350/-	Class & D
5	Restoration of rain damages on link road to Village Kangar km. 0/00 to 1/700(SH:-C/O R/wall at RD. 0/750 to 0/756.10 RHS)	98676	2000/-	One Month	350/-	Class & D
6	Restoration of rain damages on link road from Umrli Beetan Goua Via Thakur Behli km. 0/00 to 1/600(SH:-Repair of existing 900 mm dia pipe culvert at RD. 1/350 & C/O Causeway at RD. 1/345 to 1/353)	97569	2000/-	One Month	350/-	Class & D
7	Restoration of rain damage on link road Subowana to Baliwal 0/00 to 5/00(SH:-C/O R/wall at RD. 2/562 to 2/568-LHS)	99202	1700/-	15 day	350/-	Class & D
8	A/R & M/O Non-residential Building of Sub-Division HPPWD Haroli(SH:-P/L Mate flooring & PVC Panelling in Assistant Engineer room)	99159	2000/-	One Month	350/-	Class & D
9	Restoration of rain damages on 1) Lалуwal to Gondpur Km 0/0 to 6/315, 2) Link Road vill Gondpur to Jai Chand to Satsang Ghar via Dyala Mohall Km 0/0 to 1/200 (SH: Deployment of excavator cum loader & tractor for treading of access soil in berm removal of slips & C/o unlined drain etc. in rainy season)	98100	2000/-	One Month	350/-	Class & D
10	Restoration of rain damages on link road from Una Jaijon road to Gulaban da Toba km. 0/00 to 1/700 (SH:-C/O R/wall at RD. 1/080 to 1/086.10 LHS)	99546	2000/-	One Month	350/-	Class & D
11	Restoration of rain damages link road from Umrli to Dulehar via Goua km. 0/00 to 3/200(SH:-P/L thick paver block at RD. 1/930 to 1/945)	99475	2000/-	One Month	350/-	Class & D
12	Restoration of rain damage on link road Subowana to Baliwal 0/00 to 5/00(SH:-C/O R/wall at RD. 2/568 to 2/574-LHS)	99434	2000/-	One Month	350/-	Class & D

13	C/O Path to Dalit Basti Gondpur JaiChand Length 150.00 Mtr. (Deposit work)(SH:-Dismantling of old V-Shape drain and C/O new U-Shape coverd with grating drain Length=26.00 mtr.	99216	2000/-	One Month	350/-	Class & E
14	Restoration of rain damages on link road Harijan Basti Polian km. 0/00 to 1/500(SH:-P/L 60mm thick paver block at RD. 0/023.50 to 0/046.90)	99739	2000/-	One Month	350/-	Class & D
15	C/O link road to Harijan Basti Panjwar (SH:- C/O CC Pavement at RD. 0/289 to 0/298.50)Deposit Work	99837	2000/-	One Month	350/-	Class & D
16	C/O Harijan Basti Khad to Khas Khad (SH:-C/O CC Pavement-Phase-II Deposit Work	99568	2000/-	One Month	350/-	Class & D
17	Restoration of rain damages on link road Polian to Janani km. 0/00 to 6/00(SH:-C/O R/wall at RD. 4/350 to 4/364-LHS)	99605	2000/-	One Month	350/-	Class & D
18	Restoration of rain damages on various roads in Khad section under Khad Sub-Division Haroli, Phase-II(SH:- Hiring of excavator Cum Loader for treming of access soil in berm removal of slips & C/o unlined drain etc. in rainy season)	99550	2000/-	One Month	350/-	Class & D
19	Restoration of rain damage Old Saloh Bhadouri road km. 0/00 to 9/615 (SH:-P/L CC Overlay on existing Couse way at RD. 7/530.30 to 7/550.20	99567	2000/-	One Month	350/-	Class & D
20	Restoration of rain damages on link road to Village Kangar km. 0/00 to 1/700(SH:-C/O R/wall at RD. 0/768.30 to 0/774.40 RHS)	99622	2000/-	One Month	350/-	Class & D
21	C/O link road to Harijan Basti Dulehar (SH:-C/O B/wall RD. 0/665.60 to 0/694-RHS)Deposit Work	98326	2000/-	One Month	350/-	Class & D
22	Restoration of rain damages on link road from Una Jaijon road to Gulaban da Toba km. 0/00 to 1/700 (SH:-C/O R/wall at RD. 1/086.10 to 1/092.20 LHS)	99226	2000/-	One Month	350/-	Class & D
23	Restoration of rain damages link raod from Umrli to Dulehar via Goua km. 0/00 to 3/200(SH:-P/L thick paver block at RD. 1/915 to 1/930)	99480	2000/-	One Month	350/-	Class & D
24	C/O Path to Dalit Basti Gondpur JaiChand Length 150.00 Mtr. (Deposit work)(SH:-Dismantling of old V-Shape drain and C/O new U-Shape coverd with grating drain Length=25.70 mtr.	98071	2000/-	One Month	350/-	Class & D
25	Restoration of rain damage on link road Subowana to Baliwal 0/00 to 5/00(SH:-C/O R/wall at RD. 2/550 to 2/556-LHS)	99566	1700/-	15 day	350/-	Class & D
26	Restoration of rain damages on link road Harijan Basti Polian km. 0/00 to 1/500(SH:-P/L 60mm thick paver block at RD. 0/00 to 0/023.50)	99170	2000/-	One Month	350/-	Class & D
27	C/O link road from House of Champa Devi RD. 0/00 to 1/200 (Deposit Work)(SH:-C/O R/wall at RD. 1/169.80 to 1/177.20 RHS)	99365	2000/-	One Month	350/-	Class & D
28	R/O Restoration work of rain damages on link road from Pithoyana toba to field of Jagir Singh G.P. Pubowal Tehsil Haroli Dist. Una (HP)(SH:- C/O CC Pavement & V-shape drain at RD. 0/032.20 to 0/048.30)	94951	2000/-	One Month	350/-	Class & D
29	Restoration of rain damages on 1) Old Saloh Bhadouri road Km 0/0 to 9/600(2) Link road Jaijon more to Saloh Chowk Km 0/0 to 1/040 & (3) Link Road to village Bhoogarh Km 0/00 to 2/600	99,200	2000/-	One Month	350/-	Class & D
30.	C/o link road Nagnoli to Basti Chaperian Gour Bagirian Chotti Khad Gujran Tarkhana Nainan Mohalla (SH: C/o CC Pavement RD. 0/157.50 to 0/179 approach road to Baba Sidhcharno Temple)Deposit Work	99110	2000/-	One Month	350/-	Class & D
31	Restoration of rain damage on link road Panjwar Bathri road km. 0/00 to 34/00 (SH: C/o U-shape drain at RD 4/670 to 4/687- RHS)	99591	2000/-	One Month	350/-	Class & D
32	Restoration of rain damages on link road from Umrli Bectan Goua Via Thakur Behli km. 0/00 to 1/600(SH:- C/O Causeway at RD. 1/368 to 1/382.80)	98124	2000/-	One Month	350/-	Class & D
33	Restoration of rain damage on link road Subowana to Baliwal 0/00 to 5/00(SH:-C/O R/wall at RD. 2/574 to 2/580-LHS)	99403	2000/-	One Month	350/-	Class & D

34	Upgradation of link road Umrali Dhillwan Heera Thara Pubowal to Polian via Kuthar Beet Km 0/0 to 3/400 (SH: Felling of trees & removing the roots in B/W RD 0/050 to 2/450)	99390	2000/-	One month	350/-	Class & D
35	C/O Harijan Basti Khad to Khas Khad (SH:-C/O CC Pavement-Phase-I Deposit Work)	99568	2000/-	One Month	350/-	Class & D
36	Restoration of rain damages on link road Polian to Janani km. 0/00 to 6/00(SH:-C/O R/wall at RD. 4/364 to 4/378-LHS)	99349	2000/-	One Month	350/-	Class & D
37	Restoration of rain damages on various road under section Ghaluwal Sub-Division Haroli(SH:- Deployment of excavator cum loader & tractor for treading of access soil in berm removal of slips & C/o unlined drain etc. in rainy season)	98100	2000/-	One Month	350/-	Class & D
38	Restoration of rain damages on various roads in Pandoga section under Khad Sub-Division Haroli, Phase-II(SH:- Hiring of excavator Cum Loader for treading of access soil in berm removal of slips & C/o unlined drain etc. in rainy season)	99550	1700/-	15 days	350/-	Class & D
39	C/O link road to Harijan Basti Dulehar (JSH:-C/O B/wall RD. 0/636 to 0/664.60-RHS)Deposit Work	98981	2000/-	One Month	350/-	Class & D
40	C/O link road from House of Champa Devi RD. 0/00 to 1/200 (Deposit Work)(SH:-C/O R/wall at RD. 1/165 to 1/169.80 RHS and approach road CC RD. 0/163 RHS)	98703	2000/-	One Month	350/-	Class & D
41	R/O Restoration work of rain damages on link road from Pithoyana toba to field of Jagir Singh G.P. Pubowal Tehsil Haroli Dist. Una (HP)(SH:-C/O CC Pavement & V-shape drain at RD. 0/048.30 to 0/064.30)	94439	2000/-	One Month	350/-	Class & D
42	Upgradation of link road Umrali Dhillwan Heera Thara Pubowal to Polian via Kuthar Beet Km 0/0 to 3/400 (SH: Dismantling of old culvert toe wall, R/wall, Edge wall of drain included bed etc from Km 1/282 to 1/752)	99408	2000/-	One Month	350/-	Class & D
43	Restoration of rain damages on 1)Una Rampur Haroli Jaijon road 10/200 to 23/00,2)link road to Shiv Mandier village Polian beet Km 0/0 to 1/500 & 3) Link road Gondpour Turf Jai Chand to Kuthar Beet to Harijan Basti Kuthar Km 0/0 to 3/400 (SH: Deployment of excavator cum loader for Treading of access soil in berms Removal of slips & C/o unlined drain etc. In rain season etc.	98,100/-	2000/-	One month	350/-	Class & D
44	Balance work for C/o Community Park, Outdoor open gym at WNo.2 & 4 GP Dulehar (Deposit work) (SH: Hill side cutting for extended portion of park RD 0/008 to 0/012)	96600/-	2000/-	One month	350/-	Class & D
45	Restoration of rain damages on link road to Co-op Society Haroli vid GSSS Haroli Km 0/0 to 2/225(2) C/o road from Upper Karampur to Swan Border Km 0/0 to 2/650 (3) Old Haroli road Gugga Mandir upto Pajjal Yojna Haroli Km 0/0 to 2/240 (Deployment of excavator cum loader for Treading of access soil in berms Removal of slips & C/o unlined drain etc. in rain season etc	99200	2000/-	One month	350/-	Class & D
46	Upgradation of link road Umrali Dhillwan Heera Thara Pubowal to Polian via Kuthar Beet Km 0/0 to 3/400 (SH: Dismantling of old culvert toe wall, R/wall, Edge wall of drain included bed etc from Km 0/0 to 1/275)	99640	2000/-	One month	350/-	Class & D
47	Restoration of rain damage on link road from Upper Karampur to Swan Border Km 0/0 to 2/650 (SH: C/o CC pavement at RD 0/671.30 to 0/682.60)	99607	2000/-	One month	350/-	Class & D
48	Balance work for C/o Community Park, Outdoor open gym at WNo.2 & 4 GP Dulehar (Deposit work) (SH: Hill side cutting for extended portion of park RD 0/004 to 0/008)	97300/-	2000/-	One month	350/-	Class & D
49	Upgradation of link road Umrali Dhillwan Heera Thara Pubowal to Polian via Kuthar Beet Km 0/0 to 3/400 (SH: Dismantling of old culvert toe wall, R/wall, Edge wall of drain included bed etc from Km 1/630 to 2/375)	99874	2000/-	One month	350/-	Class & D


50	Restoration of rain damage on link road from Upper Karampur to Swan Border Km 0/0 to 2/650 (SH: C/o CC pavement at RD 0/650 to 0/671.30)	99497	2000/-	One month	350/-	Class & E
51	C/O link road to Harijan Basti Panjwar (SH:- C/O CC Pavement at RD. 0/279.50 to 0/289) Deposit Work	99630	2000/-	One Month	350/-	Class & C
52	Upgradation of link road Umralli Dhillwan Heera Thara Pubowal to Polian via Kuthar Beet Km 0/0 to 3/400 (SH: Dismantling of old 1.50 mtr span culvert at RD 0/880, 1/050 toe wall at RD 2/375 to 2/425 Rhs)	97102	2000/-	One month	350/-	Class & C

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FC Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No. Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

1. The contractor should produce a copy of valid enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
3. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
4. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/reject any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be in process on next date.
5. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
6. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
7. The conditional/ambiguous/telegraphic tenders by fax shall not be entertained/considered in any case.

HJM SUCHANA AVAM JAN SAMPARK.


 Executive Engineer
 HPPWD Division Haroli
 Dist. Una(HP). Pin Code-177220
 Email: ee-haroli-hp@hp.gov.in
 On behalf of Governor of Himachal Pradesh

①

SCHEDULE OF QUANTITY

Name of work :C/O Link road Nagnoli to SC Basti Chaperian Gour Bagirian Chotti Khad Gujran Tarkhana Nainan Mohalla (SH: C/o CC pavement RD 0/136 to 0/157.50 approach road to Baba Sidhcharno Temple)- Deposit work

S. No.	Description of work	Quantity	Unit	Figures	RATE IN		AMOUNT
					Words	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty, Malkana toll tax, safe tax, GST, labour cess or other taxes imposed by the Government	8.60	Per cubic metre	3300.00	Rupees three thousand three hundred only		28380
3	Providing and laying reinforcement cement concrete work of grade M-25 (M-twenty five) with minimum cement content of 400 kg (Four hundred kilogramme) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in open foundation including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty, Malkana toll tax, GST, labour cess or other taxes imposed by the Government.	12.90	Per cubic metre	5500.00	Rupees Five thousand five hundred only		70950
				Total:			99330
<p>NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018.</p> <p>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021</p>							
Percentage quoted rate in Figures							
Percentage quoted rate in words							
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.							

120

Executive Engineer
Haroli Division
HP.PWD.,Haroli

2

SCHEDULE OF QUANTITY						
		Estimates cost:-		99456		
		Earnest Money:-		Rs. 2000/-		
		Time Limit:-		One Month.		
Name of work :- Restoration of rain damage Old Saloh Bhadouri road Km 0/00 to 9/615(SH: P/L CC Overlay on existing Cause way at RD 7/510.10 to 7/530.30)						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and laying (M-25) (M-twenty five) Grade mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg.(four hundred kilo gram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST labour cess or other taxes imposed by the Government..	17.92	Per cubic metre	5550	Rupees five thousand five hundred fifty only	99456
Note:-				Total:-		99456
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)(17)20212 dated 7 8 2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No PBW(B) A(3)1/2020 dated 22 7 2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work : Restoration of Gramin Sampark from the H/O Sh. Surinder Singh to Shahid Baba Mandir Ward No. 2 GP Palkwah. (Deposit work)		Estimated Cost: Rs		Time:-		
(SH: P/L CC Pavement at Rd. 0/071.30 to 0/094)		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge, including carriage of material within all leads . The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	20.43	Cum.	160.00	Rupees One Hundred Sixty Only	3269.00
2	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	25.88	Cum.	140.00	Rupees One Hundred Forty Only	3623.00
3	Construction of Embankment with Material Obtained from Roadway Cutting Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government..	34.05	Cum.	100.00	Rupees One Hundred Only	3405.00
4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401.. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government..	5.11	Cum.	1100.00	Rupees One Thousand One Hundred Only	5618.00

5	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8), including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.81	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	22473.00
6	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802, 803, 1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.22	Cum.	5500.00	Rupees Five Thousand Five Hundred Only	56183.00
					Total	94571
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					
	Z) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITIES

Estimates cost:- 99458
 Earnest Money:- Rs. 2000/-
 Time Limit:- One Month.

Name of work :- Restoration of rain damage on link road Panjwar Bathri road Km 0/00 to 3/400 (NH: C/O U' shape drain at RD 4/721 to 4/740- RIIS)

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and rinning of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	22.80	Per Cubic metre.	160.00	Rupees one hundred sixty only	3648
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.70	Per Cubic metre.	3300.00	Rupees three thousand three hundred only	18810
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	20.00	Per Cubic metre.	3850.00	Rupees three thousand eight hundred fifty only	77000
Total						99458
Note:-	1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)@17/2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)A@31/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

172

5

Schedule of quantity

Name of work :- Restoration of rain damages on link road to village Kangar km. 0/00 to 1/700		Estimated Cost: Rs	Time:-	₹ 98,676		
(SH: C/O Retaining wall at RD. 0/750 to 0/756.10 Rhs)		One month				
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:-	
					Rate in words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil upto 3 m depth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.69	cum	160.00	Rupees One Hundred Sixty Only	1230
2	Providing & Laying Cement Concrete 1:4:8 (1 Cement : 4 Sand : 8 Graded stone aggregate 40 mm nominal size) with including cost of forms work plain/reinforced concrete in retaining wall / Breast wall, as per Drawing and H.P.P.W.D. technical Specification, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.55	cum	3300.00	Rupees Three Thousand Three Hundred Only	94208
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.00	Nos	160.00	Rupees One Hundred Sixty Only	1920
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	2.93	cum	450.00	Rupees Four Hundred Fifty Only	1318
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) (17) Z/02612 dated 07.08.2018					Total	98676
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(31)/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer.

Schedule of quantity

Name of work:- Rastoration of rain damages on link road from Umrali Beetan Goua Via Thakur behli km. 0/00 to 1/600							Estimated Cost: Rs
(54) Repair of Existing 900 mm dia pipe culvert at Rd. 1/350 & C/O Causeway at Rd. 1/345 to 1/353							One month 2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:-		
					Rate in words	Amount	
1	Downlashing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge Nominal concrete 1:3:6 or richer mix (1/c equivalent design mix) - including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.72	Cum	800.00	Rupces Eight Hundred only	7776	
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 0.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	19.40	Cum	160.00	Rupces One Hundred Sixty only	3104	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.30	Cum	3850.00	Rupces Three Thousand Eight Hundred Fifty only	8847	
4	Providing and laying Non Pressure NP-2 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm dia RCC pipes. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.50	R/mtr	40000.00	Rupces Four Thousand only	10000	
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203, P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.74	Cum	3300.00	Rupces Three Thousand Three Hundred only	25542	
6	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.50	Cum	1150.00	Rupces One Thousand One Hundred Fifty only	5175	

07

6

7

SCHEDULE OF QUANTITY

Name of work : Restoration of rain damage on link road Subowana to Baliwa 0/00 to 5/00 (SH: C/O R/wall at RD 2/562 to 2/568-LHS)		Estimated Cost	
		Earnest Money	99202
		Time limit	2000
		RATE in	One month
		Figures	AMOUNT
		Words	
S. No.	Description of work	Quantity	Unit
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.54	Per cubic metre
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under waterlor ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in- charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	28.08	Per cubic metre
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax ,octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	16.00	Each
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	4.72	Per cubic metre
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)20212 dated 7.8.2018			
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021			
Percentage quoted rate in Figures			
Percentage quoted rate in words			
Total:			99202
Rupees One hundred sixty only			2560
Rupees Three thousand three hundred only			92664
Rupees Five thousand five hundred fifty only			2596
Rupees One hundred sixty only			1382

Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

8

Schedule of quantity

Name of Work :- A/R & M/O Non residential Building of Sub Division HPPWD Haroli. (Sub head:-P/L Make flooring & PVC panelling in Assistant Engineer room).		Estimated Cost: Rs		Time:-	
		One month		2000	
		Earnest Money:-		Amount	
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words
1	Providing and laying vitrified floor wooden matting 1mm thick. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed by the Government.	14.25	Sqm	700.00	Rupees Seven Hundred Only
2	Providing and Fixing PVC panelling in ceiling lining including carriage of material with in all lead and lifts. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed by the Government.	15.54	Sqm	1250.00	Rupees One Thousand Two Hundred Fifty Only
3	Providing and Fixing PVC wall panelling lining including carriage of material with in all lead and lifts.The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed by the Government.	46.61	Sqm	1200.00	Rupees One Thousand Two Hundred Only
4	Providing and fixing anodized aluminium work for doors, windows, ventilators and partitions with linal aluminium extrusions built up standard tubular and other sections of approved make conforming to IS 733 and IS:1285 anodized transparent or dyed to required shade according to IS-1868 fixed with rawl plugs and screws or with fixing clips or with expansion bolt fasteners including necessary filling up of gaps at junctions and top and bottom, sides with required PVC/neoprene fill etc. Aluminium sections shall be smooth, rust free, straight mitered and jointed mechanically where ever required including cleat angle, aluminium snap leading, for glazing/ panelling, C.P. brass stainless steel screw, all complete as per architectural drawing and the directions of Engineer-in-Charge for. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed by the Government.	22.96	Kg	520.00	Rupees Five Hundred Twenty Only
5	Providing and fixing aluminium work for doors, windows,board flat pressed three layer or graded wood particle board 12 mm thick conforming to IS: 12823 Grade I Type II, in panelling, fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed by the Government.	2.10	Sqm	900.00	Rupees Nine Hundred Only
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) (17) 2/02012 Dated 07.08.2018				Total	
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021				99159	
Percentage quoted rate in figures					
Percentage quoted rate in words					
Note- Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

79

Draft Schedule of quantity

Name of work: -Restoration of rain damages on 1) Lалуwal to Gondpur km. 0/00 to 6/315 , 2) link road vill Gondpur to Jaichand to Satsang Ghar via Dyala Mohalla km. 0/00 to 1/200		Estimated Cost: Rs		₹ 98,100		
(SH: Deploymet of excavator Cum Loader & Trector for Treming of Access soil in berm Removal of slips & C/O unilind drain etc. in rainy season etc.)		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deploymet of Hudraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori. royalty.malkhana .toll tax.GST.labour cess or other taxes imposed by the Government..	71.00	P/ Hour	1100.00	Rupees One Thousand One Hundred Only	78100
2	Hiring of Tractor with Trolley 3.00cum. capacity to be deployed for disposing/carring of material like earth kankar moorum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori. royalty.malkhana .toll tax.GST.labour cess or other taxes imposed by the Government..	8.00	P/day	2500.00	Rupees Two Thousand Five Hundred Only	20000
				Total		98100
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						

147

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

10

Schedule of quantity

Name of work : Restoration of rain damages on Link road from Una Jaijon road to Gulaban da Toba Km. 0/00 to 1/700						Estimated Cost: Rs	₹ 99,546
(SH: C/O Retaining wall at Rd. 1/080 to 1/086.10 Lhs)						Time:-	One month
Earning Money:-						Rate in words	Amount
S.NO	DESCRIPTION	Qty	Unit	T.Rate			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.78	Cum.	160.00		Rupees One Hundred Sixty Only	1405
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.67	Cum.	3300.00		Rupees Three Thousand Three Hundred Only	94611
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	Each	160.00		Rupees One Hundred Sixty Only	1920
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.93	Cum.	550.00		Rupees Five Hundred Fifty Only	1610
						Total:	99546
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018							
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20							
Percentage quoted rate in Figures							
Percentage quoted rate in words							
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)



SCHEDULE OF QUANTITY

Name of work: **Restroaction of rain damages link road form Umraoli to Dulehar via Goua km 0/00 to 3/200 (SH: P/L thick paver block at RD 1/930 to 1/945)** Estimated Cost **99475/-**
 Earnest Money **2000/-** Time limit **One month**

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of: control, royalty, Malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	20.00	cum	160.00	Rupees One hundred sixty only	3200
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.20	cum	1100.00	Rupees one thousand one hundred only	7920
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement: four sand: eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.20	cum	3300.00	Rupees three thousand three hundred only	23760
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (Twenty) nominal mix 1:2:4 (One cement: two sand: four graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size in or under water: and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.66	cum	4500.00	Rupees four thousand five hundred only.	2970
5	Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 80mm (Sixty millimetre) (SI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of: control, royalty, Malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	72.50	sqm	850.00	Rupees Eight hundred fifty only	61625.00
				Total:		99475
NOTE: *) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)402/1712/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H P P W D Division, Haroli

12

SCHEDULE OF QUANTITY

Name of work : Restoration of rain damage on link road Subowana to Baliwal 0/00 to 5/00 (SH: C/O R/wall at RD 2/568 to 2/574-LHS)		Quantity		Unit	Estimated Cost	99434
S. No.	Description of work	Quantity	Unit	Figures	Words	2000
						One month
					RATE IN	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.64	Per cubic metre	160.00	Rupees One hundred sixty only	1382
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand: eight graded crushed / broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.04	Per cubic metre	3300.00	Rupees three thousand three hundred only	92532
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	18.00	Each	160.00	Rupees One hundred sixty only	2880
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.80	Per cubic metre	550.00	Rupees Five thousand five hundred fifty only	2640
					Total:	99434
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						

Schedule of quantity

Name of work:- C/O Path to Dait Basti Gondpur Jaichand Length 150.00 Mtr. (Deposit work)		Estimated Cost: Rs		₹ 99,216		
		Time:-		One month		
(SH: Dismantling of old V-Shape drain and C/O new U-Shape covered with grating drain Length =26.00 mtr		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in -charge.Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	7.02	CUM.	800.00	Rupees Eight Hundred Only	5616
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	11.70	CUM.	160.00	Rupees One Hundred Sixty Only	1872

3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	9.36	CUM.	3800.00	Rupees Three Thousand Eight Hundred Only	35568
4	Steel work welded in built up sections/ framed work,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder,railings, brackets, gates and similar works The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	624.00	CUM.	90.00	Rupees Ninety Only	56160
Total:						99216
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

TM

SCHEDULE OF QUANTITY

Estimated Cost 99739/-
Earnest Money 2000/-
Time limit One month

Name of work: Restroaction of rain damages on link road Harijan Basti Polian Km 0/00 to 1/500 (SH.- P/L 60mm thick paver block at RD 0/023.50 to 0/046.90)

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-charge ,including cartage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.68	cum	3300.00	Rupees three thousand three hundred only	15444
2	Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 60mm (Sixty millimetre) (ISI mark) including entire cartage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	93.60	sqm	800.00	Rupees Eight hundred only	74880
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-Twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge ,including cartage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.87	cum	4500.00	Rupees four thousand five hundred only	8415
				Total:		98739
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)12/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected						


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.A)

15

SCHEDULE OF QUANTITY

Estimated cost 99837
 Earnest money 2000
 Time limit One month

Name of Work: C/O link road to Harijan Basti Panjwar (SH:- C/O C.C. pavement at RD 01289 to D/298.50)- Deposit work

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (In. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.64	Per cubic metre	160.00	Rupees one hundred sixty only	422
2	Excavation in hilly area in all heights and depths and in all kind of soil by ordinary rock, hard rock, chielessing, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.54	Per cubic metre	145.00	Rupees One hundred forty five only	1383
3	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading-I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.40	Per cubic metre	1100.00	Rupees one thousand one hundred only	10340
4	Providing and laying cement concrete 1:4:8 (one cement: four sand eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.24	Per cubic metre	3300.00	Rupees Three thousand three hundred only	33792
5	Providing and laying (M:25) (M:twenty five) Grade mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type structure complete of reinforced concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.80	Per cubic metre	5500.00	Rupees five thousand five hundred only	53900
				G.Total		99837
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(17/20212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B), A(31/12020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

16

SCHEDULE OF QUANTITY

Name of work : C/O Harijan basti Khad to Khas Khad (SH: C/O Cement Concrete pavement - phase -II)- Deposit work

Estimated Cost 99216
Earnest Money 2000/-
Time limit One month

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	18.40	Per cubic metre	160.00	Rupees One hundred sixty only	2944
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water/ de-watering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.94	Per cubic metre	3300.00	Rupees three thousand three hundred only	36102
3	Providing and laying (M-25) (M-twenty five) Grade mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.94	Per cubic metre	5500.00	Rupees five thousand five hundred only	60170
Total:						99216
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.FBW(B)A/3/172/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No.FBW(B)A/3/220/0 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division, Haroli
Distt. Una (H.P.)

(18)

SCHEDULE OF QUANTITY

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
0					Estimated Cost	99550/-
	Restoration of rain damages on various roads in Khad section under Khad sub division HPPWD Division Haroli. Phase-II)				Earnest Money	2000/-
	(SH:- Hiring of excavator Cum Loader for Treming of Access soil in berm, removal of slips & C/O Unlind drain in rainy season).				Time limit	Two month
1	Deployment of Hydraulic excavator 0.90 cum filed with rock breaker on through rate basis for making drain and side cutlings in hard rock(where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor	90.50	Per Hour	1100.00	Rupees One thousand one hundred only	99550
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total	99550
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					


 Exedutive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

20

Schedule of quantity

Name of work :- Restoration of rain damages on link road to Village Kangar km. 0/00 to 1/700		Estimated Cost: Rs	Time:-	Amount		
(SH: C/O Retaining wall at RD. 07750 to 07756:10 RHT 0768.30 to 0774.40 RHT)		Earnest Money:-				
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil upto 3 m depth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.81	cum	160.00	Rupees One Hundred Sixty Only	1250
2	Providing & Laying Cement Concrete 1:4:8 (1Cement :4 Sand :8Graded stone aggregate 40 mm nominal size) with including cost of form work plain/reinforced concrete in retaining wall /Breast wall, as per Drawing and H.P.P.W.D. technical Specification. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	29.02	cum	3300.00	Rupees Three Thousand Three Hundred Only	95753
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 6.14, 7.09, 1.204.3.7. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	8.00	Nos	160.00	Rupees One Hundred Sixty Only	1280
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	2.98	cum	450.00	Rupees Four Hundred Fifty Only	1339
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	99622
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A)(3)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)(3)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H P)

(2)

SCHEDULE OF QUANTITY

Name of work: C/O link road to Harijan Basti Dulehar (SH : C/O B/wall RD 0/665.60 to 0/694- RHS)- Deposit work

Estimated Cost 98326
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	25.56	Per cubic metre	160.00	Rupees One hundred sixty only	4090
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.12	Per cubic metre	3300.00	Rupees three thousand three hundred only	92796
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)/dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.00	Each	160.00	Rupees One hundred sixty only	1440
				Total:		98326
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)@17/2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)A(31)/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

1799

83

SCHEDULE OF QUANTITY

Estimated Cost 99480/-
Earnest Money 2000/-

Name of work: Restroaction of rain damages link road form Umraili to Dulehar via Goua km 0/00 to 3/200 (SH; P/L thick paver block at RD 1/915 to 1/930)

Sl. No.	Description of work	Quantity	Unit	RATE IN		One month AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royaty, maikhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	20.00	cum	160.00	Rupees One hundred sixty only	3200
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements or prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading-I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, maikhana toll tax, GST, labour cess or other taxes imposed by the Government.	7.20	cum	1100.00	Rupees one thousand one hundred only	7920
3	Providing and laying mechanically mixed and vibrated concrete for plain reinforced concrete in open foundation/for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed/broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of	7.20	cum	3300.00	Rupees three thousand three hundred only	23760
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement two sand four graded crushed/ broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, maikhana toll tax, GST, labour cess or other taxes imposed by the Government.	0.68	cum	4500.00	Rupees four thousand five hundred only	3060
5	Providing and fixing heavy duty precast concrete inter locking paver block pavements having thickness 80mm (Sixty millimetre) (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, maikhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	72.40	sqm	850.00	Rupees Eight hundred fifty only	61540.00
				Total:		99480
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)E(17)/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(31)/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Schedule of quantity

Name of work:- C/O Path to Dalit Basti Gondpur Jaichand Length 150.00 Mtr. (Deposit work)		Estimated Cost: Rs		₹ 98,071		
		Time:-		One month		
(SH: Dismantling of old V-Shape drain and C/O new U-Shape covered with grating drain Length =25.70 mtr		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	6.94	CUM.	800.00	Rupees Eight Hundred Only	5551
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	11.57	CUM.	160.00	Rupees One Hundred Sixty Only	1850

3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	9.25	CUM.	3800.00	Rupees Three Thousand Eight Hundred Only	35158
4	Steel work welded in built up sections/ framed work,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder,railings, brackets, gates and similar works The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	616.80	CUM.	90.00	Rupees Ninely Only	55512
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@(17)2/0212 dated 7.8.2018						Total:
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division, Haroli
Distt. Una (H.P.)

95

SCHEDULE OF QUANTITY

Name of work : Restoration of rain damage on link road Subowana to Baliwal 0/00 to 5/00 (SH: C/O R/wall at RD 2/550 to 2/556-LHS)		Estimated Cost				
		Earnest Money	99566			
		Time limit	2000			
			One month			
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, maikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.64	Per cubic metre	160.00	Rupees One hundred sixty only	1382
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, maikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	28.08	Per cubic metre	3300.00	Rupees three thousand three hundred only	92664
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, maikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	18.00	Each	160.00	Rupees One hundred sixty only	2880
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, maikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	4.80	Per cubic metre	550.00	Rupees Five thousand five hundred fifty only	2640
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3)1/2020-1 dated 7.10.2021						
Percentage quoted rate In Figures						
Percentage quoted rate In words						
Note:- Rate quoted In figures & words are mandatory by the contractor, otherwise the tender will be rejected.						
					Total:	99566

96

SCHEDULE OF QUANTITY

Name of work: Restroaction of rain damages on link road Hanijan Basti Polian Km 0/00 to 1/500 (SH.- P/L 60mm thick paver block at RD 0/00 to 0/023.50)

Estimated Cost 99170/-
 Earnest Money 2000/-
 Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain reinforced concrete in open foundation for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement, four sand, eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water ground, complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.70	cum	3300.00	Rupees three thousand three hundred only	15510
2	Providing and fixing heavy duty precast cement concrete interlocking paver block pavements having thickness 60mm (Sixty millimetre) (ISI mark) including entire carriage of material within all leads and lifts and other incidentals, as per the direction by the Engineer-in-charge. The rates are inclusive of royalty, Malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	94.00	sq.m	800.00	Rupees Eight hundred only	75200
3	Providing and laying mechanically mixed and vibrated concrete for plain reinforced concrete in open foundation for all type structure complete of reinforced cement concrete grade M-20 (Twenty) nominal mix 1:2:4 (One cement, two sand, four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.88	cum	4500.00	Rupees four thousand five hundred only	8460
				Total:		99170
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note: Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

27

Schedule of quantity

Name of work:- C/O link road from House of Champa devi Rd. 0/00 to 1/200 (Deposit work)

		Estimated Cost: Rs		₹ 99,365		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.10	Cum.	160.00	Rupees One Hundred Sixty Only	1137
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.49	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	94017
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment . wing wall return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204, 3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.00	nos	160.00	Rupees One Hundred Sixty Only	2080
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204, 3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.74	Cum.	450.00	Rupees Four Hundred Fifty Only	2131
					Total	99365
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.K)

Schedule of quantity

Name of work :- R/O Restoration work of rain damages on link road from Pithoyana toba to field of Jagir Singh G.P. Pubowal Tehsil Haroli Distt Una (HP)		Estimated Cost: Rs		₹ 94,951		
(Sh: C/O CC Pavement & v-shape drain at rd. 0/032.20 to 0/048.30).		Time:-		One month		
DESCRIPTION		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1 including carriage of material within all leads. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	59.17	Cum	150.00	Rupees One Hundred Fifty Only	8875
2	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of material within all leads. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.04	Cum	160.00	Rupees One Hundred Sixty Only	2087
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803,1202 & 1203. P.C.C grade M 10 Nominal Mix 1 : 3 : 6 including carriage of material within all leads. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.30	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	12705
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803,1202 & 1203 P.C.C grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.64	Cum	3300.00	Rupees Three Thousand Three Hundred Only	18596
5	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of material within all leads. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.64	cum	1100.00	Rupees One Thousand One Hundred Only	6199
6	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802.803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer-in-charge, including carriage of material within all leads. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.45	cum	5500.00	Rupees Five Thousand Five Hundred Only	46489
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total		94951
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)(A)(3)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

Name of work: -Restoration of rain damages on 1)Old saloh Bihadouri road Km. 0/00 to 9/600, (2) link road Jaijon More to Saloh Chowk km. 0/00 to 1/040 & (3) link road to Village Bhoogarh kn. 0/00 to 2/600.		Estimated Cost: Rs	₹ 99,200			
		Time:-	One month			
(SI: Deploymet of excavator Cum Loader & Tractor for Treming of Access soil in berm, Removal of slips & C/O unilind drain etc. in rainy season etc.)		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deploymet of Hudraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi. royalty,malkhana ,toll tax,GST.labour cess or other taxes imposed by the Government.	72.00	P/ Hour	1100.00	Rupees One Thousand One Hundred Only	79200
2	Hiring of Tractor with Trolley 3.00cum. capacity to be deployed for disposing/carring of material like earth,kankar moorum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi. royalty,malkhana ,toll tax,GST.labour cess or other taxes imposed by the Government.	8.00	P/day	2500.00	Rupees Two Thousand Five Hundred Only	20000
Total						99200
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020.1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						

30

DRAFT SCHEDULE OF QUANTITY									
		Estimated Cost			99110				
		Earnest Money			2000/-				
		Time limit			One month				
S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT			
				Figures	Words				
Name of work :C/O Link road Nagnoli to SC Basti Chaperian Gour Bagirian Chotti Khad Gujran Tarkhana Nainan Mohalla (SH: C/o CC pavement RD 0/157.50 to 0/179 approach road to Baba Sidhcharno Temple)- Deposit work									
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, maikana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.60	Per cubic metre	3300.00	Rupees three thousand three hundred only	26380			
3	Providing and laying reinforcement concrete work of grade M-25 (M-twenty five) with minimum cement content of 400 kg (Four hundred kilogramme) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in open foundation including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, maikana , toll tax, GST, labour cess or other taxes imposed by the Government.	12.86	Per cubic metre	5500.00	Rupees Five thousand five hundred only	70730			
						Total:	99110		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt of HP vide letter No. PBW(B)A(17)/20212 dated 7.8.2018									
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt of HP vide letter No. PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021									

Executive Engineer
Haroli Division
HP, PWD., Haroli

121


31

SCHEDULE OF QUANTITY

Estimates cost:- 99591
 Earnest Money:- Rs. 2000/-
 Time Limit:- One Month.

Name of work :- Restoration of rain damage on link road Panjawat Bathri road Km 0/00 to 3/00 (SH: C/O 1' shape drain at RD 4/670 to 4/687-RIIS)


S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	20.40	Per Cubic metre.	160.00	Rupees one hundred sixty only	3264
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water ground complete including pumping or baling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate	5.10	Per Cubic metre.	3300.00	Rupees three thousand three hundred only	16830
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water ground complete including pumping or baling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate	15.82	Per Cubic metre.	3850.00	Rupees three thousand eight hundred fifty only	60907
4	Providing and laying (M-25) (M-twenty five) Grade mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi,	1.10	Per cubic metre	5500.00	Rupees five thousand five hundred only	6050
5	Providing and laying mild steel medium tensile steel bars for steel (approved make) reinforcement for reinforced cement concrete work including bending, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST labour cess or other taxes imposed by the Government	132.000	Per Kg	95.00	Rupees ninety five only	12540
	Total					99591
Note:-	1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)/20212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(3)/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					


Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)

171

Schedule of quantity

Name of work: -Upgradation of link road Umralli Dhillwan Heeran- Thara Pubowal to Polian Via Kuthar Beet from 0/00 to 3/400.		Estimated Cost: Rs	₹ 99,390			
		Time:-	One month			
(SH: Felling of trees & removing the roots in B/W Rd. 0/050 to 2/450).		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. Beyond 30 cm girth upto and including 60 cm girth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	80.00	Each	204.00	Rupees Two Hundred Four Only	16320
2	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	142.00	Each	585.00	Rupees Five Hundred EightyFive Only	83070
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					Total	99390
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)

281

SCHEDULE OF QUANTITY

Estimated Cost 99568
 Earnest Money 2000/-
 Time limit One month

Name of work : C/O Harijan basti Khad to Khas Khad (SH: C/O Cement Concrete pavement - phase -I)- Deposit work

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	18.40	Per cubic metre	160.00	Rupees One hundred SIXTY only	2944
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	10.98	Per cubic metre	3300.00	Rupees three thousand three hundred only	36234
3	Providing and laying (M-25) (M-twenty five) Grade mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205 4 and 1205 5, as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government	10.98	Per cubic metre	5500.00	Rupees five thousand five hundred only	60390
Total:						99568
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)@1712/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No PBW(B)@1712/0212 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

117


DARFT SCHEDULE OF QUANTITY

		Estimated Cost		99349/-	
		Earnest Money		2000/-	
		Time limit		One month	
Sl. No.	Description of work	Quantity	Unit	RATE IN	
				Figures	Words
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.00	Per cubic metre	160.00	Rupees One hundred sixty only
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1 : 4 : 8 (One cement four sand eight graded crushed /broken stone aggregate #0mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	28.20	Per cubic metre	3300.00	Rupees three thousand three hundred only
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v): 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause B 14 709, 1204 3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	9.00	Each	160.00	Rupees One hundred sixty only
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3 8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana toll tax GST, labour cess or other taxes imposed by the Government.	6.78	Per cubic metre	550.00	Rupees five hundred fifty only
				Total:	
				99349	
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(31)/2020 dated 22.07.20					
Percentage quoted rate in Figures					
Percentage quoted rate in words					
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					


 Executive Engineer,
 H.P.P.W.D. Divising Haroli
 Distt. Una (H.P.)

Draft Schedule of quantity

Name of work: -Restoration of rain damages on various road under section Ghaluwal Sub-Division Haroli.		Estimated Cost: Rs	₹ 98,100			
		Time:-	One month			
(SH: Deploymet of excavator Cum Loader & Trector for Treming of Access soil in berm Removal of slips & C/O unlined drain etc. in rainy season etc.)		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deploymet of Hudraulic excavator (0.90) cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	71.00	P/ Hour	1100.00	Rupees One Thousand One Hundred Only	78100
2	Hiring of Trector with Trolley 3.00cum. capacity to be deployed for disposing/carring of material like earth kankar mootum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	P/day	2500.00	Rupees Two Thousand Five Hundred Only	20000
					Total	98100
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note :-Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						


Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

134

SCHEDULE OF QUANTITY							Estimated Cost	99550/-
Restoration of rain damages on various roads in Pandoga section under Khad sub division HPPWD Division Haroli, Phase-II)							Earnest Money	2000/-
(SH:- Hiring of excavator Cum Loader for Treiming of Access soil in berm, removal of slips & C/O Unlined drain in rainy season).							Time limit	Two month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Deployment of Hydraulic excavator 0.90 cum filed with rock breaker on through rate basis for making drain and side cuttings in hard rock (where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor	90.50	Per Hour	1100.00	Rupees One thousand one hundred only	99550		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)20212 dated 7.8.2018				Total:	99550		
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
	Percentage quoted rate in Figures							
	Percentage quoted rate in words							
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

729

SCHEDULE OF QUANTITY

Estimated Cost 98981
 Earnest Money 2000/-
 Time limit One month

Name of work: C/O link road to Harijan Basti Dulehar (SH : C/O Biwall RD 0/636 to 0/664-60- RHS)- Deposit work

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and raiming of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty maikhana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	25.74	Per cubic metre	160.00	Rupees One hundred sixty only	4118
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty millimeter) nominal size in or under water/ round complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty maikhana , toll tax GST, labour cess or other taxes imposed by the Government.	28.31	Per cubic metre	3300.00	Rupees three thousand three hundred only	93423
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) (one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 6.14. 709. 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty maikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	9.00	Each	160.00	Rupees One hundred sixty only	1440
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)(17)/2012 dated 7.8.2018				Total:	98981
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(31)/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

180

40


Schedule of quantity

Name of work:- C/O link road from House of Champa devi Rd. 0/00 to 1/200 (Deposit work)		Estimated Cost: Rs		₹ 98,703		
[SH: C/O Retaining wall at Rd. 1/165 to 1/169,80 Rhs and approach road CC Rd. 0/163 Rhs]		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lit upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.61	Cum.	160.00	Rupees One Hundred Sixty Only	737
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203 P.C.C. grade M20 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	22.38	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	73854
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204,3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	nos	160.00	Rupees One Hundred Sixty Only	1280
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.07	Cum.	450.00	Rupees Four Hundred Fifty Only	1382
5	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer-in-charge, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.90	Cum.	5500.00	Rupees Five Thousand Five Hundred Only	21450
				Total		98703
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p>						
<p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work :- R/o Restoration work of rain damages on link road from Pithoyana toba to field of Jagir Singh G.P. Pubowal Tehsil Haroli Distt Una (HP)		Estimated Cost: Rs		₹ 94,439		
(Sh: C/O CC Pavement & v-shape drain at rd. 0/048.30 to 0/064.30)		Time:-		One month		
DESCRIPTION		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1 including carriage of material within all leads. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	58.80	Cum	150.00	Rupees One Hundred Fifty Only	8820
2	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas exceeding 30 cm in depth 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge including carriage of material within all leads. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.96	Cum	160.00	Rupees One Hundred Sixty Only	2074
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803.1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6 including carriage of material within all leads. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.30	Cum	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	12705
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803.1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.60	Cum	3300.00	Rupees Three Thousand Three Hundred Only	18480
5	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401 including carriage of material within all leads. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.60	cum	1100.00	Rupees One Thousand One Hundred Only	6160
6	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802.803.1202 & 1203. M 25 Nominal Mix 1 : 1.5:3 and as per Direction of Engineer-in-charge, including carriage of material within all leads. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.40	cum	5500.00	Rupees Five Thousand Five Hundred Only	46200
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total		94439
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note:-Rate quoted in Figures & words are mandatory by the contractor, other wise the tender will be rejected						


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

Name of work: -Upgradation of link road Umralli Dhillwan Heeran- Thara Pubowal to Polian Via Kuthar Beet from 0/00 to 3/400.		Estimated Cost: Rs	₹ 99,408			
(SH: Dismantling of old Culverts toe wall, R/wall, Edge wall of Drain included bed etc. from Km. 1/282 to 1/752).		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deployment of Hydraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(wher blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty.malkhana .toll tax.GST.labour cess or other taxes imposed by the Government..	124.26	Cum	800.00	Rupees Eight Hundred Only	99408
					Total	99408
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)(3)1/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

228

43

Draft Schedule of quantity

		Estimated Cost: Rs		₹ 98,100		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deployment of Hydraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock (where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	71.00	P/ Hour	1100.00	Rupees One Thousand One Hundred Only	78100
2	Hiring of Tractor with Trolley 3.00 cum. capacity to be deployed for disposing/carrying of material like earth kankar moorum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	8.00	P/day	2500.00	Rupees Two Thousand Five Hundred Only	20000
				Total		98100
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						

UW

Schedule of quantity

Name of work:- Balance work for the C/O Community Park, Outdoor open gym at ward no. 2 & 4 G.P. Dulehar Tehsil Haroli Distt Una							Estimated Cost: Rs
HP. (Deposit work)							One month
Sft: Hill side cutting for extended portion of park Rd. 0/008 to 0/012 }							Time:-
EARNEST MONEY:-							2000
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount	
1	Earth work in excavation in hilly area in all heights and depths and in all kind of soil by mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer in- Charge at site according to the M.S.D. technical specification 2014 clause 302, 303, in association with other clauses, including carriage of materials within all leads and lifts and other incidental. The rate includes site tax octroi, royalty, malkhana, toll, GST, labour cess or other taxes imposed by the Government.	690.00	Cum.	140.00	Rupees One Hundred Fourty Only	96600	
Note 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. P.BW (S) (17) Z/02012 dated 07.08.2018					Total	96600	
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. to the Govt. of HP vide letter no. PBW (S) (17) Z/02012 Dated 12.07.2020 & Govt. of HP vide letter no. PBW (S) (17) Z/02012 Dated 07.08.2018							
Percentage quoted rate in figures							
Percentage quoted rate in words							
Note -Rate: quoted in figures & words are mandatory by the contractor, other wise the tenders will be rejected							

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work: -Restoration of rain damages on 1) Link road to Co-Operative society Haroli via GSSS Haroli K.M. 0/00 to 2/225, (2) Construction road from Upper Karampur to Swan Border Km. 0.000 to 2.650 & (3) Old Haroli Road Gugga Mandir upto Pajjal Yojan Haroli 0/000 to 2/240		Estimated Cost: Rs	₹ 99,200			
(SH: Deployment of excavator Cum Loader & Tractor for Treminj of Access soil in berm; Removal of slips & C/O unlined drain etc. in rainy season etc.)		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deployment of Hydraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock/where blasting is prohibited) as per direction of the Engineer in charge i/e all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	72.00	P/ Hour	1100.00	Rupees One Thousand One Hundred Only	79200
2	Hiring of Tractor with Trolley 3.00cum. capacity to be deployed for disposing/carrying of material like earth kankar moorum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	8.00	P/day	2500.00	Rupees Two Thousand Five Hundred Only	20000
					Total	99200
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B/A)(3)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)(3)/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						
Executive Engineer, H.P.W.D. Division Haroli Distt. Una (H.F.)						

46

Schedule of quantity

Name of work: -Upgradation of link road Umralli Dhilwan Heeran- Thara Pubowal to Polian Via Kuthar Beet from 0/00 to 3/400.		Estimated Cost: Rs		Time:-		One month		
S.NO		DESCRIPTION		Qty	Unit	T.Rate	Rate in words	Amount
1		Deployment of Hydraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(wher blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana toll tax,GST,labour cess or other taxes imposed by the Government..		124.55	Cum	800.00	Rupees Eight Hundred Only	99640
		Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					Total	99640
		2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
		Percentage quoted rate in figures						
		Percentage quoted rate in words						
		Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

2024

SCHEDULE OF QUANTITY

Estimated cost 99607
Earnest money 2000
Time limit One month

Name of Work: Restoration of rain damage on link road from Upper Karampur to Swan Border Km 0/00 to 2/650 (SH:- C/O C.C. pavement RD 0/671.30 to 0/682.60)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Loosening of ground upto a level of 300mm (Three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300 1 and 300 2 with power Road Roller 8-10 Tonne capacity for sub grade construction as per M O R D. Technical specification-2014 section 300 of rural roads Cluse 303 5 2. The rate shall include carriage of machineries, equipment, tools and materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate includes sale tax octroi, royalty, malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	25.56	Per cubic metre	47.00	Rupees forty seven only	1201
2	Providing and laying cement concrete 1:4:8 (one cement four sand eight graded crushed stone aggregate 40mm(forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	8.52	Per cubic metre	3300.00	Rupees Three thousand three hundred only	28116
3	Providing and laying (M:25) (M-twenty five)Grade mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard design mix of with cement contents not less than 400kg.(four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	12.78	Per cubic metre	5500.00	Rupees five thousand five hundred only	70290
				G.Total		99607
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy,PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						


 Executive Engineer
 Haroli Division
 HP.PWD.,Haroli

518


Schedule of quantity

Name of work:- Balance work for the C/O Community Park, Outdoor open gym at ward no. 2 & 4 G.P. Dulehar Tehsil Haroli Distt Una		Estimated Cost: Rs				
HP. (Deposit work)		Time:-				
(S.M. Hill side cutting for extended portion of park Rd. 0/004 to 0/008)		Earnest Money:-				
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation in hilly area in all heights and depths and in all kind of soil by mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging, out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D technical specification 2014 clause 30Z, 1603 in association with other clauses including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	695.00	Cum.	140.00	Rupees One Hundred Fourty Only	97300
					Total	97300
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work: -Upgradation of link road Umraii Dhillwan Heeran- Thara Pubowal to Polian Via Kuthar Beet from 0/00 to 3/400.		Estimated Cost: RS		₹ 99,874		
		Time:-		One month		
(SH: Dismantling of old Culverts toe wall, R/wall, Edge wall of Drain included bed etc. from Km. 1/630 to 2/375).		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deployment of Hydraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of L-tubricant diesel etc. operator will be borne by the contractor.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi. royalty,malkhana .toll tax,GST,labour cess or other taxes imposed by the Government..	124.84	Cum	800.00	Rupees Eight Hundred Only	99874
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	99874
	2) The bidder are requested to submit there bid as per notification Issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

229

50

SCHEDULE OF QUANTITY

Estimated cost 99497
Earnest money 2000
Time limit One month

Name of Work: Restoration of rain damage on link road from Upper Karampur to Swan Border Km 0/00 to 2/650 (SH:- C/O C. C. pavement at RD 0/650 to 0/671.30)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Loosening of ground upto a level of 300mm (Three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power Road Roller 8-10 Tonne capacity for sub grade construction as per M.O.R.D. technical specification-2014 section 300 of rural roads Clause 303.5.2. The rate shall include carriage of machineries, equipment, tools and materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	25.56	Per cubic metre	47.00	Rupees forty seven only	1201
2	Providing and laying cement concrete 1:4:8 (one cement four sand eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.52	Per cubic metre	3300.00	Rupees Three thousand three hundred only	28116
3	Providing and laying (M-25) (M-twenty five) Grade mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORJ 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.76	Per cubic metre	5500.00	Rupees five thousand five hundred only	70180
				G.Total		99497
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, P.W to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						

Executive Engineer
Haroli Division
HP, PWD, (R&B)

232

SCHEDULE OF QUANTITY

Estimated cost 99630
Earnest money 2000
Time limit One month

Name of Work: C/O link road to Harijan Basti Panjwar (SH.- C/O C.C. pavement at RD 0/279.50 to 0/289). Deposit work

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, Malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.66	Per cubic metre	160.00	Rupees one hundred sixty only	426
2	Excavation in hilly area in all heights and depths and in all kind of soil by ordinary rock, hard rock, chieseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MCRD technical specification clause 302, 1603.1 and 1603.2 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.60	Per cubic metre	145.00	Rupees One hundred forty five only	1392
3	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount, appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -1 material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.40	Per cubic metre	1100.00	Rupees one thousand one hundred only	10340
4	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, Malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.24	Per cubic metre	3300.00	Rupees Three thousand three hundred only	33792
5	Providing and laying (M:25) (M twenty five) Grade mechanically mixed and vibrated concrete for plain reinforced concrete in open foundation/ for all type structure complete of reinforced concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.76	Per cubic metre	5500.00	Rupees five thousand five hundred only	53680
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)/20212 dated 7.8.2018						99630
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3)/1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work: -Upgradation of link road Umrali Dhilwan Heeran- Thara Pubowal to Polian Via Kuthar Beet from 0/00 to 3/400.		Estimated Cost: Rs		₹ 97,012		
		Time:-		One month		
(SH: Dismantling of old 1.50 mtr span slab culvert at Rd. 0/880,1/050 toe wall at Rd. 2/375 to 2/425 Rhs)		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deployment of Hydraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(wher blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant (diesel) etc. operator will be borne by the contractor.including carriage of materials within all leads and lifts and other incidental . The rate includes site tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	121.26	Cum	800.00	Rupees Eight Hundred Only	97012
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	97012
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)


230