



OFFICE OF
Executive Engineer Jaishingpur Division HPPWD Jaishingpur Himachal Pradesh Works
Department Jaishingpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide
this office letter No. PWD/JSD/TA/NIT/ 2025-26- 4221-30 dated 26/08/2025

Executive Engineer
Jaishingpur Division
HPPWD Jaishingpur.

OFFICE OF

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department Jaisinghpur
176095 Phone No. 01894-228030 Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **01.09.2025 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **30.08.2025 up to 4:00 PM** and the application for issue of tender form shall be received on **29.08.2025 up to 11.30 AM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.


The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain damages on various roads under Jaisinghpur Section (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Jaisinghpur Section)	99000.00	2000.00	Two Month	350/-
2	Restoration of rain damages on Ropri to Harot road Km 0/00 to 6/00 (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms) DC Deposit SDF/2025/592	99000.00	2000.00	Two Month	350/-
3	Restoration of rain damages on Alampur to Harsipattan road Km 8/00 to 17/00 (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms) DC Deposit SDF/2025/593	99000.00	2000.00	Two Month	350/-
4	Restoration of rain damages on various roads under Panchrukhi Sub Division (SH:- Removal of slips under Jalag Section)	99761.00	2000.00	One Month	350/-
5	Restoration of rain damages on Gander to Siara Kuhdana road km 0/00 to 9/780 (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms) DC Deposit SDF/2025/589	99110.00	2000.00	Two Month	350/-
6	Restoration of rain damages on various roads under Balakrupi Sub Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Alampur Section)	99550.00	2000.00	Two Month	350/-
7	Restoration of rain damages on various roads under Jaisinghpur Sub Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Lambagoan Section)	99400.00	2000.00	Two Month	350/-
8	Restoration of rain damages on Khera Bhulla to Praga Da Gallu Road Km 0/00 to 16/330 (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms) DC Deposit SDF/2025/590	99110.00	2000.00	Two Month	350/-
9	Restoration of rain damages on Bheri Bhallunder Dali Kuhan Oach road Km 0/00 to 10/250 (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms) DC Deposit SDF/2025/591	99550.00	2000.00	Two Month	350/-
10	Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Alampur Section)	99550.00	2000.00	Two Month	350/-
11	A/R & M/O link road from Gander to Kudana road Km 0/00 to 8/688 (Portion 5/00 to 8/688) Tehsil jaisinghpur Distt. Kangra (HP) under Balakrupi Sub Division) (SH:- Preparation of forest Diversion case under FCA, 1980)	52222.00	2000.00	Two Month	350/-
12	Restoration of rain damages on Link road to village Alung Km 0/00 to 0/750 (SH:- P/L 60 mm Thick interlocking paver blocks Km 0/00 to 0/030)	99991.00	2000.00	Two Month	350/-
13	C/O road from main road Dalli to SC Basti Kuhan Ward No.5 Km 0/00 to 1/100 (SH:- F/C of road at RD 0/00 to 0/120) (BSP/2024/26)	99745.00	2000.00	Two Month	350/-
14	Restoration of rain damages on Gander to Karonthi road Km 0/00 to 3/500 (SH:- P/L Interlocking paver block tiles for raising of portion at RD 0/284 to 0/298.10)	99693.00	2000.00	Two Month	350/-

15	Restoration of rain Damages on Bhuana Ashapuri road Km 0/00 to 12/300 (SH:- C/O R/wall from RD 1/314.50 to 1/319 along with Kuhl 1/310 to 1/312)	99923.00	2000.00	Two Month	350/-
16	Restoration of rain damages on Jalag dali Nahalna Dhupkiara Jhunga Devi road Km 0/00 to 10/250 (SH:- C/O Breast wall at RD 0/225 to 0/234.30)	99603.00	2000.00	Two Month	350/-
17	Restoration of rain damages on Panchrukhi Lambagoan road Km 10/00 to 22/00 (SH:- C/O R/wall at RD 14/068.65 to 14/073.20) DC Deposit SDF/2025/597	99856.00	2000.00	Two Month	350/-
18	Restoration of rain damages on Tinbar Jaisinghpur road Km 0/00 to 18/300 (SH:-C/O Edge wall/R/wall at Rd 0/210 to 0/220)	99590.00		Two Month	350/-
19	Restoration of rain damages on Bahroo to Nadli road Km 0/00 to 5/000 (SH:- C/O Toe wall of damaged Hume pipe Culvert alongwith wing wall at Km 1/355)	99754.00	2000.00	Two Month	350/-
20	C/O road from main road Dalli to SC Basti kuhan Ward No.5 Km 0/00 to 1/100 (SH:- F/C of road at Rd 0/120 to 0/210) (BSP/2024/26)	99740.00	2000.00	Two Month	350/-
21	A/R & M/O various roads under Panchrukhi Sub Division (Section Panchrukhi) (SH:- Painting, lettering of Kms stones and sign boards ect.)	99826.00	2000.00	Two Month	350/-
22	Restoration of rain damages on Gander to karonthi road Km 0/00 to 3/500 (SH:- P/L Interlocking paver block tiles for raising of portion at RD 0/270 to 0/283.50)	99485.00	2000.00	Two Month	350/-
23	Restoration of rain Damages on Bhuana Ashapuri road Km 0/00 to 12/300 (SH:- C/O Edge wall for Kuhl 1/312 to 1/322)	70754.00	5400.00	Two Month	350/-

Terms & conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST,EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

On behalf of Governor of Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26-

4221-30

Dated: 26/08/2025

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineer under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on various roads under Jaisinghpur Section (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Jaisinghpur Section)

Estimated cost Rs.	99000.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99000.00
	Total					99000.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Ropri to Harot road Km 0/00 to 6/00 (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms) DC Deposit SDF/2025/592

Estimated cost Rs.	99000.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99000.00
	Total					99000.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Alampur to Harsipattan road Km 8/00 to 17/00 (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms) DC Deposit SDF/2025/593

Estimated cost Rs.	99000.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99000.00
	Total					99000.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
H.P.PWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain damages on various roads under Panchrukhi Sub-Division (SH:- Removal of slips under Jalag Section)				Estimated cost Rs.		99761.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000 metre as per technical specification 302.3.5 and 1611 (One hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing as per the direction of Engineer-in-Charge within all lifts and other lifts and other incidentals. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	890.72	112.00	Rupees One Hundred Twelve Only	Per cubic metre.	99761.00
	Total					99761.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Gander to Siara Kuhdana road km 0/00 to 9/780 (SH:-
Hiring of JCB /Excavator for removal of slips and clearing of berms) DC Deposit SDF/2025/589

Estimated cost Rs.	99110.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Enginer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	90.10	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99110.00
	Total					99110.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer.
Jaisinghpur Division.
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Alampur Section)

Estimated cost Rs.		99550.00	
Earnest Money Rs.		2000.00	
Time Limit		Two Month	
Rate		Unit	Amount
s	In Word		
	Rupees One Thousand One Hundred Only	Per Hour	99550.00
			99550.00
		%	
		%	

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Jaisinghpur Sub-Division (SH:-
Hiring of JCB /Excavator for removal of slips and boulder of various road under Lambagoan Section)

Estimated cost Rs.	99400.00
Earnest Money Rs.	2000.00
Time	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	84.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	92400.00
2	Hiring of carriage Tipper for carriage of material such as Crusher and Sand labour and T & P stricals and other essential material from PWD store Jaisinghpur/quarry site to various roads Under Jaisinghpur Sub Division in HP.PWD. Jaisinghpur as directed by the Engineer-In-Charge. Any loss to the public private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for carriage vehicle also be borne by the contractor owner. The daily 70 Km per day running charges will be assuming and log book will also be maintained at site which should be verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per day basis	2.00	3500.00	Rupees Three Thousand Five Hundred Only	Per Day	7000.00
	Total					99400.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division.
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Khera Bhulla to Praga Da Gallu Road Km 0/00 to 16/330
(SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms) DC Deposit SDF/2025/590

Estimated cost Rs.	99110.00
Earnest Money Rs.	2000.00
mits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	90.10	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99110.00
	Total					99110.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Bheri Bhallunder Dali Kuhan Oach road Km 0/00 to 10/250 (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms) DC Deposit

Estimated cost Rs.	99550.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	90.50	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99550.00
	Total					99550.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division.
H.P.WD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under B. lakrupi Sub-Division (SH:- Hiring of JCB / ~~Excavator for Removal~~ of slips and boulder of various ~~Road under~~ ~~Area~~ Section)

Estimated cost Rs.	99550.00
Earnings ~~cost~~ Rs.	2000.00
Time Limits	h

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	90.50	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99550.00
	Total					99550.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP, PWD Jaisinghpur

SCHEDULE OF QUANTITY

77

SCHEDULE OF QUANTITY						
Name of work :-A/R & M/O link road from Cander to Kudana road Km 0/00 to 8/688 (Portion 5/00 to 88) Tensil jaisinghpur Distt. Kangra (HP), under Galakrupi Sub Division) (SH:- Preparation of Forest Division case under FCA 1980)				Estimated cost Rs.		52222.00
				Earnest Money Rs.		2000.00
				Time Limit		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, Khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. Assistance to User Agency to procure DC Certificate for unavoidable and in-escapable and Certificate NFL for CA from Director Land Records, Shimla as per latest requirement of ministry of environment and forest conservation Govt. of India. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.688	14160.00	Kupees Fourteen Thousand One Hundred Sixty Only	Per kilometre	52222.00
	Total					52222.0
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Link road to village Alung Km 0/00 to 0/750 (SH:- P/L 60 mm Thick interlocking paver ~~blade~~ **kmqo** to 0/030)

Estimated cost Rs. 99235.00

Earnest Money Rs. 900.00

~~Time Limit~~

~~Two month~~

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) nominal size Grading-III to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.18 cum(zero point one eight cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the by the Government.	0.68	2000.00	Rupees Two Thousand Only	Per cubic Metre	1360.00
2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.26	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per Cubic Metre	7875.00

3	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre), as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	90.00	1000.00	Rupees One Thousand Only	Per square metre	90000.00
	Total					99235.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer.
Jaisinghpur Division.
HP/PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O road from main road Dalli to SC basti kuhan Ward No.5 Km 0/00 to 1/100 (SH:-F/C of road at Rd 0/00 to 3/120) (BSP/2024/26)

Estimated cost Rs.	99745.00
Earnest Money Rs.	2000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil. complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 28.92 (twenty eight cubic decimal nine two) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax. GST or other taxes imposed by the Government.	578.23	172.50	Rupees One Hundred Seventy Two And Paise Fifty Only	Per cubic metre	99745.00
	Total					99745.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Gander to karonthi road Km 0/00 to 3/500 (SH:- P/L Interlocking paver block tiles for raising of portion at RD 0/284 to 0/298.10)

Estimated cost Rs.	99693.00
Earnest Money Rs.	2000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			in figures	In Word		
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. for grading-I material and as per direction by the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	6.66	1500.00	Rupees One Thousand Five Hundred Only	Per cubic metre	9990.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.44	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic Metre	18204.00
3	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shell be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	44.42	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per square metre	59967.00

4	Providing and laying in position cement concrete of specified grade or reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand . four graded stone aggregate) 20 mm (twenty milimetre) nominal size includi" carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.86	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic Metre	11532.00
	Total					99693.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

15

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain Damages on Bhuana Ashapuri road Km 0/00 to 12/300 (SH:- C/O R/wall from RD 1/314.50 to 1/319 along with Kuhl 1/310 to 1/312)				Estimated cost Rs.		99923.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	21.02	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	80927.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	3.08	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	15246.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete. including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the	15.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	3750.00
	Total					99923.1
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Jalag dali Nahalna Dhupkiara Jhunga Devi road Km 0/00 to 10/250 (SH:- C/O Breast wall at RD 0/225 to 0/234.30)

Estimated cost Rs.	99603.00
Earnest Money Rs.	2000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17.39	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	3913.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.27	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	93440.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700.1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana. Octroi, toll tax, GST or any other taxes imposed by the	9.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	2250.00
	Total					99603.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Panchrukhi Lambagoan road Km 10/00 to 22/00 (SH:- C/O R/wall at RD 14/068.65 to 14/073.20) DC Deposit SDF/2025/597

Estimated cost Rs.	99856.00
Earnest Money Rs.	2000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.47	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	2356.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.64	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	92400.00

3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	3.00	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	2850.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the	9.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	2250.00
Total						99856.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Tinbar Jaisinghpur road Km 0/00 to 18/300 (SH:-C/O
Edge wall/R/wall at Rd 0/210 to 0/220)

Estimated cost Rs.	99590.00
Earnest Money Rs.	2000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	19.20	200.00	Rupees Two Hundred Only	Per Cubic Metre	3840.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	25.00	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	93750.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700.1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the	8.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	2000.00
	Total					99590.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer.
Jaisinghpur Division.
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Bahroo to Nadli road Km 0/00 to 5/000 (SH:- C/O Toe wall of damaged Hume pipe Culvert alongwith wing wall at Km 1/355)

Estimated cost Rs.	99754.00
Earnest Money Rs.	2000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.74	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	3542.00

2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ectera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	2.00	4650.00	Rupees Four Thousand Six Hundred Fifty Only	Per cubic metre	9300.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	3.00	5400.00	Rupees Five Thousand Four Hundred Only	Per cubic metre	16200.00
4	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	14.26	3700.00	Rupees Three Thousand Seven Hundred Only	Per Cubic Metre	52762.00

5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	9.60	750.00	Rupees Seven Hundred Fifty Only	Per cubic metre.	7200.00
6	Providing and laying (to level or slope) 900mm dia (nine hundred millimeter) diameter reinforced cement concrete pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101 and as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, toll tax , or other taxes imposed by the Government.	2.50	3800.00	Rupees Three Thousand Eight Hundred Only	Per Running metres	9500.00
7	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	1250.00
Total						99754.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

SCHEDULE OF QUANTITY

Name of work :-C/O road from main road Dalli to SC basti kuhan Ward No.5 Km 0/00 to 1/100 (SH:-F/C of road at Km 0/12 to 0/210) (BSP/2024/26)

Estimated cost Rs.	99740.00
Earnest Money Rs.	2000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figure	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual/mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil. complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 28.92 (twenty eight cubic decimal nine two) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	578.20	172.50	Rupees One Hundred Seventy Two And Paise Fifty Only	Per cubic metre	99740.00
	Total					99740.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-A/R & M/O various roads under Panchrukhi Sub Division (Section Panchrukhi) (SH:-
Painting, lettering of Kms stones and sign boards ect.)

Estimated cost Rs.	99826.00
Earnest Money Rs.	2000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
13	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint of Asian/ Nerolac brushing to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters with enamel paint of approval shade as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	58.50	70.00	Rupees Seventy Only	Per square metre	4095.00
2	Applying Painting two coats(excluding priming coat on new concrete masonry/plaster surfaces with readymixed paint brushing for use on floors to give an even shade including cleaning the surface of all dirt,dust and other foreign matter and sand papering as required. The rate includes octroi,royalty,Malkana,Tol tax, sale tax, GST or any other taxes imposed by the Government.	53.00	18.15	Rupees Eighteen And Paise Fifteen Only	Per Square metre	962.00
3	Writing letters of figures on any surface with synthetic enamel paint (other than white) (stop, comas, border, hyphens and like not to be measured and paid separately) in Indian letter/figure complete and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation with in all leads, lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	48850.00	1.94	Rupees One And Paise Ninety Four Only	Per letter per centimetre	94769.00
	Total					99826.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
H.P. PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Gander to karonthi road Km 0/00 to 3/500 (SH:- P/L Interlocking paver block tiles for raising of portion at RD 0/270 to 0/283.50)				Estimated cost Rs.		99485.00
				Earnest Money Rs.		20000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401, for grading-I material and as per direction by the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	6.68	1500.00	Rupees One Thousand Five Hundred Only	Per cubic metre	10020.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.46	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic Metre	18286.00
3	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	44.55	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per square metre	60143.00

4	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finish and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.78	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic Metre	11036.00
	Total					99485.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Bhuana Ashapuri road Km 0/00 to 12/300 (SH:- C/O Edge wall for Kuhl 1/312 to 1/322)

Estimated cost Rs.	70754.00
Earnest Money Rs.	2000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	13.93	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	68954.00
2	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700.1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.20	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	1800.00
	Total					70754.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
H.P.WD Jaisinghpur