

NOTICE INVITING TENDER


Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Division, HP: PWD, Kangra on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors/firms enlisted in HPPWD in the appropriate class for the work mentioned below on **02.09.2025 up to 11-00 A.M.** and will be opened on the same day at **11-30 A.M.** in the presence of intending contractors or their authorized representatives who may wish to be present. The tender forms can be obtained from this office on cash payment (non refundable) on **01.09.2025 up to 4.00 P.M.** The tender applications for issue of tender forms will be received in this office on **30.08.2025 up to 05.00 P.M.** The earnest money in shape FDR National Saving certificate/Saving Account/Time Deposit Account in any of the Post Office/National Bank in H.P. duly pledged in favour of Executive Engineer, HPPWD., Division, Kangra. The conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of tender form	Time Limit
1.	C/O link road from Salol to Damanbeda 0/00 to 2/00(SH- Preparation of Detailed Project Report)(Under NABARD)	54000/-	1100/-	350/-	Three Month
2.	Bridge Estimate of 24.75 mtr. Span Bridge Over Toorwali Khad at RD 0/390 on link road from Salol to Damanbeda)	99000/-	2000/-	350/-	Two Month
3.	C/O Community Bhawan/Mahila Mandal in ward No-04 Upperadhi Khoala Tehsil & Distt. Kangra(SH-C/O civil work)	83262/-	1700/-	350/-	Two Month
4.	C/O Community Bhawan/Mahila Mandal in ward No-04 Upperadhi Khoala Tehsil & Distt. Kangra(SH- C/O civil work)	66152/-	1400/-	350/-	Two Month
5.	Restoration of Rain Damages on various road under Lunj Sub Division(SH- Supplying and stacking of crushed stone aggregate 63mm to 45mm(G-II)	99988/-	2000/-	350/-	One Month
6.	C/O link road Jheerballah Via Shamshan Ghat to Bassi near Rait Salol road km. 0/00 to 1/00(SH- C/O Breast wall at RD 0/555)(Deposit work)	72772/-	1500/-	350/-	Two Month
7.	Repair & Maintenance of Combined Office Building at Kangra(SH- Plaster, Pre painted sheet, Roofing and Ride etc.(Deposit work)	89991/-	2000/-	350/-	One Month
8.	Repair & Maintenance of Combined Office Building at Kangra(SH- Cleaning of Gutter)(Deposit work)	92400/-	2000/-	350/-	One Month

Certified that tender of above works are being called of urgent nature in public interest.


TERMS & CONDITIONS:-

1. The contractors/firms should be produce the attested copy of latest enlistment and renewal enlisted in HPPWD, GST No. and EPF No. with the application failing which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The contractor/firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason


Executive Engineer,
HPPWD, Division, Kangra.
Distt. Kangra (H.P.)
(On behalf of Governor of Himachal Pradesh)

Endst:- No.PW/KD/CB/Tenders/2025-26-
Copy is forwarded to:-

1. The Computer Cell Office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Department website.
2. The Chief Engineer (KZ) HPPWD., Dharamshala for information please.
3. The Superintending Engineer, 5th Circle, HPPWD., Palampur for information please.
4. All the Assistant Engineer's working under Kangra Division.
5. NIT Register.
6. All Head of Branches.
7. Notice Board.


Executive Engineer,
HPPWD, Division, Kangra.
Distt. Kangra (H.P.)

2729-80

Dated:- 25/8/25

Schedule of Quantity

NAME OF WORK :- C/O LINK ROAD FROM SALOL TO DAMANBEDA 0/00 TO 2/000.SUB HEAD : PREPARATION OF DETAILED PROJECT REPORT (UNDER NABARD)				ESTIMATED COST:- EARNEST MONEY:- TIME LIMIT :-		54,000.00 1,100.00 THREE MONTHS
Sr. No.	Description of Items	Quantity	RATES		Unit	Amount
			In Fig	In Words		
1	2	3	4	5	7	
1	Preparation of Detailed Project report in shape of manuscript along with drawing which include the following provision as given below and drawing complete in all respect in manuscript from desired by the head office the same may be corrected as desired and directed by the Engineer-in-charge complete in all respect. (a) Topography survey by Digital Total station/Dual Frequency DGPS with two second Accuracy, Showing all offsets such as trees, culvert, bridge, electric poles, hand pumps, schools, habitants village etc. (b) Draw cross-section at 15 m (Fifteen meter) intervals, L-sections & calculate the quantity of earth work in standard format of Autocad showing all layers of Pavement components. (c) Preparation of survey plan showing all provision and preparation of detailed project report as per HPPWD specification and NABARD guidelines.	2.000 KMS	27,000.00	TWENTY SEVEN THOUSAND RS ONLY	Per Km	54,000.00
TOTAL						54,000.00

Excess = %

Less = %


 EXECUTIVE ENGINEER
 DIVISION KANGRA
 HPPWD KANGRA

Schedule of Quantity

NAME OF WORK:- BRIDGE ESTIMATE OF 24.75 MTR SPAN BRIDGE OVER TOORWALI KHAD AT RD 0/390 ON LINK ROAD FROM SALOL TO DAMANBEDA.					ESTIMATED COST:-	
					EARNEST MONEY:-	99,000.00
					TIME LIMIT :-	2,000.00
SUB HEAD : PREPARATION OF BRIDGE ESTIMATE (UNDER NABARD)					TWO MONTHS	
SR. NO.	DESCRIPTION OF ITEMS	NO./ QTY./ JOB	UNIT	ESTIMATED RATE (IN RS.)	ESTIMATED RATE IN WORDS	TOTAL AMOUNT INCLUSIVE OF ALL TAXES
1	2	3	4	5	6	7
1	PREPARATION OF BRIDGE ESTIMATE IN SHAPE OF MANUSCRIPT ALONG WITH DRAWING WHICH INCLUDE THE FOLLOWING PROVISIONS AS GIVEN BELOW :- AND DRAWING COMPLETE IN ALL RESPECT IN MANUSCRIPT FROM AND SUBMISSION OF THE SAME IN HIGHER OFFICE FOR APPROVAL IF ANY CORRECTION AMENDMENT HAS DESIRED BY THE HEAD OFFICE THE SAME MAY BE CORRECTED AS DESIRED AND DIRECTED BY ENGINEER-IN-CHARGE COMPLETE IN ALL RESPECT, AFTER APPROVAL THE SAME SHOULD BE SUBMITTED IN TWO NO. SET OF THE FAIR DPR AND DRAWING AGAIN IF ANY CORRECTION/AMENDMENT AS DESIRED BY HEAD OFFICES. THE RATES ARE INCLUSIVE OF ALL TAXES I.E. GST.	1.000	JOB	99,000.000	RUPEES NINETY NINE THOUSAND ONLY/-	99,000.000
					TOTAL	99,000.00

Excess = %

Less = %


EXECUTIVE ENGINEER
DIVISION KANGRA
HPPWD KANGRA

SCHEDULE OF QUANTITY

NAME OF WORK : CONSTRUCTION OF COMMUNITY BHAWAN/MAHILA MANDAL IN WARD NO-04 UPPERADH) KHOALA TEH.& DISTT. KANGRA.(SUB HEAD:- C/O CIVIL WORK.						
				(	Estimated Cost:-	83262.00
					Earnest Money:-	1700.00
					Time Limit:-	Two Month
Sr. No	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Earthwork in excavation for all type of road structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3 m depth The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, toll tax, sale tax or other taxes imposed by the Government.	22.53	Per Cubic metres	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	11022.00
2	Providing and laying cement concrete 1:4:8 (One Cement isto four Sand isto eight graded crushed stone aggregate 40 mm (forty milimetre) nominal size mechanically mixed and curing complete excluding the cost of form work. in foundation and Plinth, as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	5.92	Per Cubic metres	4955.20	Rupees Four Thousand Nine Hundred & Fifty Five - Paise Twenty Only	29335.00
3	Random rubble masonry coursed with hard stones of approved quality in foundation and plinth including raking out joints in cement mortar 1:6 (one cement is to six sand) as per specifications, approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	7.50	Per Cubic metres	5720.65	Rupees Five Thousand Seven Hundred & Twenty Paise Sixty Five Only	42905.00
		Total:				83262.00

EXCESS = %

LESS = %


 Executive Engineer,
 HPPWD Kangra
 Division Kangra

SCHEDULE OF QUANTITY


NAME OF WORK : CONSTRUCTION OF COMMUNITY BHAWAN/MAHILA MANDAL IN WARD NO-04 (UPPERADH) KHOALA TEH.& DISTT. KANGRA.(SUB HEAD:- C/O CIVIL WORK.							Estimated Cost:- Earnest Money:- Time Limit:-	66152.00 1400.00 Two Month
Sr. No	Description of work	Qty	Unit	In Figures	Rates		AMOUNT	
					In Words			
1	Random rubble masonry coursed with hard stones of approved quality in foundation and plinth including raking out joints in cement mortar 1:6 (one cement is to six sand) as per specifications, approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	7.74	Per Cubic metres	5720.65	Rupees Five Thousand Seven Hundred & Twenty Paise SIXTY Five Only		44278.00	
2	Square rubble masonry coursed with hard stones of approved quality in foundation and plinth including raking out joints in cement mortar 1:6 (one cement is to six sand) as per specifications, approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.95	Per Cubic metres	5720.65	Rupees Five Thousand Seven Hundred & Twenty Paise Sixty Five Only		16876.00	
3	Boulder filling dry hand packed tightly as in under floor The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. as per the direction of the Engineer - In-Charge including carriage of material with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the government.	3.50	Per Cubic metres	1428.00	Rupees One Thousand Four Hundred & Twenty Eight Only		4998.00	
	Total:						66152.00	

EXCESS =

0/0

LESS =

0/0


 Executive Engineer,
 HPPWD Kangra
 Division Kangra

SCHEDULE OF QUANTITY

NAME OF WORK :-RESTORATION RAIN DAMAGES ON VARIOUS ROAD UNDER LUNJ SUB
DIVISION(SH:- SUPPLYING AND STACKING OF CRUSHED STONE AGGREGATE 63MM TO
45MM (G-II)

Sr. No	Description of work	Qty	Unit	Rates		Time Limit:-	Estimated Cost:- Earnest Money:-	99988.00 2000/- One Month
				In Figures	In Words			
1	Supplying and stacking stone aggregate of specific size 63mm to 45mm (sixty three millimetre to forty five millimetre)Grading-G-II,75mm(seventy five millimetre) consolidated thick to water bound Macadam,specifications including spreading in uniform thickness using templates,hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade and camber applying and brooming stone screening type-A of size 13.2mm(thirteen point two millimetre) nominal size at the rate of 0.27 cum(Zero point two seven cubic metre) per ten square metre and binding material at the rate of 0.08 cum(zero point eight cubic metre) to fill to fill up the interstices of course, aggregate watering and compating to the required density as per MORD technical specifications clause No, 405 and as per the entire satisfaction and direction of Engineer-in-ChargeThe rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, toll tax, sale tax or other taxes imposed by the Government.	79.99	Per Cubic metres	1250.00	Rupees One Thousand Two Hundred & Fifty Only			99988.00
		Total:						99988.00

EXCESS = %

LESS = %


Executive Engineer,
HPPWD Kangra
Division Kangra


SCHEDULE OF QUANTITY.

NAME OF WORK:- CONSTRUCTION OF LINK ROAD JHEERBALLAH VAI SHAMSHAN GHAT TO BASSI NEAR RAIT SALOL ROAD
KM.0/00 TO 1/00(SUB HEAD:- CONSTRUCTION OF BREAST WALL AT RD 0/555) (DEPOSIT)

NAME OF WORK:- CONSTRUCTION OF LINK ROAD JHEERBALLAH VAI SHAMSHAN GHAT TO BASSI NEAR RAIT SALOL ROAD					Estimated Cost:-	72772.00
KM.0/00 TO 1/00(SUB HEAD:- CONSTRUCTION OF BREAST WALL AT RD 0/555) (DEPOSIT)					Earnest Money:-	1500/-
					Time Limit:-	Two Month
Description of work					Rates	AMOUNT
Sr. No.	Qty	Unit	In Figures	In Words		
1	3.90	Per Cubic metres	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only		1908.00
2	13.50	Per Cubic metres	4998.80	Rupees Four Thousand Nine Hundred & Ninety Eight - Paise Eighty Only		67484.00
3	8.00	Each	422.50	Rupees Four Hundred & Twenty Two - Paise Fifty Only		3380.00
				TOTAL		72772.00

EXCESS = %


LESS = %


Executive Engineer,
HPPWD Kangra
Division Kangra.

SCHEDULE OF QUANTITY						
Name of work :- Repair & Maintenance of Combind office building at Kangra .						
(Sh:- Plaster, Prepainted sheet , Roofing and Ridge etc. (Deposit work)						
Sr.No.	Sub-Head and items of work	Quantity	Unit	Estimate cost-		89991.00
				Figures	Rates in Words	2000.00
1	15 mm (Fifteen milimetre) thick cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering up to all floor level including arises, internal angles, chamfers and rounded angles any girth and finished even and smooth with cement mortar 1:6 (One cement isto Six sand) as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	198.00	Per/ Sq Metres	248.2	Rupees Two Hundred & Fourty Eight - Paise Twenty Only	49144.00
2	Providing and fixing 0.60 mm thick prepainted steel sheet TATA/Shakti or equivalent in roofing over steel trusses hot dip metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (TWENTY) microns over 5 (five) microns of primer back coat of polyester and 5 (five) microns coating fixed with J or L hooks bolts and nuts 8mm (eight millimeter) dia bitumen and GI limpet washer filled with required colour and laid completed as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental.	17.92	Per/Sqm	1250.00	Rupees One Thousand Two Hundred & Fifty Only	22400.00
3	Providing and fixing ridges or hips 60 cm overall with 0.60mm thick prepainted steel sheets in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts & nuts 6mm dia & prepainted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer in Charges.	20.50	Per/ R/ Mtr	899.85	Rupees Eight Hundred & Ninety Nine - Paise Eighty Five Only	18447.00
	total					89991.00

ESCESS = %


LESS = %


Executive Engineer
HP.PWD. Division
Kangra Division

SCHEDULE OF QUANTITY					
Name of work :- Repair & Maintenance of Combind office building at Kangra . Sh:- Cleaning of Gutter). (Deposit work)				Estimate cost-	
				(Earnest money- Time limit-	
Sr.N o.	Sub-Head and items of work	Quantity	Unit	Rates in	
				Figures	Words
1	Repair of RCC Gutter including claning and remove the deposit soil/ loose material as per specification, approved drawing, design, as per entire specification and direction of the Engineer-in- Charge including carriage of materials within all leads andlifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	264	Per/Runni ng metre	350.00	Rupees Three Hundred & Fifty Only
total					
					92400.00
					2000.00
					One month.
					Amount
					92400.00
					92400.00

ESCESS = %

LESS = %


Executive Engineer
HP.PWD. Division
Kangra Division