



OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811 E-MAIL:- cc-sol-hp@nic.com

No.PW-SD/CB-Tender/-2025-26- 7374-80

Dated:- 26/8/25


To

✓ The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID:-cc-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.


Executive Engineer,
B&R Division,
HP.PWD, Solan

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.

1
Executive Engineer,
B&R Division,
HP.PWD, Solan.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Exigency

Scaled item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD, Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act, 1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	01.09.2025	Upto 3.00 P.M.
2	The last date sale of tender forms.	02.09.2025	Upto 4.00 P.M.
3	The date for receipt of tender forms.	03.09.2025	Upto 10.30 P.M.
4	The date of opening of tender	03.09.2025	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 03.09.2025 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Time	Cost of Form
1	Annual repair and maintenance of Berti Manlog road km 0/0 to 4/0 (SH: Clearance of drains and trimming of grass at RD 2/0 to 4/0)	91500/-	2000/-	One Month	Rs.350/-
2	Annual repair and maintenance of officer colony road at Kotla Nallah Solan (SH: C/o PCC B/wall)	84077/-	1700/-	One Month	Rs.350/-
3	Annual repair and maintenance of Assistant Engineer residence at Oachghat (SH: Repair of septic tank and wooden paint)	98017/-	2000/-	One Month	Rs.350/-
4	Annual repair and maintenance of Assistant Engineer residence at Oachghat (SH: Providing and applying putty and distemping)	99472/-	2000/-	One Month	Rs.350/-
5	Annual repair and maintenance of chhaila Neripul Yashwant Nagar Oachghat Kumarhatti road km 62/00 to 75/375 (SH: Repair and laying patchwork at RD 72/160 to 72/180 & 73/300 to 73/360)	92970/-	2000/-	One Month	Rs.350/-
6	Annual repair and maintenance of chhaila Neripul Yashwant Nagar Oachghat Kumarhatti road km 62/00 to 75/375 (SH: Repair and laying Grade-III at RD 72/160 to 72/180 & 73/300 to 73/360)	98049/-	2000/-	One Month	Rs.350/-
7	Repair and maintenance of type-I Quarter set No. 1 near new bus stand Solan (SH: Painting and distemping work)	37146/-	800/-	One Month	Rs.350/-
8	A/R & M/O type-I quarter set No. 1 at tank road Solan (SH: Providing and fixing wood work, painting and distemping etc.)	72504/-	1500/-	One Month	Rs.350/-
9	Repair and maintenance Residential building LAO office HPPWD at Solan (SH: Providing and fixing teak wood wall paneling and other repair works)	96794/-	2000/-	One Month	Rs.350/-
10	Restoration of rain damages on HRTC workshop to Kather road km 0/0 to 2/0 (SH: Hiring of JCB for slip removal)	99750/-	2000/-	Two Month	Rs.350/-
11	Restoration of rain damages on Rajgarh bye pass road km 0/0 to 5/410 (SH: Hiring of JCB for slip removal)	99750/-	2000/-	One Month	Rs.350/-
12	Restoration of rain damages on Rajgarh bye pass road km 0/0 to 5/410 (SH: Hiring of tipper for slip removal)	96000/-	2000/-	Two Month	Rs.350/-
13	Restoration of rain damages on Rajgarh bye pass road km 0/0 to 5/410 (SH: Hiring of tipper for slip removal)	96000/-	2000/-	Two Month	Rs.350/-

14	Restoration of rain damages on Jatoli Garog road km 0/0 to 5/590 (SH: Hiring of tipper for slip removal)	96000/-	2000/-	Two Month	Rs.350/-
15	Restoration of rain damages on Galanag Matial road km 0/0 to 2/0 (SH: Hiring of tipper for slip removal)	96000/-	2000/-	Two Month	Rs.350/-
16	Restoration of rain damages on Galanag Matial road km 0/0 to 2/0 (SH: Hiring of tipper for slip removal)	96000/-	2000/-	Two Month	Rs.350/-
17	Restoration of rain damages on Jatoli Garog road km 0/0 to 5/590 (SH: Hiring of JCB for slip removal)	99750/-	2000/-	Two Month	Rs.350/-
18	Restoration of rain damages on Galanag Matial road km 0/0 to 2/0 (SH: Hiring of JCB for slip removal)	99750/-	2000/-	Two Month	Rs.350/-
19	Restoration of rain damages on various roads under Oachghat sub-division HPPWD Solan (SH: Hiring of tipper for slips removal)	96000/-	2000/-	Two Months	Rs.350/-
20	A/R & M/O to various roads under Jatoli section in Oachghat sub-division Solan (SH: Providing and supplying 10mm to 12.5mm stone aggregate)	99875/-	2000/-	15 days	Rs.350/-
21	R/R damages on various roads under Oachghat sub-division (SH: Hiring of excavator cum loader for removal of debris, slips in Gaura section)	98700/-	1000/-	One Month	Rs.350/-
22	R/R damages on various roads under Oachghat sub-division (SH: Hiring of excavator cum loader for removal of debris, slips in Jaunaji section) job-2	98700/-	2000/-	Two Months	Rs.350/-
23	R/R damages on various roads under Oachghat sub-division (SH: Hiring of excavator cum loader for removal of debris, slips in Jaunaji section) job-1	98700/-	2000/-	Two Months	Rs.350/-
24	Restoration of rain damages on HRTC workshop to Kather road km 0/0 to 2/0 (SH: Hiring of tipper for slip removal)	96000/-	2000/-	Two Month	Rs.350/-
25	R/R damages on various roads under Oachghat sub-division (SH: Hiring of excavator cum loader for removal of debris, slips in Jaunaji section) job-3	98700/-	2000/-	Two Month	Rs.350/-

TERMS & CONDITIONS:-

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.


Executive Engineer,
B&R Division,
HPPWD, Solan

Exigency Certificate

It is certified that the tenders which were invited vide this office NIT No.PW-SD/CB-Tender/20025-26-7374-80 Dated: 28-08-2015 are of emergent nature of work and in public interest.

Dated:-

Place:- Solan


Executive Engineer
B&R Division
HPPWD, Solan

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- (1)						
Name of Work :- Annual repair and maintenance of Bertu Manlog road Km.0/00 to 4/00 (SH: - Clearance of drains and trimming of grass at Rd.2/00 to 4/00)						
1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	2000.00	Per running meter	34.50	Rupees Thirty Four and Paise Fifty Only	69000.00
2	Trimming of grass and weeds from the shoulder / berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	10000.00	Per Square Meter	2.25	Rupees Two and Paise Twenty Five Only	22500.00
Total :-						91500.00
Rupees Ninety One Thousand Five Hundred Only						
Quoted Percentage rate upto Three Digits :-					(+) / (-)	

T/S No.57 for the 2025-26
Sr. No. 90 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Job No. :- 12

Estimated Cost :- 84077.00
 Earnest Money :- 1700.00
 Time limit :- One Month

Name of Work :- Annual repair and maintenance of Officer colony road at Kotla Nallah Solan (SH:- Construction of PCC Breast wall)

Sl. No.	Description of Work	Rate	Quantity	Amount	Total
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1.(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	15.00	Per Cubic Meter	392.00	Rupees Three Hundred Ninety Two Only
2	Providing and laying plain cement concrete Grade M- 10 (Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed hard stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed, vibrated and curing complete in open foundations including form work as per drawings and MORDTechnical Specifications Clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts, and other incidentals	14.52	Per Cubic Meter	5290.00	Rupees Five Thousand Two Hundred Ninety Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	6.00	Each	231.00	Rupees Two Hundred Thirty One Only
Total:-					
					84077.00
				Rupees Eighty Four Thousand Seventy Seven Only	
				(+) / (-)	

Quoted Percentage rate upto Three Digits :-

T/S No.100 for the 2025-26
 Sr. No.169 for the year 2025-26

Executive Engineer
 B&R Division, HP.PWD. Solan.

Schedule of Quantity

Job No. :- (3)

Estimated Cost :- 98017.00
 Earnest Money :- 2000.00
 Time limit :- One Month

Name of Work :- Annual repair and maintenance of Assistant Engineer residence at Oachghat (SH:- Repair of septic tank and wooden paint)

Sl. No.	Description of Work	Quantity	Unit	Rate	Amount
1	Brick work with common burnt clay machine moulded with F.P.S.(non modular) perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.	13.47	Per Cubic Meter	6820.00	Rupees Six Thousand Eight Hundred Twenty Only
2	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications painting wood work with deluxe multi surface paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	45.91	Per Square Meter	134.00	Rupees One Hundred Thirty Four Only
Total:-					98017.00
Quoted Percentage rate upto Three Digits :-					
(+) / (-)					
Rupees Ninety Eight Thousand Seventeen Only					

T/S No. 102 for the 2025-26
 Sr. No. 103 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Job No. :- 9

Estimated Cost :-	99472.00
Earnest Money :-	2000.00
Time limit :-	One Month

Name of Work :- Annual repair and maintenance of Assistant Engineer residence at Oachghat (SH:- Providing and applying putty and distempering)

	568.41	Per Square Meter	80.00	Rupees Eighty Only	
1 Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	568.41	Per Square Meter	80.00	Rupees Eighty Only	45473.00
2 Distempering One coat with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacturer, including applying additional coats wherever required, to achieve even shade and colour as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	568.41	Per Square Meter	95.00	Rupees Ninety Five Only	53999.00
Total:-					99472.00
Rupees Ninety Nine Thousand Four Hundred Seventy Two Only					

Quoted Percentage rate upto Three Digits :-

(+) / (-)

T/S No. 101 for the 2025-26

Sr. No. 167 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99472.00 only.

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 5						
Name of Work :- Annual repair and maintenance of Chhaila Neripul Yashwant Nagar Oacghat Kumarhatti road Km.62/00 to 75/375 (SH: - Repair and laying patchwork at Rd. 72/160 to 72/180 & 73/300 to 73/360)						
1	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg (zero point two five to zero point three kilogramme) per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lift and other incidental charges.	280.00	Per Square Meter	19.91	Rupees Nineteen and Paise Ninety One Only	5575.00
2	Providing and laying bituminous concrete 25mm (Twenty Five milimetres) thick with 100-120 (one hundred to one hundred twenty) TPH batch type hot mix plant producing an average output of 75 (seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.5 (five point five) per cent of total weight of mix, aggregate Grading II (thirteen milimetres nominal size) i.e. 13.2 - 10 mm thirty per cent, 10 - 5 mm twenty five per cent, 5 mm and below forty three per cent of volume of aggregate and filler @ 2 per cent of weight of aggregates, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 (five zero nine) complete in all respects and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all	7.00	Per Cubic Meter	12485.00	Rupees Twelve Thousand Four Hundred Eighty Five Only	87395.00
Total:-						92970.00
Quoted Percentage rate upto Three Digits :-						
				(+) / (-)		
				Rupees Ninety Two Thousand Nine Hundred Seventy Only		

T/S No. 106 for the 2025-26

Sr. No. 166 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
					Estimated Cost:-	98049.
					Earnest Money:-	2000
					Time limit :-	One Mo
Job No. :- 16						
Name of Work :- Annual repair and maintenance of Chhaila Neripul Yashwant Nagar Oacghat Kumarhatti road Km.62/00 to 75/375 (SH Repair and laying Grade-III at Rd. 72/160 to 72/180 & 73/300 to 73/360)						
1	Providing and laying, spreading by Mechanical means and compacting to 75mm (seventy five millimeters) compacted thickness stone aggregates of Grading- III, 53mm to 22.5 mm (fifty three millimeters to twenty two point five millimeters) size @ 0.91cum (point nine one cubic meters) per 10 (ten) square meters to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, stone screening of type B of size 11.2mm (eleven point two millimeters) @ 0.20 (point two zero) cubic meters per ten square meters to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per MORD Technical Specification Clause 405 (Four hundred five) and entire satisfaction & direction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	42.00	Per Cubic Meter	2334.50	Rupees Two Thousand Three Hundred Thirty Four and Paise Fifty Only	98049
Total:-						98049.0
				Rupees Ninety Eight Thousand Forty Nine On		
				(+) / (-)		
Quoted Percentage rate upto Three Digits :-						

T/S No. **105** for the 2025-26
Sr. No. **165** for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Job No. :- 7

Estimated Cost :- 37146.00

Earnest Money :- 800.00

Time limit :- One Month

Name of Work :- Repair and maintenance of Type-I quarter set No.1 near New Bus Stand at Solan (SH;- Painting and distemping work)

		114.35	Per Square Meter	116.70	Rupees One Hundred Sixteen and Paise Seventy Only	13345.00
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	114.35	Per Square Meter	48.00	Rupees Forty Eight Only	5489.00
2	Distemping One coat with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacturer, including applying additional coats wherever required, to achieve even shade and colour as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	114.35	Per square meter.	11.15	Rupees Eleven and Paise Fifteen Only	1275.00
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	43.260	Per Square Meter	79.45	Rupees Seventy Nine and Paise Forty Five Only	3437.00
5	Providing and placing on terrace (at all floor levels) 1000 litre Capacity polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank as per HP.PWD specification, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	1000.00	Per Liter	13.60	Rupees Thirteen and Paise Sixty Only	13600.00
Total:-						37146.00

Rupees Thirty Seven Thousand One Hundred Forty Six Only

(+) / (-)

Quoted Percentage rate upto Three Digits :-

T/S No.93 for the 2025-26

Sr. No. 164 for the year 2025-26

Executive Engineer
B&R-Division, HP.PWD. Solan.

Schedule of Quantity

Job No. :- (8)

Estimated Cost :- 72504.00

Earnest Money :- 1500.00

Time limit :- One Month

Name of Work :- A/R & M/O Type-I quareter set no.1 at tank road Solan (SH:- Providing and fixing wood work, painting and distempering etc.)

Sl. No.	Description of Work	Quantity	Unit	Rate	Amount	Estimated Cost
1	Providing wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position in Sal wood as per H.P.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	0.14	Per Cubic Meter	95763.05		13407.00
2	Providing and fixing 35 mm thick shutters Kiln seasoned and chemically treated hollock wood panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in charge.	5.460	Per Square Meter	1890.80		10324.00
3	Providing and fixing Second class teak wood wire gauge shutters using galvanized mild steel wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 for door, windows and clear story windows with hinges and necessary screws 35mm (thirty five millimeter) thick second class teak wood as per HP.PWD specification 1990 volume-I, including carriage of all labour equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	3.96	Per square meter.	3669.30		14530.00
4	Providing and fixing mild steel Tower bolts (barrel type) anodized transparent or dyed to required shade and color with screws etc. Complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.					
4.1	250*10(Two hundred fifty into Ten) millimeters size	4.000	Each	370.15		1481.00
4.2	200*10 (Two Hundred Fifty into Ten) millimeters size	16.000	Each	296.35		4742.00
5	Providing and fixing bright finished brass handles with screws etc. as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.					
5.1	125 mm (one hundred twenty five melimeter)	4.000	Each	202.55		810.00
5.2	100 mm (one hundred melimeter)	8.000	Each	187.35		1499.00

14160.00	Rupees Eighty Five and Paise Ten Only	85.10	Per Square Meter	166.39	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.
5283.00	Rupees Thirty One and Paise Seventy Five Only	31.75	Per Square Meter	166.39	Distemping One coat with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.
1855.00	Rupees Eleven and Paise Fifteen Only	11.15	Per square meter.	166.39	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.
4413.00	Rupees Ninety Four and Paise Thirty Only	94.30	Per Square Meter	46.80	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications painting wood work with deluxe multi surface paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.
72504.00					Total:-
					Rupees Seventy Two Thousand Five Hundred Four Only
					Quoted Percentage rate upto Three Digits :-

T/S No.287 for the 2023-24
Sr. No.163 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Job No. :- 9

Estimated Cost :- 96794.00

Earnest Money :- 2000.00

Time limit :- One Month

Name of Work :- Repair and maintenance Residential building LAO Office HPPWD at Solan (SH: - Providing and fixing teak wood wall paneling and other repair works)

		17.00	Per Square Meter	5369.91	Rupees Five Thousand Three Hundred Sixty Nine and Paise Ninety One Only	91288.00
1	Providing and fixing in position teak wood panelling in wall with plank size of 130mm x 25mm above the 12mm thick ply board including polish of approved quality as per direction of Engineer in charge and as per HPPWD specifications.	14.00	Per Square Meter	223.95	Rupees Two Hundred Twenty Three and Paise Ninety Five Only	3135.00
2	Providing and fixing chromium plated brass handles 125 mm (one hundred twenty five millimeter) with necessary screws etc. complete as per HP.PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges and as per direction of engineer in charge.	1.00	Each	962.75	Rupees Nine Hundred Sixty Two and Paise Seventy Five Only	963.00
3	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	10.00	Each	140.75	Rupees One Hundred Forty and Paise Seventy Five Only	1408.00
4	Providing and fixing magnetic catcher Double strip (horizontal type) of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete. as per HP.PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges and as per direction of engineer in charge.					
	Total:-					96794.00

Rupees Ninety Six Thousand Seven Hundred Ninety Four Only

Quoted Percentage rate upto Three Digits :-

(+) / (-)

T/S No.94 for the 2025-26

Sr. No. 162 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- (10) Name of work: - Restrotration of rain damages on HRTC work shop to kather road Km.0/00 to 2/00 (SH:- Hiring of JCB/ loader cum-excavator for removal of slips)						
1	Hiring of JCB / loader cum-excavator	105.00	Per hour	950.00	Rupees Nine Hundred Fifty Only	99750.00
Terms and Conditions :-						
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
Total in figures :-						99750.00
Total in Words :-					Rupees Two Thousand Two Hundred Fifty Only	
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

Sr. No. 150 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD.Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 11						
Name of work: - Restrotration of rain damages on Rajgarh Bye Pass road Km.0/00 to 5/410 (SH:- Hiring of JCB/ loader cum-excavator for removal of slips)						
1	Hiring of JCB / loader cum-excavator	105.00	Per hour	950.00	Rupees Nine Hundred Fifty Only	99750.00
Terms and Conditions :-						
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
Total in figures :-						99750.00
Total in Words :-		Rupees Two Thousand Two Hundred Fifty Only				
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

Sr. No. 1111 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD.Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- (12)						
Name of work: - Restoration of rain damages on Rajagarh Bye Pass road Km.0/00 to 5/410 (SH:- Hiring of Tipper for removal of slips)						
1	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.000	Per Day	4000.00	Rupees Four Thousand Only	96000.00
Total in figures :-						96000.00
Total in Words :-				Rupees Ninety Six Thousand Only		
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

Sr. No. 148 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD.Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- (13)						
Name of work: - Restoration of rain damages on Rajgarh Bye Pass road Km.0/00 to 5/410 (SH):- Hiring of Tipper for removal of slips)						
1	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.000	Per Day	4000.00	Rupees Four Thousand Only	96000.00
Total in figures :-						96000.00
Total in Words :-				Rupees Ninety Six Thousand Only		
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

Sr. No. 147 for the year 2025-26

Executive Engineer
 B&R Division, HP.PWD.Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- <u>14</u> Estimated Cost: - 96000.00 Earnest Money: - 2000.00 Time limit : - Two Months						
Name of work: - Restoration of rain damages on Jatoli to gadog road Km.0/00 to 5/590 (SH:- Hiring of Tipper for removal of slips)						
1	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.000	Per Day	4000.00	Rupees Four Thousand Only	96000.00
Total in figures :-				Rupees Ninety Six Thousand Only		96000.00
Total in Words :-						
Quoted Percentage rate upto Three Digits :-						
				(+) / (-)		

Sr. No. 1151 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD.Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
					Estimated Cost: -	96000.00
					Earnest Money: -	2000.00
					Time limit: -	Two Months
Job No. :- 15						
Name of work: - Restoration of rain damages on Galang to Matual road Km.0/00 to 2/00 (SH:- Hiring of Tipper for removal of slips)						
1	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.000	Per Day	4000.00	Rupees Four Thousand Only	96000.00
Total in figures :-				Rupees Ninety Six Thousand Only		
Total in Words :-				(+) / (-)		
Quoted Percentage rate upto Three Digits :-						

Sr. No. 15A for the year 2025-26

Executive Engineer
B&R Division, HP.PWD.Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 16						
Name of work: - Restoration of rain damages on Galang to Matual road Km.0/00 to 2/00 (SH:- Hiring of Tipper for removal of slips)						
1	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.000	Per Day	4000.00	Rupees Four Thousand Only	96000.00
Total in figures :-				Rupees Ninety Six Thousand Only		96000.00
Total in Words :-				(+ / -)		
Quoted Percentage rate upto Three Digits :-						

Sr. No. 153 for the year 2025-26

(Signature)

**Executive Engineer
B&R Division, HP.PWD.Solan.**

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- (17)						
Name of work: - Restoration of rain damages on Jatoli to Gadog road Km.0/00 to 5/590 (SH:- Hiring of JCB/ loader cum-excavator for removal of slips)						
1	Hiring of JCB / loader cum-excavator	105.00	Per hour	950.00	Rupees Nine Hundred Fifty Only	99750.00
Terms and Conditions :-						
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
Total in figures :-						99750.00
Total in Words :-				Rupees Two Thousand Two Hundred Fifty Only		
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

Sr. No. 154 for the year 2025-26

Executive Engineer
 B&R Division, HP.PWD.Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- (18)						
Name of work: - Restroation of rain damages on Galang tomatural road Km.0/00 to 2/00 (SH:- Hiring of JCB/ loader cum-excavator for removal of slips)						
1	Hiring of JCB / loader cum-excavator	105.00	Per hour	950.00	Rupees Nine Hundred Fifty Only	99750.00
Terms and Conditions :-						
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.					
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
Total in figures :-						
Total in Words :-						
Rupees Two Thousand Two Hundred Fifty Only						
Quoted Percentage rate upto Three Digits :-						
(+) / (-)						

Sr. No.155 for the year 2025-26


Executive Engineer
 B&R Division, HP.PWD.Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- (19)						
Name of work: - Restrotration of rain damages on various road under Oachghat Sub Division (SH:- Hiring of Tipper for removal of slips)						
1	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.000	Per Day	4000.00	Rupees Four Thousand Only	96000.00
Total in figures :-				Rupees Ninety Six Thousand Only		96000.00
Total in Words :-						
Quoted Percentage rate upto Three Digits :-						

Sr. No. 156 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 96000.00 only.


 Executive Engineer
 B&R Division, HP.PWD.Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
					Estimated Cost: -	99875.00
					Earnest Money: -	2000.00
					Time limit: -	Fifteen days
Name of work: -Annual repair and maintenance of various roads under Jatoli Section in Oachahat Sub Division (SH : - Providing and supplying 10mm to 12.5mm stone aggregate)						
1	Supplying and stacking of crushed/ broken stime aggregate chipping 10mm to 12.5mm nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per HPPWD specification and as desired by the Engineer-In-Charge including carriage of matetial with in all leads and lift complete in all respect.	85.00	Per Cubic Meter	1175.00	Rupees Thousand Hundred Five Only	99875.00
Total in figures :-						99875.00
Total in Words :-				Rupees Ninety Nine Thousand Eight Hundred Seventy Five Only		
Quoted Percentage rate :-				(+) / (-)		

Sr. No. 1 57 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD.Solan.

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 98,700.00
EARNEST MONEY ₹ 2,000.00
TIME ALLOWED Two Months

Name of Work :- Restoration of rain damages on various roads under Oachghat Sub-Division (SH :- Hiring of Excavator Cum Loader for removal of Debris , slips in Gaura Section)

Sr. No.	Description of item	Quantity (Hours)	Rate (Rs.) in Figures	Rate in words	Unit	Amount
1	Hiring of excavator cum loader for removal of snow , removal of debris and dressing of berms with minimum capacity of 45 cum per hour , minimum 6 hours per day including pay of operator , POL charges , maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge.	94.00	1050.00	Rupees One Thousand and Fifty Only	Per Hour	98700.00
TOTAL						Rs. 98700.00
Total in Words :-		Ninety Thousands Seven Hundred Fifty Only				
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor.

Sr No 158

Executive Engineer
B&R HPPWD Division
Solani

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 98,700.00
EARNEST MONEY ₹ 2,000.00
TIME ALLOWED Two Months

Name of Work :- Restoration of rain damages on various roads under Oachghat Sub-Division (SH :- Hiring of Excavator
Cum Loader for removal of Debris , slips in Jaunaji Section) (Job No.2)

Sr. No.	Description of item	Quantity (Hours)	Rate (Rs.) in Figures	Rate in words	Unit	Amount
1	Hiring of excavator cum loader for removal of snow , removal of debris and dressing of berms with minimum capacity of 45 cum per hour , minimum 6 hours per day including pay of operator , POL charges , maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge.	94.00	1050.00	Rupees One Thousand and Fifty Only	Per Hour	98700.00
TOTAL						Rs. 98700.00
Total in Words :-		Ninety Thousands Seven Hundred Fifty Only				
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor.

St No: 159

Executive Engineer
B&R HPPWD Division
Solani

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 98,700.00
EARNEST MONEY ₹ 2,000.00
TIME ALLOWED Two Months

Name of Work :- Restoration of rain damages on various roads under Oachghat Sub-Division (SH :- Hiring of Excavator Cum Loader for removal of Debris, slips in Jaunaji Section) (Job No.1)

Sr. No.	Description of item	Quantity (Hours)	Rate (Rs.) in Figures	Rate in words	Unit	Amount
1	Hiring of excavator cum loader for removal of snow, removal of debris and dressing of berms with minimum capacity of 45 cum per hour, minimum 6 hours per day including pay of operator, POL charges, maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge.	94.00	1050.00	Rupees One Thousand and Fifty Only	Per Hour	98700.00
TOTAL						Rs. 98700.00
Total in Words :-		Ninety Thousands Seven Hundred Fifty Only				
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor.

S.No. 1-160

Executive Engineer
B&R HPPWD Division
Solani

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- (24)						
Name of work :- Restoration of rain damages on HRTC workshop to kather road Km.0/00 to 2/00 (SH:- Hiring of Tipper for removal of slips)						
1	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.000	Per Day	4000.00	Rupees Four Thousand Only	96000.00
Total in figures :-						96000.00
Total in Words :-				Rupees Ninety Six Thousand Only		
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

Sr. No. 146 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD.Solan.

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 98,700.00
EARNEST MONEY ₹ 2,000.00
TIME ALLOWED Two Months

Name of Work. :- Restoration of rain damages on various roads under Oachghat Sub-Division (SH :- Hiring of Excavator Cum Loader for removal of Debris , slips in Jaunaji Section) (Job No.3)

Sr. No.	Description of item	Quantity (Hours)	Rate (Rs.) in Figures	Rate in words	Unit	Amount
1	Hiring of excavator cum loader for removal of snow , removal of debris and dressing of berms with minimum capacity of 45 cum per hour , minimum 6 hours per day including pay of operator , POL charges , maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge.	94.00	1050.00	Rupees One Thousand and Fifty Only	Per Hour	98700.00
TOTAL						Rs. 98700.00
Total in Words :-		Ninety Thousands Seven Hundred Fifty Only				
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor.

Sr No :- 161

Executive Engineer
B&R HPPWD Division
Solani