

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed item/ percentage rate tender on form NO. 6&8 are hereby invited by the Executive Engineer, Bilaspur Division No. I, HP.PWD., Bilaspur on behalf of Governor of Himachal Pradesh from the approved and eligible contractors enlisted in PWD Department so as to reach in this office on or before **18/09/2025** up to 10.30 A.M. and will be opened on the same day at **11.00 A.M.** in the presence of the intending contractors or their authorized representatives who may like to be present. If it happens to be holiday on that day tenders will be opened on next working day. The application for obtaining the tender forms will be received up to **15/09/2025** up to 5.00 PM and the tender form can be had from this office on **17/09/2025** during the office hours.

The Earnest money in the shape of National Saving Certificate Time deposit Accounts/FDR of any Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, Division No. I., HP.PWD., Bilaspur must be accompanied with each application for obtaining the tenders. The tender application received without earnest money /cost of tender forms will similarly be rejected. The undersigned reserves the right to reject the tenders without assigning any reason.

Sr. No	Name of work	Estimated cost (In Rs.)	Earnest Money (In Rs.)	Cost of form (In Rs.)	Time limit
1	Repair of Govt. Degree College Bilaspur Distt. Bilaspur H.P. (SH:- Providing and fixng pre-painted sheet/BP sheet to close monkey entry at roof top).	44,979/-	1000	350	One month
2	Restoration of rain damages on Chandigarh Mandi Manali road km 127/000 to 140/00. (SH:- Re-construction of B Wall Required at RD 137/360 to 137/366.50). (UNDER PDNA 2023)	84,584/-	2000	350	One month
3✓	Restoration of rain damages on Kothi Tarer Road km 0/0 to 7/200.(SH:- Re-construction of B Wall at RD 3/810 to 3/817) (UNDER PDNA 2023).	86,865/-	2000/-	350	One month
4✓	Restoration of rain damages on Kothi Tarer Road km 0/0 to 7/200. (SH:- Re-construction of R/Wall at RD 2/900 to 2/915) (UNDER PDNA 2023).	43,027/-	1000/-	350	One month
5✓	Restoration of rain damages on Circular Road Roura km 0/0 to 2/000. (SH:- Re-construction of B/Wall at RD 1/300 to 1/305.40). (UNDER PDNA 2023).	90,160/-	2000/-	350	One month
6.	A/R & M/O on residential building at Changer Sector Distt. Bilaspur. (SH:- Wood works in frame and tiles flooring in CJM residence).	63,847/-	1500/-	350	One month
7.	Upgaradation of GNM Training School Bilapsur to levelof College of Nurshing and C/o Hostel/ accommodation for students/wardens. (SH:- Preparation of contour site plan, X-Section, L-Section in all medical campus Bilaspur).	95,000/-	2000/-	350	One month

	Special repair on Punch Karma Unit at R/wall in Distt. Ayurvedic Hospital Bilaspur. (SH:- P/L interlocking, plaste work, shutter & painting etc.).	99,695/-	2000/-	350	One month
	A/R & M/O residetnail type-IV Qtrs at Changer sector Bilapsur (H.P.). (SH:- Emulsion painting wood painting and W.S. & S.I.) E-3 D/S.	97,518/-	2000/-	350	One month
10.	A/R & M/O on residential building in Changer sector Bilaspur. (SH:- Supplying of building/ painting/distempering material).	99,977/-	2000/-	350	One month
11.	A/R & M/O PWD Circuit House Bilapsur. (SH:- Providing supplying of toilet seat, Polish door and emulsion painting).	96,954/-	2000/-	350	One month
12.	Restoration of rain damages on Shaheed Sukh Ram Bhatoli Malywar road Km. 0/00 to 4/0. (SH:- C/o CC pedestal under B/wall in wire crate at RD. 0/425 to 0/445).	99,002/-	2000/-	350	One month
13.	Construction of New GNM Training School building at Bilaspur Distt. Bilaspur. (SH:- Supplying and installation of Computer,UPS and Printer). Job No.I	92,909/-	2000/-	350	One month
14.	Construction of New GNM Training School building at Bilaspur Distt. Bilaspur. (SH:- Supplying and installation of Computer,UPS and Printer). Job No.II	92,909/-	2000/-	350	One month
15.	Construction of Deputy Director Agriculture office building at Dholra Distt. Bilaspur. (SH:- Supplying and installation of Computer,UPS and Printer). Job No.I	99,947/-	2000/-	350	One month
16.	Construction of Deputy Director Agriculture office building at Dholra Distt. Bilaspur. (SH:- Supplying and installation of Computer,UPS and Printer). Job No.II	99,947/-	2000/-	350	One month
17.	Restoration of rain damages on Shaheed Sukh Ram Bhatoli Malywar road Km. 0/00 to 4/0. (SH:- C/o CC pedestal under B/wall in wire crate at RD. 0/45 to 0/65).	99,002/-	2000/-	350	One month
18.	Improvement of Black Spot on link road Beri Gugaghat Panjgain road Km. 0/00 to 2/500. (SH:- C/o balance work R/wall at RD. 0/130 to 0/135).	97,657/-	2000/-	350	One month
19.	Restoration of rain damages on Banoha Parnal Kulwari road Km. 0/00 to 9/00. (SH:- C/o R/wall at RD, 4/330 to 4/335.50).	97,282/-	2000/-	350	One month

1. Certified that the tenders for above said works are being called of emergent nature in exigency of public interest.

TERMS & CONDITIONS: -

1. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
2. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactorily including adherence to quality future work will be awarded to him. All undertaking that he is not having more than two works in hand must be recorded in the application, failing which application of such contractor shall be rejected without any notice to him.

money should be accompanied with application. Application without earnest money will not be retained.
photo copy of Pan Number/GST/EPF/Registration should be attached with the application otherwise tender form will not be issued.

NO.PW-BLP-I-CB-EA-I-Tender/ 2025- 9684-98

**Executive Engineer,
Bilaspur, Division No.I
HP.PWD, Bilaspur.
Dated :- 10/09/2025**

Copy forwarded to the following for information please.

1. The Engineer-in-Chief, HP.PWD; Shimla-I.
2. The Chief Engineer (HZ) HP.PWD, Hamirpur.
3. The Superintending Engineer, 10th Circle, HP.PWD, Bilaspur .
4. The Executive Engineer (IT) O/o the Engineer-in-Chief, HP.PWD, Shimla through email:- cc-pwd-hp@nic.in alongwith copies of Schedule of quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. All the contractors as per record of this office.
7. Accounts Branch/ Drawing Branch/Supdt. in this office.
8. Notice Board.


**Executive Engineer,
Bilaspur, Division No.I,
HP.PWD, Bilaspur.**

Draft Schedule of quantity

Name of work:- Repair of Govt.Degree Collage Bilaspur Distt. Bilaspur H.P. (SH):- Providing and Fixing Pre-painted sheet/BP sheet to close monkey entry at roof top.-)

Draft Schedule of quantity						
Estimated cost Rs.44979/-only						
Earnest Money Rs. 1000/- only.						
Time Limit. = one month						
Name of work:- Repair of Govt.Degree Collage Bilaspur Distt. Bilaspur H.P. (SH:- Providing and Fixing Pre-painted sheet/BP sheet to close monkey entry at roof top.)						
Sr No	Description of items.	Qty.	Unit	Rates		Amount
				In Figure	In Word	
1	Providing and fixing 0.63mm (Zero point sixty three millimeter) thick pre-painted steel sheet of TATA / DURO SHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) micron over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J opr L hooks, bolts and nuts , 6mm diameter with pre-painted limpet and rubber washers complete with all accessories. as per HP PWD Specification . including carriage of materials , within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.75	Per Square Metre			
2	Providing ridges or hips of width 60 cm (Sixty centimetre) overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.80 mm (Zero point eighty millimetre) thick with zinc coating not less than 275 gm/m ² (Two hundred seventy five gramme / Per Square Metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.30	Per /Rmt.			
3	Structural steel work in single section, fixed with or without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials , within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	65.85	Per kg			
4	Providing and fixing M.S.B.P sheet 1.66 mm to 2mm (one point sixty six millimeters to two millimeter) thick in eaves board /facia/soffits/ceiling including cutting,fixing and welding to steel roof members and applying a coat of red led primer coating with all accessories. as per HP PWD Specification . including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.86	Per Square Metre			


 Executive Engineer
 Bilaspur Division No.1
 HP PWD Bilaspur

2

Draft Schedule of quantity

Draft Schedule of quantity							Estimated cost Rs.84584/-only
							Earnest Money Rs. 2000/- only.
Name of work:- Repair & Restoration of rain damages on Chandigarh Mandi Manali road (old NH-154):(SH:- Proposed Breast wall at RD.137/360 to 137/366.5).(Length 6.50 mtrs. Height-2.50 mtrs.)(under PDNA 2023)							Time Limit. = one month
Description of items.							
Sr No		Qty.	Unit	Rates		Amount	
				In Figure	In Word		
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.48	Per Cubic Metre				
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.35	Per Cubic Metre				
3	Providing and laying cement concrete 1:5:10 (One cement : Five sand : 10 graded stone aggregate) with steel shuttering etc complete and curing complete including the cost of form work with steel shuttering for plain / reinforced concrete in retaining walls, breast walls, as per drawing & HP, PWD, technical specifications & including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.28	Per Cubic Metre				
4	Providing weap holes in brick masonry / stone masonry / plan reinforced concrete abutment wing wall and laying cement concrete in retaining walls,return walls, 100 mm dia PVC pipe extending through the full width of the structure with slop of 1 (v): 20 (H) towards drawing face complete as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Each				


 Executive Engineer
 Bilaspur Division No.I
 HP PWD Bilaspur

3

Draft Schedule of quantity

Name of work:- Repair & Restoration of rain damages on kothi Tarer road km 0/0 to 7/200.(SH:- Re construction of B/ wall at RD.3/810 to 3/817 (under PDNA 2023)		Estimated cost Rs.86865/-only	
		Earnest Money Rs. 2000/- only.	
		Time Limit. = one month	

Sr No	Description of items.	Qty.	Unit	Rates		Amount
				In Figure	In Word	
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.68	Per Cubic Metre			
2	Providing and laying cement concrete 1:5:10 (One cement : Five sand : 10 graded stone aggregate) with steel shuttering etc complete and curing complete including the cost of form workwith steel shuttering for plain / reinforced concrete in retaining walls, breast walls, as per drawing & HP, PWD, technical specifications & including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.52	Each			
3	Providing weap holes in brick masonry / stone masonry / plan reinforced concrete abutment wing wall and laying cement concrete in retaining walls,return walls, 100 mm dia PVC pipe extending through the full width of the structure with slop of 1 (v): 20 (H) towards drawing face complete as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.000	Per Cubic Metre			


Executive Engineer
Bilaspur Division No.I
HP PWD Bilaspur

4

Draft Schedule of quantity

Estimated cost Rs.43027/-only Earnest Money Rs. 1000/- only. Time Limit. = one month						
Name of work:- Repair & Restoration of rain damages on kothi Tarer road km 0/0 to 7/200.(SH:- Re construction of R/ wall at RD.2/900 to 2/902.4 (under PDNA 2023)						
Sr No	Description of items.	Qty.	Unit	Rates		Amount
				In Figure	In Word	
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	Excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.27	Per Cubic Metre			
3	Providing and laying cement concrete 1:5:10 (One cement : Five sand : 10 graded stone aggregate) with steel shuttering etc complete and curing complete including the cost of form work with steel shuttering for plain / reinforced concrete in retaining walls, breast walls, as per drawing & HP, PWD, technical specifications & including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.35	Per Cubic Metre			
4	Providing weap holes in brick masonry / stone masonry / plan reinforced concrete abutment wing wall and laying cement concrete in retaining walls, return walls, 100 mm dia PVC pipe extending through the full width of the structure with slop of 1 (v): 20 (H) towards drawing face complete as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.56	Each			
5	Back filling behind abutment, wing wall, return wall and retaining / breast walls with granular material complete as per drawings and technical specification clause 1204.3.8 complete as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.000	Per Cubic Metre			
		2.160	Per Cubic Metre			


 Executive Engineer
 Bilaspur Division No.1
 HP PWD Bilaspur

3

Draft Schedule of quantity

				Estimated cost Rs.90160/-only		
				Earnest Money Rs. 2000/- only.		
				Time Limit. = one month		
Name of work:- Repair & Restoration of rain damages on circular road Roura km 0/0 to 2/0.(SH:- Re construction of B/ wall at RD.1/300 to 1/305.4 (under PDNA 2023)						
Sr No	Description of items.	Qty.	Unit	Rates		Amount
				In Figure	In Word	
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.56	Per Cubic Metre			
2	Providing and laying cement concrete 1:5:10 (One cement : Five sand : 10 graded stone aggregate) with steel shuttering etc complete and curing complete including the cost of form work with steel shuttering for plain / reinforced concrete in retaining walls, breast walls, as per drawing & HP, PWD, technical specifications & including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.05	Each			
3	Providing weap holes in brick masonry / stone masonry / plan reinforced concrete abutment wing wall and laying cement concrete in retaining walls,return walls, 100 mm dia PVC pipe extending through the full width of the structure with slop of 1 (v) 20 (H) towards drawing face complete as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	8.000	Per Cubic Metre			

Executive Engineer
Bilaspur Division No.1
HP PWD Bilaspur

Draft Schedule of quantity

Draft Schedule of quantity		Estimated cost Rs.63,847/-only				
		Earnest Money Rs. 1500/- only.				
		Time Limit. = one month				
Name of work:- A/R and M/O on residential building at changer sector Distt Bilaspur. (SH:- Wood works in frame and Tailles flooring in CJM residence.)						
Sr No	Description of items.	Qty.	Unit	Rates		Amount
				In Figure	In Word	
1	2	3	4	5	6	7
1	Providing wood work in frames of doors, windows,clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).Second class teak wood					
2	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws :35 mm thick shutters(Second class teak wood)	0.05	Per Cubic Metre			
3	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge.35mm to 40 mm thick Second class teak wood	1.95	Each			
4	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave,holdfasts etc. complete and stacking within 50 metres lead :Of area 3 sq. metres and below	1.95	Per Cubic Metre			
5	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	1.00	Each			
6	Painting two coats (excluding priming coat)on new wood and wood based surface under coat with ready mixed paint brushing to give an even shade including cleaning the surface all dirt,dust and other foreign matter :-- With White readymixed paint. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.94	P/sqm			
7	Applying priming coat:With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)	17.94	P/sqm			

8	Providing and fixing aluminum tower bolts with screws etc. Complete as per HP-PWD, Specification. 250x10mm. (Two hundred fifty millimetre into ten millimetre.)	4.00	Per/each		
9	Providing and fixing aluminum handles with screws etc. Complete as per HP-PWD, Specification. 125mm. (one hundred twenty five millimetre.)	4.00	Per/each		
10	Providing and fixing Hydraulic door closer bottle type M.S. body with necessary accessories and screws complete	1.00	Per/each		
11	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	1.62	P/cum		
12	Repairs to plaster of thickness 12 mm to 20 mm in patches with cement mortar 1:4.	51.00	P/sqm		
13	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete. 75 mm diameter	3.60	Per/Rmts		
14	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. complete. 75 mm dia	3.00	Each		


 Executive Engineer
 Bilaspur Division No.1
 HP PWD Bilaspur

Job No. 7

Schedule of Quantity			Estimated cost Rs. = 95,000/- only			
			Earnest Money Rs. = 2,000/- only			
			Time Limit. = One month			
Name of work:- Upgradation of GNM Training School Bilaspur to the level of College of Nurshing and C/O Hostel / accommodation for students / wardens. (SH:- Preparation of contour site plan, X-section, L-Section in all medical campus Bilaspur).						
Sr No	Description	Qty.	Rates		Unit	Amount
			In Figure	In words		
1	2	3	5	6	7	8
1	Preparation of detail contour site plan, X-section & L-section with the help of total station to the accuracy of 100% at site and marking of all existing infrastructure with the boundaries f medical department land, so that detail plan of existing structure and cacant land can be sent to the architectural wing to this department for marking proposal of Nurshing Hostel, class room etc. if any other requirement by the architectural wing will be prepared and submitted by the contractor and submitted 3 Nos. set of hard copy and soft copy complete as per the direction Engineer-in-Charge of site. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constnuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Per Job	
			TOTAL			



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Schedule of Quantity						Estimated cost Rs. = 99,695/- only
						Earnest Money Rs. = 2,000/- only
						Time Limit. = One month
Name of Work:- Special repair on Punch Karma Unit at R/Wall in Distt. Ayurvedic Hospital Bilaspur. (SH;- P/L interlocking, plaste work, shutter & painting etc.).						
Sr No	Description	Qty.	Rates		Unit	Amount
			In Figure	In words		
1	2	3	5	6	7	8
1	Providing and laying granite stone 20mm thick over self steel already laid thin granite laid single without cement.. including carriage of materials , within all leads and lifts as per direction of Engineer in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.98			Per Square Metre	
2	Providing and fixing Door spring of approved brand and manufacture (Confirming to IS 6315) floor aluminium doors complete. including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00			Each	

3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and weeping extra sand. complete all as per direction of Engineer-in Charge 6 0 mm (sixty milimetre) thick ISI marked C.C. paver block of M-50 grade with approved color design and pattern. including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.42			Per Square Metre
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : Three coarse sand) : Six graded stone aggregate 20 mm(Twenty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.51			Per Cubic Metre
5	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 40mm (Forty milimetre) thick 2nd (Second) class deodar wood. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.44			Per Square Meter
6	Repairs to plaster in patches of 2.50 Sq.M (Two point fifty Per Square Metre). and under and 10 to 15mm (Ten to fifteen milimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 (Twenty) metres with Cement Mortar 1:5 (One Cement : five) Sand). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.3			Per Square Metre

7	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equivalent on undecorated wall surface (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including snad smooth complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.90			Per Square Metre	
8	Providing and fixing 10 liter hot water tank in best quality cromton as WH-3D/0 including all type fitting, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
9	Providing and fixing wash basin with C.I. brackets, 15 mm (Fifteen milimetre) C.P. brass pillar taps, 32 mm (Thirty two milimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 450x300 mm (four hundred fifty into three hundred milimetre) with a pair of 15 mm (Fifteen milimetre) C.P. brass pillar taps including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
10	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.73			Kilogramme	

11	Providing and fixing 0.47mm (Zero point forty seven millimeter) thick pre-painted steel sheet of TATA / DURO SHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 (Twenty) micron over 5 (Five) microns primer coating to back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J opr L hooks, bolts and nuts , 6mm diameter with pre-painted limpet and rubber washers complete with all accessories. as per HP.PWD Specification . including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.55			Per Square Meter
		TOTAL			


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Schedule of Quantity

Schedule of Quantity						Estimated cost Rs. = 97,518/- only
						Earnest Money Rs. = 2,000/- only
						Time Limit. = One month
Name of Work:- A/R & M/O residential type-IV Qtrs at Changer Sector Bilaspur (H.P). (SH:- Emulsion painting wood painting and W.S & D).						
Sr No	Description	Qty.	Rates		Unit	Amount
			In Figure	In words		
1	2	3	5	6	7	8
1	Removing dry oil bound distemper, water proofing cement paint and like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	356.09			Per Square Metre	
2	Providing and applying Birla white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	213.65			Per Square Metre	
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	356.09			Per Square Meter	

4	Painting one coat(excluding priming coat)on previously painted wood and wood based surfaces with enamel paint brushing to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	91.25			Per Square Metre	
5	Repairs to plaster in patches of 2.50 Sq.M (Two point fifty Per Square Metre). and under and 10 to 15mm (Ten to fifteen milimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 (Twenty) metres with Cement Mortar 1:5 (One Cement : five) Sand). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19			Per Square Metre	
6	Providing and fixing wash basin with CI brackets, 15mm (Fifteen milimetre) PTMT pillar cock, 32 mm (Thirty two milimetre) PTMT waste coupling of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required. White Vitreous China Flat back wash basin size 550x400 mm (five hundred fifty into four hundred milimetre) with single 15 mm (Fifteen milimetre) PTMT pillar cock. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
7	Providing and fixing wash basin with pedestal in best quality. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	

8	Providing and fixing C.P. brass stop / angle cock (concealed) of approved quality conforming to IS:8931 : 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
9	Providing and fixing C.P. brass Pillar cock (concealed) of standard design and approved make conforming to IS:8931. 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
10	Providing and fixing uplasticsed PVC connection pipe with brass unions : 30 cm length 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
11	Providing and fixing C.P. brass bib cock Cera/Hindware/Jaquar or equivalent of approved quality conforming to IS:8931 : 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
12	Providing and fixing aluminium door & windows frame with shutter frame including backlite sheet including tower bolt & handles , hinges as per need at site complete fitting at site as per direction of engineer. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.40			Per Square Metre	
		TOTAL				


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Schedule of quantity

Schedule of quantity						
Estimated cost Rs. 99,977/-only						
Earnest Money Rs. 2,000/- only.						
Time Limit. = One month						
Name of work:- A/R & M/O on residential building in Changer Sector Bilaspur. (SH:- Supplying of building /painting/ distempering material).						
Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Supply and stacking emulsion in best quality interior asian / Nerolack/burger. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	140.00			Per Kilogramme	
2	Supply and stacking of stainer 100 ml various color in best quality. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00			Each	
3	Supply and stacking enamel paint Asian/Nerolack. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00			Each	
4	Supply and stacking Tarpin oil in best quality. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.00			Per Litre	

5	Supply and stacking 5 inch painting brush in best quality, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00			Each	
6	Supply and stacking 4 inch painting brush in best quality, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00			Each	
7	Supply and stacking 3 inch painting brush in best quality, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00			Each	
8	Supply and stacking Birla white putty in best quality, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	200.00			Per Kilogramme	
9	Supply and stacking PVC pipe Finolux 4 inch in best quality, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00			Per Running Metre	
10	Supply and stacking PVC pipe Finolux 3 inch in best quality, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00			Per Running Metre	

11	Supply and stacking PVC plain bend & door bend 4 inch in best quality, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00			Each	
12	Supply and stacking PVC plain bend & door bend 3 inch in best quality, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00			Each	
13	Supply and stacking Steel taps 15mm nominal size in best quality, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	50.00			Each	
14	Supply and stacking G.I.L-Bow 15mm nominal size in best quality, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	50.00			Each	
15	Supply and stacking G.I Tee 15mm nominal size in best quality, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00			Each	
16	Supply and stacking G.I Nipple 15mm nominal size in best quality, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	205.00			Per Inch	
		TOTAL				


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Schedule of quantity

Schedule of quantity						
Estimated cost Rs. 96,954/-only						
Earnest Money Rs. 2,000/- only.						
Time Limit. = One month						
Name of work:- A/R & M/O PWD Circuit House Bilaspur. (SH:- Providing Supplying of toilet seat, Polish door and emulsion painting).						
Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Supply and stacking toilet seat European type with flush & cover Jaquar make model No. CHS white 363 SPPZ. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
2	Supply and stacking Jet spray SS / CP 8mm dia in best quality Jaquar make. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
3	Providing and fixing wall tile premium quality with making with cement mortar 1: 3. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00			Per square metre	
4	Providing and fixing angle cock C.P 15mm nominal size Jaquar make. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00			Each	

5	French spirit polishing : Two or more coats on new works including a coat of wood filler. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	136.33			Per Square Metre	
6	Repair to plaster of thickness 12mm to 20mm (Twelve to twenty millimetre) in patches of 2.50 (Two point fifty) Square meter and under and 10 (Ten) to 15mm (Fifteen millimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground upto 20m (twenty metre) lead with cement mortar 1:5 (One Cement : five approved Sand) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	64.13			Per Square Meter	
7	Finishing wall with weather proof exterior grade emulsion of approved design (Apex ultima) or its equarllied on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete. including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	64.13			Per Square Meter	
		TOTAL				



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

SCHEDULE OF QUANTITY.				Estimated cost Rs. = 99,002/-only		
				Earnest Money Rs. = 2,000/- only.		
				Time Limit. = One Month		
Name of Work:- Restoration of rain damages on Shaheed Sukhram Bhatoli Malyawar road KM. 0/00 to 4/00. (SH:- C/O pusta / toe wall under R/wall in wire crates at RD. 0/425 to 0/445).						
No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure 5	In words 6	
1	2	14.40	Per Cubic metre			8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constnuction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constnuction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.20	Per Cubic metre			
TOTAL						


Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Schedule of Quantity

Schedule of Quantity						
Estimated cost Rs. = 92,909/-						
Earnest Money Rs. = 2,000/-						
Time Limit. = One month						
Name of work:- Construction of New GNM Training School building at Bilaspur Distt. Bilaspur. (SH:-Supplying and installation of Computer, UPS and Printer). Job No. I						
Sr. No.	Description of items.	Quantity	Rate		Amount	
			In Figure	In words		
1	2	3	4	5	7	
1	HP make Desktop model HP 280 G9 with Intel core i7-12700-12th Gen. Processor, 8GB DDR4 RAM exandable up to 16GB, 512 GB SSD, 23" LED color display with FHD (1920x1080), integrated HD graphics & 5 MP pull up webcam with integrated dual array and digital microphone, 2xUSB 3.0, USB 2.0, Audio jack/VGA/HDMI/DP port, 10/100/1000M IPV6 comlaint LAN, USB Keyboard & USB Mouse, internal Speaker, 1x802.11b/g/n/ac, Wifi 6with Bluetooth 5.0 PL-Window 11 pro 64 bit-OS with Three years onsite warranty. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.			
2	Printer:- HP Laser MFP M1188FNW with printer, Scan & copy and fax A4 size paper, Printing, Printing speed 20 PPM, Resolution 1200 dpi Memory 128 MB, Scan resolution 1200dpi memory ADF, wireless connectivity, USB 2.0, paper tray capacity 150 pages with one year warranty. (Expect consumable & breakage & burnt items). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other constntruction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.			

3	600VA Offlie UPS (Numberic or equivalent) with SMF batteries to provide 10 min. backup:- with 3 years carry in warranty. Note: - This UPS is plug & play and needs no installation, including carriage of materials, within all leads and lifts as per direction of Engineer-in- Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constreution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		
TOTAL					


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Draft Schedule of Quantity					
Estimated cost Rs. = 92,909/-					
Earnest Money Rs. = 2,000/-					
Time Limit. = One month					
Name of work:- Construction of New GNM Training School building at Bilaspur Distt. Bilaspur. (SH:-Supplying and installation of Computer, UPS and Printer). Job No. II.					
Sr. No.	Description of items.	Quantity	Rate		Amount
			In Figure	In words	
1	2	3	4	5	7
1	HP make Desktop model HP 280 G9 with Intel core i7-12700-12th Gen. Processor, 8GB DDR4 RAM expandable up to 16GB, 512 GB SSD, 23" LED color display with FHD (1920x1080), integrated HD graphics & 5 MP pull up webcam with integrated dual array and digital microphone, 2xUSB 3.0, USB 2.0, Audio jack/VGA/HDMI/DP port, 10/100/1000M IPV6 compliant LAN, USB Keyboard & USB Mouse, internal Speaker, 1x802.11b/g/n/ac, Wifi 6with Bluetooth 5.0 PL-Window 11 pro 64 bit-OS with Three years onsite warranty. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		
2	Printer:- HP Laser MFP M1188FNW with printer, Scan & copy and fax A4 size paper, Printing, Printing speed 20 PPM, Resolution 1200 dpi Memory 128 MB, Scan resolution 1200dpi memory ADF, wireless connectivity, USB 2.0, paper tray capacity 150 pages with one year warranty. (Expect consumable & breakage & burnt items). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		

3	600VA Offlie UPS (Numberic or equivalent) with SMF batteries to provide 10 min. backup:- with 3 years carry in warranty. Note:- This UPS is plug & play and needs no installation. including carriage of materials, within all leads and lifts as per direction of Engineer-in- Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.			
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. 15


Estimated cost Rs. = 99,947/-
Earnest Money Rs. = 2,000/-
Time Limit. = One month

Draft Schedule of Quantity

Name of work:- Construction of Deputy Director Agriculture office building at Dholra Distt. Bilaspur. (SH:-Supplying and installation of Computer, UPS and Printer). Job No. I

Sr. No.	Description of items.	Quantity	Rate		Amount
			In	In words	
1	2	3	4	5	7
1	HP make AIO Desktop model HP 440 G9 with Intel core i7-12700-12th Gen. Processor, 8GB DDR4 RAM expandable up to 16GB, 512 GB SSD, 23" LED color display with FHD (1920x1080), integrated HD graphics & 5 MP pull up webcam with integrated dual array and digital microphone, 2xUSB 3.0, USB 2.0, Audio jack/VGA/HDMI/DP port, 10/100/1000M IPV6 compliant LAN, USB Keyboard & USB Mouse, internal Speaker, 1x802.11b/g/n/ac, Wifi 6with Bluetooth 5.0 PL-Window 11 pro 64 bit-OS with Three years onsite warranty. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		
2	Printer:- HP Laser MFP M1188FNW with printer, Scan & copy and fax A4 size paper, Printing, Printing speed 20 PPM, Resolution 1200 dpi Memory 128 MB, Scan resolution 1200dpi memory ADF, wireless connectivity, USB 2.0, paper tray capacity 150 pages with one year warranty. (Expect consumable & breakage & burnt items). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		

3	600VA Offlie UPS (Numeric or equivalent) with SMF batteries to provide 10 min. backup:- with 3 years carry in warranty. Note:- This UPS is plug & play and needs no installation. including carriage of materials, within all leads and lifts as per direction of Engineer-in- Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		
TOTAL					



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Estimated cost Rs. = 99,947/-

Earnest Money Rs. = 2,000/-

Time Limit. = One month

Draft Schedule of Quantity

Name of work:- Construction of Deputy Director Agriculture office building at Dholra Distt. Bilaspur. (SH:-Supplying and installation of Computer, UPS and Printer). Job No. II.

Sr. No.	Description of items.	Quantity	Rate		Amount
			In	In words	
1	2	3	4	5	7
1	HP make AIO Desktop model HP 440 G9 with Intel core i7-12700-12th Gen. Processor, 8GB DDR4 RAM expandable up to 16GB, 512 GB SSD, 23" LED color display with FHD (1920x1080), integrated HD graphics & 5 MP pull up webcam with integrated dual array and digital microphone, 2xUSB 3.0, USB 2.0, Audio jack/VGA/HDMI/DP port, 10/100/1000M IPV6 compliant LAN, USB Keyboard & USB Mouse, internal Speaker, 1x802.11b/g/n/ac, Wifi 6with Bluetooth 5.0 PL-Window 11 pro 64 bit-OS with Three years onsite warranty. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		
2	Printer:- HP Laser MFP M1188FNW with printer, Scan & copy and fax A4 size paper, Printing, Printing speed 20 PPM, Resolution 1200 dpi Memory 128 MB, Scan resolution 1200dpi memory ADF, wireless connectivity, USB 2.0, paper tray capacity 150 pages with one year warranty. (Expect consumable & breakage & burnt items). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.		

3	600VA Office UPS (Numeric or equivalent) with SMF batteries to provide 10 min. backup: with 3 years carry in warranty. Note: - This UPS is plug & play and needs no installation. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Nos.			
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

SCHEDULE OF QUANTITY.							Estimated cost Rs. = 99,002/-only
							Earnest Money Rs. = 2000/- only.
							Time Limit. = One Month
Name of work:- Restoration of rian damages on Saheed Sukhram Bhatoli Malyawar road Km. 0/00 to 4/00. (SH):- C/O CC pedestal under B/Wall in wire crate at Rd. 0/045 to 0/065).							
Sr No	Description of items.	Qty.		Rates		Amount	
		3	4	In Figure	In words		
1	2	3	4	5	6	8	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centemere) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (TenPer Square Metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m, (One point five metre) as directed by Engineer-in-Charge. The including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other constnuction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.40	Per Cubic metre				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty milimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constnuction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.20	Per Cubic metre				
TOTAL							


Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

SCHEDULE OF QUANTITY.						
Estimated cost Rs. = 97,657/-only						
Earnest Money Rs. = 2,000/- only.						
Time Limit. = One Month						
Name of Work: Improvement of Black Spot on link road Beri Guggaghat Panjgain road Km. 0/00 to 2/500. (SH:- C/O Balance work R/Wall at RD. 0/130 to 0/135/).						
Sr No	Description of items.	Qty.	Rates		Amount	
			In Figure	In words		
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.97	Per Cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.96	Per Cubic metre			
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	Each			

4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.22	Per Cubic metre		
TOTAL					


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Estimated cost Rs. = 97,282/-only
 Earnest Money Rs. = 2,000/- only.
 Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of Work: Restoration of damages on Banoha Parnal Kulwari road Km. 0/00 to 9/00. (SH:- C/O R/Wall at RD. 4/330 to 4/335.50).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure 5	In words 6	
1	2	7.26	Per Cubic metre			8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, (One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	29.79	Per Square Metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.33	Per Cubic metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.00	Each			

5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	4.37	Per Cubic metre			
			TOTAL			


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur