

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DEH/CB/TENDER/2024-25-
To

5504-24

DATED: 27/08/25

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :- Tender Notice.

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above


Executive Engineer,
HPPWD Division,
Dehra.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President MC Dehra.
9. The BDO Dehra /Pragpur/ Nagrota Surian.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Dehra Division.


Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

H. P. P.W.D. TENDER

Sealed item percentage tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|----------------------------|
| 1. Date and time of receipt of application for tender form: | 04.09.2025 upto 12.00 Noon |
| 2. Date and time of issue of tender form: | 05.09.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 06.09.2025 upto 10.30AM |
| 4. Date and time of opening of tenders: | 06.09.2025 at 11.00 AM |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
01	A/R & M/O HPPWD Rest House Building at Dehra in District Kangra (H.P.) (SH: C/o Plaster Work and Sanitary Work etc.).	Rs. 99,662.00	Rs.2,000/-	One Month	Rs.350/-
02	Repair and Maintenance of Civil Hospital at Dehra in Distt. Kangra (H.P.) (SH: Wood Work, Plastering, Distempering and Painting etc.).	Rs. 99,986.00	Rs.2,000/-	One Month	Rs.350/-
03	A/R & M/O Non-Residential Building HPPWD Dehra in Distt. Kangra (H.P.) (SH: Aluminium Work in Hall Portion-III).	Rs. 99,622.00	Rs.2,000/-	Three Months	Rs.350/-
04	A/R & M/O Non-Residential Building HPPWD Dehra in Distt. Kangra (H.P.) (SH: Aluminium Work in Hall Portion-IV).	Rs. 99,912.00	Rs.2,000/-	Three Months	Rs.350/-
1	The contractors/firms should possess the following documents (Photocopy to be attached):				
(i)	Latest renewal of enlistment.				
(ii)	PAN (Permanent Account No.)				
(iii)	Registration under HP GST/ (TIN No.).				
(iv)	EPF (Employee Provident Fund Account No.)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.				
4	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
5	The Contractor will have to submit affidavit alongwith application for issue of tender that he has not more than two works in hand.				
6	The next tender will be issued only after completion of previous works in hand.				
7	The offer of the tender shall remain valid upto 30 days after the opening.				

Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P.


on behalf of Governor of Himachal Pradesh

Exigency Certificate

It is certified that the tenders invited vide this office NIT No. 5504-24 dated 27/08/25 are of emergent nature of work and in public interest.

Place:

Dated:


Executive Engineer,
HPPWD Division,
Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99662.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of Work:- A/R & M/O HPPWD Rest House building at Dehra Tehsil Dehra Distt. Kangra H.P. (SH:- C/o Plaster work, Beading work and Sanitary work etc.)

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for structures as per drawings and technical specifications clause 305.1(three hundreds five point one) including setting of shoring and bracing, removal of stumps and other deleterious material complete and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	90.70 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	26,303.00
2	Second class Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven point five) in super structure above plinth level upto all floor level in cement mortar 1:6 (one cement isto six sand) and curing complete as per approved drawing, design, specification and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.28 Cubic metre	4900.00	Rupees Four Thousand Nine Hundred Only	Per Cubic metre	1,372.00
3	Providing and applying 15mm (fifteen millimeters) thick cement plaster with cement mortar 1:6 (one cement isto six sand) in single coat on rough side of brick/concrete/ stone walls for interior plastering up to all floor level including arises, internal rounded angles, chamfers and/or rounded angles in all girth and finished even and smooth as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Royalty, Malkhana, Octroi, GST, Toll Tax, Sales tax or any other taxes imposed by the Government.	51.38 Square metre	200.45	Rupees Two Hundred And Paise Forty Five Only	Per Square metre	10,299.00
4	Supplying and fixing C.I. cover without frame for manholes 455x610 mm rectangular C.I. cover (light duty) the weight of the cover to be not less than 23 kg complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Octroi, Toll Tax Sales tax or any other taxes imposed by the Government.	2.00 Numbers	1288.15	Rupees One Thousand Two Hundred Eighty Eight And Paise Fifteen Only		2,576.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
5	Providing and fixing 1st call sagwan wooden moulded corner beading size 32x32mm (thirty two into thirty two millimetre) (base and weight) of triangular shape to the junction of panneling s with iron screws, plugs and priming coat on unexposed surface etc. complete :and as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	17.00 Running metre	221.70	Rupees Two Hundred Twenty One And Paise Seventy Only	Running metre	3,769.00
6	Providing and fixing 15mm dia (Fifteen millimetre) nominal bore G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. complete and as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	80.00 Running metre	225.50	Rupees Two Hundred Twenty Five And Paise Fifty Only	Running metre	18,040.00
7	Providing and fixing wooden Dressing Table Big size including polishing complete and as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	1.00 Numbers	13800.00	Rupees Thirteen Thousand Eight Hundred Only	Each	13,800.00
8	Providing and fixing wall mixing faucet for shower and bath hand shower with Angular and rest holder complete and as per direction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	2.00 Numbers	1600.00	Rupees One Thousand Six Hundred Only	Each	3,200.00
9	Providing and fixing wall mixture for water outlet of standard design and of approved make conforming to IS 8931 complete and as per direction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	2.00 Numbers	6000.00	Rupees Six Thousand Only	Each	12,000.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
10	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings. or its equivalent with single hole for pillar tap with CI or MS brackets painted white including cutting holes and making good the same but excluding fitting. complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, Toll Tax Sales tax or any other taxes imposed by the Government	2.00 Numbers	1650.00	Rupees One Thousand Six Hundred Fifty Only	Each	3,300.00
11	Providing and fixing 19mm (Nineteen millimetre) thick black granite gang saw cut, mirror polished, premoulded and prepolished, machine cut for tread of steps, pantary / under counter wash basin and water trough, kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20mm (twenty millimetre) thick base cement mortar 1:4 (one cement isto 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etcetra all complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government	0.56 Square metre	3800.00	Rupees Three Thousand Eight Hundred Only	Per Square metre	2,128.00
12	Providing and fixing 15mm (Fifteen millimetre) diametre plastic tap of continental series of Jaquar / Hindon series of Jal / ESS (superior or heavy type) and colour complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government	4.00 Numbers	400.00	Rupees Four Hundred Only	Each	1,600.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
13	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in foundation and plinth and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sales tax, GST or any other taxes imposed by the Government.	0.34 Cubic metre	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic metre	1,275.00
	TOTAL					99,662.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Below Quantity checked
410220/-
 Executive Engineer, R 996621/-
 Dehra Division,
 WPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99986.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of Work:- Repair and maintenance of Civil Hospital at Dehra District Kangra (HP) (SH - Wood Work, Plastering, Distempering & Painting etc).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Taking out doors, windows and clerestory windows shutters (steel or wood) including stacking within 50 metres lead, etc. complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	5.00 Number	60.80	Rupees Sixty And Paise Eighty Only	Each	304.00
2	Providing Second class teak wood work in frames of doors, windows, clerestory window sand other frames, wrought framed and fixed in position with hold fast lugisor with dash fasteners of required dia& length (hold fast lugisor dash fastener shall be paid for separately complete upto all floor level as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	0.1915 Cubic metre	120519.10	Rupees One Lakh(s) Twenty Thousand Six Hundred Nineteen And Paise Ten Only	Per Cubic metre	23,099.00
3	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately all complete as per direction of Engineer-in charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	5.20 Square Metre	3122.50	Rupees Three Thousand One Hundred Twenty Two And Paise Sixty Only	Per Square Metre	16,238.00
4	Providing and fixing 35 mm thick Second class teak wood shutters wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws complete as per direction of Engineer-in charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	3.10 Square metre	3659.30	Rupees Three Thousand Six Hundred Sixty Nine And Paise Thirty Only	Per Square metre	11,375.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
5	Applying priming coat over new wood and wood based surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter sand papering and kitting with ready mixed paint brushing wood priming pink and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	15.1600 Square metre	38.95	Rupees Thirty Eight And Paise Ninety Five Only	Per Square metre	590.00
6	Painting two or more coat on wood work with Deluxe Multi Surface Paint of required shade applied @ 0.90ltr/10 sqm under coat of primer applied @ 0.75 ltrs/10 sqm complete including cost of priming coat complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malikhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	29.94 Square metre	94.30	Rupees Ninety Four And Paise Thirty Only	Per Square metre	2,823.00
7	Repairs to plaster of thickness 12 mm to 20 mm in Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Royalty, Malikhana, Octroi, GST, Toll Tax, Sales tax or any other taxes imposed by the Government	75.35 Square metre	399.75	Rupees Three Hundred Ninety Nine And Paise Seventy Five Only	Per Square metre	30,121.00
8	Distemping with oil bound washable distemper of (Nerolac/Asian/Dulux/Berger) approved brand and manufacture (two or more coats) of required shade on new work over and including water thinnable priming coat with cement primer to give an even shade complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	159.38 Square metre	96.85	Rupees Ninety Six And Paise Eighty Five Only	Per Square metre	15,436.00
	TOTAL					99,986.00

% Above/below

Quoted Amount in Figures

Quoted Amount in Words

Per cent 18.44% 944014 c h s e c o t & 999001
for R 97986/-

Executive Engineer
Dehra Division
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99622.00
 Earnest Money :-Rs. 2,000.00
 Time Limit :- Three Months.

Name of work:- A/R & M/O to non Residential building Building HPPWD at Dehra (SH:-Aluminium work in Hall Portion-3)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS 733 and IS 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) complete as per HPPWD specifications or as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, GST, toll tax or any taxes imposed by the Government.	134.40 Kilogramme	630.00	Rupees Six Hundred Thirty Only	Per Kilogramme	84,672.00
2	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. With float glass panes of 4.0 mm thickness (weight not less than 10 kg/ sqm) (Cost of aluminium snap beading shall be paid in basic item) complete as per the architectural drawings and the directions of engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, GST, toll tax or any taxes imposed by the Government.	13.05 Square metre	832.95	Rupees Eight Hundred Thirty Two And Paise Ninety Five Only	Per Square metre	10,870.00
3	Providing and fixing 300x16mm (Three hundred into Sixteen millimetres) nominal size aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS 1868) transparent or dyed to required colour or shade, with nuts and screws etcetera complete, including carriage of material within all leads, lifts and other incidentals and as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	6.00 Number	95.00	Rupees Ninety Five Only	Each	570.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and fixing 200x10mm (two hundred into Ten millimetres) nominal size Brass Tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS 1868) transparent or dyed to required colour or shade with nuts and screws etcetera, complete, including carriage of material within all leads, lifts and other incidentals and as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	18.00 Number	90.00	Rupees Ninety Only	Each	1,620.00
5	Providing and fixing 125x34x24 mm (one hundred twenty five into thirty four into twenty four millimetre) weighing not less than 23 (twenty three) gms size of bright finished PTMT handles with screws complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications drawing, design and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	18.00 Number	105.00	Rupees One Hundred Five Only	Each	1,890.00
	Total					99,622.00
	%Above/below					
	Quotted percentage in Figures					
	Quotted percentage in words					

Percentage 18.4 of quantity checked 7 ppd
for Rs 99622/-

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99912.00
 Earnest Money :-Rs. 2,000.00
 Time Limit :- Three Months.

Name of work:- A/R & M/O to non Residential building Building HPPWD at Dehra (SH-Aluminium work in Hall Portion-4)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS 733 and IS 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P.brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge (Glazing, paneling and dash fasteners to be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) complete as per HPPWD specifications or as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, GST, toll tax or any taxes imposed by the Government.	134.40 Kilogram	630.00	Rupees Six Hundred Thirty Only	Per Kilogram	84,672.00
2	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. With float glass panes of 4.0 mm thickness (weight not less than 10 kg/ sqm) (Cost of aluminium snap beading shall be paid in basic item) complete as per the architectural drawings and the directions of engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, GST, toll tax or any taxes imposed by the Government.	13.05 Square metre	832.95	Rupees Eight Hundred Thirty Two And Paise Ninety Five Only	Per Square metre	10,870.00
3	Providing and fixing 300x15mm (Three numbered into Sixteen millimetres) nominal size aluminium sliding door bolts ISI marked, anodised (anodic coating not less than grade AC 10 as per IS 1868) transparent or dyed to required colour or shade, with nuts and screws etcetera complete, including carriage of material within all leads, lifts and other incidentals and as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	5.00 Number	95.00	Rupees Ninety Five Only	Each	570.00

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and fixing 200x10mm (two hundred into Ten millimetres) nominal size Brass Tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with nuts and screws etcetera, complete, including carriage of material within all leads, lifts and other incidentals and as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government	20.00 Number	85.00	Rupees Eighty Five Only	Each	1,700.00
5	Providing and fixing 125x34x24 mm (one hundred twenty five into thirty four into twenty four millimetre) weighing not less than 23 (twenty three) gms size of bright finished PTMT handles with screws complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications drawing, design and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	20.00 Number	105.00	Rupees One Hundred Five Only	Each	2,100.00
	Total					99,912.00
	%Above/below					
	Quotted percentage in Figures					
	Quotted percentage in words					

Percentage/Billed 9991200/146
 9991200/146
 79912/-

Executive Engineer
 Dehra Division
 H.P.W.D. Dehra