

NO. PWF/CB/2nd C /Tender/2025:-
To,

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

4797-4822 Dated:-

8/09/2025


The Executive Engineer, (IT Cell),
Nirman Bhawan, Nigam Vihar Shimla-2
e-mail:- cc-pwd-hp@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of HP letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
*NOTICE INVITING TENDER***

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 15.09.2025 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 16.09.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 17.09.2025 upto 11.00AM |
| 4. Date and time of opening of tenders: | 18.09.2025 at 11.30 AM |

The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class o Contracto
1	Restoration of Rain Damages on Lohali to Bhatoli road km 0/0 to 2/0 (SH:- Removal of slips, maintenance of drain and shoulder.	99196/-	2000/-	One Month	350/-	Class D&C
2	Restoration of Rain Damages on link road from Ludhiar to Garan via Sidhpurghar Jhaloon Harnota Larth Chakwari road(SH:- Removal of slips, maintenance of drain and shoulder.	99994/-	2000/-	One Month	350/-	Class D&C
3	Restoration of rain damages on Hatli Khadoun Kuthar Mohar Takwal road km 0/0 to 10/855 (SH:- C/o Unlined drain and removal of slips in various reaches in km 0/0 to 9/0)	98071/-	2000/-	One Month	350/-	Class D&C
4	Restoration of rain damages on various roads under Fatepur Sub Division HPPWD Fatehpur Section-II Maira Palli (SH:- C/o Unlined drain and removal of slips in various road selected reaches of roads.	98100/-	2000/-	One Month	350/-	Class D&C
5	Restoration of rain damages on Badukhar Hatli Khas Moukhar road km 2/0 to 18/200 (SH:- C/o Unlined drain and removal of slips in various reaches km 2/0 to 10/0)	97538/-	2000/-	One Month	350/-	Class D&C
6	Restoration of rain damages on various road under Fatehpur Sub Division HPPWD Fatehpur Section-I Fatehpur (SH:- C/o unlined drain and removal of slips in various road) (Selected reaches of roads.)	96114/-	2000/-	One Month	350/-	Class D&C
7	Restoration of rain damages on various road under Dhameta Sub Division Section -I (SH:- Hiring of Tractor with trolley for removal of debris).	61250/-	1300/-	One Month	350/-	Class D&C
8	A/R & M/O Various roads under Fatehpur Sub-Division, HPPWD, Fatehpur Section-II (SH:- P/L Granular Sub base, unlined drain in Hill sides, trimming of grass & weeds at Various RDs on various roads under Section-II Fatehpur.	99210/-	2000/-	One Month	350/-	Class D&C
9	Restoration of rain damages on various road under Dhameta Sub Division Section -I (SH:- Hiring of Tractor with trolley for removal of debris).	61250/-	1300/-	One Month	350/-	Class D&C
10	Construction of various roads under Sub Division Fatehpur HPPWD Fatehpur (SH:- Painting lettering on roads sign boards and km stones etc.)	99993/-	2000/-	One Month	350/-	Class D&C
11	A/R & M/O Various roads under Fatehpur Sub-Division, HPPWD, Fatehpur Section-II (SH:- P/L Granular Sub base,unlined drain in Hill sides, trimming of grass & weeds at Various RDs on various roads under Section-II Fatehpur.	99327/-	2000/-	One Month	350/-	Class D&C
12	Construction of various roads under Sub Division Fatehpur HPPWD Fatehpur (SH:- Painting lettering on road sign boards and km stones etc.	99993/-	2000/-	One Month	350/-	Class D&C

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.

3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender from shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. **Only two tenders form will be issued to the contractor/ firms which may be noted.**
6. **The Contractor complete the work with in stipulated period if fail do the work will be rescinded and E/money be forfeited without any notice**
7. The intending contractors are requested to see the site of the work before submitting the tender.
8. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
9. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
10. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Fatehpur Division RPPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damages on Lohali to Bhatoli road km.0/00 to 2/00 (SH:- Removal of slips, maintenance of drain and shoulder)

Estimated Cost:- Rs.99196/- only
Earnest Money:- Rs.2000/- only
Time limit:- One Month

Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.
			In figures.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto a any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	381.25 cubic meter	103.00	Rupees One Hundred Three Only	Per cubic meter	39269.00
2	Construction of unlined surface drains of average cross-sectional area 0.40 square meter (zero point forty square meter) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3mtr. (three meter) and lead of 50mtr. (fifty meter) (average lead 25metre) as per technical specification clause 307 Manual Means as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	750.00 Running meter	45.20	Rupees Forty Five And Paise Twenty Only	Per Running meter	33900.00
3	Making up loss of materials/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads and lifts as per technical specification clause 1903 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	743.62 square meter	35.00	Rupees Thirty Five Only	Per square meter	26027.00
					Total:-	99196.00
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 PWD
 Fatehpur Division
 Fatehpur Distt. Allahabad (U.P.)

SCHEDULE OF QUANTITY

Estimated Cost:- Rs.99994/- only
 Earnest Money:- Rs.2000/- only
 Time limit:- One Month

Name of Work:- Restoration of Rain Damages on Link road from Ludhian to Garan via Sidhpurghar Jhaloon Harnota
 Lath Chakwari road (SH:- Removal of slips, maintenance of drain and shoulder)

Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.
			In figures.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto a any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	350.50 cubic meter	98.00	Rupees Ninety Eight Only	Per cubic meter	34349.00
2	Construction of unlined surface drains of average cross-sectional area 0.40 square meter (zero point forty square meter) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3mtr. (three meter) and lead of 50mtr. (fifty meter) (average lead 25metre) as per technical specification clause 307 Manual Means as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1160.00 Running meter	45.20	Rupees Forty Five And Paise Twenty Only	Per Running meter	52432.00
3	Making up loss of materials/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads and lifts as per technical specification clause 1903 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	377.50 square meter	35.00	Rupees Thirty Five Only	Per square meter	13213.00
					Total:-	99994.00
	Amount quoted by the contractor in % Above/Below					

[Signature]
 Executive Engineer
 Patanjali Division
 Patanjali Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Hatli Khadoun Kuthar Mohar Takwal road Km. 0/0 to 10/855 Estimated Cost:- Rs.98071/- only
(SH:- Construction of Unlined drain and removal of slips in various Reaches in Km. 0/0 to 9/0) Earnest Money:- Rs.2000/- only

Time limit:- One Month

Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.
			In figures.	In words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 square meter (zero point forty square meter) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3mtr. (three meter) and lead of 50mtr. (fifty meter) (average lead 25metre) as per technical specification clause 307 Manual Means as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	250.00 Running meter	60.45	Rupees Sixty And Paise Forty Five Only	Per Running meter	15113.00
2	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto a any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	750.75 cubic meter	110.50	Rupees One Hundred Ten And Paise Fifty Only	Per cubic meter	82958.00
					Total:-	98071.00
	Amount quoted by the contractor in % Above/Below					


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various road under Fatehpur Sub Division HPPWD Fatehpur					Estimated Cost:- Rs.98100/- only	
Section-II Maira Palli (SH:- Construction of Unlined drain and removal of slips in various road (Selected Reaches of roads))					Earnest Money:- Rs.2000/- only	
					Time limit:- One Month	
Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.
			In figures.	In words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 square meter (zero point forty square meter) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3mtr. (three meter) and lead of 50mtr. (fifty meter) (average lead 25metre) as per technical specification clause 307 Manual Means as per direction of Engineer – in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	500.00 Running meter	60.45	Rupees Sixty And Paise Forty Five Only	Per Running meter	30225.00
2	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto a any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	614.25 cubic meter	110.50	Rupees One Hundred Ten And Paise Fifty Only	Per cubic meter	67875.00
					Total:-	98100.00
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Badukhar Hatli Khas Moukhar road Km. 2/0 to 18/200 (SH:- Construction of Unlined drain and removal of slips in various reaches km.2/0 to 10/0)				Estimated Cost:- Rs.97538/- only	
				Earnest Money:- Rs.2000/- only	
				Time limit:- One Month	
Sr. No.	Description of items	Quantity	Rate		Amount.
			In figures.	In words	
1	Construction of unlined surface drains of average cross-sectional area 0.40 square meter (zero point forty square meter) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3mtr. (three meter) and lead of 50mtr. (fifty meter) (average lead 25metre) as per technical specification clause 307 Manual Means as per direction of Engineer – in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	210.00 Running meter	60.45	Rupees Sixty And Paise Forty Five Only	12695.00
2	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto a any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	767.81 cubic meter	110.50	Rupees One Hundred Ten And Paise Fifty Only	84843.00
				Total:-	97538.00
	Amount quoted by the contractor in % Above/Below				


Executive Engineer
 Fatehgarh Division HPPWD
 Fatehgarh Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various road under Fatehpur Sub Division HPPWD Fatehpur Section-I Fatehpur (SH:- Construction of Unlined drain and removal of slips in various road) (Selected Reaches <i>of roads</i>)					Estimated Cost:- Rs.96114/- only	
					Earnest Money:- Rs.2000/- only	
					Time limit:- One Month	
Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.
			In figures.	In words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 square meter (zero point forty square meter) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3mtr. (three meter) and lead of 50mtr. (fifty meter) (average lead 25metre) as per technical specification clause 307 Manual Means as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	280.00 Running meter	60.45	Rupees Sixty And Paise Forty Five Only	Per Running meter	16926.00
2	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto a any leads and lifts as per technical specification 302.3.5 and 1611 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	716.63 cubic meter	110.50	Rupees One Hundred Ten And Paise Fifty Only	Per cubic meter	79188.00
					Total:-	96114.00
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various road Under Dhameta Sub-Division (Section-I) (SH:- Hiring of Tractor with trolley for removal of debris).				Estimated cost:- Rs.61250/- only		
				Earnest Money:- Rs.1300/-		
				Time limit:- One Month		
Sr. No	Description of items	Quantity	In words	Rate	Unit	Amount
				In figures		
1	Hiring of tractor with trolley 3 to 5 tonne (three to five tone) capacity trip on through rate bases for transportation of material like mix material, granular sub base, river shingle etc. for filling in road formation, berms etc. complete in all respect as per direction of entire satisfaction of the Engineer-in-charge. The cost of lubricant, diesel oil, repair maintenance will be borne by the contractor.	125.00 Hours	490.00	Rupees Four Hundred Ninety Only	Per Hour.	61250.00
					Total:-	61250.00
	Amount quoted by the contractor in % Above/Below					
	Terms and Conditions:-					
1	Hire charges should be including of all expenses i.e. fuel, lubricant and on account of establishment for major /minor repair, loading and deployment of all equipment required.					
2	Hire charges should a also include insurance of machine and establishment. Department will not responsible for fatal and non fatal accident.					
3	The minimum quantity of material should not be less than 5 (Five) tonne/trip.					


 Engineer
 Sub-Division HPPMD
 (Fatehpur, Mangra) H.P.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Fatehpur Sub-Division, HPPWD, Fatehpur Section-II (SH):- Providing and laying Granular Sub Base, unlined drain in Hill sides, trimming of grass & weeds at various R.D.'s on various roads under Section-II Fatehpur)				Estimated Cost:- Rs. 99210/- only	
				Earnest Money:- Rs.2000/- only	
				Time limit:- One Month	
Sr. No.	Description of items	Quantity	Rate		Amount.
			In words	In figures.	
1	Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.4 as per technical specification clause 408 Using naturally occurring gravel as per the entire satisfaction and direction of Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	37.50 Cubic meter.	850.60	Rupees Eight Hundred Fifty And Paise Sixty Only	31898.00
2	Making up loss of materials/Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads and lifts as per technical specification clause 1903 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1000.00 Square meter	43.70	Rupees Forty Three And Paise Seventy Only	43700.00
3	Construction of unlined surface drain of average cross-sectional area 0.4 sqm (Zero point four) Square metre in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site Mechanical Means as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	320.00 Running metre	55.10	Rupees Fifty Five And Paise Ten Only	17632.00
4	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications clause 1914 as per direction of Engineer – in- Charge including carriage of materials, within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2600.00 Square meter	2.30	Rupees Two And Paise Thirty Only	5980.00
				Total:-	99210.00
	Amount quoted by the contractor in % Above/Below				


 Engineer
 Fatehpur Division HPPWD
 Fatehpur (Kangra) H 4

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on various road Under Dhameta Sub-Division (Section-I) (SH:- Hiring of Tractor with trolley for removal of debris).				Estimated cost:- Rs.61250/- only		
				Earnest Money:- Rs.1300/-		
				Time limit:- One Month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Hiring of tractor with trolley 3 to 5 tonne (three to five tone) capacity trip on through rate bases for transportation of material like mix material, granular sub base, river shingle etc. for filling in road formation, berms etc. complete in all respect as per direction of entire satisfaction of the Engineer-in-charge. The cost of lubricant, diesel oil, repair maintenance will be borne by the contractor.	125.00 Hours	490.00	Rupees Four Hundred Ninety Only	Per Hour.	61250.00
					Total:-	61250.00
	Amount quoted by the contractor in % Above/Below					
	Terms and Conditions:-					
1	Hire charges should be including of all expenses i.e. fuel, lubricant and on account of establishment for major /minor repair, loading and deployment of all equipment required.					
2	Hire charges should a also include insurance of machine and establishment. Department will not responsible for fatal and non fatal accident.					
3	The minimum quantity of material should not be less than 5 (Five) tonne/trip.					

Executive Engineer
Fatehpur Division HPPWD
Fatehpur (Kangra) H.P.

SCHEDULE OF QUANTITY

Name of work:- Construction of various roads Under Sub Division Fatehpur HPPWD Fatehpur (SH:- Painting Lettering on road sign boards and Km. stones etc.)							Estimated Cost:- Rs.	99993.00
							Earnest Money:- Rs.	2000.00
							Time limit:- Tne Months	
Sr. No.	Description of items	Quantity	Rate		Unit.	Amount.		
			In words	In figures				
1	Painting steel work with Deluxe Multi Surface paint to give an even shade Two or more coat applied @ 0.90 ltr/10 sam (Zero point nine zero litre/ten square meter) over an under coat of primer @ 0.80 ltr./10 sqm (Zero point eight zero litre/ ten square meter) of approved bran and manufacture as required including carriage of material with in all leads and lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	22.50	99.20	Rupees Ninety Nine And Paise Twenty Only	Per square metre	2232.00		
2	Finishing walls with textured exterior paint shade Old work (one or more coats) applied @ 1.82 Ltr./10 Sqm. (Zero point eight two litre/ten square meter)including carriage of material with in all leads and lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	20.00	95.30	Rupees Ninety Five And Paise Thirty Only	Per square metre	1906.00		
3	Writing letters of figures on any surface with black japan paint (Stop commas, hyphens and like not to be measured and paid separately)							
	(a) Indian Letter/Figure.	18650.00	3.30	Rupees Three And Paise Thirty Only	Per letter Per centi metre Height	61545.00		
	(b) Block letter/Figure.	10300.00	3.20	Rupees Three And Paise Twenty Only	Per letter Per centi metre Height	32960.00		
4	Painting index hand normal size or arrows (up to 40cm) long on any surfaces either black japan paint including carriage of material with in all leads & lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	20.00	67.50	Rupees Sixty Seven And Paise Fifty Only	Per Figure	1350.00		
					Total:-	99993.00		
	Amount quoted by the contractor in % Above/Below							


 Engineer
 Fatehpur Division, HPPWD
 Fatehpur (Kargila) H

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Fatehpur Sub-Division, HPPWD, Fatehpur Section-II (SH:- Providing and laying Granular Sub Base, unlined drain in Hill sides, trimming of grass & weeds at various R.D.'s on various roads under Section-II Fatehpur)				Estimated Cost:- Rs. 99327/- only		
				Earnest Money:- Rs.2000/- only		
				Time limit:- One Month		
Sr. No.	Description of items	Quantity	In words	Rate		Amount.
				In figures.	Unit.	
1	Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.4 as per technical specification clause 408 Using naturally occurring gravel as per the entire satisfaction and direction of Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	32.50 Cubic meter.	850.60	Rupees Eight Hundred Fifty And Paise Sixty Only	Per cubic meter	27645.00
2	Making up loss of materials/Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads and lifts as per technical specification clause 1903 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1100.00 Square meter	43.70	Rupees Forty Three And Paise Seventy Only	Per square meter	48070.00
3	Construction of unlined surface drain of average cross-sectional area 0.4 sqm (Zero point four) Square metre in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site Mechanical Means as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	320.00 Running metre	55.10	Rupees Fifty Five And Paise Ten Only	Per Running metre	17632.00
4	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications clause 1914 as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2600.00 Square meter	2.30	Rupees Two And Paise Thirty Only	Per square meter	5980.00
Amount quoted by the contractor in % Above/Below					Total:-	99327.00

[Signature]
 Engineer
 Sub-Division HPPWD
 Fatehpur, (Kargil) H.A.

SCHEDULE OF QUANTITY

Name of work:- Construction of various roads Under Sub Division Fatehpur HPPWD Fatehpur (SH:- Painting Lettering on road sign boards and Km. stones etc.) Job No.-1									
Estimated Cost:- Rs. 99993.00									
Earnest Money:- Rs. 2000.00									
Time limit:- The Months									
Sr. No.	Description of items	Quantity	Rate		Unit	Amount.			
			In words	In figures					
1	Painting steel work with Deluxe Multi Surface paint to give an even shade Two or more coat applied @ 0.90 ltr/10 sam (Zero point nine zero litre/ten square meter) over an under coat of primer @ 0.80 ltr./10 sqm (Zero point eight zero litre/ ten square meter) of approved bran and manufacture as required including carriage of material with in all leads and lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government	22.50	99.20	Rupees Ninety Nine And Paise Twenty Only	Per square metre	2232.00			
2	Finishing walls with textured exterior paint shade Old work (one or more coats) applied @ 1.82 Ltr./10 Sqm. (Zero point eight two litre/ten square meter)including carriage of material with in all leads and lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government	20.00	95.30	Rupees Ninety Five And Paise Thirty Only	Per square metre	1906.00			
3	Writing letters of figures on any surface with black japan paint (Stop commas, hyphens and like not to be measured and paid separately)								
	(a) Indian Letter/Figure.	18650.00	3.30	Rupees Three And Paise Thirty Only	Per letter Per centi metre Height	61545.00			
	(b) Block letter/Figure.	10300.00	3.20	Rupees Three And Paise Twenty Only	Per letter Per centi metre Height	32960.00			
4	Painting index hand normal size or arrows (up to 40cm) long on any surfaces either black japan paint including carriage of material with in all leads & lifts. The rate including octroi, royalty, malkana toll tax,sale tax, GST or other taxes imposed by the Government.	20.00	67.50	Rupees Sixty Seven And Paise Fifty Only	Per Figure	1350.00			
					Total:-	99993.00			
	Amount quoted by the contractor in % Above/Below								



 Engineer
 Fatehpur Division HPPWD
 Fatehpur (Kangra)