



OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG

PH: 01907-222229 Fax: 222229, e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024-

S392

Dated:- 4-9-2025

To

✓ The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :-

Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.

Executive Engineer,
B&R Division,
HP PWD Karsog

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , E-mail : ce-kar-hp@nic.in**

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **15.09.2025 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 12.09.2025** for which the application should reach in this office **upto 1.00 PM 12.09.2025**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Bakhrot Sanarli Kelodhar road Km. 0/00 to 41/800 (SH:- C/o R/wall at RD 6/970 to 6/977.50)	4,77,583/-	9,600/-	Two months	350/-
2	R/R damages on Chindi Pangna road Km. 0/00 to 12/480 (SH:- C/o PCC R/wall at RD 7/850 to 7/860)	2,73,971/-	5,500/-	Two months	350/-
3	R/O Restoration of road damaged on Karsog Kao to village Lol and Dogri Km. 0/00 to 5/00 (SH:- C/o R/wall at RD 0/015 to 0/045)	3,67,511/-	7,400/-	Two months	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.

6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP, PWD.
9. As per Govt. Notification PW/CTR/32-20 Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

Executive Engineer
B&R Division
HPPWD Karsog

No. PW-B-Tender-NIT/2023-26-

53,86-91

Dated:- 4-9-2023

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Schedule of Quantity

Estimated Cost 477583
Earnest Money 9600
Time Two Month

Name of Work:- R/R Damages on Bakhrot Sanarli Kelodhar Luhri road Km. 0/00 to 41/800 (SH:- C/O R/Wall at RD 6/970 to 6/977.50)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with lift upto any meter and lead upto any meter as per technical specification clause 1603.1.1 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals	18.45	Per Cubic Metre	185.00	3413.00	Rupees Three Thousand Four Hundred Thirteen and Paise Zero Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	41.74	Per Cubic Metre	355.00	14818.00	Rupees Fourteen Thousand Eight Hundred Eighteen and Paise Zero Only
3	Providing and laying concrete for plain/reinforcement concrete 1:4:8 (one cement : eight sand : eight graded stone aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	81.38	Per Cubic Metre	5400.00	439452.00	Rupees Four Lakhs Thirty Nine Thousand Four Hundred Fifty Two and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.73	Per Cubic Metre	1150.00	12340.00	Rupees Twelve Thousand Three Hundred Forty and Paise Zero Only
5	Providing weepholes in bricks masonry/stone masonry plain/reinforced complete abutment wing wall, return wall with 100 mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 70, 1204.3.7 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	21.00	Each	360.00	7560.00	Rupees Seven Thousand Five Hundred Sixty and Paise Zero Only
Total in Figures					477583.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
AHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

273971
5500
Two Months

Name of Work:- R/R Damages on Chindi Pangna road Km. 0/00 to 12/480 (SH:- C/O PCC R/Wall at RD 7/850 to 7/860).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	21.35	Per Cubic Metre	350.00	7473.00	Rupees Seven Thousand Four Hundred Seventy Three and Paise Zero Only
2	Providing and laying concrete for plain/reinforcement concrete 1:4:8 (one cement : eight sand : eight graded stone aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	44.65	Per Cubic Metre	5500.00	245575.00	Rupees Two Lakhs Forty Five Thousand Five Hundred Seventy Five and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.30	Per Cubic Metre	1150.00	16445.00	Rupees Sixteen Thousand Four Hundred Forty Five and Paise Zero Only
4	Providing weepholes in bricks masonry/stone masonry plain/reinforced complete abutment wing wall, return wall with 100 mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 70, 1204.3.7 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	12.00	Each	373.15	4478.00	Rupees Four Thousand Four Hundred Seventy Eight and Paise Zero Only
Total in Figures					273971.00	
Quoted Rate in Figures						
Quoted Rate in Words					0.00	

Executive Engineer,
Karsog Division,
SHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 367511
 Earnest Money 7400
 Time Two Months

Name of Work:- R/O Restoration of road Damaged on Karsog Kao to village Lol and dogri km 0/00 to 5/00 (Sh:- C/O R/Wall at km 0/015 to 0/045)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	35.10	Per Cubic Metre	355.00	12461.00	Rupees Twelve Thousand Four Hundred Sixty One and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:4:8.(one cement: four sand: eight graded stone aggregate as per direction of Engineer in charge including carriage of materials with in all lead and lifts and other incidentals As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	57.60	Per Cubic Metre	5500.00	316800.00	Rupees Three Lakhs Sixteen Thousand Eight Hundred and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of	27.00	Per Cubic Metre	1150.00	31050.00	Rupees Thirty One Thousand Fifty and Paise Zero Only
4	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Per Cubic Metre Each	360.00	7200.00	Rupees Seven Thousand Two Hundred and Paise Zero Only
Total In Figures					367511.00	
Quoted Rate In Figures					0.00	
Quoted Rate In Words						

Executive Engineer,
 Karsog Division,
 PAPPWD, Karsog.