

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed percentage rate tender on form No. 6 and 8 are hereby invited by the Executive Engineer (NH) Division HPPWD Nahan on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on **15.09.2025** up to 11:00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to **12.09.2025 04:00 PM**

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer NH Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 120 days.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form
1	A/R & M/O to Kala Amb Paonta Sahib Dehradun road km 46/00 to 103/00 (SH:-Hiring of Tipper for carriage of debris between Km 46/00 to 60/00).	97,4,98/-	2000/-	01 Month	350/-
2	A/R & M/O to Kala Amb Paonta Sahib Dehradun road km 46/00 to 103/00 (SH:-Hiring of Tipper for carriage of debris between Km 60/00 to 83/00).	97,4,98/-	2000/-	01 Month	350/-
3	A/R & M/O to Kala Amb Paonta Sahib Dehradun road km 46/00 to 103/00 (SH:-Providing and fixing road side furniture on NH-07 (Road Safety)).	94,6,70/-	2000/-	15 Days	350/-
4	A/R & M/O to Nahan Do Saraka Sarahan Kumarhatti Road on NH-907A km 0/00 to 78/00 (SH:- Providing and supplying of Convex safety mirror & sign board on NH-907A km 0/00 to 5/00) (Road Safety).	99,7,85/-	2000/-	15 Days	350/-
5	A/R & M/O to Nahan Do Saraka Sarahan Kumarhatti Road on NH-907A km 0/00 to 78/00 (SH:- Hiring of Tipper for carriage of debris between km 0/00 to 20/00)	97,4,98/-	2000/-	01 Month	350/-
6	A/R & M/O to Nahan Do Saraka Sarahan Kumarhatti Road on NH-907A km 0/00 to 78/00 (SH:- Hiring of Excavator cum loader for removal of slips in km 10/00 to 20/00 for ensuing monsoon season in 2025-26)	99,7,50/-	2000/-	3 Months	350/-
7	A/R & M/O to Nahan Do Saraka Sarahan Kumarhatti Road on NH-907A km 0/00 to 78/00 (SH:- Hiring of Excavator cum loader for removal of slips in km 0/00 to 10/00 for ensuing monsoon season in 2025-26))	99,7,50/-	2000/-	3 Months	350/-

CERTIFICATE:- It is certified that the tenders of above work are exigency/emergent nature and in public interest.

Terms & Conditions:-

1. The Contractors/Bidders must quote their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.

6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The provision of guidelines issued vide the Principal Secretary (PW) to the Govt. of H.P, Shimla vide notification No. PBW (B) A (3) 1/2020-I dated Shimla-2 the 22nd July, 2020 and 07.10.2021 regarding adoption of CPWD work manula 2019 & other publication of CPWD in HPPWD Shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.


Executive Engineer
NH Division HPPWD
Nahan

For & on behalf of Governor of Himachal Pradesh
dated:- 05-09-2025

No. PW/NHD-NHN/TA-Tender Notice/ 2025-26: 2770-98

Copy along with NIT is forwarded to the following for kind information and necessary action please:-

- 1 The Engineer in Chief HPPWD Nirman Bhawan, Niagam Bihar Shimla.
- 2 The Chief Engineer (NH) HPPWD Shimla please.
- 3 The Deputy Commissioner, Sirmour at Nahan please.
- 4 The Superintending Engineer (NH) Circle HPPWD Shimla with the request to issue necessary certificate regarding display of above tender notice in the notice board of Circle office in view of the Principal Secretary (PW) to the H.P. notification No. PBW(B) A (3)1/2020 dated Shimla-2 the 07 January, 2021 and even file No. PBW (B) A (3) dated 16 July, 2021 please.
- 5 The Executive Engineer (IT Cell), to the Engineer-in-Chief HPPWD, Nigam Vihar, HPPWD Shimla-2 alongwith Schedule of Quantity through (email) for taking necessary action in view of Principal Secretary (PW) to the H.P. notification No. PBW (B) A (3) dated 16 July, 2021 please for uploading of Notice Inviting Tender on departmental website please.
- 6 The Sub-Divisional Magistrate Nahan/ Paonta Sahib please.
- 7 The District Panchayat Officer, Nahan please.
- 8 The Executive Officer, Municipal Committee Nahan/ Paonta Sahib please.
- 9 All the Assistant Engineer under this division to display on their respective Notice Boards.
- 10 Notice Board of this Office.


Executive Engineer
NH Division HPPWD
Nahan

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O to Kala Amb Paonta Sahib Dehradun road Km 46/00 to 103/00 (SH :-Hiring of Tipper for carriage of debris between km 60/00 to 83/00).				Estimated cost :-		Rs.97498/- only
				Earnest Money :-		RS.2000/-only
				Time Limit :-		01 Month.
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word
1	2	3		4	5	7
1	Hiring of tipper (5.5 cum) of Light commerical vehicaltegrory for carriage of earth/debris/holder and other contruction materials from various location etc. Including wiges of tipper driver I cleaner including P.O.I. Any repair/damaged during the work will be absolute responsibility of the contractor. Any accidental and other damages to public and private properties occurred during working hours is the sole responsibility of the contractor No payment will be made of holidays as will as on Sunday if there is no work to the entire satisfaction as per direction of the Engineer-in-Charge.	58.00	Per hour	1681.00	97498.00	Rupees Ninety seven thousand four hundred ninety eight only
		Total :-			97498.00	Rupees Ninety seven thousand four hundred ninety eight only
Quoted Rate % (Percentage) in Figures				(+) / (-)		
Quoted Rate % (Percentage) in Words						

Note:-1 The payment will be made only for working hours.

2 Machinery must be made available within one hour on emergency call by the Engineer-in-Charge.

3 Draft schedule of quantity recommended for approval please.


 Executive Engineer
 NH Division
 HPPWD Nahar

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O to Kala Amb Paonta Sahib Dehradun road Km 46/00 to 103/00 (SH :-Hiring of Tipper for carriage of debris between km 46/00 to 60/00).				Estimated cost :-		Rupees/- only
				Earnest Money :-		RS.2000/-only
				Time Limit :-		01 Month.
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word
1	2	3		4	5	7
1	Hiring of tipper (5.5 cum) of Light commercial vehicaltegrory for carriage of earth/debris/holder and other contruction materials from various location etc. Including wiges of tipper driver I cleaner including P.O.I. Any repair/damaged during the work will be absolute responsibility of the contractor. Any accidental and other damages to public and private properties occurred during working hours is the sole responsibility of the contractor No payment will be made of holidays as will as on Sunday if there is no work to the entire satisfaction as per direction of the Engineer-in-Charge.	58.00	Per hour	1681.00	97498.00	Rupees Ninety seven thousand four hundred ninety eight only
Total :-					97498.00	Rupees Ninety seven thousand four hundred ninety eight only
Quoted Rate % (Percentage) in Figures			(+) / (-)			
Quoted Rate % (Percentage) in Words						

- Note:-1 The payment will be made only for working hours.
 2 Machinery must be made available within one hour on emergency call by the Engineer-in-Charge.
 3 Draft schedule of quantity recommended for approval please.


 Executive Engineer
 NH Division
 HPPWD Nahar

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O to Nahan Do Sarka Sarahan Kumarhatti road Km 0/00 to 20 00 (SH :-Hiring of Tipper for carriage of debris between km 0/00 to 20/00).				Estimated cost :- Earnest Money :- Time Limit :-		Rs.97498/- only RS.2000/-only 01 Month.
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word
1	2	3		4	5	7
1	Hiring of tipper (5.5 cum) of Light commercial vehicaltegrory for carriage of earth/debris/holder and other contruction materials from various location etc. Including wiges of tipper driver I cleaner including P.O.I. Any repair/damaged during the work will be absolute responsibility of the contractor. Any accidental and other damages to public and private properties ocured during working hours is the sole responsibility of the contractor No payment will be made of holidays as will as on Sunday if there is no work to the entire satisfaction as per direction of the Engineer-in-Charge.	58.00	Per hour	1681.00	97498.00	Rupees Ninety seven thousand four hundred ninety eight only
Total :-					97498.00	Rupees Ninety seven thousand four hundred ninety eight only
Quoted Rate % (Percentage) in Figures						
Quoted Rate % (Percentage) in Words						

Note:-1 The payment will be made only for working hours.

2 Machinery must be made available within one hour on emergency call by the Engineer-in-Charge.

3 Draft schedule of quantity recommended for approval please.


 Executive Engineer
 NH Division
 HPPWD Nahan

SCHEDULE OF QUANTITY						
Name of Work:-A/R & M/O to Nahan Do Sarka Sarahan Kumarhatti road Km 0/00 to 78/00 (SH :-Hiring of Excavator cum loader for removal of Slips in km 10/00 to 20/00 for ensuing moonsoon season in 2025-26).			Estimated cost :-		Rs.99750/- only	
			Earnest Money :-		RS.2000/-only	
			Time Limit :-		03 Month.	
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word
1	2	3		4	5	7
1	Hiring of Excavator-Cum-loader having Bucket capacity @ 45 cum per hour i/c operating and service staff as required , POL including full time chowkidar for machine complete in all respect. Any loss or damage caused by/to the machinery during transit or at site of work shall be responsibility of the contractor and will be born by the contractor at his own cost. The break down or any kind of hindrence charges of machinery or operating staff shall be met out of his own cost. Other conditions shall be subject to the various clauses of contract aggrement including all leads, lifts and carriage as per entire satisfaction of Engineer-in-charge.	95.00	Per hour	1050.00	99750.00	Rupees Ninety nine thousand seven hundred fifty only
					99750.00	Rupees Ninety nine thousand seven hundred fifty only
Quoted Rate % (Percentage) in Figures		(+) / (-)				
Quoted Rate % (Percentage) in Words						

The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.


Executive Engineer
NH Division
HPPWD Nahana

SCHEDULE OF QUANTITY						
Name of Work:-A/R & M/O to Nahan Do Sarka Sarahan Kumarhatti road Km 0/00 to 78/00 (SH :-Hiring of Excavator cum loader for removal of Slips in km 0/00 to 10/00 for ensuing moonsoon season in 2025-26).				Estimated cost :- Earnest Money :- Time Limit :-		Rs.99750/- only RS.2000/-only 03 Month.
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word
1	2	3		4	5	7
1	Hiring of Excavator-Cum-loader having Bucket capacity @ 45 cum per hour i/c operating and service staff as required , POL including full time chowkidar for machine complete in all respect. Any loss or damage caused by/to the machinery during transit or at site of work shall be responsibility of the contractor and will be born by the contractor at his own cost. The break down or any kind of hindrence charges of machinery or operating staff shall be met out of his own cost. Other conditions shall be subject to the various clauses of contract aggrement including all leads, lifts and carriage as per entire satisfaction of Engineer-in-charge.	95.00	Per hour	1050.00	99750.00	Rupees Ninety nine thousand seven hundred fifty only
Total :-					99750.00	Rupees Ninety nine thousand seven hundred fifty only
Quoted Rate % (Percentage) in Figures			(+) / (-)			
Quoted Rate % (Percentage) in Words						


The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.


Executive Engineer
NH Division
HPPWD Nahan

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O to Kala Amb Paonta Sahib Dehradun road on NH-07 Km 46/00 to 103/00 (SH:- Providing and fixing road side furniture on NH-07 (Road Safety)							Estimated cost :-	Rs.94670.00/- only
							Earnest Money :-	RS.2000/-only
							Time Limit :-	15 days.
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word		
1	2	3		4	5	7		
1	Providing and fixing of retro- reflectorised cautionary, mandatory and informatory sign as per IRC :67 made of Class-B Type IV retro reflective sheeting fixed over 2 mm thick Aluminium sheeting vide clause 801.3, 3mm/4mm thick Aluminium composite material sheet depending on the size of the sign fixed over back support frame of min 25 x 25 x 3mm Angle mounted on a mild steel circular pipe 65 NB ,3.2 mm thickness firmly fixed to the ground by means of properly designed foundation with M25 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing. The sign shall be maintained as per section 12 of IRC 67, including all leads, lifts and carriage of materials as per the direction and entire satisfaction of the Engineer-in-charge.	8.00	Nos	6054.70	48438.00	Rupees Forty eight thousand four hundred thirty eight only		
	90cm equilateral triangle (Cautionary Sign Board)	6.00	Nos	7705.35	46232.00	Rupees Forty six thousand two hundred thirty two only		
	80 mm x 60 mm rectangular (Informatory Sign Board)				94670.00	Rupees Ninety four thousand six hundred seventy only		
	Total :-							
		(+) / (-)						
Quoted Rate % (Percentage) in Figures								
Quoted Rate % (Percentage) in Words								

The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government


 Executive Engineer
 NH Division
 HPPWD Nahan

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY									
Name of work:- A/R & M/O to Nahana Do Sarka Sarahan Kumarhatti Road on NH-907A Km 0/00 to 78/00 (SH:- Providing and fixing road side furniture on NH 907A km 0/00 to 5/00) (Road Safety)									
		Estimated cost :-			Rs.99785.00/- only				
		Earnest Money :-			RS.2000/-only				
		Time Limit :-			15 days.				
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word			
1	2	3		4	5	7			
1	Providing and supplying of Convex safety mirror complete with mounting hardware having polycarbonate reflective mirror made of polycarbonate and outdoor use with hood made of ABS fiber, plastic dimension 80cm complete with clamps, nut bolt and fittings and post of 50mm dia G.I. pipe and as per direction of the Engineer-in-Charge including carriage of material within all leads and lift and other incidentals. The rate includes sale tax, octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the contractor.								
	Convex Safety Mirror	4.00	Nos	15864.35	63457.00	Rupees Sixty three thousand four hundred fifty seven only			
	Providing and fixing of retro- reflectorised cautionary, mandatory and informatory sign as per IRC :67 made of Class-B Type IV retro reflective sheeting fixed over 2 mm thick Aluminium sheeting vide clause 801.3, 3mm/4mm thick Aluminium composite material sheet depending on the size of the sign fixed over back support frame of min 25 x 25 x 3mm Angle mounted on a mild steel circular pipe 65 NB, 3.2 mm thickness firmly fixed to the ground by means of properly designed foundation with M25 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing. The sign shall be maintained as per section 12 of IRC 67, including all leads, lifts and carriage of materials as per the direction and entire satisfaction of the Engineer-in-charge.								
	90cm equilateral triangle (Cautionary Sign Board)	6.00	Nos	6054.70	36328.00	Rupees Thirty six thousand three hundred twenty eight only			
	Total :-				99785.00	Rupees Ninety nine thousand seven hundred eighty five only			
Quoted Rate % (Percentage) in Figures		(+) / (-)							
Quoted Rate % (Percentage) in Words									

The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.


 Executive Engineer
 NH Division
 HPPWD Nahana