

**Himachal Pradesh
Public Works Department**

No. PWP/Agr. Asstt./Tender/2024-25/ 7793-822, Dated/1-9-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter No. PBW(B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur


Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this
office NIT No. PWP/ Agr. Asstt/ NIT/ 2025/- **7793-822** dated **1-9-2025**
01.09.2025 are urgent in nature and in public interest.


Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **11.09.2025** up to 11.00 A.M. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 10.09.2025 up to 4.00 P.M and the application for issue of tender form shall be received 09.09.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	R/D on Parour Lahla Gopalpur Rakh Jyuen Sukeri Kandi Bandla Palampur road Km 0/00 to 33/00 (SW:- P/L C.C Pavement alongwith U-shape drain at RD 3/180 to 3/200.50)	Rs. 98,508.00	Rs. 2,000.00	Two Month
2	C/o Foot Path near the house of Sh. Parkash Chand to Pritam Chand house Ward No. 3 GP Darati (Deposit)	Rs. 98,557.00	Rs. 2,000.00	Two Month
3	R/D on Yol Dadh Palampur road Km 15/00 to 27/00 (SW:- Removing of slips & cleaning of drains at various Rd's between Km 15/00 to 27/00)	Rs. 98,900.00	Rs.2,000.00	Two Month
4	R/D on Kandi Thalla Malenta road Km 0/00 to 4/600 (SW:- Painting of Steel board & Writing letters etc)	Rs. 99,411.00	Rs. 2,000.00	Two Month
5	Steel Crash Barrier Sidhpur Sarkari link road steel Crash Barrier (SW:- P/F " W" Metal beam crash Barrier at RD 5/940 to 5/963) (D.C. Deposit)	Rs. 98,680.00	Rs. 2000.00	Two Month
6	R/o road from Brahmtheru to Assanpatt (SH:- Hiring of JCB for removal of slips (Deposit)	Rs. 98,900.00	Rs. 2,000.00	Two Months
7	C/o Retaining wall near Shamshan Ghat Kumar Kholi (SW:- C/o R/Wall (VKVNY Deposit)	Rs. 99,776.00	Rs. 2,000.00	Two Months
8	Comli road from Shiv Mandir to Sh. Khazana Ram Ghart Ward No. 4 Sidhpur Sarkari (SW:- Providing and fixing grating over drain, CC on extended portion & C/o drain (Deposit)	Rs. 69,192.00	Rs. 1,400.00	Three Months
9	Repair of pot holes in Shitla Mata Nihang Tikka Degree College road Km 0/00 to 1/600 (SH:- Repair of Pot holes at various RDs (MMSRRY)	Rs. 99,422.00	Rs. 2,000.00	Three Months
10	Restoration of Rain damages on Lohna Surad road (SW:- P/L G-III and Interlocking concrete Block Pavement (DC Deposit)	Rs. 93,236.00	Rs. 1,900.00	Three Months
11	Restoration of Rain damages on Bindraban Sidhpur Sarkari road to Pharer road (SW:- P/L G-III and Interlocking concrete Block Pavement (DC Deposit)	Rs. 89,447.00	Rs. 1,800.00	Three Months

12	Repair of road from Banuri to Deogran Km 0/00 to 2/500 (SW:- Providing and laying wearing and CC Pavement from RD 1/800 to 1/829.60)	Rs. 99,567.00	Rs. 2,000.00	Three Months
13	Additional Accommodation Govt. Senior Secondary School Kandwari (SW:- Providing Putty and Priming coat etc)	Rs. 95,501.00	Rs. 2,000.00	Three Months
14	Additional Accommodation Govt. Senior Secondary School Kandwari (SW:- Providing Painting work and PVC Pipes (Deposit)	Rs. 99,931.00	Rs. 2,000.00	Three Months
15	Argumentation and improvement of water supply scheme Chandpur Langha Kulani road (SW:- Hiring of JCB (IPH Deposit)	Rs. 99,533.00	Rs. 2,000.00	Three Months
16	Argumentation and improvement of water supply scheme Chandpur Langha Kulani road (SW:- Hiring of JCB (IPH Deposit)	Rs. 99,475.00	Rs. 2,000.00	Three Months
17	OFC Dagame on Dharamshala Yol Dadh Holta Chadiyar Sandhole road Km 33/00 to 40/500 (SW:- Supply and stacking of Sign boards)	Rs. 99,792.00	Rs. 2,000.00	Three Months
18	OFC Dagame on Dharamshala Yol Dadh Holta Chadiyar Sandhole road Km 33/00 to 40/500 (SW:- Supply and stacking of Sign boards)	Rs. 99,792.00	Rs. 2,000.00	Three Months
19	Restoration of rain damages on link road Tanda Pantehar Band Vihar Molichak Dharman Kandwari road Km 0/00 to 10/00 (SW:- Hiring of JCB)	Rs. 99,245.00	Rs. 2,000.00	Three Months
20	Restoration of rain damages on NH-154 to SCVB Degree College to connect SC Basti Tanda Km 0/00 to 5/00 (SW:- Hiring of JCB)	Rs. 99,475.00	Rs. 2,000.00	Three Months
21	C/o Pucca Path alongwith paver tile work from Vikramjeet House towards Sh. Pritam Chand House Ward No. 2 Mohal Rakh (SW:- P/L Interlocking Tiles (VKVNY)	Rs. 74,605.00	Rs. 1,500.00	Two Months
22	C/o Pucca Path alongwith paver tile work from Sh. Milap Chand house towards Sh. Kashmir Singh House Ward No. 4 Mohal Rakh (SH:- P/L Interlocking tiles (VKVNY)	Rs. 99,652.00	Rs. 2,000.00	Two Months
23	C/o link road from Ghar to Upper Dattal and Ghar to Ropa Km 0/000 to 4/800 (SW:- P/L CC pavement at RD 2/280 to 2/288 (MNP)	Rs. 99,135.00	Rs. 2,000.00	Three Months
24	C/o Jeepable road from Raj Kumar House to Mahila Mandal Matt Lamlehar (SH:- P/L Interlocking Paver Block (Deposit)	Rs. 99,768.00	Rs. 2,000.00	Two Months
25	C/o Jeepable road from Ashok Kumar House to Sh. Mukesh Kumar House Lamlehar (SH:- Providing and laying G-II, G-III & CC Pavement (Deposit)	Rs. 99,468.00	Rs. 2,000.00	Two Months
26	R/D on link road to village Drognu Km 0/00 to 1/600 (SW:- C/O R/Wall at Rd 0/960 to 0/967)	Rs. 99,706.00	Rs. 2,000.00	Two Months
27	R/D on link road village Badsar to Ardi Km 0/00 to 4/00 (SW:- C/o R/Wall at RD 1/120 to 1/127)	Rs. 99,678.00	Rs. 2,000.00	Two Months

28	R/D on Dharer Rajnali Bhagotla road Km 0/00 to 5/00 (SH:- Removing of slips at various RD's Between Km 0/00 to 5/00)	Rs. 98,900.00	Rs. 2,000.00	Two Months
29	R/D on Parour Lahla Gopalpur Rakh Sukeri Jyun Kandi Bandla Palampur road Km 0/00 to 33/00 (SH:- C/o Unlined drain at various Rd's beteen 16/00 to 31/00)	Rs. 99,200.00	Rs. 2,000.00	Two Months
30	C/o Pucca Path from Sh. Okhu Ram House to Sh. Vishnu House Ward No. 1 GP Rakh (SW:- Providing and laying Interlocking tiles (Deposit)	Rs. 49,980.00	Rs. 1,000.00	Two Months
31	R/D on Parour Lahla Gopalpur Rakh Jyun Sukeri Kandi Bandla Palampur road Km 0/00 to 33/00 (SH:- C/o R/Wall at RD 4/200 to 4/207)	Rs. 99,678.00	Rs. 2,000.00	Two Months
32	Ambulance road from link road to Pardhan Singh House Ward No. 2 GP. Aima Palampur (SH:- P/L Interlocking concrete block Pavement at RD 0/420 to 0/443) (VKNY)	Rs. 98,932.00	Rs. 2000.00	Three Months
33	Repair of road from Banuri to Deogran Km 0/00 to 2/500 (SW:- P/L wearing and CC Pavement from RD 1/800 to 1/829 (Deposit)	Rs. 99,234.00	Rs. 2000.00	Three Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand . Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Palampur Division
HPPWD Palampur

SCHEDULE OF QUANTITY

Name of work:- R/D on Parour Lahla Gopalpur Rakh Jyuen Sukeri Kandi Bandla Palampur Road Km 0/00 to 33/00. (SH:- P/L C.C. Pavement alongwith U Shape drain at Rd 3/180 to 3/200.50).					
			Estimated cost Rs.		98508.00
			Earnest Money Rs.		2000.00
			Time Limits		Two Months
Sr./No	Description of Item	Quantity	Rate		Amount
			In Figures	In Word	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	9.84		Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	5.95		Per cubic metre,	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	10.76		Per cubic metre,	
	Total				


 Executive Engineer,
 Palampur Division
 HP.PWD Palampur

12

SCHEDULE OF QUANTITY

Name of work:- C/o Foot path Near the House of Sh. Parkash Chand to Pritam Chand House ward No. 3 G.P., Darati.
(Deposit 1.00 Laes)

Name of work:- C/o Foot path Near the House of Sh. Parkash Chand to Pritam Chand House ward No. 3 G.P. Darati. (Deposit 1.00 Lacs)							Estimated cost Rs.	
							Earned Money Rs.	Two Months Amount
Sr. No.	Description of Item	Quantity	Rate		Unit			
			In Figures	In Word				
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	13.40			Per cubic metre			
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combet including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour). The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	13.40			Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	16.75			Per cubic metre.			
	Total							

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Sl. No.

Quantity

Summary

In Word

Per Hour

1001

Total

Executive Engineer,
Palampur Division
HP PWD Palampur.

SCHEDULE OF QUANTITY


Name of work:- R/D on Kandli Thalla Malenia road Km 0/00 to 4/600.(SH)- Painting of steel board & writing letters etc.)

Name of work:- R/D on Kandi Thalla Malenta road Km 0/00 to 4/600.(S/H:- Painting of steel board & writing letters etc.)							Estimated cost Rs.	99411.00
							Earned Money Rs	2000.00
							Two Months	Two Months
Sr.No	Description of item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	84.60			Per square metre,			
2	Writing letters or figures on any surface with black japan paint (stops, commas, hyphens and the like not to be measured and paid separately) Indian(letters/figures) . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30000.00			Per letter per cm. height			
2	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	234.52			Per square metre.			
	Total							


 Executive Engineer,
 Palampur Division
 HP PWD Palampur

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY									
Name of work:- Steel Crash Barrier Sadhpur Sarkeri Link road steel crash barrier (S/H:- P/F "W" metal beam crash barrier at Rd 5/940 to 5/963) , D.C. Deposit									
Sr. No.	Description of item	Quantity	In Figures		In Words		Unit	Estimated cost Rs.	
								Lowest Money	Rs.
								Two Months	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19					Per cubic metre		
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.19					Per cubic metre.		
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm (three millimetre) thick corrugated sheet metal beam rail, 70 cm (Seventy Centimetre) above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 m (two metre) centre to centre, 1.80 m (one point eight zero metre) high, 1.10 m (One point one zero metre) below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, (one hundred fifty into seventy five into five millimetre) 330 mm (three hundred thirty millimetre long complete as per clause 810 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.00					Per running metre		
	Total								


 Executive Engineer
 Palampur Division
 HP PWD Palampur

6

SCHEDULE OF QUANTITY

Name of work:- R/o road from Brahmtheru to Assanpatt, (SH:- Hiring of JCB for removal of slips), Deposit 2.25 Lacs

SCHEDULE OF QUANTITY							Unlimited cost Rs.		98900.00	
Name of work:- R/o road from Brahmitheru to Assanpatt. (SH:- Hiring of JCB for removal of slips). Deposit 2.25 Lacs							Earnest Money Rs.		2000.00	
							Time Limits		Two Months	
							Rate		Amount	
Sr. No.	Description of Item	Quantity	In Figures		In Word		Unit		Per Hour	
1	Hiring of JCB (Excavator-Cum-Loader) including P.O.L charges shifting charges and other ancillary equipments as per required at site of work for removal of slips. The disposal of this un-servicceable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage mttook place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	86.00								
					Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Retaining wall near Shamsan Ghat Kumar Kholi, (SH- C/o R/wall), (V.K.V.N.Y deposit 1.00 Lacs)

Sr. No.	Description of Item	Quantity	Rate		Unit	Two Months Amount	
			In Figures	In Word		Estimated cost Rs.	Estimated cost Rs.
						99776.00	2000.00
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters compacted thickness including shoring and strutting and pumping and balling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	10.80			Per cubic metre		
2	Providing and laying mechanically mixed and vibrated plant cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and, materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.60			Per cubic metre.		
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The work should be done as per MORD technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.40			Per cubic metre		
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and MORD technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each		
	Total						

Executive Engineer,
Palampur Division
HP.PWD Palampur

Name of Work :- Compl road from Shiv Mandir to Sh. Khazana Ram Gharat W. No. 4 Sidhipur Sarkari
(S.W. :- Providing/ Fixing Grating over drain, CC on extended portion & c/o drain) Deposit

Schedule of Quantity

Work No. 9

Estimated Cost :- Rs. 69,192/-

Earnest Money :- Rs. 1400/-

Time limit :- Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	17.43			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	1.37			Per Cubic metre	
3	Providing Concrete for plain/reinforced cement concrete1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical SpecificationsClause802,803,1202 &1203 including carriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	5.22			Per Cubic metre	
4	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	2.84			Per Cubic metre	
5	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames ,guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	200.60			Per Kilogram	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- Repair of pot holes in Shitla Mata Nihang Tikka Degree college road km 0/00 to 1/600

Estimate Cost :- Rs. 99,422/-

Earnest Money :- Rs. 2000/-

Time Limit :- Three months

Sub Work :- Repair of Pot Holes at various RDs (MMSRRY)

S. No	Description of Item	Quantity	Rate		Unit	Amount Rupees
			In figure	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm(twenty millimetres) thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	285.18			Per Square metre	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.07			Per Cubic metre.	
Total :-						

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Name of Work :- Restoration of Rain Damages on Lohna Surad road
(S.W. :- P/LG-III and Interlocking Concrete Block Pavement (Dc Deposit)

Work No. 10

Estimated Cost :- Rs.93,236/-

Earnest Money :- Rs.1900/-

Time limit : Three Months.

S. No.	Description of Item -	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.00	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 80 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	72.00	Square Metre			Per square metre	
3	Providing Concrete for plain/reinforced cement concrete1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical SpecificationsClause802,803,1202 &1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.72	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- Restoration of Rain Damages on Bindraban Sidhpur Sarkari road *to phases road*
(S. W. :- P/LG-III and Interlocking Concrete Block Pavement)

Work No.

Estimated Cost :- Rs. 89,447/-

Earnest Money :- Rs.1800/-

Time limit : Three Months.

S- No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.00	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 80 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	69.00	Square Metre			Per square metre	
3	Providing Concrete for plain/reinforced cement concrete1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix .P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical SpecificationsClause802,803,1202 &1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.69	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

of Work :- C/O link road from Ghar to Upper Dattal & Ghar to Ropa km. 0/000 to 4/800
W. :- P/L CC Pavement at RD 0/250 to 0/275 2/255 to 2/280

Work No. 12

Estimated Cost :- Rs. 99,668/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	7.50			Per Cubic metre	
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	5.63			Per Cubic metre	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	11.25			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Name of Work :- Additional Accomodation Govt. Senior Secondary School Kandwari
Sub Work :- Providing putty And priming coat etc.

Schedule of Quantity

Estimated Cost : Rupees 95,501/-
Earnest Money : Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words				
1	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1057.90	Square metre			Per Square metre	
2	Providing and fixing 110 mm. (One hundred ten millimetre) diameter on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm(Ten millimetre) gap for thermal expansion,(i) Single socketed pipes with in all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	77.00	Running metre			Per Running metre	
3	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge.Kiln seasoned selected planks of sheesham wood of 35 mm thick shutters with in all leads, lifts and other incidental .The rate is including octroi, royalty,GST, toll tax, or other taxes imposed by the Government.	8.97	Square metre			Per Square metre	
Total:-							

Executive Engineer
Palampur Division
H.P.PWD Palampur

(14)

Schedule of Quantity

Name of Work :- Additional Accomodation Govt. Senior Secondary School Kandwari
Sub Work :- Providing Painting work & PVC pipes etc. (Deposit)

Estimated Cost : Rupees 99,931/-
Earnest Money : Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	248.71	Square metre			Per Square metre	
2	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm) with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	306.00	Square metre			Per Square metre	
3	Applying Priming Coat With ready mixed pink or Grey primer on wood work (hard and soft wood) having VOC content less than 50 grams/litre (fifty grammes per litre) of approved brand and manufacture, with in all leads, lifts and other incidental .The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	41.76	Square metre			Per Square metre	
4	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	41.76	Square metres			Per Square metre	
5	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works including carriage of materials with in all leads, lifts and other	219.10	Square metres			Per Square metre	
6	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana.Tol tax, GST or any other taxes imposed by the	219.10	Square metres			Per Square metre	

14

7	Providing and fixing 110 mm. (One hundred ten millimetre) diameter on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm(Ten millimetre) gap for thermal expansion,(i) Single socketed pipes with in all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	59.00	Running metre		Per Running metre
				Total:-	

Executive Engineer
Palampur Division
H.P.PWD Palampur

15

Work No.

Estimated Cost :- Rs. 99,533/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

Schedule of Quantity

Work :- Augmentation and improvement of Water Supply Scheme Chandpur Langha kulani road

S. W. :- Hiring of JCB (IPH deposit)

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Hiring of J.C.B.(Excavator -Cum -Loader) including P.O.L. charges,shifting charges and other ancillary equipments as required at site of Maintenance of Earthen Shoulder and work for removal of slips. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-in -Charge including all leads and lifts other incidentals.i/c all taxes imposed by the Government.	86.55			Per Hour	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- - OFC Damages on Dharamshala Yol Dadh Holta Chadhiyar Sandhole road km. 33/000 to 40/500
(S. W. :- Supplying and Stacking of Sign Boards

Work No.

Estimated Cost :- Rs. 99,792/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing and Supplying Direction and place identifications of Semi Reflective sign boards as per IRC:67 made of 2 mm thick M.S. Sheet duly bstove enamelled paint in white colour in front and Grey colour on back with Red reflective border of 70 mm width and required mwssage, letters, figures with Reflective Engineering Grade tape as per MORD Specifications of required shade and colour. Supported and welded on 47mm x 47mm of 12 SWG Square tube of 3050 mm height duly strengthened by 25mm x 5mm M/S flat iron on edges on back firmly fixed to the ground by means of properly designed foundations with below ground level as per approved drawing and Technical Specification Clause 1701 including all leads and lifts and other incidentals.	23.76	Square Metre			Per Square Metre	
						Total :-	


Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. 19

Estimated Cost :- Rs. 99,245/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

Name of Work :- Restoration of rain damages on link road Tanda Pantehar Band Vihar Molichak Dharman Kandwari

road Km. 0/000 to 10/000

(S. W. :- Hiring of JCB

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Hiring of J.C.B.(Excavator -Cum -Loader) including P.O.L. charges,shifting charges and other ancillary equipments as required at site of Maintenance of Earthen Shoulder and work for removal of slips.The disposal of this un-serviceable material has to be done in the aquired width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-in -Charge including all leads and lifts other incidentals.i/c all taxes imposed by the Government.	86.30			Per Hour	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Work No. 20

Estimated Cost :- Rs. 99,475/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

Schedule of Quantity

Name of Work :- Restoration of rain damages on NH 154 to SCVB Degree College to connect SC Basti Tanda ^{km} 0/000 to _A

5/000

(S. W. :- Hiring of JCB

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Hiring of J.C.B.(Excavator -Cum -Loader) including P.O.L. charges,shifting charges and other ancillary equipments as required at site of Maintenance of Earthen Shoulder and work for removal of slips.The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-in -Charge including all leads and lifts other incidentals,i/c all taxes imposed by the Government.	86.50			Per Hour	
					Total :-	


Executive Engineer
Palampur Division
HP.PWD Palampur

(21)

SCHEDULE OF QUANTITY

Name of work:- C/o Pucca Path alongwith paver tile work from Sh. Vikramjeet House towards Sh. Pritam Chand House
Ward. No. 2 Mohal Rakh. (SH):- P/L Interlocking tiles). **VKNY Deposit 0.75 Lacs**

Name of work:- C/o Pucca Path alongwith paver tile work from Sh. Vikramjeet House towards Sh. Pritam Chand House Ward. No. 2 Mohal Rakh. (SH):- P/L Interlocking tiles). VKVNY Deposit 0.75 Lacs							Estimated cost Rs.		74605.00
							Earnest Money Rs.		1500.00
							Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount			
			In Figures	In Word					
1	Providing and laying Cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) Nominal Mix P.C.C. grade for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	2.00			Per cubic metre.				
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	43.20			Per square metre				
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.62			Per cubic metre.				
	Total								


Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Pucca Path alongwith paver tile work from Sh. Milap Chand House towards Sh. Kashmir Singh House
Ward. No. 4 Mohal Rakh. (SH:- P/L Interlocking tiles). VKVNY Deposit 1.00 Lacs

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word		Two Months	Two Months
1	Providing and laying Cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) Nominal Mix P.C.C. grade for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	2.00			Per cubic metre.		99652.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	67.20			Per square metre		2000.00
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.72			Per cubic metre		
Total							

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Estimated Cost :- Rs. 99,135/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

Name of Work :- C/O link road from Ghar to Upper Dattal and Ghar to Ropa km. 0/000 to 4/800
(S.W. :- P/L CC pavement at RD 2/280 to 2/288)

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	59.25			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	1.74			Per Cubic metre	
3	Providing, laying, Wearing 90 to 45mm. (Ninety to forty five milimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	17.38			Per Cubic metre	
4	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals.The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	1.74			Per Cubic metre.	
5	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.30			Per Cubic metre.	


23

6	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	300.00	Kilogram me		Per Kilogram me	
					Total :-	


Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Jeepable road from Raj Kumar House to Mahila Mandal Matt Lamlehar (SH:- P/L Interlocking Paver block). Deposit 1.00 Lac					Estimated cost Rs.	
					Earnest Money Rs.	2000.00
					Time Limits	Two Months
Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	75.00			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.60			Per cubic metre.	
	Total					


 Executive Engineer
 Palampur Division
 HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Jeepable road from Ashok Kumar House to Sh. Mukesh Kumar House Lamlehar (SH:- P/L, G-II, G-III & C.C.Pavement). Deposit 1.00 Lacs				Estimated cost Rs.		99468.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr No.	Description of item	Quantity	In Figures	Rate		Unit
				In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K N static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.70			Per cubic metre	
2	Providing laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III 75mm (seventy five millimetre) thickness to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N, static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2 mm (eleven point two millimetre) nominal size at the rate of 0.18 cum (zero point eighteen cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D technical specifications clause No. 405 including carriage of materials within all leads , lifts and other incidentals or as per the directions of Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.70			Per cubic metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P C C grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	10.26			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- R/D on Link road to village Drognu Km 0/00 to 1/600. (SH:- C/o R/wall at Rd 0/960 to 0/967).		Estimated cost Rs.		99706.00	
		Earnest Money Rs.		2000.00	
		Time Limits		Two Months	
Sl. No	Description of item	Quantity		Rate	
		In Figures	In Word	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.40		Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement five sand ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government	21.32		Per cubic metre	
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC-78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	5.88		Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	6.00		Each	
Total					

Executive Engineer
Palampur Division
HP PWD Palampur

27

SCHEDULE OF QUANTITY

Name of work:- R/D on Link road village Badsar to Ardi Km 0/00 to 4/00. (SH:- C/o R/wall at Rd 1/120 to 1/127).							Estimated cost Rs.		99678.00
							Earnest Money Rs.		2000.00
							Time Limits		Two Months
Sr No	Description of item	Quantity	Rate		Unit	Amount			
			In Figures	In Word					
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government time to time.	6.30			Per cubic metre				
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement five sand ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.32			Per cubic metre				
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC- 78 & 2200. The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government time to time.	5.88			Per cubic metre				
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each				
Total									


 Executive Engineer,
 Palampur Division
 HP.PWD Palampur

Particulars	Estimated cost Rs.
1. Material	1000
2. Labour	2000
3. Overhead	1000
Total	3000

98900.00

Time Limits

Description of Item

Quantity

Rate

In Word

1

1

Total

1

12

2

1

Executive Engineer,
Palampur Division
H.P. PWD Palampur

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work:- R/D on Parour Lahla Gopalpur Rakh Sukeri Jyuen Kandi Bandla Palampur road Km 0/00 to 33/00. (SH:-						
C/o Unlined drain at various Rd's between 16/00 to 31/00).						
Sr No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government .	1600.00			Per Running metre	99200.00
						2000.00
						Two Months
						Amount

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY


Name of work:- C/o Pucca Path from Sh. Okhu Ram House to Sh. Vishnu House Ward No. 1 G.P. Rakh. (Sh:- Providing and Laying interlocking tiles). **Deposit 0.50 Laacs**

SCHEDULE OF QUANTITY						
Name of work:- C/o Pucca Path from Sh. Okhu Ram House to Sh. Vishnu House Ward No. 1 G.P. Rakh. (Sh:- Providing and Laying interlocking tiles). Deposit 0.50 Lacs			Estimated cost Rs.		49980.00	
			Earnest Money Rs.		1000.00	
			Time Limits		Two Months	
Sr No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	35.70			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix. P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time	0.68			Per cubic metre.	
	Total					

Executive Engineer
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- R/D on Parour Lahla Gopalpur Rakh Jyuen Sukeri Kandi Bandla Palampur Road Km 0/00 to 33/00. (SH:- C/o R/wall at Rd 4/200 to 4/207).				Estimated cost Rs.		99678.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORTI technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time	6.30			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement, five sand, ten graded crushed stone aggregate, 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government	21.32			Per cubic metre	
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time	5.88			Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plan or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government	8.00			Each	
Total						


 Executive Engineer
 Palampur Division
 HP PWD Palampur

Schedule of Quantity

Work :- Ambulance road from link road to Pradhan Singh house W.No. 2 GP Alma Palampur (VKNY)
 :- P/L Interlocking Concrete Block Pavement RD. 0/420 to 0/0443

Work No. **32**

Estimated Cost :- Rs. 98,932/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and Laying concrete 1:4:8 (one cement : four sand : eight crushed graded stone aggregate) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	0.35			Per Cubic metre	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 80 mm. as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	69.00			Per square metre	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.44			Per Cubic metre	
					Total :-	

Executive Engineer
 Palampur Division
 HP. PWD Palampur

Schedule of Quantity

Name of Work :- Repair of road from Banuri to Deogran Km. 0/000 to 2/500
(S.W. :- P/L wearing and C.C. Pavement from RD 1/800 to 1/829 (Deposit))

Work No. 33

Estimated Cost :- Rs.99,234/-

Earnest Money :- Rs.2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	6.66			Per Cubic metre.	
2	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C-grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	13.32			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur