

Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur Distt. Kangra (H.P.)-176206
e-mail id: ce-shahpur-pwd@hp.gov.in
"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before 12-09-2025 up to 11:00 AM. and the same shall be opened on the same day at 11:30 AM. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) from 10-09-2025 to 11-09-2025 up to 5:00 P.M and the application for issue of tender form shall be received on 10-09-2025 up to 5:00PM.

The earnest money in the shape of NSC/FDR/Saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time Limit	Cost of tender form
1.	Restoration of rain Damages on link road from Rajol to Dolla Bhatti KM 0/00 to 3/00 (S.H:- Construction of Edge wall & Embankment between KM 1/721 to 1/736 (Bhatti side)	96440.00	1950.00	Two Months	350/-
2.	C/o Pucca path from Cow shed of Ishwer Dass house to Parkesh chand house G.P. Kaliyara (Deposit work)(S.H:-Providing and Laying interlocking paver block at RD 0/035 TO 0/070)	99860.00	2000.00	Two Months	350/-
3.	C/o Pucca path from Land of Surinder to Panihaari Basti at Kaliyara ward No-06 (Deposit work)(S.H:-Providing and Laying interlocking paver block at RD 0/127 to 0/187)	98681.00	1950.00	Two Months	350/-
4.	C/o Pucca path alongwith Protection wall near the House of Sh. Bhisham Singh S/o Bhuri Singh Ward No-2 G.P. Mundla.(Under Head-VKVN(MLALAD) (Deposit work). (S.H:- Providing and laying Interlocking paver block.	96875.00	1950.00	Two Months	350/-
5.	C/o Salli to Lahari road KM 0/0 to 1/800 (S.H:- C/o 900 mm Hume pipe culvert at RD 1/750.)	99461.00	2000.00	Two Months	350/-
6.	C/o Noun to Harizan Basti Hara road GP Shahpur Km 0/00 to 0/750 (Deposit work)(S.H:- C/o Pushta 3 rd step for Protection of Sh.Ashok Dhiman House by Erecting R/wall from RD 0/410 to 0/419.	74588.00	1500.00	Two Months	350/-
7.	C/o Pucca path from Land of Surinder to Panihaari Basti at Kaliyara ward No-06 (Deposit work)(S.H:-Providing and Laying interlocking paver block at RD 0/190 to 0/250)	98681.00	2000.00	Two Months	350/-
8.	C/o Pucca path from Cow shed of Ishwer Dass house to Parkesh chand house G.P. Kaliyara (Deposit work)(S.H:-Providing and Laying interlocking paver block at RD 0/071 to 0/104)	98912.00	2000.00	Two Months	350/-
9.	C/o Noun to Harizan Basti Hara road GP Shahpur Km 0/00 to 0/750 (Deposit work)(S.H:- C/o Pushta 4th step for Protection of Sh.Ashok Dhiman House by Erecting R/wall from RD 0/410 to 0/418.	57460.00	1200.00	Two Months	350/-
10.	C/o Protection wall near the Land of Sushil Kumar S/o Sh. Puran Chand Ward No-1 G.P. Mundla. (Deposit work).(S.H:-C/o Proction wall. (Part-II).	97617.00	2000.00	Two Months	350/-
11.	Restoration of Rain damages on Shahpur Chakban Lapiana road KM 0/00 to 20/250.(S.H:- Retaining wall in C/C 1:4:8 and Wire crate at Km 13/280.60 to 13/282.)	92278.00	1900.00	Two Months	350/-
12.	A/R & M/O salli to Khari Bahi road km 0/000 to 9/570 in tehsil Shahpur Distt. Kangra (H.P) (S.h:- Providing and laying Grading - III and repair of Pot holes at km 8/000 to 9/000)	99585.00	2000.00	Two Months	350/-
13.	Restoration of rain damages on Various roads under Darini Section under HP.PWD Sub Division Darini . (S.H:-Hiring of JCB/excavator cum loader for removal of slips).	99000.00	2000.00	One month	350/-
14.	Restoration of rain damages on Various roads under Boh Section under HP.PWD Sub Division Darini . (S.H:-Hiring of JCB/excavator cum loader for removal of slips).	98900.00	2000.00	One month	350/-

15.	Special Repair of Veterinary Hospital Gohju in Tehsil Shahpur at Distt. Kangra (H.P)(S.H:- providing and fixing Prepalinted Sheet	99996.00	2000.00	Two Months	350/-
16.	Construction of community Bhawan at Ghad Mata Gram Panchayat Nerti (Deposit Work)(S.H:- construction of Column in 1st Floor.	93353.00	1900.00	Two Months	350/-
17.	Special Repair of Veterinary Hospital Gohju in Tehsil Shahpur at Distt. Kangra (H.P)(S.H:- providing and Laying interlocking concrete block)	99763.00	2000.00	Two Months	350/-
18.	Construction of Link road link road Palwala to Lanjot in G.P Durgella Km 0/000 to 0/900 in Tehsil Shahpur Distt Kangra (H.P).(S.H:-Providing and Laying G-II & G-III at RD 0/610 to 0/673 (Under SCSP)	97638.00	2000.00	Two Months	350/-
19.	Restoration of Rain damages on Shahpur Chakban Lapiana road KM 0/00 to 20/250.(S.H:- Retaining wall in C/C 1:4:8 and Wire crate at Km 13/270 to 13/272.40)	93566.00	1900.00	Two Months	350/-
20.	C/o Protection wall near the Land of Sushil Kumar S/o Sh. Puran Chand Ward No-1 G.P. Mundla. (Deposit work).(S.H:-C/o Proction wall. (Part-I).	98137.00	2000.00	Two Months	350/-
21.	Construction of Link road link road Palwala to Lanjot in G.P Durgella Km 0/000 to 0/900 in Tehsil Shahpur Distt Kangra (H.P).(S.H:-Providing and Laying G-II & G-III at RD 0/675 to 0/738 (Under SCSP)	95977.00	1950.00	Two Months	350/-
22.	Construction of community Bhawan at Ghad Mata Gram Panchayat Nerti (Deposit Work)(S.H:- construction of 1st Floor.)	90670.00	1850.00	Two Months	350/-
23.	Stock Storage under HPPWD Sub Division Gaggal (providing and Laying prepainted Roof Front side)	99995.00	2000.00	Two Months	350/-
24.	C/O Chattri Pehad Road km 0/00.to 3/780 (S.H:- C/O B/Wall at Rd 3/620 to 3/625 and V-Shape Drain from RD 3/620 to 3/630 (portion Kholi Khad road km 3/000 to 3/780	88132.00	2000.00	Two Months	350/-
25.	Landslide Disaster Related Mitigation work on salli to Khari Belh Road km 0/00 to 9/570 (S.H:-C/O Edge Wall with pusta at Rd 2/795 to 2/811	96126.00	1950.00	Two Months	350/-
26.	Construction of Link road link road Palwala to Lanjot in G.P Durgella Km 0/000 to 0/900 in Tehsil Shahpur Distt Kangra (H.P).(S.H:-Providing and Laying G-II & G-III at RD 0/740 to 0/810 (Under SCSP)	99306.00	2000.00	Two Months	350/-
27.	Construction of Stairs at Chhinj Mela Batwala G.P.Manie (VKV/2022/2152) (Deposit work)(S.H:- Constrution of stairs steps)(Blance work)	98184.00	2000.00	Two Months	350/-
28.	C/o Chattri Pehad road km 0/00 to 3/780 (C/o V-Shape drain at Rd 3/190 to 3/240 and 3/335 to 3/367)	90188.00	1950.00	Two Months	350/-
29.	Stock Storage under HPPWD Sub Division Gaggal (S.H:- Construction of Pillar for Gate)	99999.00	2000.00	Two Months	350/-
30.	A/R & M/O Link Salli to lahari Road km 0/00 to 1/750 (S.H:- Providing and laying G-II at RD 1/685 to 1/750 (under MMSRRY)	48375.00	1000.00	Two Months	350/-
31.	Restoration of Rain Damages on Various Roads under Boh section (S.H:- Hiring of Poclain for removal of slips)	99200.00	2000.00	One month	350/-
32.	Restoration of Rain Damages on Various Roads under Darini Sub Division(S.H:- Hiring of Poclain for removal of slips)	99200.00	2000.00	One month	350/-
33.	Stock Storage under HPPWD Sub Division Gaggal (S.H:-Providing and Laying prepainted Roof back side)	96514.00	2000.00	Two Months	350/-
34.	Restoration of Rain Damages on Various Roads under Darini Sub Division (S.H:- Hiring of Excavator cum loader for removal of slips)	98900.00	2000.00	One month	350/-
35.	Restoration of Rain Damages on Various Roads under Boh section under Darini Sub Division (S.H:- Hiring of Excavator cum loader for removal of slips)	98900.00	2000.00	One month	350/-

36.	Restoration of Rain Damages on Various Roads under Boh section under Darini Sub Division (S.H:- Hiring of Excavator cum loader for removal of slips)	98900.00	2000.00	One month	350/-
37.	Balance work of ATC Building at shahpur Distt. Kangra (H.P) (Deposit work)(S.H:-Providing and laying Paver Blocks in courtyard and approach road at ATC Building shahpur.	99875.00	2000.00	Two Months	350/-
38.	Restoration of Rain Damages on Charri to Bhitlu Road km 0/00 to 5/780 (S.H:- Hiring of Excavator cum loader for removal of slips at various RDs)	99000.00	2000.00	Two Months	350/-
39.	Restoration of Rain Damages on various roads under HPPWD Gaggal Sub Division (S.H:- Hiring of Excavator cum loader for removal of slips at various RDs)	99000.00	2000.00	Two Months	350/-
40.	C/o Mini Secretariat Building at shahpur Tehsil Shahpur Distt Kangra (H.P)(S.H:- Providing and Fixing Sanitary installation and water Tank stand.	99463.00	2000.00	Two Months	350/-
41.	Restoration of Rain damages Shahpur Kairi Gandhrrop road km 0/00 to 2/400 in Tehsil Shahpur distt. Kangra (H.P)(S.H:- C/O breast Wall at km 1/728 to 1/731	98133.00	2000.00	Two Months	350/-
42.	Manai Bhandarla Mawa road.(S.H:-Improvement of curves C/o Retaining Wall at RD 3/905.80 to 3/911.25 for bus passing.)	99137.00	2000.00	Two Months	350/-
43.	C/o Mini Secretariat Building at shahpur Tehsil Shahpur Distt Kangra (H.P)(S.H:- Proviing and Fixing stainless steel pipe handrail.	98112.00	2000.00	Two Months	350/-
44.	Manai Bhandarla Mawa road.(S.H:-Improvement of curves C/o Retaining Wall at RD 3/900 to 3/905.60 for bus passing.	99066.00	2000.00	Two Months	350/-
45.	Special Repair of Veterinary Hospital Gohju in Tehsil Shahpur at Distt. Kangra (H.P)(S.H:- Sanitary Installation etc.	84400.00	2000.00	Two Months	350/-
46.	Restoration of Rain Damages on various roads under shahpur Sub Division (S.H:- Hiring of Excavator cum loader on Rehlu to Boru sarna road km 0/000 to 5/000)	99000.00	2000.00	One Month	350/-
47.	Restoration of Rain Damages on various roads under shahpur Sub Division (S.H:- Hiring of Excavator cum loader on Rait to Kohla Bhalla road km 3/500 to 7/500)	99000.00	2000.00	One Month	350/-
48.	Manai Bhandarla Mawa road.(S.H:-Improvement of curves C/o Retaining Wall at RD 2/494.80 to 2/500 for bus passing.	99972.00	2000.00	Two Months	350/-
49.	Restoration of Rain damages Shahpur Kairi Gandhrrop road km 0/00 to 2/400 in Tehsil Shahpur distt. Kangra (H.P)(S.H:- C/O breast Wall at km 1/720 to 1/727	99056.00	2000.00	Two Months	350/-
50.	C/o Mini Secretariat Building at shahpur Tehsil Shahpur Distt Kangra (H.P)(S.H:- Proviing and laying sewage system	92205.00	1850.00	Two Months	350/-
51.	Manai Bhandarla Mawa road.(S.H:-Improvement of curves C/o Retaining Wall at RD 2/501 to 2/503.40 for bus passing.	99946.00	2000.00	Two Months	350/-
52.	Construction of Harnera Baranj Sidhpur sirmani Khabbal salwana Tatwani road km 0/00 to 9/920 (S.H: Construction of R/Wall between 4/150 to 4/160 & Parapets.	98259.00	2000.00	Two Months	350/-
53.	Special Repair of Veterinary Hospital Gohju in Tehsil Shahpur at Distt. Kangra (H.P)(S.H:- Providing and laying Distempering Painting flooring etc.	99711.00	2000.00	Two Months	350/-
54.	Restoration of Rain Damages on various roads under shahpur Sub Division (S.H:- Hiring of Excavator cum loader on Rehlu to Boru sarna road km 5/000 to 6/000)	99000.00	2000.00	One Month	350/-
55.	Construction of Harnera Baranj Sidhpur sirmani Khabbal salwana Tatwani road km 0/00 to 9/920 (S.H: Construction of Sub structure of RCC Slab culvert at RD 4/300	99650.00	2000.00	Two Months	350/-
56.	Balance work of ATC Building at shahpur Distt. Kangra (H.P) (Deposit work)(S.H:-Providing and Fixing Aluminium section i/c glazing in the office room R-4	99097.00	2000.00	Two Months	350/-
57.	Restoration of Rain Damages on Various Roads under Darini Sub Division (S.H:- Hiring of Excavator cum loader for removal of slips)	98900.00	2000.00	One Month	350/-

58.	Stock Storage in PWD Store under Shahpur Sub Division HPPWD Shahpur Division Distt. Kangra (H.P)(Sub:-Supplying&Stacking CC2001002000 quick lime.	99500.00	2000.00	One Month	350/-
59.	A/R & M/O Various roads under HP.PWD Sub Division Shahpur (S.H:-painting on Bridges Rain Shelter and writing lettering Figures kilometres stonesign Boards and Parapets etc.	98148.00	2000.00	Two Months	350/-
60.	Stock Storage in PWD Store under Gaggal Sub Division HPPWD Shahpur Division Distt. Kangra (H.P)(Sub:-Supplying &Stacking CC2001002000 quick lime.	99500.00	2000.00	One Month	350/-
61.	Restoration of Rain Damages on Various Roads under Rajol section HPPWD Sub Division Gaggal (S.H:- Hiring of Excavator cum Loader for removal of slips at Various roads and RDs)	99000.00	2000.00	one month	350/-
62.	Restoration of Rain damages on Charri Ghera road km 0/00 to 8/555 (S.H:-RCC wall at RD 8/412.40 to 8/413.90	99790.00	2000.00	Two Months	350/-
63.	Restoration of Rain Damages on Various Roads under Gaggal section (S.H:- Hiring of Excavator cum Loader for removal of slips at Various roads and RDs)	99000.00	2000.00	one month	350/-
64.	Restoration of Rain damages on Charri Ghera road km 0/00 to 8/555 (S.H:-RCC wall at RD 8/410 to 8/411.40	99946.00	2000.00	Two Months	350/-
65.	Restoration of Rain Damages on Various Roads under Charri section HPPWD Sub Division Gaggal (S.H:- Hiring of Excavator cum Loader for removal of slips at Various roads and RDs)	99000.00	2000.00	one month	350/-
66.	Restoration of Rain Damages on Various Roads under Gaggal section (S.H:- Hiring of Excavator cum Loader for removal of slips at Various roads and RDs)	97900.00	2000.00	one month	350/-
67.	Restoration of Rain Damages on Various Roads under Charri section (S.H:- Hiring of Excavator cum Loader for removal of slips at Various roads and RDs)	97900.00	2000.00	one month	350/-
68.	Restoration of Rain Damages on Various Roads under Charri section (S.H:- Hiring of Excavator cum Loader for removal of slips at Various roads and RDs)	99550.00	2000.00	one month	350/-
69.	C/o R/Wall from Navneet Kumar Dhiman house to Ramesh House Gram Panchyat Garoh (VKVNY) (SH:- R/Wall at RD 0/00 to 0/008)	88013.00	1850.00	Two months	350/-
70.	C/o R/Wall from Navneet Kumar Dhiman house to Ramesh House Gram Panchyat Garoh (VKVNY) (SH:- R/Wall at RD 0/010 to 0/017)	88465.00	1800.00	Two months	350/-
71.	C/o R/Wall from Navneet Kumar Dhiman house to Ramesh House Gram Panchyat Garoh (VKVNY) (SH:- R/Wall at RD 0/019 to 0/023)	71253.00	1450.00	Two months	350/-
72.	C/o 40.00 Meter span bridge over Gaj Khad at Km 0/300 in Ghera on Baladi Mod to Balla Km 0/00 to 1/500 in Tehsil Shahpur Distt. Kangra Shahpur (SH:- Geo-Technical Investigation)	98000.00	2000.00	one month	350/-
73.	C/o 40.00 Meter span bridge over Gaj Khad at Km 0/300 in Ghera on Baladi Mod to Balla Km 0/00 to 1/500 in Tehsil Shahpur Distt. Kangra Shahpur (SH:- Geo-Technical Investigation)	98000.00	2000.00	one month	350/-
74.	C/o 35.00 Meter Span bridge over Banoi Khad at Km 0/300 on Ruhru to Narghota road km 0/00 to 1/500 (SH:- Geo-Technical Investigation)	98000.00	2000.00	one month	350/-
75.	C/o 35.00 Meter Span bridge over Banoi Khad at Km 0/300 on Ruhru to Narghota road km 0/00 to 1/500 (SH:- Geo-Technical Investigation)	98000.00	2000.00	one month	350/-
76.	C/o Mini Secretariat Building at Shahpur Tehsil Shahpur Distt. Kangra (HP) (SH:- Providing and fixing submersible pump including all fitting)	94271.00	1900.00	Two months	350/-
77.	A/R & M/O various roads under Shahpur sub Division (SH:- Hiring of excavator cum loader on Shahpur Darini road km 0/00 to 6/00)	99000.00	2000.00	one month	350/-
78.	Repair and Restoration of various roads under Shahpur Sub Division (SH:- Hiring of rock breaker on Shahpur Darini road)	99200.00	2000.00	one month	350/-
79.	Repair and Restoration of various roads under Shahpur Sub Division (SH:- Hiring of rock breaker on Dramman section)	99200.00	2000.00	one month	350/-

35	80.	Restoration of Rain damages on various roads under Darini Section under HP.PWD Darini Sub-Division (SH:- Hiring of Excavator cum loader for removal of slips)	99000.00	2000.00	one month	350/-
	81.	Restoration of Rain damages on various roads under Darini Section under HP.PWD Darini Sub-Division (SH:- Hiring of Excavator cum loader for removal of slips)	99000.00	2000.00	one month	350/-
	82.	Restoration of Rain damages on various roads under Darini Section under HP.PWD Darini Sub-Division (SH:- Hiring of Excavator cum loader for removal of slips)	99000.00	2000.00	one month	350/-
	83.	C/o path alongwith interlocking Tiles from Bhupinder House to Kamal House Gram Panchyat Garoh ward no-04 (VKVNY) (SH:- C/o Edge wall P/L interlocking Paver Block)	98440.00	2000.00	Two Months	350/-
	84.	C/o path alongwith interlocking Tiles from Bhupinder House to Kamal House Gram Panchyat Garoh ward no-04 (VKVNY) (SH:- P/L interlocking Paver Block)	97900.00	2000.00	Two Months	350/-
	85.	A/R & M/O various roads of HPPWD sub Division Gaggal. (SH:- Removal of old paint painting on old and new surface bridge Rain shutters Boards and writing letters of figures)	99470.00	2000.00	Two Months	350/-
	86.	Restoration of Rain damages on various roads under Darini Section under HP.PWD Darini Sub-Division (SH:- Hiring of Excavator cum loader for removal of slips.)	99000.00	2000.00	one month	350/-

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions: -

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Shahpur Division
HP.PWD Shahpur.

(on behalf of Governor of Himachal Pradesh)

Dated: 04/09/25

No.PWD/SD/Tender/NIT/2025-26/- 350-58

Copy to following for information and necessary action:-

1. The Superintending Engineer 5th Circle HPPWD Palampur.
2. The Executive Engineer (IT) Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. N.I.T Register.
6. Notice Board

Executive Engineer
Shahpur Division
HP.PWD Shahpur.

① Sr no - 304

RJD

SCHEDULE OF QUANTITY

Name of work :- ~~Construction of Link road from Rajul to Dulla Bhatti~~ Km 0/000 to 3/000.
(NH-2 Construction of Edge wall & Embankment between km 1/721 to 1/736 (Bhatti side).

S. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of silt which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.65	350.00	Ruppes Three Hundred Fifty Only	Per cubic metre	2328.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 500, 503, 1200 and 1600 nominal mix 1:5:10 (One cement iso five sand iso ten graded/crushed stone aggregate) 40mm (Forty millimeters) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	16.40	4100.00	Ruppes Four Thousand Three Hundred Only	Per cubic metre	70520.00
3	Providing and Laying 100mm (one Hundred millimeter) dia P.V.C pipe sweep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (K.V):20(H:X)One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	7.00	350.00	Ruppes Three Hundred Fifty Only	Each	2450.00
4	The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government. Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government	5.10	850.00	Ruppes Eight Hundred Fifty Only	Per cubic metre	4335.00
5	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.30	239.10	Ruppes Two Hundred Thirty Nine And Paise Ten Only	Per cubic metre	3060.00

Estimated cost Rs. 96,440.00
Earnest Money Rs. 1,950.00
Time Limits Two Month

82

SCHEDULE OF QUANTITY

Dr No - 300

NAME OF WORK :- C/o Pucca path from Cow shed of Ishwar Dass House to Parkash chand house G.P.Kallayara (Deposit work).

SUB-HEAD :- Providing and laying interlocking paver block at RD 0/035 to 0/070.

ESTIMATED COST: ₹ 99850.00
EARNEST MONEY ₹ 2000.00
TIME LIMIT Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement conforming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	85.75	1100.00	Rupees One Thousand One Hundred Only	Per square metre	94325.00
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.90	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	5535.00
TOTAL :-						99850.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
H.P.W.D. Shahpur

(3)

SCHEDULE OF QUANTITY

S No 302

ESTIMATED COST: ₹ 98681.00
 EARNEST MONEY ₹ 1950.00
 TIME LIMIT Two Months

NAME OF WORK :- C/o Pucca path from Land of Surinder to Panihauri Basti at Kalyara ward No-06 (Deposit work).
 SUB-HEAD :- Providing and laying interlocking paver block at RD 0/127 to 0/187

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	1.68	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	7980.00
2	Providing and laying 60 mm thick interlocking M-40 grade Concrete paver block pavement conforming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-in-charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	72.00	1100.00	Rupees One Thousand One Hundred Only	Per square metre	79200.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.87	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	11501.00
TOTAL :-						98681.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure.)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shehnur Division,
 H.P.P.W.D. Shikhar

51

SCHEDULE OF QUANTITY

5875 - 284

ESTIMATED COST: ₹ 96875.00
EARNEST MONEY ₹ 1950.00
TIME LIMIT Two Months

NAME OF WORK :- C/o Pucca path alongwith Protection wall near the House of Sh. Bhisham Singh S/o Bhuri Singh, Ward No-2, G.P. Mundla, (Under Head-VKVVV(MALALAD) (Deposit work).

SUB-HEAD :- Providing and laying interlocking paver block.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	1 Providing and laying 60 mm thick interlocking M-40 grade concrete paver block pavement conforming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	54.00	1100.00	Rupees One Thousand One Hundred Only	Per square metre	59400.00
2	2 Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.63	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	3875.00
3	3 Steel work welded in built up sections in railing work including cutting hoisting and fixing in position and applying a paint in gratings framed guard bars ladders railings and similar work etc. including carriage of materials within all leads lifts and other incidentals and as per direction of the Engineer-in-charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	320.00	105.00	Rupees One Hundred Five Only	Per kilogram	33600.00
TOTAL :-						96875.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- C/o Sālli to Lahari road Km 0/0 to 1/800.
SUB-HEAD :- C/o 900 mm Hume pipe culvert at RD 1/750.

ESTIMATED COST :- ₹ 99461.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.22	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1477.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.70	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	30666.00
3	Providing and laying (to level or slope) 900mm dia (nine hundred millimetre) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-3 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1100 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.00	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per Running metre	27250.00

4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete M-15 (M-fifteen) nominal mix 1:2½:5 (one cement is to two and half sand is to five graded crushed stone aggregate 40mm (forty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen) days, in cradle bedding for hume pipe including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying concrete complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification section 800,900 and 1100 as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	1.30	5750.00	Rupees Five Thousand Seven Hundred Fifty Only	Per cubic metre	7475.00
5	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.95	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	18763.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	13.80	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	11730.00
7	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls. Extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00	350.00	Rupees Three Hundred Fifty Only	Each	2100.00
TOTAL :-						
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 HPPWD Shabbar

6

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 74588.00
 EARNEST MONEY :- ₹ 1500.00
 TIME LIMIT : Two Months

NAME OF WORK :- C/O Noun to Hanzan Basti Hara Road GP Shahpur KM 0/000 to 0/750 (Deposit Work)

SUB-HEAD :- C/O Pushta 3rd step for Protection of Sh. Ashok Ohlman House by Erecting R/wall from RD 0/410 to 0/419

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement 1sto five sand 1sto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octrol, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.55	4250.00	Rupees Four Thousand Two Hundred fifty only	Per cubic metre	74588.00
TOTAL :-						74588.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor In Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

7

SCHEDULE OF QUANTITY

8 mo 303

NAME OF WORK :- C/o Pucca path from Land of Surinder to Panihari Basti at Kaliyara ward No-06 (Deposit work).
SUB-HEAD :- Providing and laying interlocking paver block at RD 0/190 to 0/250.

ESTIMATED COST: ₹ 98681.00
EARNEST MONEY ₹ 2000.00
TIME LIMIT Two Months

5. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	1.68	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	7980.00
2	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement conforming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-in-charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	72.00	1100.00	Rupees One Thousand One Hundred Only	Per square metre	79200.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	1.87	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	11501.00
TOTAL :-						98681.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

8r no - 301

NAME OF WORK :- C/o Pucca path from Cow shed of Ishwar Dass House to Parkash chand house G.P. Kaliyara (Deposit work).

ESTIMATED COST: ₹ 98912.00
EARNEST MONEY ₹ 2000.00
TIME LIMIT = Two Months

SUB-HEAD :- Providing and laying interlocking paver block at RD 0/071 to 0/104.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying 60 mm thick interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	85.00	1100.00	Rupees One Thousand One Hundred Only	Per square metre	93500.00
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.88	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	5412.00
TOTAL :-						98912.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
APJWD Shahpur

9

SCHEDULE OF QUANTITY

ESTIMATED COST :- 57460.00
EARNEST MONEY :- 1200.00
TIME LIMIT : Two Months

NAME OF WORK :- C/O Noun to Harizan Basti Hara Road GP Shahpur KM 0/000 to 0/750 (Deposit Work)

SUB-HEAD :- C/O Pushta 4th step for Protection of Sh. Ashok Dhillman House by Erecting R/wall from RD 0/410 to 0/418

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3				7
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement 1sto five sand 1sto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other Incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	13.52	4250.00	Rupees Four Thousand Two Hundred fifty only	Per cubic metre	57460.00
TOTAL :-						57460.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

100

SCHEDULE OF QUANTITY

443


ESTIMATED COST :- ₹ 97617.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- C/o Protection wall near the Land of Sushil Kumar S/o Sh. Puran Chand, Ward No-1, G.P. Mundla. (Deposit work).

SUB-HEAD :- C/o Protection wall. (Part-II).

5. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4.68	Rupees Three Hundred Fifty Only	Per cubic metre	1638.00
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802, 804, 806, 807, 1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	7.14	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per cubic metre	44625.00

3	Supplying fitting and placing HVSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	499.80 Kilogram	95.00	Rupees Ninety Five Only	Per Kilogram	47481.00
4	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16.20 Cubic metres	239.10	Rupees Two Hundred Thirty Nine And Paise Ten Only	Per cubic metre	3873.00
TOTAL :-						97617.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED ₹ 92278.00
EARNEST MONEY ₹ 1900.00
TIME LIMIT Two Months

NAME OF WORK :- Restoration of Rain damages on Shahpur Chakhan Lapiana road KM 0/00 to 20/250.

SUB-HEAD :- Retaining wall in C/C 1:4:8 and W/re crate at Km 13/280.60 to 13/282

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within bill leads, lifts and other incidentals. The rate is including Octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	Rupees Three Hundred Fifty Only	Per cubic metre	2671.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetera including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including Octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.90	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	28025.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	0.89	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	757.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.00	350.00	Rupees Three Hundred Fifty Only	Each	700.00
5	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.50	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	60125.00
TOTAL :-						92278.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99585.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- A/R & M/O Sallu Khari Bahi Road KM 0/000 TO 9/570 In Tehsil Shahpur Distt Kangra (H.P).

SUB-HEAD :- Providing and laying Grading -III and repair of pot holes at KM 8/000 to 9/000.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size (75mm) seventy five millimeters) compacted thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	44.26 cubic	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per Cubic metre	99585.00
TOTAL :-						99585.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

13

SCHEDULE OF QUANTITY

Serial - 255

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF Restoration of Rain damages on various roads under Darini Section under HP.PWD Darini Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road such opening of drains and catchpits etc. In all kind of earths, boulder, rocks etc. completely as per inspections of engineer-in-charge and minimum 25 (Twenty-five) cubic per hours output for slips / removal activates. Any loss to the public property or accident etc. happened during the course of hiring period/execution, shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	7100.00	Rupees One Thousand One Hundred Only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HP.PWD Shahpur

SCHEDULE OF QUANTITY

14

ESTIMATED COST :- ₹ 98890.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under Boh Section under H.P.PWD Darini Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	89.90	1100.00	Rupees one thousand and or hundred only	Per Hour	98890.00
TOTAL :-						98890.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

[Signature]
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99996.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :-

SUB-HEAD :- Special repair of Vethary Hospital Gohju in Tehsil Shahpur at Distt. Kangra Himachal Pradesh.
 Providing and fixing perpaainted sheet.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and fixing 0.60mm (sixty millimetre) thick prepaainted steel sheet (IS marked Z-120) of TATA Durashine/ sail over steel trussed in roofing with hot dipped metallic zinc coated steel with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepaainted iron J or L hooks, bolts and nuts 6mm (six millimetre) diametres with prepaainted limpet, rubber washers complete with all accessories as required as per specification, drawing and design including carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-in-charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	20.00	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per square metre	27000.00
2	Steel work welded in built up sections of Tata/Sail composed in beams, joists, channels, angles, tees flats with connecting plates or angles, cleats as in trusses and trussed purlins, main and cross beams, hips, jack rafters, purlins connect to common rafter and like work including cutting hoisting fixing in position & applying a priming coat of red lead paint complete including entire carriage of material within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	695.20	105.00	Rupees One Hundred Five Only	Per Kilogram	72996.00
TOTAL :-						99996.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

13-1
 Executive Engineer,
 Shahpur Division,
 HPWD-Shahpur

SCHEDULE OF QUANTITY

(16)

NAME OF WORK :-

Construction of Community Bhawan at Ghad Mata Gram Panchayat Nerti (Deposit Work).

SUB-HEAD :-

Construction of column in 1st floor.

ESTIMATED COST :-
EARNEST MONEY :- ₹ 93353.00
TIME LIMIT : Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-20 (M- twenty) design mix to obtain the compressive strength of 20N/mm ² (twenty newton per Square milimetre) for reinforced cement concrete work, using cement with cement content not less than @ 320 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work above plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.10	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	15015.00
2	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-25 (M- twenty) design mix to obtain the compressive strength of 20N/mm ² (twenty newton per Square milimetre) for reinforced cement concrete work, using cement with cement content not less than @ 360 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work above plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	5.10	7250.00	Rupees Seven Thousand Two Hundred Fifty Only	Per cubic metre	36975.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
3	Providing and laying for steel of TataISCO, SAIL reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all respects as per approved drawing, design, and specification in all floor levels including the cost of binding wire and dewatering if arisen during placement of reinforcement as per PWD specification and approved, drawing design including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	435.40	95.00	Rupees Ninety Five Only	Per Killogram	41263.00
TOTAL :-						93353.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

13/11/21
 Executive Engineer,
 Shapur Division,
 HPPWD Shapur

SCHEDULE OF QUANTITY

NAME OF WORK :-
SUB-HEAD :-

Special repair of Veterinary Hospital Gohju In Tehsil Shahpur at Distt. Kangra Himachal Pradesh.
Providing and Laying interlocking concrete block.

ESTIMATED COST :-
EARNEST MONEY :-
TIME LIMIT :-

99763.00
2000.00
Two Months

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying factory made chamfered edge precast Cement Concrete paver blocks 60mm (sixty millimetre) thick of NTC/ Unistone/ Atlantic/ as per approved shade and design in parking of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm (fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete, as per direction of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	58.00	1200.00	Rupees One Thousand Two Hundred Only	Per square metre	69800.00
2	Providing and laying cement concrete 1:4:8 (One cement, six Four sand, six Eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size and down gauge) mechanically mixed and curing complete excluding cost of forms work in foundation and plinth within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is including Royalty, Malkana, Octroi, Toll Tax, Sale Tax, GST or any other taxes imposed by the Government.	6.35	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	30163.00
TOTAL :-						99763.00
	Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPWD, Shahpur

SCHEDULE OF QUANTITY

243

(18)

NAME OF WORK :-

Construction of Link road Palwala to Lanlot in G.P. Durgella KM 0/00 to 0/900 in Tehsil Shahpur Distt. Kangra (H.P.) (Under S.C.S.P)


ESTIMATED COST :- ₹ 97638.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

SUB-HEAD :-

Providing and laying G-II & G-III at RD 0/610 to 0/673.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading by mechanical means to required slope and compacted with three wheel 80-100 (eighty -one hundred) KN static roller to meet requirement of Table 300.2 complete as per MCRD technical Specification section 400 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	40.20	91.30	Rupees Ninety One And Paise Thirty Only	Per cubic metre	3670.00
2	Providing, laying, spreading and compacting by mechanical means crushed stone aggregate size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II (75mm (seventy five millimetres) consolidated thickness) to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.20 cum (zero point two zero cubic metres) per ten square metres, and binding material at the rate of 0.06 cum (zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications section 400 and as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads, lifts and other incidental The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	26.70	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per cubic metre	57405.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
			4	5	6	7
1		3				
3	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	16.25	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	36563.00
TOTAL :-						97638.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shalgar

SCHEDULE OF QUANTITY


285

ESTIMATED
EARNEST MONEY ₹ 93566.00
TIME LIMIT ₹ 1900.00
Two Months

NAME OF WORK :- Restoration of Rain damages on Shahpur Chakhan Lapiana road KM 0/00 to 20/250.
SUB-HEAD :- Retaining wall in C/C 1:4:8 and Wire crate at Km 13/270 to 13/272.40

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.63	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2671.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement 150 Four sand 150 Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	28500.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	0.89	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	757.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
2						
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain/ reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)/(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.00	350.00	Rupees Three Hundred Fifty Only	Each	700.00
5	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.75	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	60938.00
TOTAL :-						93566.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shapur Division,
 HPPWD Shapur

20

SCHEDULE OF QUANTITY

292

NAME OF WORK :- C/o Protection wall near the Land of Sushil Kumar S/o Sh. Puran Chand, Ward No-1, G.P. Mundla. (Deposit work).

SUB-HEAD :- C/o Protection wall. (Part-I).

ESTIMATED COST :- ₹ 98137.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Two Months

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4.32	Rupees Three Hundred Fifty Only	Per cubic metre	1512.00
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	7.14	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per cubic metre	44625.00

3	Supplying fitting and placing HYSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	499.80	95.00	Rupees Ninety Five Only	Per Kilogramme	47481.00
4	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - In- Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	18.90	239.10	Rupees Two Hundred Thirty Nine And Paise Ten Only	Per cubic metre	4519.00
TOTAL :-						98137.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

434
 Executive Engineer,
 Shapur Division,
 HPPWD Shapur

81

242

SCHEDULE OF QUANTITY

NAME OF WORK :-

Construction of Link road Palwala-to Lanjot in G.P. Durgella KM 0/00 to 0/900 in Tehsil Shahpur Distt. Kangra (H.P.). (Under S.C.S.P)

SUB-HEAD :-

Providing and laying G-II & G-III at RD 0/675 to 0/738.

ESTIMATED COST:-
EARNEST MONEY :- ₹ 95977.00
TIME LIMIT : 1950.00
Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading by mechanical means to required slope and compacted with three wheel 80-100 (eighty - one hundred) KN static roller to meet requirement of Table 300.2 complete as per MORD technical Specification section 400 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	39.40	91.30	Rupees Ninety One And Paise Thirty Only	Per cubic metre	3597.00
2	Providing, laying, spreading and compacting by mechanical means crushed stone aggregate size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II (75mm (seventy five millimetres) consolidated thickness) to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.20 cum (zero point two zero cubic metres) per ten square metres and binding material at the rate of 0.06 cum (zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications section 400 and as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	25.70	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per cubic metre	55255.00

22

SCHEDULE OF QUANTITY

216

NAME OF WORK :-

Construction of Community Bhawan at Ghad Mala Gram Panchayat Nerd (Deposit Work).

SUB-HEAD :-

Construction of 1st floor..

ESTIMATED COST :- ₹ 90670.00
EARNEST MONEY :- ₹ 1850.00
TIME LIMIT : Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-20 (M- twenty) design mix to obtain the compressive strength of 20N/mm ² (twenty newton per Square millimetre) for reinforced cement concrete work, using cement with cement content not less than @ 320 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work above plinth level to give a smooth surfaces mechanically mixed and vibrated Including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.10	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	15015.00
2	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-25 (M- twenty) design mix to obtain the compressive strength of 20N/mm ² (twenty newton per Square millimetre) for reinforced cement concrete work, using cement with cement content not less than @ 360 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work above plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.86	7250.00	Rupees Seven Thousand Two Hundred Fifty Only	Per cubic metre	35235.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
3	Providing and laying for steel of TataTISCO. SAIL reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all respects as per approved drawing, design, and specification in all floor levels including the cost of binding wire and dewatering if arisen during placement of reinforcement as per PWD specification and approved, drawing design including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government	425.47	965.00	Rupees Ninety Five Only	Per Killogram	40420.00
TOTAL						90670.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

13/5/21
 Executive Engineer,
 Shalpur Division,
 MPWD Shalpur

SCHEDULE OF QUANTITY

NAME OF WORK :-
SUB-HEAD :-

Stock storage under HP.PWD Sub Division Gaggal.
Providing and laying pre-painted Roof front side.

ESTIMATED COST :- ₹ 93935.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
1	Providing and fixing ridges or hips 60 cm (Sixty centimetres) over all with 0.60mm (Zero decimal Sixty millimetres) thick pre-painted steel sheet ISI marked:- Z 120 of approved make in ridges of Sail / Reliance / Jindal / Raja Durashine with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted top J or L hooks, bolts and nuts 6mm (Six millimetres) diameters with pre-painted G.I. Impet and bitumen washers complete with all accessories as required within all leads, lifts of materials and other, incidentals, as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government	14.60 Running metres	750.20	Rupees Seven Hundred Fifty And Paise Twenty Only	Per running metre	10853.00
2	Providing and fixing plain M.S. B.R. sheet of TATA/SAIL/JINDAL steel 2.00 mm (Two decimal zero millimeter) thick fixed in leaves board / fascia / soffits including cutting, fixing and welding to steel rafters, member and applying a coat of red lead primer with gas/ electric welding in position complete (frame work is to be measured and paid for separately) within all leads, lifts of materials and other, incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government	57.50 Square metres	1495.00	Rupees One Thousand Four Hundred Ninety Five Only	Per square metre	85963.00
3	Painting with satin enamel paint of Asian/Nerolac Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government	43.68 Square metres	70.50	Rupees Seventy And Paise Fifty Only	Per square metre	3079.00
TOTAL :-						99995.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

25

So no-253


ESTIMATED COST :- ₹ 88132.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Two Months

NAME OF WORK :- C/O Chattri Pehad Road Km 0/00 to 3/780

SUB-HEAD :- C/O B/wall at Rd 3/620 to 3/625 and V-Shape Drain from Rd 3/620 to 3/630 (Portion Kholi khad road Km 3/00 to 3/780)

5. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.93	350.00	Rupees Three hundred Fifty only	Per cubic metre	4526.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement 1sto five sand 1sto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	16.38	4250.00	Rupees Four Thousand two hundred Fifty only	Per cubic metre	69615.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.00	350.00	Rupees Three hundred Fifty only	Each	3500.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetra as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.95	5380.00	Rupees Five Thousand three hundred eighty only	Per cubic metre	10491.00
TOTAL :-						
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				
88132.00						


 Executive Engineer,
 Shajapur Division,
 HP PWD Shajapur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 96126.00
 EARNEST MONEY :- ₹ 1350.00
 TIME LIMIT : Two Months

80m - 256

NAME OF WORK :- Landslide Disaster Related Mitigation work on Sall to Khan, Beil Road Km. 0/00 to 9/570.

SUB-HEAD :- C/o Edge wall with pusta at Rd 2/795 to 2/811.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.20	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2520.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement 1 to three sand 1 to six crushed stone aggregate 40 mm (four millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section clause 800, 900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials within in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.20	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	86670.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials within in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.16	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	6936.00
TOTAL :-						96126.00
Quoted Rate in Figure (%)		A	(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)		a	(Amount to be quoted by the contractor in words)			

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

26

241

ESTIMATED COST:- ₹ 99306.00
EARNEST MONEY :- ₹ 2000.00

TIME LIMIT : Two Months

NAME OF WORK :-

Construction of Link road Palwala to Lanjot in G.P. Durgella KM 0/00 to 0/900 in Tehsil Shahpur Distt. Kangra (H.P.), (Under S.C.S.P)

SUB-HEAD :-

Providing and laying G-II & G-III at RO 0/740 to 0/810.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading by mechanical means to required slope and compacted with three wheel 80-100 (eighty-one hundred) KN static roller to meet requirement of Table 300.2 complete as per MORD technical Specification section 400 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	40.10	91.30	Rupees Ninety One And Paise Thirty Only	Per cubic metre	3661.00
2	Providing, laying, spreading and compacting by mechanical means crushed stone aggregate size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II (75mm (seventy five millimetres) consolidated thickness using template, hand packing, rolling with three wheel 80-100 spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.20 cum (zero point two zero cubic metres) per ten square metres and binding material at the rate of 0.06 cum (zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications section 400 and as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	26.80	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per cubic metre	57620.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1						
3	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel brooming, stone screening type-B of size 11.2mm (eleven point two millimeters) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	3	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	38025.00
TOTAL :-						99306.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

27

SCHEDULE OF QUANTITY

Ser no - 289

ESTIMATED COST: ₹ 98184.00
 EARNEST MONEY ₹ 2000.00
 TIME LIMIT Two Months

NAME OF WORK :- Construction of Stairs at Chhni Meia Barwala G.P Manie, (VKV/2022/2152) (Deposit work)
 SUB-HEAD :- Construction of Stairs steps. (Balance work).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including petrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.70	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1295.00
2	Providing and laying cement concrete 1:4:8 (One Cement isto Four Sand isto eight) graded stone aggregate 40mm (Forty millimetre) nominal size for haunching of pipes of the 150 mm (One hundred fifty millimetre) internal diameters, necessary form work and curing complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	17.20	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	81700.00
3	Providing 40mm (Forty millimetre) thick Cement concrete flooring 1:2:4 (one cement isto two sand isto four aggregate) graded/crushed stone aggregate 20 mm (twenty millimetre) nominal size mechanically mixed including curing complete as per PWD specification, laid in one layer finished with a floating coat of neat cement. The rate is inclusive of cost and carriage of materials within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	70.45	215.60	Rupees Two Hundred Fifteen And Paise Sixty Only	Per square metre	15189.00
TOTAL :-						98184.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 H.P.W.D. System

SCHEDULE OF QUANTITY

200-200

ESTIMATED COST :- ₹ 90128.00

EARNEST MONEY :- ₹ 1950.00

TIME LIMIT :- Two Months

NAME OF WORK :- C/O Chattri Pehad road Km 0/00 to 3/780

SUB-HEAD :- C/O V-Shape Drain at RD 3/190 to 3/240 and 3/335 to 3/367

200

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	11.89	Rupees Three hundred Fifty only	Per cubic metre	4162.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.99	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	86026.00
TOTAL :-						90188.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shabpur Division,
HPWD Shabpur

SCHEDULE OF QUANTITY

NAME OF WORK :- Stock storage under HP.PWD Sub Division Gaggal.
SUB-HEAD :- Construction of Pillar for Gate.

279

ESTIMATED COST :- ₹ 59999.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Steel work in built up tubular, round, square or rectangular hollow tubes trusses etc, including cutting, fixing, lifting, hoisting and placing in position complete and applying a coat of red lead paint, within all leads, lifts of materials and other incidentals, as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or any other taxes imposed by the Government	930.66 Kilo gram	107.45	Rupees One Hundred Seven And Paise Forty Five Only	Per kilogramme	99999.00
TOTAL :-						99999.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

278

SCHEDULE OF QTY

ESTIMATED COST :-
EARNEST MONEY :-
TIME LIMIT :-

48375.00
1000.00
Two Months

28 no - 271

30

NAME OF		A/R & M/O link road salil to Lahari km 0/00 to 1/750		ESTIMATED COST :-		48375.00
SUB-HEAD :		Providing and laying G-II at RD 1/585 to 1/750 (INDUSTRY)		EARNEST MONEY :-		1000.00
5.				TIME LIMIT :		Two Months
No.	Description of items	Quantity	RATES		Unit	Amount
1	1	3	4	5	6	7
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 63mm to 45mm (Sixty three millimeter to fourty five millimeter) Grading-II size 75mm(seventy five millimeters) compacted thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-8 of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	21.50	2250.00	Rupee two thousand two hundred fifty only	Per cubic metre	48375.00
TOTAL :-		48375.00				
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Sipahpur Division,
Meerut Shahpur

SCHEDULE OF QUANTITY

(31)

Estimated cost:- Rs. 99200.00
Earnest Money:- Rs.2000.00
Time Allowed:- One Month

Name of Work:- R/O R/D On various Roads under Boh Section.
Sub Head:- Hiring of Poclain for removal of slips.

Sr. No.	Sub-Head/ Items of Work.	Quantity	Rates		Unit	Amount
			In Figures	In Words		
1.	Hiring of Poclain with Bucket/breaker (140 HP) for excavation/cutting removal of debris & dressing of road as per desired level, clearing the entire debris generated during the excavation work including all leads and lift with a maximum bucket capacity of 1 cum capacity of 45.00 per hour minimum six hour per day including pay of operator, POL charges maintenance of any minor or major accidental and other damages to private and Govt. property is the whole responsibility of the contractor. the work shall be excuted as per the direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges..	31.00	3200.00	(Rupees Three Thousand Two Hundred only)	Per Hour	99200.00
					Total:-	99200.00
	Quated Rate in Figure (%)	Amount to be Quoted by contractor in Figure				
	Quated Rate in Words (%)	Amount to be Quoted by contractor in Words				

P. S. T.
Executive Engineer
Shahpur Division,
HPPWD, Shahpur.

SCHEDULE OF QUANTITY

(32)

S.No - 264

Name of Work: - R/O R/D On various Roads under Darini Sub Division
Sub Head:- Hiring of Poclain for removal of slips.

Estimated cost:- Rs. 99200.00
Earnest Money:- Rs.2000.00
Time Allowed:- One Month

Sr. No.	Sub-Head/ Items of Work.	Quantity	Rates		Unit	Amount
			In Figures	In Words		
1.	Hiring of Poclain with Bucket/breaker (140 HP) for excavation/cutting removal of debris & dressing of road as per desired level, clearing the entire debris generated during the excavation work including all leads and lift with a maximum bucket capacity of 1 cum capacity of 45.00 per hour minimum six hour per day including pay of operator, POL, charges maintenance of any minor or major accidental and other damages to private and Govt. property is the whole responsibility of the contractor. the work shall be excuted as per the direction of Engineer in Charge including cartage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges..	31.00	3200.00	(Rupees Three Thousand Two Hundred only)	Per Hour	99200.00
					Total:-	99200.00
	Quated Rate In Figure (%)	Amount to be Quoted by contractor In Figure				
	Quated Rate in Words (%)	Amount to be Quoted by contractor in Words				

Executive Engineer
Shahpur Division
HPPWD, Shahpur.

SCHEDULE OF QUANTITY

280

NAME OF WORK :- Stock storage under HP,PWD Sub Division Gaggal.

SUB-HEAD :- Providing and laying pre-painted Roof back side.

ESTIMATED COST :- 96514.00
EARNEST MONEY :- 2000.00
TIME LIMIT :- Two Months

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick pre-painted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (Five) microns primer fixing with pre-painted iron J or L hooks, bolts and nuts with pre-painted limpet and rubber washers complete with all accessories as required within all heads, lifts of materials and other incidentals as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, makhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	58.43	1650 10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	96514.00
GRAND TOTAL :-						96514.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur


SCHEDULE OF QUANTITY

(39)

ESTIMATED COST :- ₹ 98890.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads HP.PWD Darini Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	89.90	1100.00	Rupees one thousand and or hundred only	Per Hour	98890.00
TOTAL :-						98890.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shapur Division,
 HPPWD Shapur

SCHEDULE OF QUANTITY

Estimated cost:- Rs. 98900.00
 Earnest Money:- Rs.2000.00
 Time Allowed:- One Month

Name of Work:- R/O R/D On various Roads under Boh Section under Darini Sub-Division.
 Sub Head:- Hiring of Excavator cum loader for removal of slips.

Sr. No.	Sub-Head/ Items of Work.	Quantity	Rates		Unit	Amount
			In Figures	In Words		
1.	Hiring of Excavator cum loader for improvement of profile correction of road in various reaches up to any height and lead including trimming to required line,width and grade in all kind and classification of soil including rocky portion and saturated soil as per and saturated soil as per direction and entire specification of Engineer-in-charge.The direction JCB/Excavator cum loader should work minimum 8 hours from 9.00 to 5.00 daily and excavate at least 30 cum Qty per hour.A ny loss to the public property or accident etc.happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases.The fuel and operational staff for excavator will be provided by the owner.The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge.	86.00	1150.00	(Rupees one thousand One Hundred Fifty only)	Per Hour	98900.00
					Total:-	98900.00
	Quated Rate in Figure (%)	Amount to be Quoted by contractor in Figure				
	Quated Rate in Words (%)	Amount to be Quoted by contractor in Words				

Assistant Engineer
 H.P.P.W.D.
 Sub-Division Darini

Executive Engineer
 Shahpur Division,
 H.P.W.D. Shahpur

SCHEDULE OF QUANTITY

(36)

ESTIMATED COST :- ₹ 98990.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under Boh Section under HP.PWD Darini Sub-Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	89.90	1100.00	Rupees one thousand and or hundred only	Per Hour	98990.00
TOTAL :-						98990.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

37

Sr No - 308

ESTIMATED COST :- ₹
EARNEST MONEY :- ₹

09/07/2020
09/06/2020
Time Limit

NAME OF WORK :- Balance work of ATC Building at Shahpur Dist Kangra (H.P.) (Deposit work).

SUB-HEAD :- Providing and Laying Paver blocks in courtyard and approach road at ATC Building Shahpur.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	1 Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement is to Four sand is to Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.50	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	30875.00
2	2 Providing and laying 60 mm thick Interlocking M-40 grade concrete paver block pavement conforming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	54.90	1100.00	Rupees One Thousand One Hundred Only	Per square metre	60390.00
3	3 Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	1.40	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	8610.00
TOTAL :-						99875.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

30

S.No - 347

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on Charri to Bhitlu Road km 0/000 to 5/780
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips at various RDs.

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

59

SCHEDULE OF QUANTITY

Serial-308

ESTIMATED COST :- ₹ 89000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on on various roads under H.P.PWD Gaggal Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips at various roads and RDs

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

46

SCHEDULE OF QUANTITY

Scanned - 313

NAME OF WORK :-

Construction of Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P.).

SUB-HEAD :-

Providing and fixing Sanitary Installation and water tank stand.

ESTIMATED COST: ₹ 39453.00
EARNEST MONEY: ₹ 20000.00
TIME LIMIT: Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes light grade ISI marked of lenolux/vectus/price 4.6mm thick having pressure not less than 5Kg/cm ² (six kilogramm per centimetre square) including fixing with approved adhesive etc. complete including entire carriage of materials within all leads/lifts and other incidentals. The rate is inclusive of octroi, royalty, melkhana, toll tax, sale tax, GST or any other taxes imposed by the Government. 110 mm dia (one hundred ten millimetre dia).	65.00	395.20	Rupees Three Hundred Ninety Six And Paise Twenty Only	Per Running metre	25753.00
2	Providing and fixing PVC door bend with oval access door, insertion rubber washer 3 mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. complete as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, melkhana, toll tax, sale tax, GST or any other taxes imposed by the Government. 110 mm dia (one hundred ten millimetre dia).	10.00	280.00	Rupees Two Hundred Eighty Only	Each	2800.00
3	Providing and fixing 15mm dia (fifteen millimetres) diametres C.P. (chromium plated) brass stop cock conforming ISI Marked IS No. 8934 (Eight thousand nine hundred thirty four) of Continental series of Jaquar / Classic series of Hindware / Floral Series of Cera / Hindon series of Jal as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, melkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	29.00	850.00	Rupees Eight Hundred Fifty Only	Each	24650.00

4	Providing and fixing 15mm dia (fifteen millimetres) diameters nominal bore chromium plated brass (ISI marked No. 8934) (Eight thousand nine hundred thirty four) bib tap (superior or heavy type) of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	14.00	950.00	Rupees Nine Hundred Fifty Only	Each	13300.00
5	Providing and fixing 8mm dia C.P. Jet spray of Continental series of Jaquar / Classik series of Hindware / Floral Series of Cera / Hindon series of Jal of approved quality and colour with one metre tube within all leads, lifts of materials and other incidentals and as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	13.00	450.00	Rupees Four Hundred Fifty Only	Each	5850.00
6	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (Handle lever) conforming to ISI 7231 with all fittings and fixtures complete. as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	9.00	910.40	Rupees Nine Hundred Ten And Paise Forty Only	Each	8194.00
7	Providing and fixing 32mm (Thirty two millimetres) diameters PVC brass waste and plug for glazed ware sinks, basins etcetera. with long screwed shank and fly nut and fixed to steel pipe including vulcanite plug, brass chain and stud complete as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	10.00	170.00	Rupees One Hundred Seventy Only	Each	1700.00
8	Providing and fixing 15mm (Fifteen millimetres) nominal bore PVC (polyvinyl chloride) connection pipe with brass union 30/ 45cm (Thirty or Forty five Centimetres) length, of Finolex, Reliance, Vectus complete as per H.P.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	21.00	120.00	Rupees One Hundred Twenty Only	Each	2520.00

9	Providing and fixing 15mm dia (fifteen millimetres) diameters nominal bore chromium plated brass (ISI marked No. 8934) (Eight thousand nine hundred thirty four) long nose bib tap (superior or heavy type) of Continental series of Jaquar / Classic series of Hindware / Floral Series of Cera / Hindon series of Jal as per H.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00	850.00	Rupees Eight Hundred Fifty Only	Each	2550.00
10	Providing and fixing PTMT waste coupling for wash basin and sink of approved quality and colour. Waste coupling 31 millimetre dia of 79 millimetre length and 62 millimetre breadth weighing not less than 45 grams, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00	99.75	Rupees Ninety Nine And Paise Seventy Five Only	Each	299.00
11	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in beams, joists, channels, angles, tee flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like, complete as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	110.20	107.50	Rupees One Hundred Seven And Paise Fifty Only	Per Kilogramme	11847.00
TOTAL :-						99463.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPWD Shahpur

511

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 98133.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Restoration of rain damages Shahpur Kiari Gandhrup road Km 0/00 to 2/400 in Tehsil Shahpur Distt Kangra (H.P).
SUB-HEAD :- C/o Breast wall at Km 1/728 to 1/731

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drain and Parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer- In - Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not exceeding 150 mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth any quantam of water including cleaning of slush which may arise out during dewatering complete as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	4	Rupees Three Hundred Fifty Only	Per cubic metre	2240.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in all type of structure as per drawing and MORD technical specification section 800, 900, 1200 and 1600 for nominal mix 1: 4: 8 (one cement isto four sand isto eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of farm work in retaining walls, breast walls etcetera as per the direction of Engineer-in-Charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.05	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic metre	92393.00

5600-309

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/foreast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including cartage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.00	350.00	Rupees Three Hundred Fifty Only	Each	3500.00
TOTAL :-						
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				
						98133.00


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

42

ESTIMATED COST:- ₹ 99137.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :-

Manal Bhandaria Mawa road.

SUB-HEAD :-

Improvement of curves and C/o Retaining Wall at RD 3/905.80 to 3/911.25 for bus passing.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.82	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5537.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement 150 five sand 150 ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	20.05	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	87218.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.39	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2882.00

4	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
2		3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORC technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.00	350.00	Rupees Three Hundred Fifty Only	Each	3500.00
TOTAL :-						99137.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

1351
 Executive Engineer,
 Shahpur Division,
 HPP, MB Shahpur

MS

NAME OF WORK :- Construction of Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P.)
SUB-HEAD :- Providing and fixing stainless steel pipe handrail.

ESTIMATED COST :- ₹ 98112.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Two Months

SCHEDULE OF QUANTITY

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying mechanically mixed and vibrated plain cement in open foundations for all type of structure using plain cement concrete grade M-10 (M-Ten) nominal mix (1:3:6) (One cement into Three sand into Six graded crushed stone aggregate 20mm (Twenty millimetres) nominal size) in or under water and curing complete including pumping of bailing out water, dewatering removal of slush as required at side which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in drains as per drawing and MORD technical Specification section 800.900 and 1200 as per direction of Engineer-in-Charge including cartage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	5.30	530.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	28514.00
2	Providing and fixing hand rail of 50 mm dia SST stainless steel pipe handrail fixed with 35 mm dia sst pipe as per detail in combination of 35 mm dia and 15 /20 mm sst baluster complete in all respect by welding etc. to steel ladder railing, balcony railing, staircase railing as per specification, drawing, design and direction by the Engineer in charge. as per approved drawing, design including cartage of materials within all leads, lifts and other incidental, and as per directions of Engineer-in-Charge. The rate is including Royalty, Malkana, Octroi, Toll Tax, Sales tax, GST or any other taxes imposed by the Government.	126.45	550.40	Rupees Five Hundred Fifty And Paise Forty Only	Per Killograme	69598.00
TOTAL :-						98112.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

(44)

319

NAME OF WORK :-

Manal Bhandaria Mawa road.


SUB-HEAD :-

Improvement of curves C/o Retaining Wall at RD 3/900 to 3/905.60 for bus passing.

ESTIMATED COST :- ₹ 99066.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other Incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.68	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5488.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement 1sto five sand 1sto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other Incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.89	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	86522.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other Incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.36	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2856.00

Description of Items	Quantity	RATES		Unit	Amount
		In fig	In words		
2	3	4	5	6	7
providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	12.00	350.00	Rupees Three Hundred Fifty Only	Each	4200.00
TOTAL :-					99066.00
Quoted Rate In Figure (%)	(Amount to be quoted by the contractor in Figure)				
Quoted Rate In Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 Haryana Shahpur

SCHEDULE OF QUANTITY

45

NAME OF WORK :-

Special repair of Veterinary Hospital Gohju in Tehsil Shahpur at Distt. Kangra Himachal Pradesh.

SUB-HEAD :-

Sanitary Installation etc.


ESTIMATED COST :- ₹ 84400.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Two Months

325

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octrol, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	4.25	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	20188.00
2	Providing and placing water tank of PVC (Poly vanyl chloride) Sinlex/Supreme/Finolox (Triple Layer) ISI marked having capacity 1000 (One thousand) litres each with necessary fitting including over flow pipes, scour pipe, ball valve and with cover locking arrangement of good quality including providing pads of sizes as required good quality all complete as per specifications including entire carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	2.00	10500.00	Rupees Ten Thousand Five Hundred Only	Each	21000.00
3	Providing and fixing vitreous china wash basin Garnet No 10072 and size 58x43 cm (fifty eight into forty three centimeters) of Hindware/Cera/Jaguar of of white/ snow white with double hole for pillar trap with C.I. or M.S. brackets painted white including cutting holes in walls and making good the same including all fitting complete in all respect including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00	2450.00	Rupees Two Thousand Four Hundred fifty Only	Each	2450.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing and fixing unplasticised PVC Pipe clips / Clamps of Supreme/Finolex/ Prince/Relpipe (reliance)vector of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs; screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete including carriage of material within all leads, lifts and other incidentals. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	1				
a	75 mm (Seventy five millimetre) diameter	20.00	185.10	Rupees One Hundred Eighty Five And Paise Ten Only	Per Running metre	3702.00
b	110 mm (One hundred ten millimetre) diameter	20.00	260.55	Rupees Two Hundred Sixty And Paise Fifty Five Only	Per Running metre	5211.00
5	Providing and fixing polyethylene aluminum polyethylene (PE- AL-PE) composite pressure pipe U.V. stabilized with carbon black conforming to I.S. 15450-2004 of Kitec for water supply including clamps at appropriate spacing, cutting fixing and making good the walls etcetera, but excluding the cost of fittings (internal work), including filling the joints with approved adhesive complete including entire carriage of materials within all leads lifts and other incidentals. The rate is inclusive of octrol, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government. 1620 (20mm) twenty millimeter diameter pipe O.D. pipe	12.00	425.00	Rupees Four Hundred Twenty Five Only	Per Running metre	5100.00
6	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is inclusive of octrol, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.02	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hectare	449.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In Fig	In words		
1	2	3	4	5	6	7
7	Providing and fixing concealed C.P. bib stop cock of continental series of Jaguar/ Classic series of Hindware/ Floral series of Cera/ Hindon series of Jal (heavy duty makes ISI marked) 15mm (Fifteen millimetre) as per specifications including entire carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	4.00	850.00	Rupees Eight Hundred Fifty Only	Each	3400.00
8	Providing and fixing concealed C.P. brass long body bib cock of continental series of Jaguar/ Classic series of Hindware/ Floral series of Cera/Hindon series of Jal (heavy duty makes ISI marked) 15mm (Fifteen millimetre) as per specifications including entire carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	2.00	950.00	Rupees Nine Hundred Fifty Only	Each	1900.00
9	Constructing brick masonry chamber for under ground CI inspection chamber and bends with common burnt clay building bricks in cement mortar 1:5 (one cement : five sand) cover with frame (light duty) 355mmx6mm internal dimensions total weight of cover with frame to be not less than 38Kg. (weight of cover 23Kg. and weight of frame 15Kg) RCC top slab with 1:2:4 (one cement : two sand : four graded stone aggregate 20mm nominal size) foundation concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm nominal size) in side plaster 15mm thick with cement mortar 1:3 (one cement : three sand) finished smooth with floating coat of neat cementon wall and bed concrete etc. complete. Inside dimension 45x610x450mm deep single pipe line. The rates are including cost and carriage within all leads and lifts and other incidentals as per PWD specification and entire satisfaction/direction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	4.00	5250.00	Rupees Five Thousand Two Hundred Fifty Only	Each	21000.00
TOTAL :-						84400.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

46

321

NAME OF

Restoration of Rain damages on Various Roads under Shahpur Sub Division.

SUB-HEAD

: - Hiring of Excavator cum loader on Rehlu to Boru sarma Road km 0/000 to 5/000

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octrol, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF

AR&M/O Various Roads under Shahpur Sub Division.

SUB-HEAD

Hiring of Excavator cum loader on Ralt kohla Bhalla Road km 3/500 to 7/500

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octrol, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

15/5
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

318

ESTIMATED COST:- ₹ 99972.00

EARNEST MONEY:- ₹ 2000.00

TIME LIMIT : Two Months

NAME OF WORK :-

Manal Bhandarwa Mawa road.

SUB-HEAD :-

Improvement of curves C/o Retaining Wall at RD 2/494.80 to 2/500 for bus passing.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	26.93	300.00	Rupees Three Hundred Only	Per cubic metre	8079.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14.56	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5096.00

Description of Items			Quantity	RATES		Unit	Amount
1	2		3	In fig	In words	6	7
3	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement 150 five sand 150 ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other Incidentals. The rate is Including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.		18.70	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	81345.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other Incidentals. The rate is Including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.		3.12	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2652.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other Incidentals. The rate is Including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.		8.00	350.00	Rupees Three Hundred Fifty Only	Each	2800.00
TOTAL :-							99972.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)				

151
 Executive Engineer,
 Shapur Division,
 HPWD Shapur

149

SCHEDULE OF QUANTITY


Sever-8 to

ESTIMATED COST :- ₹ 99056.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Restoration of rain damages Shahpur Kiarī Gandhtrap road Km 0/00 to 2/400 in Tehsil Shahpur Distt Kangra (H.P).
SUB-HEAD :- C/o Breast wall at Km 1/720 to 1/727

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drain and Parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiselling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer- in - Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of slides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not exceeding 150 mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth any quantum of water including cleaning of slush which may arise out during dewatering complete as per direction of Engineer- in-Charge. Including cartage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.65	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2328.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in all type of structure as per drawing and MORD technical specification section 800, 900, 1200 and 1600 for nominal mix 1: 4: 8 (one cement two four sand two eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in retaining walls, breast walls etcetra as per the direction of Engineer-in-Charge including cartage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.15	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic metre	92878.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	11.00	350.00	Rupees Three Hundred Fifty Only	Each	3850.00
TOTAL :-						
	Quoted Rate In Figure (%)	(Amount to be quoted by the contractor in figure)				
	Quoted Rate In Words (%)	(Amount to be quoted by the contractor in words)				
						99056.00


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

See no - 314

NAME OF WORK :- Construction of Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P.).

SUB-HEAD :- Providing and Laying sewage system.

ESTIMATED COST :- ₹ 92205.00
EARNEST MONEY :- ₹ 1850.00
TIME LIMIT : Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	23	3	4	5	6	7
1	Providing and laying mechanically mixed and vibrated plain cement in open foundations for all type of structure using plain cement concrete grade M- 10 (M- Ten) nominal mix (1:3:6) (One cement into Three sand into Six graded crushed stone aggregate 20mm (Twenty millimetres) nominal size) in or under water and curing complete including pumping of bailing out water, dewatering removal of slush as required at side which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in drains as per drawing and MORD technical Specification section 800,900 and 1200 as per direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes Imposed by the Government.	6.1	5380	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	32818.00
2	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes light grade ISI marked of (tenolex)/vectus/price 4.6mm thick having pressure not less than 6kg /cm ² (six kilogram per centimetre square) including fixing with approved adhesive etc. complete including entire carriage of materials within all leads lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government. 150 mm dia (one hundred fifty millimetre dia).	35.00	625.35	Rupees Six Hundred Twenty Five And Paise Thirty Five Only	Per running metre	21887.00
3	Providing and fixing on wall face 150 mm (One hundred fifty millimetre) diameter plain bend Providing and fixing on wall face PVC (D-plate) accessories for rain water pipes of Supreme/Finox/Prince /Relpipe (reliance)/ vectus including filling the joints with approved adhesive complete as per PWD specification, approved drawing and design including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer- in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government. 150 mm dia (one hundred fifty millimetre dia).	1.00	220.00	Rupees Two Hundred Twenty Only	Each	220.00

4	Providing and fixing on-wall face 150 mm (One-hundred twenty millimetre) diameter plain bend Providing and fixing on wall face PVC (D-pest) accessories for rain water pipes of Supreme/Finolex/Prince /Relpipe (reliance)/ vectus including filling the joints with approved adhesive complete as per PWD specification, approved drawing and design including cost and cartage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government. 110 mm dia (one hundred ten millimetre dia).	7.00	280.00	Rupees Two Hundred Eighty Only	Each	1960.00
5	Providing and fixing PVC door bend with oval access door, insertion rubber washer 3 mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc complete as per H.P.W.D specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including cartage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government. 150 mm dia (one hundred fifty millimetre dia).	6.00	220.00	Rupees Two Hundred Twenty Only	Each	1320.00
6	Constructing brick masonry chamber 60x60x75 cm (Sixty into sixty into seventy five centimetre) inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) , i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design, as per the entire satisfaction and direction of the Engineer-in-Charge including cartage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.00	8500.00	Rupees Eight Thousand Five Hundred Only	Each	34000.00
TOTAL :-						92205.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

154
 Executive Engineer,
 Shapur Division,
 HPPWD Shapur

SCHEDULE OF QUANTITY

317-

ESTIMATED COST:- ₹ 99946.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

(51)

NAME OF WORK :-


Manal Bhandaria Mawa road.

SUB-HEAD :-

Improvement of curves C/o Retaining Wall at RD 2/501 to 2/503.40 for bus passing.

5. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	187.20	300.00	Rupees Three Hundred Only	Per cubic metre	56160.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge. Including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.72	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2352.00

Description of Items		Quantity	RATES		Unit	Amount
			In fig	In words		
3	2	3	4	5	6	7
Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement 1sto five sand 1sto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-In-charge including cartlage of material, within all leads, lifts of materials and other Incidentals. The rate is including octrol, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.		8.60	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	37410.00
4		1.44	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	1224.00
Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-In-Charge complete, including cartlage of materials with in all leads, lifts and other Incidentals. The rate is including Royalty, Malkana, Octrol, toll tax, GST or any other taxes imposed by the Government.						
5		8.00	350.00	Rupees Three Hundred Fifty Only	Each	2800.00
Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-In-charge including cartlage of materials within all leads, lifts and other Incidentals. The rate is including octrol, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.						
TOTAL :-						99946.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPK, Shahpur


SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 98259.00
 EARNEST MONEY:- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Harnera Baran Sidhpur Sirmari Khabhal Salwana Talwani road km 0/00 to 9/320.
 SUB-HEAD :- Construction of R/Wall between 4/150 to 4/160 & Parapets.

5 No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.50 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1575.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement two five sand ten ten graded/crushed stone aggregate) 40mm (forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetera including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00 Cubic metres	4300.00	Rupees Four Thousand Three Hundred Only	Per cubic metre	34400.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	2100.00

4	Providing and laying mechanically mixed and vibrated reinforced cement concrete in super structure as per drawing and M.O.R.D., technical specification section 800, 900 and 1400 using R.C.C. grade M-25 (twenty five) design mix with cement contents not less than 400 kg (four hundred kilogram) per cubic metre with 20mm (twenty millimetre) nominal size graded crushed stone aggregate and curing complete including cost of form work but excluding the cost of reinforcement for reinforced concrete work in deck slab and to the entire satisfaction and as per the direction of Engineer-In-Charge including carriage of material within all leads , lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.76 Cubic metres	7150.00	Rupees Seven Thousand One Hundred fifty Only	Per cubic metre	41184.00
5	Supplying fitting and placing HYSD bar reinforcement in super-structures complete as per drawings and MORTH technical specifications clause 1600 and 2200, including cutting bending, binding, Straightening and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-In-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	0.20 Tonne	95000.00	Rupees Ninety Five Thousand Only	Per Tonne	19000.00
TOTAL :-						98259.00
	Quoted Rate In Figure (%)	b.	(Amount to be quoted by the contractor in Figure)			
	Quoted Rate In Words (%)	b.	(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Bahour Division,
 Hapur Shiksha

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99741.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Special repair of Veterinary Hospital Gohju In Tehsil Shahpur at Distt. Kangra Himachal Pradesh.
SUB-HEAD :- Providing and laying Distemper, painting, flooring etc.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying factory made chartered edge precast Cement Concrete paver blocks 60mm (sixty millimetre) thick of NTC/ Unislone/ Atlantic/ as per approved shade and design in parking of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm (fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete, as per direction of Engineer-In- Charge, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.25	1200.00	Rupees One Thousand Two Hundred Only	Per square metre	5100.00
2	Providing and laying mechanically mixed and vibrated concrete for plain concrete in foundation of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802.803.1202 and 1203 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	6.75	7250.00	Rupees Seven Thousand Two Hundred Fifty Only	Per cubic metre	48938.00
3	Applying Birda white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, toll tax, GST and all type of other taxes imposed by the Government.	25.00	85.10	Rupees Eighty Five And Paise Ten Only	Per square metre	2128.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Distemping (two coats) with acrylic oil bound washable distemper with Nerolac/ Asian paints of approved brand and manufacture and of required shade on ceiling/sloping roof surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge.	158.22	56.25	Rupees Fifty Six And Paise Twenty Five Only	Per square metre	8900.00
5	Finishing wall with Apex weather proof exterior grade emulsion of Asians Paints /Nerolac suraksha /Berger paint Exterior Emulsion as per approved shade approved design (Apexultima) on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	65.00	95.10	Rupees Ninety Five And Paise Ten Only	Per square metre	6182.00
6	Painting two or more coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brushing of Asian paint/ Nerolac/Berger of approved shade to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matter enamel paint other than white within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	10.08	82.40	Rupees Eighty Two And Paise Forty Only	Per square metre	831.00
7	Painting two or more coats of Nerolac/Asian paint/ Berger (excluding priming coat) on new wood and wood based surface with enamel paint other than white to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering and stoping within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	16.50	95.00	Rupees Ninety Five Only	Per square metre	1568.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
8	Providing and laying plinth protection 50 mm (fifty millimetre) thick in cement concrete 1:3:6 (one cement into three sand into four aggregate 20 mm nominal size with rammed and consolidated and grouted with fine sand including preparation of ground complete as per PWD specification. The rates are inclusive cost and cartage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	35.95	725.00	Rupees Seven Hundred Twenty Five Only	Per square metre	26064.00
TOTAL :-						99771.00
	Quoted Rate in Figure (%)	uc	(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)	uc	(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 HPPWD Shajapur

Regulation & Rai darog

DNT

(54)

Name of Work:- A/R & M/O various roads under Shahpur Sub Division				Estimated Cost	99000.00
(SH:-Hiring of excavator cum loader on Relhu Boru Sarma road km 5/00 to 6/00)				Earnest Money	2000.00
Sr. No.	Description of Item	Qty.	Rate in Figure	Time Limit	
				Rate in words	Unit
1	Hiring of Excavator cum loader for removal of slips, improvement of profile correction of road in various reaches up to any height ,depth and lead including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per direction and entire satisfactions of Engineer- in charge. The JCB/Excavator cum Loader should work minimum 8.00 hours daily. Any loss to the public property or any accident etc happened during the course of hiring period/execution shall be the absolute responsibility of the JCB/Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare watch and ward of Excavator also be born by the Contractor/Owner. The daily log book will be maintained at site which should be duly certified by the Engineer in Charge.	90.00	1100.00		P/Hours
No deviation shall be allowed in any cases.					99000.00
Total					99000.00

Assistand Engineer
Shahpur Sub-Division
HPPWD Shahpur

Executive Engineer
Shahpur Division
HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF

Restoration of Rain damages on Various Roads under Shahpur Sub Division.

SUB-HEAD :-

Hiring of Excavator cum loader on Rehlu to Boru sarra Road km 5/000 to 6/000

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor In all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

55

ESTIMATED COST:- 99650.00
EARNEST MONEY:- 2000.00
TIME UNIT : Two Months

NAME OF WORK :- Construction of Harera Baran/ Sidhpur Sirmari Khabhal Salwana Tatwani road km 0/00 to 9/920.
SUB-HEAD :- Construction of Sub Structure of RCC Slab culvert at Rd 4/300.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2275.00
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in super structure as per drawing and M.O.R.D. technical specification section 800, 900 and 1400 using R.C.C grade M-25 (twenty five) design mix with cement contents not less than 400 kg (four hundred kilogram) per cubic metre with 20mm (twenty millimetre) nominal size graded crushed stone aggregate and curing complete including cost of form work but excluding the cost of reinforcement for reinforced concrete work in deck slab and to the entire satisfaction and as per the direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.75	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	5363.00
3	Supplying fitting and placing HYSD bar reinforcement in super-structures complete as per drawings and MORO technical specifications clause 1600 and 2200, including cutting bending, binding, straightening and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	0.45	95000.00	Rupees Ninety Five Thousand Only	Per Tonne	42750.00

4	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	8.01	Cubic metres	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per Tonne	49261.00
TOTAL :-				99650.00			
	Quoted Rate in figure (%)			(Amount to be quoted by the contractor in figure)			
	Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Sahpur Division,
 H.P.W.D. Shahdol

SCHEDULE OF QUANTITY

S.No - 306


NAME OF WORK :- Balance work of ATC Building at Shahpur Dist Kangra (H.P.). (Deposit work).

SUB-HEAD :- Providing and fixing Aluminium section i/c glazing in the office room R-4.

ESTIMATED COST :- ₹ 99097.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Two Months.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing coloured aluminium in frame work Jindal/ Hindalco for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate 2 sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete for shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15 (fifteen) within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government. ge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government	60.50	490.10	Rupees Four Hundred Ninety And Paise Ten Only	Per Kilogramme	29651.00
2	Providing and fixing glazing glass panes of 5 mm (Five millimetres) thickness (weight not less than 12.50kg/square metre) of mod. guard/saint gobain/ATS/Atul/Gold Plus in door, windows, ventilators shutter and partitions with EPDM rubber/Neoprene gasket etcetera as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or any other taxes imposed by the Government.	5.47	1150.00	Rupees One Thousand One Hundred fifty Only	Per square metre	6291.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.38	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	20805.00

4	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement conforming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of Interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	38.50	1100.00		Per square metre	42330.00
TOTAL :-						99097.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

(57)

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98890.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under HP.PWD Darhul Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, In all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	89.90	1100.00	Rupees one thousand and or hundred only	Per Hour	98890.00
TOTAL :-						98890.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shabgar

58

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99500.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Stock and storage in PWD Store under ~~General~~ ^{Shahpur} Division, HPPWD Shahpur Division, Distt. Kangra HP

SUB-HEAD :- Supplying & stacking CC 2001002000 quick lime

S. No.	Description of items	Quantity	RATES		Amount
			In fig	In words	
1	2	3	4	5	7
1	Supplying and stacking CC2001002000 Quick lime corresponding to class A as per specification 712-000 As amended in polythene based gunny bags of 40 kg (forty kilograms) containing total calcium magnesium oxide 70 % (seventy percent) for construction works completed fitting including carriage of material, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	5000.00 kilograms	19.90	Rupees nineteen and paise ninety only	99500.00
Total :-					99500.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- A/R & M/O various roads of HPPWD Sub Division Shahpur.

ESTIMATED COST :- 98148.00
CARVEST MONEY :- 2000.00
TIME LIMIT :- Two Months

SUB-HEAD :- Painting on Bridges, Rain Shelter and writing lettering, figures, Kilometers stone, sign boards and parapets etc.

5. No.	Description of items	Quantity	RATES			Unit	Amount
			3	4	5		
1	2	3	In fig	In words	6	7	
1	Finishing wall with weather proof exterior grade emulsion of approved design (Aqueulnial) or its equivalent on undecorated wall surface (two coats) to give an even shade and final after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc. including sand paper smooth complete as per teh direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	98.00	110.00	Rupees One Hundred Ten Only	Per Square meter	10780.00	
2	Painting two coats(excluding priming coat) on new concrete masonry/plaster surfaces with enamel paint of approved brand and manufacture for use on floors to give an even shade including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required with as per teh direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by teh Government.	80.00	86.10	Rupees Eighty Six And Paise Ten Only	Per Square meter	6888.00	
3	Painting two coats (excluding priming coat) on new steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt, dust and other foreign matter with enamel paint other than white within all leads, lifts of material and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	70.00	45.00	Rupees Forty Five Only	Per Square meter	3150.00	
4	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, comas, hyphens and the like not to be measured and paid separ. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Governmentally, Block letters, Indian letters/figures within all leads, lifts of materials and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	35150.0	2.20	Rupees Two And Paise Twenty Only	Per letter per cm. height	7730.00	
		TOTAL :-					98148.00
		Quoted Rate in Figure (%)					
		Quoted Rate in Words (%)					

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

60

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99500.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- Stock and storage in PWD Store under Gaggal Sub Division, HPPWD Shahpur Division, Distt. Kangra HP

SUB-HEAD :- Supplying & stacking CC 2001002000 quick lime

S. No.	Description of items	Quantity	RATES		Amount
			In fig	In words	
1	2	3	4	5	7
1	Supplying and stacking CC2001002000 Quick lime corresponding to class A as per specification 712- ood As amended in polythene based gunny bags of 40 kg (forty kilograms) containing total calcium magnesium oxide 70 % (seventy percent) for construction works completed fitting including carriage of material , as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	5000.00 kilograms	19.90	Ruppes nineteen and paise ninety only	Per Kilogram
Total :-					99500.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

61

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on on various roads under Rajol section H.P.PWD Gaggal Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips at various roads and RDs

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc. In all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor In Figure)				
Quoted Rate In Words (%)		(Amount to be quoted by the contractor In words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST :- ₹ 99790.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Months

NAME OF WORK :- Restoration of Rain damages on Charri to Ghera road Km 0/00 to 8/555.

SUB-HEAD :- RCC Wall at RD 8/412.40 to 8/413.90

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1575.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement 1sto Four sand 1sto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.19	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	903.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	7.50	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	53625.00

4	Supplying fitting and placing HYSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, or any other taxes imposed by the Government.	460.80	90.50	Rupees Ninety And Paise fifty Only	Per Killogram	41702.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (1V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.00	350.00	Rupees Three Hundred Fifty Only	Each	1050.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.10	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	935.00
TOTAL :-						99790.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

63

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF Restoration of Rain damages on on various roads under Gaggal section HP,PWD Gaggal Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips at various roads and RDs

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, cleaning road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

654


SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration of Rain damages on Charri to Ghera road Km 0/00 to 8/555.
SUB-HEAD :- RCC Wall at RD 8/410 to 8/411.40.

ESTIMATED COST :- ₹ 99946.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift, including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.56	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1596.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.18	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	855.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete Grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	7.27	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	51981.00

4	Supplying fitting and placing HVSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-In-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	472.42	90.50	Rupees Ninety And Paise Fifty Only	Per Kilogram	42754.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and M.O.R.D technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.00	350.00	Rupees Three Hundred Fifty Only	Each	1400.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-In-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.60	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	1360.00
TOTAL :-						99946.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shabdar

SCHEDULE OF QUANTITY

65

NAME OF Restoration of Rain damages on on various roads under Charri section HP.PWD Gaggal Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips at various roads and RDs

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

66

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97900.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF Restoration of Rain damages on on various roads under Gaggal section HP.PWD Gaggal Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips at various roads and RDS

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc. in all kind of soil like boulder, rocks done etc. completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	89.00	1100.00	Rupees one thousand and or hundred only	Per Hour	97900.00
TOTAL :-						97900.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate In Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

67

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97900.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on on various roads under Charri section HP.PWD Gaggal Sub-Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips at various roads and RDS

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc. In all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	89.00	1100.00	Rupees one thousand and or hundred only	Per Hour	97900.00
TOTAL :-						97900.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

(68)

ESTIMATED COST: - ₹ 99550.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT: One Month

NAME OF Restoration of Rain damages on on various roads under Charri section HP.PWD Gagal Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips at various roads and RDS

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.50	1100.00	Rupees one thousand and or hundred only	Per Hour	99550.00
TOTAL :-						99550.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED ₹ 88013.00
EARNEST MONEY ₹ 1350.00
TIME LIMIT Two Months

NAME OF WORK :- C/o Retaining Wall from Naveen Kumar Dhiman House to Ramesh House Gram Panchayat Garoh, VIKRANT

SUB-HEAD :- C/o Retaining Wall at Rd 0/00 to 0/008.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift. Including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers, not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1873.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 15:30 (One cement 150 five sand 150 ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.40	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	84390.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):2(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00	350.00	Rupees Three Hundred Fifty Only	Each	1750.00
TOTAL :-						88013.00
	Quoted Rate In Figure (%)	n	[Amount to be quoted by the contractor in Figure]			
	Quoted Rate In Words (%)	n	[Amount to be quoted by the contractor in words]			

Executive Engineer,
Shahpur Division,
HPPWD Sahaspur

SCHEDULE OF QUANTITY

ESTIMATED ₹ 88465.00
EARNEST MONEY ₹ 1800.00
TIME LIMIT Two Months

NAME OF WORK :- C/o Retaining Wall from Naveen Kumar Dhillan house to Ramesh House Gram Panchayat Garoh (VKVNT)
SUB-HEAD :- C/o Retaining Wall at Rd 0/0.10 to 0/0.17.

5. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1890.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1.5:1.0 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.50	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	84825.00
3	Providing and Laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00	350.00	Rupees Three Hundred Fifty Only	Each	1750.00
TOTAL :-						88465.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HIPWID Saharapur

SCHEDULE OF QUANTITY

ESTIMATED ₹ 71253.00
EARNEST MONEY ₹ 1450.00
TIME LIMIT Two Months

324

NAME OF WORK :- C/o Retaining Wall from Naveen Kumar Ohiman house to Ramnesh House Gram Panchayat Garoh JKUMY :-
SUB-HEAD :- C/o Retaining Wall at Rd 0/019 to 0/023.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including cartage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.45	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1208.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (forty millimeters) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including cartage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	15.70	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	68295.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H):(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in- charge including cartage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00	350.00	Rupees Three Hundred Fifty Only	Each	1750.00
TOTAL :-						71253.00
	Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure)			
	Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- C/O 40.00 Metre Span Bridge Over Gaj Khad at Km 0/300 in Ghera on Baladi Mod. to Balla Km 0/00 to 1/500 in Tehsil Shahpur Distt. Kangra H.P.
SUB-HEAD :- Geo-Technical Investigation.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Investigation Bearing capacity of soil at Bridge Site at different locations (ie. Left side Abutment of minimum 14.00 (Fourteen) meter depth of each bore and submitted the test result complete in all respect. The rate is including GST, toll tax, Sale Tax or other taxes imposed by the government.	14.00 Running metres	7000.00	Rupees Seven Thousand Only	Per Running metre	98000.00
Total:-						98000.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT One Month

NAME OF WORK :-

C/O 40.00 Metre Span Bridge Over Gaj Khad at Km 0/300 in Ghera on Baladi Mod to Balla Km 0/00 to/500 in Tehsil Shahpur Distt. Kangra H.P.

SUB-HEAD :-

Geo- Technical Investigation.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Investigation Bearing capacity of soil at Bridge Site at different locations(i.e. Right side Abutment of minimum 14.00 (Fourteen) meter depth of each bore and submitted the test result complete in all respect .The rate is including GST, toll tax, Sale Tax or other taxes imposed by the government.	14.00 Running metres	7000.00	Rupees Seven Thousand Only	Per Running metre	98000.00
Total:-						98000.00
Quoted Rate in figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

134
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

1-344-8
(79)

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT One Month

NAME OF WORK :- C/O 35.00 Metre Span Bridge Over Banoi Khad at Km 0/300 on Ruhru to Narghota road Km 0/00 to 1/500

SUB-HEAD :- Geo- Technical Investigation.

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Investigation Bearing capacity of soil at Bridge Site at different locations (ie. Left side Abutment of minimum 14.00 (Fourteen) meter depth of each bore and submitted the test result complete in all respect .The rate is including GST, toll tax, Sale Tax or other taxes imposed by the government.	14.00 Running metres	7000.00	Rupees Seven Thousand Only	Per Running metre	98000.00
Total:-						98000.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

(75)

ESTIMATED COST :- ₹ 98000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT One Month

NAME OF WORK :-

C/O 35.00 Metre Span Bridge Over Banoi Khad at Km 0/300 on Ruhru to Narghota road Km 0/00 to 1/500

SUB-HEAD :-

Geo- Technical Investigation.

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Investigation Bearing capacity of soil at Bridge Site at different locations (i.e. Right side Abutment of minimum 14.00 (Fourteen) meter depth of each bore and submitted the test result complete in all respect . The rate is including GST, toll tax, Sale Tax or other taxes Imposed by the government.	3	7000.00	Rupees Seven Thousand Only	Per Running metre	98000.00
Total:-						98000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

HPWD
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

Serno - 312

ESTIMATED COST :- ₹ 94271.00
EARNEST MONEY :- ₹ 1900.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Mini Secretariat Building at Shahpur Tehsil Shahpur Dist Kangra (H.P).
SUB-HEAD :- Providing and fixing submersible pump including all fitting.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying mechanically mixed and vibrated plain cement in open foundations for all type of structure using plain cement concrete grade M- 10 (M- Ten) nominal mix (1:3:6) (One cement 150 Three sand 150 Six graded crushed stone aggregate 20mm (Twenty millimetres) nominal size) in or under water and curing complete including pumping of bailing out water, dewatering removal of slush as required at site which may arrive at the time of laying under water complete for all heights/ depths including the cost of form work in drains as per drawing and MOHD technical Specification section 800,900 and 1200 as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	4.30	5360.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	23134.00
2	Providing and fixing submersible water pump of crimpion 1.00 H P Including electrical fittings upto distance of 50 metre is required for the smooth working of submersible pump automatically fix automatic starter for submersible pump which efficiently switches on and off, on increase/ decrease of water level in the pit and fixing the pump at raised level in the pit so that minimum water level of 0.50 to 0.60 meter is always maintained in the pit including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	1.00	24500.00	Rupees Twenty Four Thousand Five Hundred Only	Each	24500.00
3	Providing and fixing polyethylene aluminium polyethylene (PE- AL-PE) composite pressure pipe U.V. stabilized with carbon black conforming to IS. 15450:2004 of Kirec for water supply including clamps at appropriate spacing, cutting, fixing and making good the walls etcetera; but excluding the cost of fittings (internal work), including filling the joints with approved adhesive complete including entire carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government. 1620 (50mm) fifty millimeter diameter pipe O.D. pipe	45.00	550.00	Rupees Five Hundred Fifty Only	Each	24750.00

4	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes light grade ISI marked of fenolex/vecus/price 4.6mm thick having pressure not less than 6kg /cm ² (six kilogram per centimetre square) including fixing with approved adhesive etc. complete including entire carriage of materials within all leads lifts and other incidentals. The rate is inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or any other taxes imposed by the Government. 150 mm dia (one hundred fifty millimetre dia).	35.00	625.35	Rupees Six Hundred Twenty Five And Paise Thirty Five Only	Per running metre	21887.00
TOTAL :-						
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY


(77)

ESTIMATED COST :- ₹ 99000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF A/R&M/O Various Roads under Shahpur Sub Division.

SUB-HEAD :- Hiring of Excavator cum loader on Shahpur Darini Road km 0/000 to 6/000

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slps, clearing road opening of drains and catchpits etc. In all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octrol, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	3	4	5	6	7
		90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
	Quoted Rate In Figure (%)	(Amount to be quoted by the contractor In Figure)				
	Quoted Rate In Words (%)	(Amount to be quoted by the contractor In words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

78

ESTIMATED COST :- ₹ 99200.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF Repair and Restoration of various roads under shahpur sub Division
SUB-HEAD :- Hiring of rock Breaker on Shahpur Darini road.

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Rock Breaker having 2 to 4 tonne hammer capacity for removal of boulder slips, rock cutting for drains, removal of boulders from catchpits, opening of blocked drains due to boulders etc and other similar road works requiring breaking of rock and boulders on road in various reaches up to any height, depth and disposal of material up to 20.00 meters lead in all kind and classification of soil including rocky portion as per direction and entire satisfactions of Engineer-in charge. The Rock Breaker should work minimum 8.00 hours daily. Any loss to the public property or any accident etc happened during the course of hiring period/execution of work, shall be the absolute responsibility of the Rock Breaker owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff will be provided by the owner. The repair, spare and watch and ward of Rock Breaker will also be born by the Contractor/Owner. The daily log book will be maintained at site which should be duly certified by the Engineer in Charge. The rate is inclusive of GST and all other type taxes, royalties etc imposed by central or state government.	32.00	3100.00	Rupees Three thousand and one hundred only	Per Hour	99200.00
TOTAL :-						99200.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

(79)

ESTIMATED COST :- ₹ 99200.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF Repair and Restoration of various roads under shahpur sub Division
SUB-HEAD :- Hiring of rock Breaker under Dramman section

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Rock Breaker having 2 to 4 tonne hammer capacity for removal of boulder slips, rock cutting for drains, removal of boulders from catchpits, opening of blocked drains due to boulders etc and other similar road works requiring breaking of rock and boulders on road in various reaches up to any height, depth and disposal of material up to 20.00 meters lead in all kind and classification of soil including rocky portion as per direction and entire satisfactions of Engineer- in charge. The Rock Breaker should work minimum 8.00 hours daily. Any loss to the public property or any accident etc happened during the course of hiring period/execution of work, shall be the absolute responsibility of the Rock Breaker owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff will be provided by the owner. The repair, spare and watch and ward of Rock Breaker will also be born by the Contractor/Owner. The daily log book will be maintained at site which should be duly certified by the Engineer in Charge. The rate is inclusive of GST and all other type taxes, royalties etc imposed by central or state government.	32.00	3100.00	Rupees Three thousand and one hundred only	Per Hour	99200.00
TOTAL :-						99200.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under Darini Section under HP.PWD Darini Sub-Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc. in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shabgar

SCHEDULE OF QUANTITY

(81)

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under Darini Section under HP.PWD Darini Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, cleaning road opening of drains and catchpits etc, In all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
	Quoted Rate In Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under Darinl Section under HP.PWD Darinl Sub- Division.

SUB-HEAD :- Hiring of Excavator cum loader for removal of silps.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of silps, clearing road opening of drains and catchpits etc, In all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98440.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- C/O Path alongwith interlocking Tiles from Bhupinder House to Kamal House Gram Panchayat Garoh ward No-04 JKRYN
 SUB-HEAD :- C/O Edge Wall and P/L interlocking Paver Block.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.80	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	630.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.O. technical specification section/ clause 800.900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	2.50	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	13450.00
3	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetera including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.20	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	19950.00
4	Providing and laying 60 mm thick interlocking M-40 grade Concrete paver block pavement conforming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	50.00	1100.00	Rupees One Thousand One Hundred Only	Per Square metre	55000.00

328

5	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in situ structure for all heights of structure of plain cement concrete grade M-20 (twenty) with minimum nominal min. 12.5 (one cement to 2.50 sand to 2.50 four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Wakara, toll tax, GST and any other taxes imposed by the Government.	1.53	5,555.55	Supplies for Transportation for 20000 m³ concrete for 14 days curing	5000.00
TOTAL					5000.00
Quoted Rate in Figure (%)		Amount to be quoted by the contractor in Figure			
Quoted Rate in Words (%)		Amount to be quoted by the contractor in words			


 Engineer-in-Charge
 District Engineer
 District Engineer

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97900.00
 EARNEST MONEY :- ₹ 1000.00
 TIME LIMIT : Two Months

329

NAME OF WORK :- C/o Path alongwith Interlocking Tiles from Dhupinder House to Kamal House Gram Panchayat Garoh ward No-04 (VKVNY)
 SUB-HEAD :- P/L Interlocking Paver Block.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement conforming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	89.00	1100.00	Rupees One Thousand One Hundred Only	Per Square metre	97900.00
TOTAL :-						97900.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPMD Shahpur

SCHEDULE OF QUANTITY

85

NAME OF WORK :- A/R & M/O various roads of HPPWD Sub Division Gargol.

SUB-HEAD :- Removal of old paint, Painting on old and new surface, bridges, Rain Shelters, Boards and writing letters or figures.

ESTIMATED COST :- ₹ 99470.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Two Months

5 No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Removing old paint from steel and other metal surfaces and making the surface even with paint remover of approved brand and manufacture including carriage of material with all leads lift and as per direction of Engineer-in-Charge. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	220.00	26.200	Rupees Twenty Six And Paise Twenty Only	Per Square meter	5764.00
2	Painting one coat excluding priming coat on previously painted steel and other metal surfaces of all dirt dust and other for matter with ready mixed paint including carriage of material with all leads lift and as per direction of Engineer-in-Charge. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	220.00	45.000	Rupees Forty Five Only	Per Square meter	9900.00
3	Painting two coats (excluding priming coat) on new steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt, dust and other foreign matter with enamel paint other than white within all leads, lifts of material and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	210.00	89.900	Rupees Eighty Nine And Paise Ninety Only	Per Square meter	18879.00
4	Applying Birds white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete as per 10th direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	80.00	55.000	Rupees Fifty Five Only	Per Square meter	4400.00
5	Finishing wall with weather proof exterior grade emulsion of approved design (Acquafinal) or its equivalent on undecorated wall surface (two coats) to give an even shade and final after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete as per 10th direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	590.00	95.000	Rupees Ninety Five Only	Per Square meter	56050.00
6	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, commas, hyphens and the like not to be measured and paid separ. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government (Malkana, toll tax, sale tax or other taxes imposed by the Government).	2035.00	2.200	Rupees Two And Paise Twenty Only	Per letter per cm. height	4477.00
TOTAL :-						99470.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under Darini Section under HP.PWD Darini Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royally, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate In Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shapur Division,
 HPPWD Shapur