

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2025-26-

5672

Dated:- 30-8-2025

To,

The Executive Engineer
IT Cell Nirman Bhawan Nigam Vihar
HP PWD Shimla

Subject: _

Regarding NIT for uploading on HP PWD website .


Enclosed please find herewith the Notice inviting tender Notice along with schedule of quantity for uploading on HP PWD website. This is for your kind information and necessary action at your end please.

Encls:- NIT copy & 20 Nos copy of Schedule of quantity.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, called vide this office letter No. PW-DT-NIT-2025-26-~~5673-87~~ Dated:- ~~30-08-2025~~ are urgent nature.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **10-09.2025** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **09.09.2025** up to **4:00 P.M** and the application for issue of tender form shall be received on **08.09.2025** up to **12:00 noon**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Construction and Beautification of various Chowks under HP PWD Division Tanda at Nagrota Bagwa in Distt. Kangra HP (SH: Supplying and placing in position Marble Statue (Elephant).	71500.00	1450.00	One Month
2	Repair of Guga Sarai Building in Gram Panchayat kharat in Tehsil Baroh, Distt. Kangra HP Deposit work (SH: Civil work only).	87254.00	1750.00	Two months
3	Restoration of rain damages on Jagrota basti to Gaiyara basti in Baroh Distt. Kangra HP (SH: Construction of cement concrete pavement in km 0/450 to 0/495SDF/2024/1648).	99592.00	2000.00	Two Months
4	Construction of Community Bhawan of Dalit Basti Palra in District Kangra H P Deposit work (SH: Balance work of community Bhawan VKV/2024/2048)	49781.00	1000.00	Two months
5	Construction and Beautification of various Chowks under HP PWD Division Tanda at Nagrota Bagwa in Distt. Kangra HP (SH: Supplying and placing in position Marble Statue (Elephant).	71500.00	1450.00	One Month
6	Repair of Administrative Block in Dr. RPGMC Tanda in Tehsil & Distt. Kangra HP Deposit work (SH: Providing and fixing wall paper in Conference Hall etc).	63400.00	1300.00	Two months
7	Special Repair of 500 Bedded Hospital at Dr. RPGMC Tanda distt. Kangra HP (SH: Providing and laying CC pavement & P/L Paver Block. etc. in Back side of Basement Medicine Dispensary).	99926.00	2000.00	One months
8	Construction of Govt. Senior Secondary School at Baldhar in District Kangra HP Deposit Work (SH: Construction of Toilet Block i.e. Civil Work, Water Supply and Sanitary Installation etc: VKV/2023/1292).	498656.00	10000.00	Two months
9	Repair of Auditorium Building in Dr. RPGMC at Tanda in Tehsil & Distt. Kangra Hp Deposit work (SH: Providing and fixing W/S & S/I etc).	44193.00	900.00	Two Months
10	Construction of Community shed Tikka Har in District Kangra, HP Deposit work (SH: Construction of Civil work VVK/2016/1349).	99888.00	2000.00	Two Months
11	Restoration of Damages on Kaisthwari kawari Bhadu Nianda Paddar road km 0/00 to 5/500 in Distt. Kangra HP (SH: Balance work of 600mm dia Hume pipe culvert at rd.s 3/545 and 3/560).	89741.00	1800.00	Two Months
12	Additional Alteration of Ino. Room in Adult ICU in Dr. RPGMC at Tanda in Tehsil & Distt. Kangra HP Deposit work (SH: Aluminium work and other repair work in Blood-Bank & Corridor).	80166.00	1650.00	Two Months
13	Restoration of Damages on Kaisthwari kawari Bhadu Nianda Paddar road km 0/00 to 5/500 in Distt. Kangra HP (SH: Balance work of 600mm dia Hume pipe culvert at rd.s 5/100,3/850 and 4/300).	89741.00	1800.00	Two Month
14	Restoration of rain damages on Kangra Tanda road km 0/00 to 6/00 in Tehsil Nagrota Bagwan Distt. Kangra HP (SH: Repair of Steel Grating at RD 1/735).	82760.00	1700.00	Two Months
15	Restoration of Damages on Kaisthwari kawari Bhadu Nianda Paddar road km 0/00 to 5/500 in Distt. Kangra HP (SH: Balance work of 450mm dia Hume pipe culvert at rd.s 3/650 and 4/780).	99125.00	2000.00	Two Months
16	Construction of Path from Sera village to the House of Sh. Balvinder Singh Gram Panchayat Serathana in Tehsil Nagrota Bagwan Distt. Kangra HP (SH: Providing and laying cement concrete pavement road VKV/2025/343).	96525.00	2000.00	Two months
17	Restoration of Damages on Kaisthwari kawari Bhadu Nianda Paddar road km 0/00 to 5/500 in Distt. Kangra HP (SH: Balance work of 600mm dia Hume pipe culvert at rd.s 3/735,3/480 and 450mm dia Hume pipe culvert at RD 3/580 and 4/150).	97953.00	2000.00	Two months
18	Construction of Veer Dawar at Daulatpur in District Kangra HP deposit work (SH: balance work of Granite stone for wall cladding etc).	99875.00	2000.00	Two Months
19	Restoration of rain damages on various roads under HP PWD Sub- Division Baroh in Distt. Kangra HP Backfilling with granular material (Radh Section).	99900.00	2000.00	Two Months
20	Restoration of rain damges on various roads under HP PWD Sub- Division Baroh in Distt. Kangra HP (SH: Backfilling with granular material (Kandi Section).	99975.00	2000.00	Two months

Terms & Conditions:-)

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.

3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender form.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

No.PW/NBD/TA/Tender/NIT/2025-26- **5673-87**

Dated/

(On behalf of Governor of Himachal Pradesh)

30-8-2025

Copy to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Director, Information & Publications Department, H.P. Shimla.
3. The Executive Engineer IT Cell Shimla HP PWD Shimla.
4. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
5. The Deputy Commissioner, Kangra at Dharamshala.
6. All the S.E.s/E.E.s under North Zone.
7. The Sub-Divisional Officer(C) Nagrota Bagwan.
8. All the Assistant Engineer under this Division.
9. The Drawing /Accounts Branch in this office.
10. Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 71500.00
 EARNEST MONEY:- ₹ 1450.00
 TIME LIMIT :- ONE MONTH

NAME OF WORK :- Construction and Beautification of various Chowks under H.P.P.W.D. Division Tanda at Nagrota Bagwan in Distt. Kangra (H.P.)
 SUB-HEAD :- Supplying and placing in position Marble Statue (Elephant).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Supplying of Elephant Statue of minimum height upto 70cms (Seventy centimetres) of white Makrana marble complete as per HPPWD Technical specifications and as directed by the Engineer-In-charge, including entire carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	1 Number			Each	
Total :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 87254.00
 EARNEST MONEY :- ₹ 1750.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Repair of Guga Sarai Building in Gram Panchayat Kharat in Tehsil Baroh, Distt. Kangra (H.P.) Depaosit work. SDF/2024/1113
 SUB-HEAD :- Civil work only.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2 Providing and laying water proofing treatment on roofs of slabs by applying cement slurry mixed with water proofing cement compound consisting of applying after surface preparation, first layer of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/sqm. (b) laying second layer of fibre glass cloth when the first layer is still green. Overlaps of joints of fibre cloth should not be less than 10 cm (c) third layer of 1.5 mm thickness consisting of slurry of cement @ 1.289 kg/sqm mixed with water proofing cement compound @ 0.670 kg/sqm and coarse sand @ 1.289 kg/sqm. This will be allowed to air cure for 4 hours followed by water curing for 48 hours. The entire treatment will be taken upto 30 cm on parapet wall and tucked into groove in parapet all around. (d) fourth and final layer of brick tiling with cement mortar (which will be paid for separately for the purpose of measurement the entire treated surface will be measured) complete and as per direction of Engineer-In-Charge, including carriage of materials within all leads, lifts and other incidentals	3 25.58 Square metres	4	5	6 Per square metre	7
2	6mm (Six millimetres) thick cement plasters in ceiling with cement mortar 1:3 (One cement: Three sand) for all heights complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge.	25.58 Square metres			Per square metre	
3	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under. including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground. all complete With cement mortar 1:4 (1 cement : 4 fine sand) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	15.00 Square metres			Per square metre	
4	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm (Five centimetre to twenty centimetre) nominal size in recharge pit, in the required thickness and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	2.11 Cubic metres			Per cubic metre	
5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size complete as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	2.11 Cubic metres			Per cubic metre	
6	Providing and laying 25mm (Twenty five millimetre) thick Kota stone slab flooring over 16mm to 20mm (Sixteen millimetre to Twenty millimetre) (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (One cement : Four coarse sand) complete and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	25.58 Square metres			Per square metre	
7	Providing 20mm to 25mm (Twenty millimetres to Twenty five millimetres) thick Kota Stone flooring Mirror polished with 7.5 cm (Seven decimal Five centimetres) wide uniform colour marble band with black mandana /raisimer yellow in base of 25mm (Twenty five millimetre) thick cement mortar 1:4 (One cement: Four sand) laid over and jointed with Grey cement slurry mixed with pigment to match the shade of the slab including hosing, rubbing and polishing complete including carriage of material within all leads, lifts and other incidentals as per approved specifications, drawing, design and as directed by the Engineer-in-charge.	4.06 Square metres			Per square metre	
8	Providing and fixing 35mm (Thirty five millimetres) thick Second class teak woodglazed shutters for doors, windows and clerestory windows using 4 mm (Four millimetres) thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws as directed by the Engineer-in-Charge, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge.	1.56 Square metres			Per square metre	

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1			4	5	6	7
9	Providing and fixing 250x16mm size (Two hundred fifty into sixteen millimetres) anodized aluminium sliding door bolts anodized transparent or dyed to required colour and shade with necessary screws etc. complete as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	3 4 Number			Each	
10	Providing and fixing 125mm (One hundred twenty five millimetres) size anodized aluminium handles with necessary screws etcetra complete within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	2 Numbers			Each	
11	Providing and fixing 100x58x1.90 mm IS marked stainless steel butt hinges bright finished with necessary screws etc. complete as directed by the Engineer-in-Charge, including entire carriage of materials within all leads, lifts and other incidentals	4 Numbers			Each	
12	Providing and applying Birla/J.I.K. white cement based putty of average thickness 1mm (One millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	40.58 Square metres			Per square metre	
13	Distempering with dry distemper of approved brand and manufacture (two or more coats) of required shade on new work, over and including water thinnable priming coat to give an even shade complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	25.58 Square metres			Per square metre	
14	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	21.39 Square metres			Per square metre	
15	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	2.07 Square metres			Per square metre	
16	Painting with synthetic enamel paint One or more coats on undecorated surface of approved brand and manufacture of required colour to give an even shade complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	2.07 Square metres			Per square metre	
17	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals .	46.69 Square metres			Per Square metre	
TOTAL :-						


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 99592.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Restoration of rain damages on Jagotra Basti to Gaiyara Basti in Tehsil Baroh, Distt. Kangra (H.P.).
 SUB HEAD :- Construction of cement concrete pavement in Km 0/450 to 0/495 (SDF/2024/1648).

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	16.88 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 49781.00
 EARNEST MONEY :- Rs. 1000.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Construction of Community Bhawan of Dalit Basti Palra in District Kangra, (H.P.). Deposit work.
SUB-HEAD :- Balance work of Community Bhawan. (VKV/2024/2048).

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	6mm (Six millimetres) thick cement plaster to ceiling in cement mortar 1:3 (One cement : Three sand) upto all floor levels complete including carriage of material within all leads, lifts and other incidentals as per approved specifications, drawing, design and as directed by the Engineer-in-charge.	47.78 Square metres			Per square metre	
2	15mm (Fifteen millimetre) thick cement plasters in single coat on rough side of single or half brick/concrete/stone walls for interior plastering upto all floor level including arrises, internal rounded angles, chamfers or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:4 (One cement : four sand) above plinth level to floor all level complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge.	44.79 Square metres			Per square metre	
3	15mm (Fifteen millimetre) thick cement plasters in single coat on fair side of brick/concrete/stone walls for interior plastering upto all floor level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement: Six sand) above plinth level to floor all level complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge.	66.96 Square metres			Per square metre	
4	Providing and laying 600x600 mm (Six hundred into six hundred millimetre) size antiskid vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (Zero point zero eight percent) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (Twenty millimetre) thick cement mortar 1:4 (One cement : four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three kilogramme per square metre) including grouting the joints with white cement and matching pigments etcetra complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	12.71 Square metres			Per square metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 71500.00
 EARNEST MONEY:- ₹ 1450.00
 TIME LIMIT :- ONE MONTH

NAME OF WORK :- Construction and Beautification of various Chowks under H.P.P.W.D. Division Tanda at Nagrota Bagwan in Distt. Kangra (H.P.)
 SUB-HEAD :- Supplying and placing in position Marble Statue (Elephant).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Supplying of Elephant Statue of minimum height upto 70cms (Seventy centimetres) of white Makrana marble complete as per HPPWD Technical specifications and as directed by the Engineer-Incharge, including entire carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	1 Number			Each	
Total :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 63400.00
 EARNEST MONEY :- Rs 1300.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Repair of Administrative Block in Dr. R.P.G.M. College at Tanda in Tehsil & Distt. Kangra (H.P.) Deposit work
 SUB-HEAD :- Providing and fixing wall paper in Conference Hall etc;

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing multicolour decorative wall paper complete, as directed by the Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals	79.25 Square metres			Per square metre	
TOTAL :-						

Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST:- Rs. 99926.00
EARNEST MONEY :- Rs. 2000.00
TIME LIMIT : ONE MONTHS

NAME OF WORK :- Special Repair to 500 Bedded Hospital at Dr.R.P.G.M.C. TANDA. Distt Kangra H.P.
SUB HEAD :- providing and Laying CC Pavement & P/L Paver Block ,Etc.in Back side of Basement Medicine Dispensary.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 (One cement : Three sand : six graded stone) or richer mix (i/c equivalent design mix) complete and as directed by the Engineer- In-charge, including carriage of materials within all leads, lifts and other incidentals . complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4.802	cubic metres		Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4.53	cubic metres		Per Cubic metre	
3	Providing and laying heavy duty precast cement concrete inter locking paver blocks vibro compacted upto M- 50 grade i/c border or kurb block grey or coloured over sub-base of concrete with 25mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curing rubbing & polishing complete (Sub base concrete floor to be paid for 60 mm thick inter locking blocks	62.16	Square metres		Per Square metre	
Total:-						


Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 498656.00
 EARNEST MONEY:- ₹ 10000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Construction of Govt. Senior Secondary School at Baldhar in District Kangra (Himachal Pradesh). **DEPOSIT WORK**
SUB-HEAD :- Construction of Toilet Block i.e. Civil work, Water Supply and Sanitary Installation etc; VKV/2023/1292

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation in foundation, trenches etc. in earth work in all classification of soil such as pick work, jumper work, pick jumper work, blasting work, jumper blasting work, soft and hard blasting and saturated soil, de-watering, including wedging out rocks where blasting work is prohibited, chiseling or any other mixed variety of soil, de-watering and/or removal of slush and incidentals, lift upto any heights, stacking the excavated soil not more than 3 mtrs (Three meters) clear from the edge of excavation and then retuning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths, sides of foundation etc; consolidating each deposited layer by ramming, watering and then disposing of all excavated earth including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-Incharge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	3 16.12 Cubic metres	4	5	6 Per cubic metre	7
2	Filling in plinth with sand under floors including watering, ramming, consolidating and dressing complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-Incharge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	0.90 Cubic metres			Per cubic metre	
3	Stone filling/boulders under flooring with hard stones in foundation and plinth including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-Incharge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	1.35 Cubic metres			Per cubic metre	
4	Providing form work with steel plates of 3.15mm (Three decimal one five millimeters) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Thirty into Five millimeters), so as to give a fair finish including centring, shuttering strutting and propping etcetera, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in beams cantilevers girders lintels window sills, cornices, arches corbelling including curved surfaces where ever required sides and soffits of beams haunchings cantilevers bressumers and lintels upto all depths including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-Incharge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	27.04 Square metres			Per square metre.	
5	Providing form work with steel plates of 3.15mm (Three decimal one five millimeters) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Thirty into Five millimeters), so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs, landings as per Architectural drawing and the like floor etc.including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-Incharge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	18.97 Square metres			Per square metre	

1	2	3	4	5	6	7
		19.94 Running metres			Per running metre	
6	Providing form work with steel plates of 3.15mm (Three decimal fifteen millimeters) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Five millimeters), so as to give a fair finish including centering, shuttering strutting and propping etcetera, with wooden battens and ballies for all heights and removal of the same for in-situ reinforced plain concrete work in work in edge of slab and breaks in floors and walls under any thickness including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.					
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level cement concrete 1:4:8 (One cement; four sand; eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	4.91 Cubic metres			Per cubic metre	
8	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stones of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (One cement : Six sand : Twelve graded crushed stone aggregate 20mm (Twenty millimetres) nominal size) at plinth level in cement mortar 1:6 (One cement: Six sand) complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	9.61 Cubic metres			Per cubic metre	
9	Providing and laying cement concrete work of grade M-25 (M-Twenty five) mix design to obtain the minimum crushing strength of 20N/mm square with minimum cement contents of 330 kg (Three hundred thirty kilogram) per cubic meter, mechanically mixed and vibrated including curing complete, excluding cost of form work and reinforcement for reinforced concrete work in Suspended floors, roofs, landings, shelves their supports balconies, beams, girder, bressumers and cantilevers including mouldings, cornices etc; including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	6.53 Cubic metres			Per cubic metre	
10	Providing-Tor steel reinforcement for reinforced cement concrete work including bending, binding and placing in position complete including cost of binding wires complete and other incidentals due for its completion for all floors etc; complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	1018.51 Kilogram			Per kilo- gram	
11	Second class brick work using common burnt clay building bricks in super structure upto any floor level in cement mortar 1:6(One cement: Six sand) complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	11.29 Cubic metres.			Per cubic metre.	
12	Second class Half brick work using common burnt clay building bricks in super-structure upto all floor level in cement mortar 1:4 (One cement: Four sand) curing complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	13.84 Square metres.			Per Square metre	

1	2	3	4	5	6	7
13	Providing and fixing 1mm (One millimetres) thick M.S. sheet garage door with frame of 40x40x6mm (Forty into forty into six millimetres) angle iron 3.15mm (Three point one five millimetres) M.S. gusset plates at the junctions and corners, all necessary fittings complete including applying a priming coat of red lead paint using M.S angles 40x40x6mm (Forty into forty into six millimetres) for diagonal braces complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	6.00 Square metres			Per square metre	
14	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel Angle sections of size 35x35x5 mm, joints mitred and welded by angle iron 35x35x5mm (Thirty five into Thirty five into Five millimetre) or 35x 5mm (Thirty five into five millimetre) flat pieces to the existing Tiron frame or to the wall with dash fastener, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer, all complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	51.40 Kilograms			Per kilo-gram	
15	Providing and fixing glazing with glass panes of 4mm (Four millimetres) thickness (weight not less than 10.00 kg/sqm (Ten kilogram per square metre) glazing in aluminium door, window, ventilator shutters and partition etc; with PVC/neoprens gasket etc; complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2.12 Square metres			Per square metre	
17	Providing and fixing 250x16 mm (Two hundred fifty into sixteen millimetre) anodized aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	4 Numbers			Each	
18	Providing and fixing 150x10 mm (One hundred fifty into ten millimetre)aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	20 Numbers			Each	
19	Providing and fixing aluminium handles, ISI marked,anodised (anodic coating not less than grade AC 10 as per IS : 1868) ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	20 Numbers			Each	
20	Providing and fixing 100mm (One hundred millimetres) size of aluminium anodised matt finished hard drwan hooks and eyes to required colour and shade with necessary screws etcetera; complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	12 Numbers			Each	

1	2	3	4	5	6	7
		2.51 Cubic metres			Per cubic metre	
21	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size as per HPPWD technical specification including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.					
22	6mm (Six millimetres) thick cement plasters in ceiling with cement mortar 1:3 (One cement: Three sand) for all heights complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	14.63 Square metres			Per square metre	
23	15mm (Fifteen millimetres) thick cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering upto all floor levels including arises internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement: six sand) complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	50.68 Square metres			Per square metre	
24	15mm (Fifteen millimetres) thick cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering upto all floor levels including arises internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement: six sand) complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	42.97 Square metres			Per square metre	
25	Providing and laying Ceramic glazed tiles 300x300x10mm (Three hundred into Three hundred into Ten millimeters) thick in grey/coloured or of approved shade in flooring, treads of steps and landing laid on a bed of 12mm (Twelve millimeters) thick cement mortar 1:3 (One cement : three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	9.00 Square metres			Per square metre	
26	Providing and laying Duro stone vetrified tiles 300x300x8mm (Three hundred into Three hundred into Eight millimeters) thick in grey/coloured or of approved shade in flooring, treads of steps and landing laid on a bed of 12mm (Twelve millimeters) thick cement mortar 1:3 (One cement : three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	44.40 Square metres			Per square metre	
27	Applying Birla J.K. white wall care putty over plastered surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters and sand papered smooth to give final matter finish to the surface complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications entire satisfaction and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	69.57 Square metres			Per square metre	

1	2	3	4	5	6	7
		69.57 Square metres			Per square metre	
28	Finishing walls with 100% (One hundred percent) Premium acrylic emulsion paint having VOC less than 50 gm/litre (Fifty grams per litre) and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives complete. New work (Two or more coats applied @ 1.43 litre/ 10 sqm (One point four three litre per ten square metre) Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm (Zero point nine zero litre per ten square metre) complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawings, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.					
Water Supply and Sanitary Installation: -						
29	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 (Ten) litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid complete, including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawings, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2 Numbers			Each	
30	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 (Ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440mm (Five hundred weighty into Four hundred forty millimetre) with integral type foot rests complete fitting including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	1 Number			Each	
31	Providing and fixing 8 mm (Eight millimetre) dia C.P. / S.S. Jet with flexible tube upto 1 (One) metre long with S.S. triangular plate to European type W.C. of quality and make as approved quality complete fitting including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2 Numbers			Each	
32	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm (Four hundred thirty into Two hundred sixty into Three hundred fifty and Three hundred forty into Four hundred ten into Two hundred sixty five millimetre) sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required One urinal basin with 5 (Five) litre white P.V.C. automatic flushing cistern including necessary fitting complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	3 Numbers			Each	

1	2	3		4	5	6	7
		0.75	Square metre				
33	Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75x50 cm (Seventy five into fifty centimetre) deep and 1.8 cm (Oen point eight centimetre) thick, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (One cement : Two coarse sand : Four graded stone aggregate 6 mm (Six millimetre) nominal size complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.					Per square metre	
35	Providing and fixing 100 mm (One hundred millimetre) inlet and 75 mm (Seventy five millimetre) outlet trap of self cleansing design with screwed down or hinged grating with or without vent arm Hubless centrifugally cast (spun) iron epoxy coated inside & outside as per IS:15905 complete, including cost of cutting and making good the walls and floors : complete as required and as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	12	Numbers			Each	
36	Providing and placing on terrace (at all floor levels polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank complete as required and as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	3000.00	Litres			Each	
36	Providing 15mm (Fifteen millimetres) dia long body brass bib tap (Superior or heavy type) complete and as per direction of Engineer- In-charge, including carriage of materials within all leads, lifts and other incidentals.	5	Numbers			Each	
41	Providing and fixing Polyethylene-Aluminium- Polyethelene PE-AL- PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes testing of joints complete as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.						
i	15mm (Fifteen millimetres) nominal bore/ diametres	14	Running metres			Per running metre	
ii	20mm (Twenty millimetres) nominal bore/ diametres	12	Running metres			Per running metre	
TOTAL :-							


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - RS 44193.00
 EARNEST MONEY :- RS 900.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Repair of Auditorium Building in Dr. R.P.G.M. College at Tanda in Tehsil & Distt. Kangra (H.P.) Deposit work
 SUB-HEAD :- Providing and fixing W/S & S/I etc;

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 110 mm (One hundred ten millimetre) M.S. grating includin necessary fitting complete as required and as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications drawing, design and as directed by the Engineer-in-charge.	12 Numbers			Each	
2	Providing and fixing 8 mm (Eight millimetre) dia C.P. / S.S. Jet with flexible tube upto 1 (One) metre long with S.S. triangular plate to European type W.C. of quality and make as approved quality complete fitting including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	11 Numbers			Each	
3	Providing and fixing 15 mm nominal bore with 45 cm length unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour complete as per architectural drawings and as per the directions of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals, including carriage of materials within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge.	14 Numbers			Each	
4	Providing and fixing Hand jet spray of Cera Brand with 1.25 m long stainless steel flexible tube and ABS Wall hook to European type W.C. of quality and make as approved by Engineer - in - charge complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge.	1 Number			Each	
5	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete : White solid plastic seat with lid including carriage of material within all leads, lifts and other approved drawing, design, entire satisfaction and as directed by the Engineer-in-charge.	4 Numbers			Each	
6	Providing and fixing one piece water closet solid plastic seat cover with lid for pedestal type W.C. pan complete : White solid plastic seat with lid including carrigae of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, entire satisfaction and as directed by the Engineer-in-charge.	1 Numbers			Each	

8-1

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
7	Providing and fixing wall mounted Liquid soap dispenser for bathroom and wash basin of Cera Brand with necessary screws etc. including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, entire satisfaction and as directed by the Engineer-in-charge.	1 Numbers			Each	
8	Providing and fixing Automatic Hand dryer of Cera Brand with necessary screws etc. including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, entire satisfaction and as directed by the Engineer-in-charge.	1 Numbers			Each	
9	Providing and fixing 32mm dia P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, entire satisfaction and as directed by the Engineer-in-charge.	8 Numbers			Each	
10	Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour Waste coupling 38 mm dia of 83 mm length and 77mm breadth, weighing not less than 60 gms as per architectural drawings and as per the directions of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals.	3 Numbers			Each	
11	Providing and fixing 32mm (Thirty two millimetres) dia C.P. Bottle Trap for wash basin and sink complete as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	4 Numbers			Each	
12	Providing and fixing 15 mm nominal C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 complete and as per the directions of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals.	20 Numbers			Each	
13	Providing and fixing 15 mm nominal C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms complete and as per the directions of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals. including carriage of materials within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	2 Numbers			Each	
TOTAL :-						

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 99888.00
EARNEST MONEY :- Rs. 2000.00
TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of Community shed Tikka Har in District Kangra, (H.P.). **Deposit work.**
SUB-HEAD :- Construction of Civil work. (VVK/2016/1349).

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	0.36 Cubic metres			Per cubic metre	
2	Stone Filling in plinth with approved stone under floors including watering, ramming, consolidating and dressing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	1.80 Cubic metres			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge.	2.16 Cubic metres			Per cubic metre	
4	Structural steel work of Tata / Sail / Reliance / Jindal riveted, bolted or welded in built up tubular (round, square or rectangular hollow tubes trusses etcetra including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	227.95 Kilograms			Per kilo-gram	
5	Structural steel work of Tata / Sail / Reliance / Jindal riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	464.50 Kilograms			Per kilo-gram	

8

6	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge.	27.30 Square metres			Per Square metre
TOTAL :-					


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 89741.00
 EARNEST MONEY :- ₹ 1800.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Restoration of ramages on Kaisthwari Kawari Bhadu Nianda Paddar road Km 0/000 to 5/500 in District Kangra (H.P.)
 SUB-HEAD :- Balance work of 600mm dia Hume Pipe culvert at various RD's 3/545 and 3/560

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing and laying non-pressure NP3 class (Medium duty) R.C.C. hume pipes 600mm (Six hundred millimetre) dia with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc; complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	22.50 Running metre			Per running metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs 80166.00
 EARNEST MONEY : - Rs 1650.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Additional Alteration of I No. Room in Adult ICU in Dr. R.P.G.M. College at Tanda in Tehsil & Distt. Kangra (H.P.) Deposit work
 SUB-HEAD :- *Aluminium work and other repair work in Blood Bank & Corridor*

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing colour coated / anodised aluminium work for door frame, window, ventilators and glazed partitions frame with extruded built up standard tubular and other sections of approved make conforming to IS 733 and IS 1285 anodised transparent or dyed to required shade according to IS 1868. (Minimum anodic coating of grade AC 15) fixed with rawplugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etcetera. Aluminium sections shall be smooth, rustfree, straight, mitred and jointed mechanically where ever required including cleast angle, aluminium, snap beading for glazing/panelling C.P. brass/stainless steel screws. All complete as per architectural drawings and as per the directions of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals.	18.77 Kilograms			Per Kilo gram	
2	Providing and fixing colour coated / anodised aluminium work for door, window, ventilators and glazed partitions shutter with extruded built up standard tubular and other sections of approved make conforming to IS 733 and IS 1285 anodised transparent or dyed to required shade according to IS 1868. (Minimum anodic coating of grade AC 15) fixed with rawplugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etcetera. Aluminium sections shall be smooth, rustfree, straight, mitred and jointed mechanically where ever required including cleast angle, aluminium, snap beading for glazing/panelling C.P. brass/stainless steel screws. All complete as per architectural drawings and as per the directions of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals.	60.21 Kilograms			Per Kilo gram	
3	Providing and fixing 12mm (Twelve millimetres) thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. Pre-laminated particle board with decorative lamination on both sides complete as directed by the Engineer-In-charge including carriage of materials	20.64 Square metres			Per Square metre	
4	Supplying and fixing plate glass 5.5mm (Five decimal Five millimetres) thick glass panes with putty and nails including removal of broken glass panes wherever necessary complete as per direction of Engineer-In-Charge, including carriage of material within all leads, lifts and other incidentals.	20.64 Square metres			Per square metre	
5	Providing and fixing 300x16mm size (Three hundred into sixteen millimetres) anodized aluminium sliding door bolts anodized transparent or dyed to required colour and shade with necessary screws etc. complete within all leads, lifts of materials and other incidentals.	1 Numbers			Each	

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2					
6	Providing and fixing 250 x 10mm (Two hundred fifty into ten millimetres) size aluminium tower bolts (barrel type) anodized trans parent or dyed to required shade and colour with screws etc. complete as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	3 2 Numbers	4	5	6 Each	7
7	Providing and fixing 125 mm (One hundred twenty millimetres) aluminium handles anodized transparent or dyed to required colour & shade with necessary screws etc. complete as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Each	
8	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etcetera including necessary fitting complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications drawing, design and as directed by the Engineer-in-charge.	1 Numbers			Each	
9	Providing and fixing 150mm (One hundred fifty milimetres) bright finished brass door stopper with rubber cushion screws etc to suit shutter thickness complete and as per direction of the Engineer-Incharge, including carriage of materials within all leads, lifts and other incidentals.	1 Numbers			Each	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

8-2

Schedule of Quantity

ESTIMATED COST :- ₹ 89741.00
 EARNEST MONEY :- ₹ 1800.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Restoration of rimages on Kaisthwari Kawari Bhadu Nianda Paddar road Km 0/000 to 5/500 in District Kangra (H.P.)
 SUB-HEAD :- Balance work of 600mm dia Hume Pipe culvert at various RD's 5/100, 3/850 and 4/300

S. No.	Description of Items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2 Providing and laying non-pressure NP3 class (Medium duty) R.C.C. hume pipes 600mm (Six hundred millimetre) dia with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc; complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	3 22.50 Running metre	4	5	6 Per running metre	7
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

NAME OF WORK :- Restoration of rain damages on Kangra Tanda road Km 0/000 to 6/000 in Tehsil Nagrota Bagwan Distt. Kangra (H.P.).
SUB HEAD :- Repair of Steel Grating at RD 1/735

ESTIMATED COST :- ₹ 82760.00
EARNEST MONEY :- ₹ 1700.00
TIME LIMIT : TWO MONTHS

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1			4	5	6	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	3.38 Cubic metres			Per cubic metre	
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	615.86 Kilogram			Per kilo-gram	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 99125.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Construction of Kaisthwari Kawari Bhabu Nianda Paddar road Km 0/000 to 5/500 in District Kangra (H.P.)
 SUB-HEAD :- Balance work of 450mm dia Hume Pipe culvert at various RD's 3/650 and 4/780

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2 Providing and laying non-pressure NP3 class (Medium duty) R.C.C. hume pipes 450mm (Four hundred fifty millimetre) dia with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc; complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	3	4	5	6	7
		32.50			Per running metre	
TOTAL :-						


 Executive Engineer,
 H.P.P. W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 96525.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of Path from Sera Village to the House of Sh. Balvinder Singh Gram Panchayat Serathana in Tehsil Nagrota Bagwan Distt. Kangra (H.P.).
 SUB HEAD :- Providing and laying cement concrete pavement road. (VKV/2025/343).

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2 Supplying, filling, spreading & leveling stone boulders of under floor wherever required thickness complete as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	3 13.50 Cubic meters	4	5	6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	13.50 Cubic metres			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 97953.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- *Rehabilitation of Kaisthwari* Kawari Bhadu Nianda Paddar road Km 0/000 to 5/500 in District Kangra (H.P.)
 SUB-HEAD :- *Construction of Kaisthwari* Balance work of 600mm dia at RD 3/735, 3/480 and 450mm dia Hume Pipe culvert at various RD 3/580 and 4/150

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2 Providing and laying non-pressure NP3 class (Medium duty) R.C.C. hume pipes 600mm (Six hundred millimetre) dia with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc; complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	3 15.00 Running metre	4	5	6 Per running metre	7
2	Providing and laying non-pressure NP3 class (Medium duty) R.C.C. hume pipes 450mm (Four hundred fifty millimetre) dia with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc; complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	12.50 Running metre			Per running metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99875.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Construction of Veer Dawar at Daulatpur in District Kangra, (H.P.). DEPAOSTI WORK.
 SUB-HEAD :- Balance work of Granite stone for wall cladding etc;

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 Providing and fixing 30mm (Thirty millimetre) thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm (Twenty millimetres) thick base cement mortar 1:4 (One cement : fourcoarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups. including rubbing, curing, moulding and polishing to edges to give high gloss finish etcetera complete at all levels (Area of slab over 0.50 sqm) complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications drawing, design and as directed by the Engineer-in-charge. .	3 23.50 Square metres	4	5	6 Per square metre	7
Total :-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: -Rs. 99900.00
 EARNEST MONEY : -Rs. 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on various roads under H.P.P.W.D. Sub-Division Baroh in Distt Kangra (H.P.).
 SUB HEAD:- Backfilling with granular material (Radh Section).

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	2 Backfilling with granular material behind abutment, wing wall, return wall and slushy portion complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	3 133.20 Cubic metres	4	5	6 Per cubic metre	7
TOTAL:-						


 Executive Engineer,
 H.P.P.W.D Division,
 Tanda at Nagrota Bagyan.

Schedule of Quantity

ESTIMATED COST: -Rs. 99975.00
 EARNEST MONEY : -Rs. 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on various roads under H.P.P.W.D. Sub-Division Baroh in Distt Kangra (H.P.),
 SUB HEAD: - Backfilling with granular material (Kandi Section).

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	2 Backfilling with granular material behind abutment, wing wall, return wall and slushy portion complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	3 133.30 Cubic metres	4	5	6 Per cubic metre	7
TOTAL:-						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.