Himachal Pradesh
Public Works Department

NO/PW/TLD/Tender/2025:- 4043-52 Dated:- 04-09-2025

To

Executive Engineer IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject:- Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of HP letter No. PBW (B) 1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA: - NIT.

Executive Engineer,
Thalout Division, HPPWD,
Thalout.

Copy is forwarded to Superintending Engineer, 1st Circle, HPPWD Mandi for information please.

Copy to All the Assistant Engineers working under this Division.

Copy to AB/DB in this office.
Copy to Notice board.

Executive Engineer,
Thalout Division, HPPWD,
Thalout.

Scanned with CamScanner

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"

Sealed item rate tender on form No. 6&8 for the following works detailed in the table below hereby invited by the Executive Engineer, Thalout Division, HPPWD, Thalout on behalf of Governor of Himachal Pradesh from the eligible contractors of appropriate Class registered in HPPWD as per revised enlistment rule so as to reach in his office on 12.09.2025 at 11.00 A.M. The tenders shall be opened on the same date at 11.30 A.M. in the presence of intending contractors or their authorized representative who wish to be present. The request for issuing tenders form along with earnest money must reach in his office up to 3.00 P.M. on 10.09.2025 and that tender documents can be had from his office on cash payment noted against each (Non-Refundable) on 11.09..2025 up to 5.00 P.M on any working day. Notice Inviting Tender and other specification and conditions of the tender can be seen by the contractor in the office of the Executive Engineer, Thalout Division, HPPWD, Thalout during office hour on any working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Cost of form	Time Period	Form No.	Eligibility of Contractors
1	RRD on various roads of Panarsa Sub Division (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Nagwain Section) Job No.2	99600	2,000	Rs. 350/-	One month	6&8	Class D enlisted in HPPWD
2	RRD on Panarsa to Kotadhar road km 0/0 to 5/625 (SHG- C/O PCC B/wall at RD 2/155 to 2/160.50).	72017	2,000	Rs. 350/-	One month	6&8	-do-
3	RRD on Panarsa to Kotadhar road km 0/0 to 5/625 (SH- C/O PCC B/wall at RD 2/160.50 to 2/166).	72237	2,000	Rs. 350/-	One month	6&8	-do-
4	RRD on Bakhali to Kholanal km 0/0 to 8/500 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms,debries at various RDs in km 0/0 to 8/500).	99600	2000	Rs. 350/-	One month	6&8	-do-
5	RRD on Baggi to Kashimblidhar road km 0/0 to 3/0 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs in km 0/0 to 3/0).	99600	2,000	Rs. 350/-	One month	6&8	-do-
6	RRD on Dhamu to Deori road km 0/0 to 2/645 (SH- C/O R/wall Dry stones masonry at km 1/195 to 1/206).	99981	2,000	Rs. 350/-	One month	6&8	-do-
7	RRD on Dhamu to Deori road km 0/0 to 2/645 (SH- C/O R/wall (wire crate) Masonary at km 0/861 to 0/868).	85617	2,000	Rs. 350/-	One month	6&8	-do-
8	RRD on various roads of Balichowki Sub Division (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Thachi Section) Job No.I	99600	2,000	Rs. 350/-	One month	6&8	-do-
9	RRD on various roads of Balichowki Sub Divison (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc at various RDs under Panjain Section) Job No.3	99600	2,000	Rs. 350/-	One month	6&8	-do-
10	Maintenance of Pandoh Takoli Kullu by pass road km 222/700 to 227/600 (SH- Earthwork in filling at RD 223/300 to 223/420) Job No.2	99980	2,000	Rs. 350/-	One month	6&8	-do-
11	RRD on nvarious roads of Pandoh Sub-Division (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Pandoh nSection-I)	99600	2,000	Rs. 350/-	One month	6&8	-do-
12	RRD on Bhatwari to Rensh road km 8/640 to 15/910 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs in km 8/640 to 11/0).	99600	2,000	Rs. 350/	One month	6&8	-do-
13	RRD on various roads of Panarsa Sub Division (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Nagewain Section) Job No.I	99600	2,000	Rs. 350/-	One month	6&8	-do-
14	RRD on Sansoi to Kashna road km 0/0 to 6/250 (SH- Hiring of excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-

Scanned with CamScanner

15	RRD on various roads of Panarsa Sub Division (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Nagewain Section) Job No.3	99600	2,000	Rs. 350/-	One month	6&8	-do-
16	RRD on various roads of Panarsa Sub Division (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Nagewain Section) Job No.4	99600	2,000	Rs. 350/-	One month	6&8	-do-
17	RRD on various roads of Panarsa Sub Division (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Panarsa Section) Job No.1	99600	2,000	Rs. 350/-	One month	6&8	-do-
18	RRD on Shiva to Gharan road km 0/0 to 10/100 (SH- C/O R/wall at RD 1/830.50 to 1/835) Job No.4	96589	2,000	Rs. 350/-	One month	6&8	-do-
19	RRD on Baggi to Kashimblidhar road km 0/0 to 3/0 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at RD 0/0 to 3/0).	99600	2,000	Rs. 350/-	One month	6&8	-do-
20	RRD on various roads of Pandoh Sub Division (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs under Pandoh Section-II) Job No.II	99600	2,000	Rs. 350/-	One month	6&8	-do-
21	RRD on Panarsa to Kotadhar road km 0/0 to 5/825 (SH- Hiring of Excvator cum loader for removal of slips/clearance of berms, debries etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
22	RRD Bhatwari to Rensh road km 0/0 to 8/640 (SH- C/O crated B/wall from RD 4/845 to 4/855).	96202	2,000	Rs. 350/-	One month	6&8	-do-
23	RRD on Hanogi Bridge to Saloi road km 0/0 to 2/500 (SH- C/O R/wall in PCC & Boulder apron RD between 1/986 to 1/994).	82566	2,000	Rs. 350/-	One month	6&8	-do-
24	RRD on Shiva to Gharan road km 0/0 to 10/100 (SH- C/O R/wall at RD 1/825 to 1/826.50) Job No.1)	99704	2,000	Rs. 350/-	One month	6&8	-do-
25	RRD on Shiva to Gharan road km 0/0 to 10/100 (SH- C/O R/wall at RD 1/835 to 1/839.50) Job No.5	96589	2,000	Rs. 350/-	One month	6&8	-do-
26	RRD Bhatwari to Rensh road km 0/0 to 8/640 (SH- C/O crated B/wall from RD 4/835 to 4/845	96202	2,000	Rs. 350/-	One month	6&8	-do-
27	RRD on Shiva to Gharan road km 0/0 to 10/100 (SH- C/O R/wall at RD 1/826.50 to 1/828).	99704	2,000	Rs. 350/-	One month	6&8	-do-
28	Maintenance of Pandoh Takoli Kullu by pass road km 222/700 to 227/500 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs) Job No.1	99600	2,000	Rs. 350/-	One month	6&8	-do-
29	RRD on various roads of Panarsa Sub Division (SH- Hiring of Tipper for carriage of muck/debries at various RDs in Nagwain Section).	98000	2,000	Rs. 350/-	One month	6&8	-do-
30	RRD on Nagwain to Shill Mashora road km 0/0 to 6/050 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
31	RRD on various roads under Pandoh Sub Division (SH- Hiring of Tipper for carriage of muck, debries etc. at various RDs Pandoh Section-I) Job nNo.2	98000	2,000	Rs. 350/-	One month	6&8	-do-
32	RRD on road from Burah to Panjain km 0/0 to 11/0 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at RD 0/0 to 5/0).	99600	2,000	Rs. 350/-	One month	6&8	-do-
33	RRD on Hanogi to Saloi road km 0/0 to 2/500 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs in km 0/0 to 2/500).	99600	2,000	Rs. 350/-	One month	6&8	-do-

Scanned with CamScanner

34	RRD on Takoli to Pali road km 0/0 to 4/0 (SH- Hiring of Excaavtor cum loader for removal of slips/clearance of berms, debries etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
35	Maintenance of Pandoh Takoli Kullu by pass road km 222/700 to 227/500 (SH- Hiring of Tipper for carriage of muck/debries etc. at various RDs) Job No.1	98000	2,000	Rs. 350/-	One month	6&8	-do-
36	Maintenance of Pandoh Takoli Kullu by pass road km 222/700 to 227/500 (SH- Hiring of Tipper for carriage of muck/debries etc. at various RDs) Job No.3	98000	2,000	Rs. 350/-	One month	6&8	-do-
37	Maintenance of Pandoh Takoli Kullu by pass road km 222/700 to 227/500 (SH- Hiring of Tipper for carriage of muck/debries etc. at various RDs) Job No.2	98000	2,000	Rs. 350/-	One month	6&8	-do-
38	Maintenance of Pandoh Takoli Kullu by pass road km 222/700 to 227/500 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs) Job No.2	99600	2,000	Rs. 350/-	One month	6&8	-do-
39	Maintenance of Pandoh Takoli Kullu by pass road km 222/700 to 227/500 (SH- Hiring of Excavator cum loader for removal of slips/clearance of berms, debries etc. at various RDs) Job No.2	99600	2,000	Rs. 350/-	One month	6&8	-do-
40	RRD on Hanogi Bridge to Saloi road km 0/0 to 2/500 (SH- C/O R/wall in PCC & Dry Masonary RD 2/280 to 2/298).	61233	2,000	Rs. 350/-	One month	6&8	-do-
41	Maintenance of Pandoh Takoli Kullu by pass road km 222/700 to 227/500 (SH- Providing and supplying WBM Grade-III between portion RDs 223/300 to 223/420) Job No.3	99290	2,000	Rs. 350/-	One month	6&8	-do-
42	Maintenance of Pandoh Takoli Kullu by pass road km 222/700 to 227/500 (SH- Providing and supplying WBM Grade-III between portion RDs 223/300 to 223/420) Job No.2	99290	2,000	Rs. 350/-	One month	6&8	-do-

TERMS & CONDITIONS: -

1. The Tender form will not be issued to those contractors whose performance is not found satisfactory.
2. The Contractor whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to complete in tendering for four months.
3. The Contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only upto completion of work Satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.
4. The rates beyond the limit over +5% will be rejected besides this the Additional Performance security will have to borne @ 20 % & 30 % for unbalanced bid in case the rates is lower than 10 % but upto 20 % & lower than 20 % upto 30 % respectively. The tender will be accepted beyond the limit of -30 % also.

Executive Engineer,
Thalout Division,
HP.PWD Thalout.

NO/PW/TLD/Tender/2025:- 4033-42 Dated: - 04.09.2025

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP.
3. The Sub Divisional Officer Balichowki, Distt. Mandi HP.
4. The Chief Engineer, (MZ) HPPWD Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD Mandi HP.
6. The Distt. Panchayat Officer Mandi HP.
7. All AEs under this Division.
8. The President of Contractor's Association.
9. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.

Executive Engineer,
Thalout Division,
HP.PWD Thalout.

Scanned with CamScanner

Certificate

Certified that the tender called vide this office letter NO. PW/TLD/Tender/2025- 4033-42 dated 04.09.2025 is emergent nature and in Public interest.

Executive Engineer,
Thalout Division, HPPWD,
Thalout.

Scanned with CamScanner

(1)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section) Job No-2

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms.Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(2)

SCHEDULE OF QUANTITY

Name of work:- RRD on Panarsa to Kotadhar road km 0/0 to 5/625 (SH: - C/O PCC B/wall at RD 2/155 to 2/160.50).

Estimated Cost: 72017.00
Earnest Money :- 2000.00
Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechnicial means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	9.25	140.20	Rs.one hundred forty and paise twenty only	Per Cubic Metre	1297.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated ssuitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	4.30	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	1712.00
3	Providing and laying concrete for plain/reinforced concrete in 1:6:12 (one cement: six sand: Twelve crushed / stone aggregate) 40 mm (forty milimetre) nominal size open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	1.32	4400.60	Rs.Four thousand four hundred and paise sixty only	Per Cubic Metre	5809.00
4	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty milimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	12.92	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	63199
					Total	**72017.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP,PWD,Thalout

Scanned with CamScanner

(3)

SCHEDULE OF QUANTITY

Name of work:- RRD on Panarsa to Kotadhar road km 0/0 to 5/625 (SH: - C/O PCC B/wall at RD 2/160.50 to 2/166).

Estimated Cost: 72237.00
Earnest Money :- 2000.00
Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechnicial means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	9.24	140.20	Rs.one hundred forty and paise twenty only	Per Cubic Metre	1295.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated ssuitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	4.28	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	1704.00
3	Providing and laying concrete for plain/reinforced concrete in 1:6:12 (one cement: six sand: Twelve crushed / stone aggregate) 40 mm (forty milimetre) nominal size open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	1.35	4400.60	Rs.Four thousand four hundred and paise sixty only	Per Cubic Metre	5941.00
4	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty milimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	12.94	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	63297
					Total	**72237.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP,PWD,Thalout

Scanned with CamScanner

(9)

SCHEDULE OF QUANTITY

Name of work:- RRD on Bakhali to Kholnal km 0/0 to 8/500 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in km 0/0 to 8/500).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout

Scanned with CamScanner

(5)

SCHEDULE OF QUANTITY

Name of work:- RRD on Baggi to Kashimblidhar road km 0/0 to 3/00 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in km 0/0 to 3/00).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(6)

SCHEDULE OF QUANTITY

Name of work:- RRD Damages on Dhamu to Deori road km 0/0 to 2/645 km. (Sub Head :- C/o R/Walls Dry stones masonary at km 1/195 to 1/206 km).

Estimated Cost: 99981.00
Earnest Money :- 2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated ssuitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	12.86	452.95	Rs. Four hundred fifty two and paise ninety five only	Per Cubic Metre	5825.00
2	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub stuctur and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	24.09	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	90366.00
3.	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	3790.00
	Total					**99981.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout

Scanned with CamScanner

(7)

SCHEDULE OF QUANTITY

Name of work:- RRD Damages on Dhamu to Deori road km 0/0 to 2/645 km. (Sub Head :- C/o R/Walls (wire crate) masonary at km 0/861 to 0/868 km).

Estimated Cost: 85617.00
Earnest Money :- 2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated ssuitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	6.58	452.95	Rs. Four hundred fifty two and paise ninety five only	Per Cubic Metre	2980.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm (four milimetre) dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm (hundred into hundred milimetre) mesh (woven) diagonally) including 10 (Ten persant) persent extra for laps and joints laid with stones boulders weighting not less then 25 kg (Twenty five kilograme) each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	25.39	3254.70	Rs.Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	82637.00
	Total					**85617.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout

Scanned with CamScanner

(8)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Balichowki Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Thachi Section) Job No-1

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

9

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Balichowki Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panjain Section) Job No-3

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout

Scanned with CamScanner

(10)

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/600 (SH: - Earthwork in filling at Rd 223/300 to 223/420) Job No-2

Estimated Cost:-99980.00
Earnest Money:- 2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Construction of embankment with approved material obtained from borrow pits upto any lift , transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto any lead as per Technical Specification Clause 301.5 including carriage of material and other incidentials with in all leads, lifts and as per the direction of the Engineer-in Charge	334.66	298.75	Rs. Two hundred ninety eigth and paise seventy Five only	Per cubic metre	99980.00
					Total	99980.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division
HP PWD Thalout

Scanned with CamScanner

(11)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-II).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(12)

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhatwari to Rensh road km 8/640 to 15/910 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in km 8/640 to 11/00).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout

Scanned with CamScanner

13

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section) Job No-1

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

14

SCHEDULE OF QUANTITY

Name of work:- RRD on Sansoi to Kashna road km 0/0 to 6/250 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout

Scanned with CamScanner

15

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section) Job No-3

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms.Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

(16)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section) Job No-4

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

17

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Panarsa Section) Job No-1	Estimated Cost:-99600.00
	Earnest Money:-2000.00
	Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

SCHEDULE OF QUANTITY

Name of work:- RRD on Shiva to Gharan road km 0/0 to 10/100 km. (SH:- C/O R/Wall at RD 1/830.50 to 1/835 km). (Job No-4)

Estimated Cost:- 96589.00
Earnest Money :-2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	11.43	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	4551.00
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty milimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	1.94	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	9490.00
3	Stone masonry work in cement mortar 1:6 (One cement: six sand) in foundation complete as per drawing and technical specifications Clause 702,704,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	7.11	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	36952.00
4	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub stuctur and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	9.93	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	37249.00
5	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	3.51	1263.40	Rs.One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	4435.00
6	Providing weepholes in brick masonary/stone masonary /plain reinfoirced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	10	391.20	Rs.Three hundred ninety one and paise Twenty only	Each	3912.00
	Total					**96589.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout

Scanned with CamScanner

19

SCHEDULE OF QUANTITY

Name of work:- RRD on Baggi to Kashimblidhar road km 0/0 to 3/0 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at RD at Km 0/0 to 3/0).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-II). Job No-II	Estimated Cost:-99600.00
	Earnest Money:-2000.00
	Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

SCHEDULE OF QUANTITY

Name of work:- RRD on Panarsa to Kotadhar road km 0/0 to 5/825 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout.

Scanned with CamScanner

22

SCHEDULE OF QUANTITY

Name of work:- RRD Bhatwari to Rensh road Km. 0/000 to 8/640 SH: - C/O crated B/wall from RD. 4/845 to 4/855.

Estimated Cost: 96,202.00
Earnest Money :- 2000.00
Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechnicial means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	36.67	213.45	Rs.Two hundred thirteen and paise forty five only	Per Cubic Metre	7826.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated ssuitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	9.00	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	3584.00
3	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 persent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	27.37	3098.00	Rs.Three thousand ninty eight and paise zero only	Per Cubic Metre	84792.00
					Total	**96202.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalcut Division,
HP,PWD,Thalout

Scanned with CamScanner

23

SCHEDULE OF QUANTITY

Name of work:- RRD on Hanogi Bridge to Saloi road Km 0/00 to 2/500 (SH:- C/O R/Wall in PCC & Boulder apron RD between 1/986 to 1/994).

Estimated Cost:- 82566.00
Earnest Money :-2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	2.79	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	1111.00
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty milimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	2.16	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	10566.00
3	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 persent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	13.82	3098.00	Rs.Three thousand ninty eigth and paise zero only	Per Cubic Metre	42814.00
4	Random rubble masonry /polygonal rubble un-coursed brought to courses with hard stone of approved qualitgy in fondation and plinth Laid dry with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	5.38	4002.10	Rs. Four thousand Two and paise ten only	Per Cubic Metre	21531.00
5	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	5.18	1263.40	Rs.One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	6544.00
	Total					**82566.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout.

Scanned with CamScanner

Scanned with CamScanner

24

SCHEDULE OF QUANTITY

Name of work:- RRD on Shiva to Gharan road km 0/0 to 10/100 km. (SH:- C/O R/Wall at RD 1/825 to 1/826.50 km). (Job No.1).

Estimated Cost:- 99704.00
Earnest Money :-2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 I/c setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	12.71	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	5061.00
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty milimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	1.43	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	6995.00
3	Stone masonry work in cement mortar 1:6 (One cement: six sand) in foundation complete as per drawing and technical specifications Clause 702,704,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	10.05	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	52232.00
4	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub stuctur and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge	8.64	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	32410.00
5	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge	2.07	1263.40	Rs.One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	2615.00
6	Providing weepholes in brick masonary/stone masonary /plain reinfoirced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	1	391.20	Rs.Three hundred ninety one and paise Twenty only	Each	391.00
	Total					99704.00
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout.

SCHEDULE OF QUANTITY

Name of work:- RRD on Shiva to Gharan road km 0/0 to 10/100 km. (SH:- C/O R/Wall at RD 1/835 to 1/839.50 km). (Job No 5)

Estimated Cost:- 96589.00

Earnest Money :-2000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	11.43	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	4551.00
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty milimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	1.94	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	9490.00
3	Stone masonry work in cement mortar 1:6 (One cement: six sand) in foundation complete as per drawing and technical specifications Clause 702,704,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	7.11	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	36952.00
4	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub stuctur and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	9.93	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	37249.00
5	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	3.51	1263.40	Rs.One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	4435.00
6	Providing weepholes in brick masonary/stone masonary /plain reinfoirced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	10	391.20	Rs.Three hundred ninety one and paise Twenty only	Each	3912.00
	Total					**96589.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout

Scanned with CamScanner

26

SCHEDULE OF QUANTITY

Name of work:- RRD Bhatwari to Rensh road Km. 0/000 to 8/640 SH: - C/O crated B/wall from RD. 4/835 to 4/845.

Estimated Cost: 96,202.00
Earnest Money :- 2000.00
Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechnicial means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	36.67	213.45	Rs.Two hundred thirteen and paise forty five only	Per Cubic Metre	7826.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated ssuitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	9.00	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	3584.00
3	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 persent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	27.37	3098.00	Rs.Three thousand ninty eight and paise zero only	Per Cubic Metre	84792.00
					Total	**96202.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout

Scanned with CamScanner

27

SCHEDULE OF QUANTITY

Name of work:- RRD on Shiva to Gharan road km 0/0 to 10/100 km. (SH:- C/O R/Wall at RD 1/826 .50 to 1/828.00 km). (Job No.2).

Estimated Cost:- 99704.00
Earnest Money :-2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	12.71	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	5061.00
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty milimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	1.43	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	6995.00
3	Stone masonry work in cement mortar 1:6 (One cement: six sand) in foundation complete as per drawing and technical specifications Clause 702,704,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	10.05	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	52232.00
4	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc for sub stuctur and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge	8.64	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	32410.00
5	Back filling behind abutment wing wall and retainling wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge	2.07	1263.40	Rs.One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	2615.00
6	Providing weepholes in brick masonary/stone masonary /plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge	1	391.20	Rs.Three hundred ninety one and paise Twenty only	Each	391.00
	Total					**99704.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout

Scanned with CamScanner

28

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/500 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs).Job No-1

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout

Scanned with CamScanner

29

BILL OF QUANTITY

Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of Tipper for carriage of muck/debris etc. at various RDs in Nagwain Section)

Estimated Cost:-98000.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Tipper in good condtion of minimum 5.50 (Five point fifty drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavaated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	28.00	3500.00	Rs. Three thousand five hundred and paise zero only	Per Day	98000.00
	Total					**98000.00**

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

30

SCHEDULE OF QUANTITY

Name of work:- RRD on Nagwain to Shill Mashora road km 0/0 to 6/050 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

(31)

SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Pandoh Sub Division (SH: - Hiring of tipper for carriage of muck, debries etc. at various RDs Pandoh Section-I) Job No- 2

Estimated Cost:-98000.00
Earnest Money:- 2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Tipper in good condition of minimum 5.50 (Five point five zero) cubic metre carriage capacity on daily basis from 9.000 AM to 5.00PM with hydraulic facility for carriage of slips and disposal of same at suitable dumping places including P.O.L. charges and wages of driver and other opratational staff as per the direction and entire satisfaction of Engineer-in-Charge .	28.00	3500.00	Rs. Three thousand five hundred and paise zero only	Per day	98000.00
	Conditions:-					
	1) The cost of P.O.L will be borne by the contractor/owner of the vehicle/machine at this own cost.					
	2) The repair etc. will be got done by the contractor at his own cost.					
	3) The daily log book will be maintained at site which should be daily verifired by the Engineer-in-Charge.					
					Total	**98000.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

22

SCHEDULE OF QUANTITY

Name of work:- RRD on road from Burah to Panjain Km 0/000 to 11/000 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at RD 0/000 to 5/000).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

(33)

SCHEDULE OF QUANTITY

Name of work:- RRD on Hanogi to Saloi road km 0/0 to 2/500 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs in km 0/0 to 2/500).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

(34)

SCHEDULE OF QUANTITY

Name of work:- RRD on Takoli to Pali road km 0/0 to 4/00 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout

Scanned with CamScanner

35

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/500 (SH: - Hiring of Tipper for carriage of muck/debris etc. at various RDs). Job No-I

Estimated Cost:-98000.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of Item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Tipper in good condtion of minimum 5.50 (Five point fifty drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavaated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	28.00	3500.00	Rs. Three thousand five hundred and paise zero only	Per Day	98000.00
	Total					**98000.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout

Scanned with CamScanner

36

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/500 (SH: - Hiring of Tipper for carriage of muck/debris etc. at various RDs). Job No-3

Estimated Cost:-88000.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Tipper in good condition of minimum 5.50 (Five point fifty drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavaated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	28.00	3500.00	Rs. Three thousand five hundred and paise zero only	Per Day	98000.00
	Total					98000.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP PWD Thalout

Scanned with CamScanner

37

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/500 (SH: - Hiring of Tipper for carriage of muck/debris etc. at various RDs). Job No-2

Estimated Cost:-98000.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Tipper in good condtion of minimum 5.50 (Five point fifty drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavaated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour.Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	28.00	3500.00	Rs. Three thousand five hundred and paise zero only	Per Day	98000.00
	Total					**98000.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

Scanned with CamScanner

38

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/500 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs).Job No-2

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour Any loss of public property or any accident etc the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	**99600.00**
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

(39)

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/500 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs).Job No-3

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diection of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
HP PWD Thalout.

Scanned with CamScanner

40

SCHEDULE OF QUANTITY

Name of work:- RRD on Hanogi Bridge to Saloi road Km 0/00 to 2/500 (SH:- C/O R/Wall in PCC & Dry Masonery RD 2/280 to 2/298).

Estimated Cost:-61233.00
Earnest Money :-2000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deletarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	3.90	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	1553.00
2	Providing and laying HYSD bars for doweling as per requirement including making hole to place the bars with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	31.28	125.00	Rs. One hundred twenty five and paise zero only	Per kg	3910.00
3	Providing and laying concrete for plain/reinforced concrete in 1:3:6 (one cement: three sand: six crushed/ stone sggregate) 40 mm (fourty milimeter) nominal size in open foundation complete as per drawing and technica! specification Clause 802,803,1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	3.90	5771.80	Rs. Five thousand seven hundred seventy one and paise eighty only	Per Cubic Metre	22510.00
4	Random rubble masonry /polygonal rubble un-coursed brought to courses with hard stone of approved qualitgy in fondation and plinth Laid dry with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	7.25	4002.10	Rs. Four thousand Two and paise ten only	Per Cubic Metre	29015.00
5	Back filling behind abutment wing wall and retainling wall complete as per drawing & technica! specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	3.36	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	4245.00
	Total					**61233.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division
HP,PWD,Thalout

Scanned with CamScanner

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/500 (SH:-Providing and supplying WBM Grade-III between portion RDs Km 223/300 to 223/420) Job No-3	Estimated cost:-99290.00 Earnest Money:-2000.00 Time:- One Month

Sr.No	Description of item	Quantity	Rate		Unit	Amount
			in figure	in words		
1	Supply and stacking at site graded broken / crushed stone aggregate53 mm to 22.4 mm (fifty three milimetre to twenty two point four milimetre) nominal size of approved quarry free from disintegrated pieces, deletarious and other organic materials in proper stacks along the road side and as per direction of Engineer -in Charge with in all leads, lifts and carriage of materials and other incidentials.	78.00	1272.95	Rs. One Thousand two hundred seventy two and paise ninety five only	Per Cubic metre	99290.00
	Total					**99290.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division
HP PWD Thalout

Scanned with CamScanner

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Pandoh, Takoli,Kullu by pass road Km 222/700 to 227/500 (SH:-Providing and supplying WBM Grade-III between portion RDs Km 223/300 to 223/420) Job No-2	Estimated cost:-99290.00 Earnest Money:-2000.00 Time:- One Month

Sr.No	Description of item	Quantity	Rate		Unit	Amount
			in figure	in words		
1	Supply and stacking at site graded broken / crushed stone aggregate53 mm to 22.4 mm (fifty three milimetre to twenty two point four milimetre) nominal size of approved quarry free from disintegrated pieces, deletarious and other organic materials in proper stacks along the road side and as per direction of Engineer -in Charge with in all leads, lifts and carriage of materials and other incidentials.	78.00	1272.95	Rs. One Thousand two hundred seventy two and paise ninety five only	Per Cubic metre	99290.00
	Total					**99290.00**
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division
HP PWD Thalout

Scanned with CamScanner