

OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS
DEPARTMENT BANGANA

No:- PW-BGN-CB/T-1/2025-26-
To

9231-39

Dated:- 21/9/25

The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.
cc-pwd-hp@nic.in.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.

Amrit Chawla
Executive Engineer
Bangana Division
HPPWD Bangana.


Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD, Una.
4. The Assistant Engineer, Sub Division, HPPWD Bangana and Basal.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.


Executive Engineer
Bangana Division
HPPWD Bangana.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

CERTIFICATE

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BGN/CB/T-1/2024-25-26-
9231-39 dated 21-11-25.

Anil Chah
Executive Engineer
Bangana Division
HPPWD Bangana.

**OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS
DEPARTMENT BANGANA**

NOTICE INVITING TENDER.

Sealed percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Bangana Division HPPWD Bangana on behalf of Governor of HP, from the approved eligible contractors enlisted in HPPWD, for the following works: so as to reach this office on **28-11-2025 up to 10.30 A.M** and same will be opened on the same day at 11.00 AM in presence of the interested contractors or their authorized representative. The application will be received in this office on at **25-11-2025 upto 03.00**

PM. The tender form can be had from the office of Executive Engineer Bangana Division HPPWD Bangana on cash payment (Non-refundable) on **27-11-2025** during office Hours **up to 4.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP or Nationalized Bank duly pledged in the name of Executive Engineer Bangana Division HPPWD Bangana cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The tender document fee shall also be deposited by the applicant/ contractor with at the time of application in the shape of Demand Draft or Cash (Non-Refundable) otherwise tender documents/ Forms shall not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment renewal exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act. Valid copy of Registration as required. Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period	Eligible of Class
1	Restoration of Rain Damages on Una Brera road (SH: C/o R wall in Km 6.821 to 6.840) Under Head PDNA	448828.00	9000.00	Two Month	C & D
2	Restoration of Rain Damages on Una Brera road (SH: C/o R wall in Km 6.300 to 6.333) Under Head PDNA	493841.00	9900.00	Two Month	C & D
3	Restoration of Rain Damages on Una Brera road (SH: C/o R wall in Km 6.800 to 6.833) Under Head PDNA	496194.00	10000.00	Two Month	C & D
4	Restoration of Rain Damages on Una Brera road (SH: P/L Interlocking Paver Block flooring in Km 6.264 to 6.334) Under Head PDNA	482191.00	9700.00	Two Month	C & D
5	Restoration of Rain Damages on Una Brera road (SH: P/L Interlocking Paver Block flooring in Km 6.500 to 6.530 & C/o Edge wall in Km 6.100 to 6.152) Under Head PDNA	411004.00	8300.00	Two Month	C & D
6	Restoration of Rain Damages on link road to Village Panoh (SH: C/o R/wall in Km 0.100 to 0.105.30) Under Head PDNA	497741.00	10000.00	Two Month	C & D
7	Restoration of Rain Damages on link road to Village Panoh (SH: C/o R/wall in Km 0.115.90 to 0.117.55) Under Head PDNA	155828.00	3200.00	Two Month	C & D
8	Restoration of Rain Damages on link road Ambehra Kokra Harot road (SH: P/L Interlocking paver block flooring in km 6/950 to 7/025) Under Head PDNA	495817.00	10000.00	Two Month	C & D
9	Restoration of Rain Damages on link road Ambehra Kokra Harot road (SH: P/L Interlocking paver block flooring in km 6.875 to 6.950) Under Head PDNA	490725.00	9900.00	Two Month	C & D
10	Restoration of Rain Damages on link road Ambehra Kokra Harot road (SH: P/L Interlocking paver block flooring in km 6.800 to 6.875) Under Head PDNA	498909.00	10000.00	Two Month	C & D
11	Restoration of Rain Damages on link road Ambehra Kokra Harot road (SH: P/L Interlocking paver block flooring in km 6.725 to 6.800) Under Head PDNA	489234.00	9800.00	Two Month	C & D
12	Restoration of Rain Damages on link road Ambehra Kokra Harot road (SH: P/L Interlocking paver block flooring in km 6.650 to 6.725) Under Head PDNA	490725.00	9900.00	Two Month	C & D
13	Restoration of Rain Damages on U.A.M road to Harot (SH: C/o R/wall in Km 13/910 to 13/915 & V-shape Drain in Km 10/200 to 10/400) Under Head PDNA	473790.00	9500.00	Two Month	C & D
14	Restoration of Rain Damages on U.A.M road to Harot (SH: C/o V-shape Drain with Edge wall in Km 3/675 to 3/827) Under Head PDNA	492097.00	9900.00	Two Month	C & D
15	Restoration of Rain Damages on U.A.M road to Harot (SH: C/o V-shape Drain with Edge wall in Km 10/325 to 10/400 & 3/600 to 3/675) Under Head PDNA	485620.00	9800.00	Two Month	C & D
16	Restoration of Rain Damages on U.A.M road to Harot (SH: C/o V-shape Drain with Edge wall in Km 13/100 to 13/250) Under Head PDNA	485620.00	9800.00	Two Month	C & D

17	Restoration of Rain Damages on U.A.M road to Harot (SH: C/o V-shape Drain with Edge wall in Km 3/827 to 3/980) Under Head PDNA	495358.00	10000.00	Two Month	C&D
18	Restoration of Rain Damages on U.A.M road Km 2/000 to 19/000 (SH: C/o B/wall in Km 8/150 to 8/202) Under Head PDNA	451250.00	9100.00	Two Month	C&D
19	Restoration of Rain Damages on U.A.M road Km 2/000 to 19/000 (SH: C/o B/wall in Km 8/202 to 8/255) Under Head PDNA	459938.00	9200.00	Two Month	C&D
20	Restoration of Rain Damages on U.A.M road Km 2/000 to 19/000 (SH: C/o B/wall in Km 8/255 to 8/306.50) Under Head PDNA	447158.00	9000.00	Two Month	C&D
21	Restoration of Rain Damages on U.A.M road Km 2/000 to 19/000 (SH: C/o B/wall in Km 7/750 to 7/802) Under Head PDNA	451250.00	9100.00	Two Month	C&D
22	Restoration of Rain Damages on Link road Boul to Madanpur Jogipanga road (SH: C/o Wire crate R/wall in km 8/819 to 8/839) Under PDNA	498634.00	10000.00	Two Month	C&D
23	Restoration of Rain Damages on Link road Boul to Madanpur Jogipanga road (SH: C/o Wire crate R/wall in km 8/800 to 8/815) Under PDNA	485823.00	9800.00	Two Month	C&D
24	Restoration of Rain Damages on link road to Village Gehra Kothhi upto Baba Garib Nath Temple Km 0/000 to 9/920 (SH: P/L Interlocking paver Block flooring in Km 8/400 to 8/490) Under Head PDNA	488367.00	9800.00	Two Month	C&D
25	Restoration of Rain Damages on link road to Village Gehra Kothhi upto Baba Garib Nath Temple Km 0/000 to 9/920 (SH: P/L Interlocking paver Block flooring in Km 8/500 to 8/542) Under Head PDNA	215901.00	4400.00	Two Month	C&D
26	Restoration of Rain Damages on link road to Village Lamlehrri (SH: C/o Edge wall in Km 0/150 to 0/232) Under Head PDNA	448228.00	9000.00	Two Month	C&D
27	Restoration of Rain Damages on link road to Village Lamlehrri (SH: C/o Edge wall in Km 0/232 to 0/279) Under Head PDNA	256813.00	5200.00	Two Month	C&D
28	Restoration of Rain Damages on link road to Village Lamlehrri (SH: C/o Edge wall in Km 0/323 to 0/314) Under Head PDNA	491980.00	9900.00	Two Month	C&D
29	Restoration of Rain Damages on Baba Balak Rupi Mandir Lam (SH: P/L Interlocking paver block flooring in Km 0/310 to 0/387) Under Head PDNA	499956.00	10000.00	Two Month	C&D
30	Restoration of Rain Damages on Baba Balak Rupi Mandir Lam (SH: C/o B/wall with V-shape Drain in Km 0/170 to 0/217) Under Head PDNA	499996.00	10000.00	Two Month	C&D
31	Restoration of Rain Damages on Baba Balak Rupi Mandir Lam (SH: C/o B/wall with V-shape Drain in Km 0/080 to 0/170 R.H.S.) Under Head PDNA	499400.00	10000.00	Two Month	C&D
32	Restoration of Rain Damages on Baba Balak Rupi Mandir Lam (SH: C/o B/wall with V-shape Drain in Km 0/080 to 0/170 L.H.S.) Under Head PDNA	493888.00	9900.00	Two Month	C&D
33	Restoration of Rain Damages on Baba Balak Rupi Mandir Lam (SH: C/o B/wall with V-shape Drain in Km 0/217 to 0/247 Both side) Under Head PDNA	318980.00	6400.00	Two Month	C&D
34	Restoration of Rain Damages on Link road Batuhi to Badoli via Dharwal Mohalla (SH: C/o R/wall in Km 0/759 to 0/768.20) Under Head PDNA	379978.00	7600.00	Two Month	C&D
35	Restoration of Rain Damages on Link road Batuhi to Badoli via Dharwal Mohalla (SH: C/o R/wall in Km 0/750 to 0/759) Under Head PDNA	379351.00	7600.00	Two Month	C&D
36	Restoration of Rain Damages on Link road Batuhi to Badoli via Dharwal Mohalla (SH: C/o R/wall in Km 0/768.20 to 0/777.40) Under Head PDNA	379978.00	7600.00	Two Month	C&D
37	Restoration of Rain Damages on Ambehra Dhamandri road (SH: P/L Interlocking Paver Block flooring in Km 2/980 to 3/050 & 3/400 to 3/440 both side) Under Head PDNA	324243.00	6500.00	Two Month	C&D

38	Restoration of Rain Damages on Ambhehra Dhamandri road (SH: P.L. Interlocking Paver Block flooring in Km 2/800 to 2/980) Under Head PDNA	307476.00	6200.00	Two Month	C&D
39	Restoration of Rain Damages on Ghandawal to Chalola road (SH: Gabion wall in Km 0/850 to 0/870) Under Head PDNA	387120.00	7800.00	Two Month	C&D
40	Restoration of Rain Damages on Ghandawal to Chalola road (SH: Gabion wall in Km 0/880 to 0/898 & B/wall Both side) Under Head PDNA	497868.00	10000.00	Two Month	C&D
41	Restoration of Rain Damages on Link road Ghandawal to Batuhi (SH: C/o Wing wall in Km 2/113 to 2/126.10) Under PDNA	499814.00	10000.00	Two Month	C&D
42	Restoration of Rain Damages on Link road Ghandawal to Batuhi (SH: C/o Wing wall in Km 2/100 to 2/113) Under PDNA	496094.00	10000.00	Two Month	C&D
43	Restoration of Rain Damages on Link road Batuhi to Badoli via Dharwal Mohalla (SH: C/o 900mm dia & 300mm dia Hume Pipe culvert with wing wall in Km 0/650) Under Head PDNA	431750.00	8700.00	Two Month	C&D
44	Restoration of Rain Damages on Ghandawal to Chalola road (SH: Gabion wall in Km 0/870 to 0/880 Guid Bund & B wall Both side) Under Head PDNA	424892.00	8500.00	Two Month	C&D
45	Restoration of Rain Damages on link road Bhiambi to Jole Km 0/000 to 0/700 (SH: C/o C.C. Pavement from RD 0/000 to 0/120) Under Head PDNA	485548.00	9800.00	Two Month	C&D
46	Restoration of Rain Damages on link road Bhiambi to Jole Km 0/000 to 0/700 (SH: C/o C.C. Pavement from RD 0/0121 to 0/241) Under Head PDNA	491841.00	9900.00	Two Month	C&D
47	Restoration of Rain Damages on link road Bhiambi to Jole Km 0/000 to 0/700 (SH: C/o C.C. Pavement from RD 0/0242 to 0/361) Under Head PDNA	487769.00	9800.00	Two Month	C&D
48	Restoration of Rain Damages on link road Bhiambi to Jole Km 0/000 to 0/700 (SH: C/o C.C. Pavement from RD 0/362 to 0/468) Under Head PDNA	434460.00	8700.00	Two Month	C&D
49	Restoration of Rain Damages on Bangana to Deehar Via Chaplah road Km 0/000 to 6/000 (SH: C/o R/wall from RD 2/110 to 2/130) Under Head PDNA	352387.00	7100.00	Two Month	C&D
50	Restoration of Rain Damages on Bangana to Deehar Via Chaplah road Km 0/000 to 6/000 (SH: C/o R/wall from RD 2/131 to 2/146) Under Head PDNA	264650.00	5300.00	Two Month	C&D
51	Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o C.C. Pavement from RD 17/700 to 17/784) Under Head PDNA	478041.00	9600.00	Two Month	C&D
52	Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o C.C. Pavement from RD 17/785 to 17/801, U-shape drain 150mtr & R/wall from Rd 17/735 to 17/741) Under Head PDNA	473235.00	9500.00	Two Month	C&D
53	Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o R/wall from Rd 17/742 to 17/765) Under Head PDNA	488950.00	9800.00	Two Month	C&D
54	Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o R/wall from Rd 17/766 to 17/789) Under Head PDNA	488950.00	9800.00	Two Month	C&D
55	Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o R/wall from Rd 17/790 to 17/798 & B/wall from RD 17/735 to 17/758) Under Head PDNA	483224.00	9700.00	Two Month	C&D
56	Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o B/wall from RD 17/758 to 17/785) Under Head PDNA	394009.00	7900.00	Two Month	C&D
57	Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o B/wall from RD 17/790 to 17/817) Under Head PDNA	393517.00	7900.00	Two Month	C&D
58	Restoration of Rain Damages on L/R to Village Nalwari Km 0/000 to 1/000 (SH: C/o C/o C.C. Pavement from RD 0/135 to 0/185, B/wall from RD 0/180 to 0/192 & U-shape drain 50mtr.) Under Head PDNA	440550.00	8900.00	Two Month	C&D

59	Restoration of Rain Damages on L/R to Village Nalwari Km 0/000 to 1/000 (SH: C/o C/o C.C. Pavement from RD 0/186 to 0/236, B/wall from RD 0/192 to 0/203 & U-shape drain 50mtr.) Under Head PDNA	444877.00	8900.00	Two Month	C&D
60	Restoration of Rain Damages on L/R to Village Nichli Kharol Km 0/000 to 1/000 (SH: C/o C/o C.C. Pavement from RD 0/300 to 0/373 & U-shape drain 50mtr.) Under Head PDNA	393204.00	7900.00	Two Month	C&D
61	Restoration of Rain Damages on L/R to Village Nichli Kharol Km 0/000 to 1/000 (SH: C/o C/o C.C. Pavement from RD 0/374 to 0/446 & U-shape drain 50mtr.) Under Head PDNA	385656.00	7800.00	Two Month	C&D
62	Restoration of Rain Damages on L/R to Village Dhatol Km 0/000 to 1/240 (SH: C/o C/o C.C. Pavement from RD 0/800 to 0/875 & U-shape drain 75mtr.) Under Head PDNA	469588.00	9400.00	Two Month	C&D
63	Restoration of Rain Damages on L/R to Village Dhatol Km 0/000 to 1/240 (SH: C/o C/o C.C. Pavement from RD 0/876 to 0/951 & U-shape drain 82mtr.) Under Head PDNA	451550.00	9100.00	Two Month	C&D
64	Restoration of Rain Damages on L/R to Village Dhatol Km 0/000 to 1/240 (SH: C/o C/o C.C. Pavement from RD 0/952 to 1/002 & U-shape drain 82mtr.) Under Head PDNA	346608.00	7000.00	Two Month	C&D
65	Restoration of Rain Damages on Hatli Talpi road Km 0/000 to 7/640 (SH: C/o U-shape Drain from RD 0/800 to 0/855 & 0/900 to 0/930) Under Head PDNA	282880.00	5700.00	Two Month	C&D
66	Restoration of Rain Damages on Hatli Talpi road Km 0/000 to 7/640 (SH: C/o B/wall from RD 1/382 to 1/402 & U-shape Drain from RD 0/600 to 0/660) Under Head PDNA	396729.00	8000.00	Two Month	C&D
67	Restoration of Rain Damages on Hatli Talpi road Km 0/000 to 7/640 (SH: C/o U-shape Drain from RD 0/661 to 0/798) Under Head PDNA	455936.00	9200.00	Two Month	C&D
68	Restoration of Rain Damages on Piploo Rachhoh road Km 0/000 to 21/770 (SH: C/o R/wall from RD 12/534 to 12/553) Under Head PDNA	397955.00	8000.00	Two Month	C&D
69	Restoration of Rain Damages on Piploo Rachhoh road Km 0/000 to 21/770 (SH: C/o R/wall from RD 4/421 to 4/431 & 12/520 to 12/533) Under Head PDNA	481892.00	9700.00	Two Month	C&D
70	Restoration of Rain Damages on Piploo Rachhoh road Km 0/000 to 21/770 (SH: C/o R/wall from RD 4/400 to 4/421) Under Head PDNA	419685.00	8400.00	Two Month	C&D
71	Restoration of Rain Damages on Hatli Talpi road Km 0/000 to 7/640 (SH: C/o B/wall from RD 1/280 to 1/330) Under Head PDNA	492112.00	9900.00	Two Month	C&D
72	Restoration of Rain Damages on Hatli Talpi road Km 0/000 to 7/640 (SH: C/o B/wall from RD 1/331 to 1/381) Under Head PDNA	492604.00	9900.00	Two Month	C&D

HIM SUCHANA AVAM JAN SAMPARK,


 Anil Chauhan
 Executive Engineer
 Bangana Division
 HPPWD Bangana.
 On behalf of Governor of Himachal Pradesh.

DRAFT SCHEDULE OF QUANTITY

					Estimated Cost Rs	448828.00
					Earnest Money Rs	9000.00
					Time Limit:	Two Month
					RATE	AMOUNT
Sr. No.	Description of work			Quantity	Unit	Figures Words Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.			39.520	Per cubic metre	384.00 Rupees Three Hundred & Eighty Four Only 15176.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			100.51	Per Cubic metre.	3932.00 Rupees Three Thousand Nine Hundred & Thirty Two Only 395205.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.			54.00	Each	383.00 Rupees Three Hundred & Eighty Three Only 20682.00
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.			20.90	Per Cubic metre	850.00 Rupees Eight Hundred Only 17765.00
Total Rs.						448828.00

384
Draft Schedule of Quantity No.....for the year 2025-26 approved for amounting to Rs. 448828/-only


Executive Engineer
Bangana Division
HP.PWD. Banga


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Una Brera road (SH: C/o R/wall in Km 6/300 to 6/333) Under Head PDNA					Estimated Cost Rs	493841.00
					Earnest Money Rs	
					Time Limit:	
					RATE	
Sr. No.	Description of work			Quantity	Unit	AMOUNT
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	45.540	Per cubic metre	384.00	Rupees Three Hundred & Eighty Four Only	17487.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. .	103.95	Per Cubic metre.	3932.00	Rupees Three Thousand Nine Hundred & Thirty Two Only	408731.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	96.00	Each	383.00	Rupees Three Hundred & Eighty Three Only	36768.00
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	36.30	Per Cubic metre	850.00	Rupees Eight Hundred Only	30855.00
Total Rs.		493841.00				


385
Draft Schedule of Quantity No.....for the year 2025-26 approved for amounting to Rs. 493841/-only

Anil Chhetri
Executive Engineer
Bangana Division
HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Una Brera road (SH: C/o R/wall in Km 6/800 to 6/833) Under Head PDNA				Estimated Cost Rs	496194.00	
				Earnest Money Rs	10000.00	
				Time Limit:	Two Month	
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
Figures	Words	Rs. P				
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	43.680	Per cubic metre	384.00	Rupees Three Hundred & Eighty Four Only	16773.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	111.09	Per Cubic metre.	3932.00	Rupees Three Thousand Nine Hundred & Thirty Two Only	436806.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters. PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	60.00	Each	383.00	Rupees Three Hundred & Eighty Three Only	22980.00
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	23.10	Per Cubic metre	850.00	Rupees Eight Hundred Only	19635.00
Total Rs.				496194.00		

387
Draft Schedule of Quantity No.....for the year 2025-26 approved for amounting to Rs. 496194/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Una Brera road (SH: P/L Interlocking Paver Block flooring in Km 6/264 to 6/334) Under Head PDNA				Estimated Cost Rs	482191.00
				Earhest Money Rs	9700.00
				Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT
		Figures	Words	Rs. P	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	56.700	Per cubic metre	384.00 Rupees Three Hundred & Eighty Four Only	21773.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	31.50	Per Cubic metre.	3932.00 Rupees Three Thousand Nine Hundred & Thirty Two Only	123858.00
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	280.00	Per Square metre	1150.00 Rupees One Thousand One Hundred & Fifty Only	322000.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	2.80	Per cubic metre	5200.00 Rupees Eight Hundred Only	14560.00
Total Rs.		482191.00			

389
Draft Schedule of Quantity No.....for the year 2025-26 approved for amounting to Rs. 482191/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Una Brera road (SH: P/L Interlocking Paver Block flooring in Km 6/500 to 6/530 & C/o Edge wall in Km 6/100 to 6/152) Under Head PDNA					Estimated Cost Rs	411004.00
					Earnest Money Rs	8300.00
					Time Limit:	Two Month
					RATE	AMOUNT
Sr. No.	Description of work			Quantity	Unit	Figures
						Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.			45.360	Per cubic metre	384.00 Rupees Three Hundred & Eighty Four Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			55.62	Per Cubic metre.	3932.00 Rupees Three Thousand Nine Hundred & Thirty Two Only
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge). including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.			120.00	Per Square metre	1150.00 Rupees One Thousand One Hundred & Fifty Only
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.			1.20	Per cubic metre	5200.00 Rupees Five Thousand Two Hundred Only
						6240.00

Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
5.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	51.00	Each	383.00	Rupees Three Hundred & Eighty Three Only	19533.00
6.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.34	Per cubic metre	4750.00	Rupees Four Thousand Seven Hundred & Fifty Only	11115.00
Total Rs.		411004.00				

390
Draft Schedule of Quantity No.....for the year 2025-26 approved for amounting to Rs. 411004/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road to Village Panoh (SH: C/o R/wall in Km 0/100 to 0/105.30) Under Head PDNA					Estimated Cost Rs	497741.00	
					Earnest Money Rs		
					Time Limit:		
					RATE		
Sr. No.	Description of work		Quantity	Unit	Figures	Words	
					Rs.	P	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		34.820	Per cubic metre	381.00	Rupees Three Hundred & Eighty One Only	13266.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.		123.54	Per Cubic metre.	3850.00	Rupees Three Thousand Eight Hundred & Fifty Only	475629.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.		16.00	Each	290.00	Rupees Two Hundred & Ninety Only	4640.00
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		6.47	Per Cubic metre	650.00	Rupees Eight Hundred Only	4206.00
Total Rs.		497741.00					

393
Draft Schedule of Quantity No.....for the year 2025-26 approved for amounting to Rs. 497741/-only

Anup Chauhan
Executive Engineer
Bangana Division
HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road to Village Panoh (SH: C/o R/wall in Km 0/115.90 to 0/117.55) Under Head PDNA					Estimated Cost Rs	155828.00
					Earnest Money Rs	3200.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
		Figures	Words	Rs. P		
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.840	Per cubic metre	381.00	Rupees Three Hundred & Eighty One Only	4130.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	38.46	Per Cubic metre.	3850.00	Rupees Three Thousand Eight Hundred & Fifty Only	148071.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each	290.00	Rupees Two Hundred & Ninety Only	2320.00
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	2.01	Per Cubic metre	650.00	Rupees Eight Hundred Only	1307.00
Total Rs.						155828.00

394 155828
Draft Schedule of Quantity No.....for the year 2025-26 approved for amounting to Rs. 497741-only

Avl Chaw
Executive Engineer
Bangana Division
HP.PWD. Banga

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road Ambehra Kokra Harot road (SH: P/L Interlocking paver block flooring in km 6/950 to 7/025) Under Head PDNA					Estimated Cost Rs	495817.00
					Earnest Money Rs	10000.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	68.44	Per cubic metre	90.00	Rupees Ninety Only	6160.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	27.38	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	104044.00
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	236.25	Per Square metre	950.00	Rupees Nine Hundred & Fifty Only	224438.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.00	Per cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	15600.00
5.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	40.50	Each	250.00	Rupees Two Hundred & Fifty Only	10125.00

Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
6.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	31.50	Per cubic metre	4300.00	Rupees Four Thousand Three Hundred Only	135450.00
Total Rs.		495817.00				

Draft Schedule of Quantity No. 401....for the year 2025-26 approved for amounting to Rs. 495817/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road Ambehra Kokra Harot road (SH: P/L Interlocking paver block flooring in km 6/875 to 6/950) Under Head PDNA					Estimated Cost Rs	490725.00
					Earnest Money Rs	
					Time Limit:	
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	67.50	Per cubic metre	90.00	Rupees Ninety Only	6075.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	27.00	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	102600.00
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge). including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	232.50	Per Square metre	950.00	Rupees Nine Hundred & Fifty Only	220875.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.00	Per cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	15600.00
5.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	40.50	Each	250.00	Rupees Two Hundred & Fifty Only	10125.00

Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
6.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	31.50	Per cubic metre	4300.00	Rupees Four Thousand Three Hundred Only	135450.00
Total Rs.						490725.00

Draft Schedule of Quantity No. 402 for the year 2025-26 approved for amounting to Rs. 490725/-only


Abdul Chisn
Executive Engineer
Bangana Division
HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road Ambehra Kokra Harot road (SH: P/L Interlocking paver block flooring in km 6/800 to 6/875) Under Head PDNA					Estimated Cost Rs	498909.00
					Earnest Money Rs	10000.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit		RATE	AMOUNT
				Figures	Words	Rs. P
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	66.56	Per cubic metre	90.00	Rupees Ninety Only	5990.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	26.63	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	101194.00
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	232.50	Per Square metre	950.00	Rupees Nine Hundred & Fifty Only	220875.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.00	Per cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	15600.00
5.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	40.50	Each	250.00	Rupees Two Hundred & Fifty Only	10125.00

Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
6.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water.dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	33.75	Per cubic metre	4300.00	Rupees Four Thousand Three Hundred Only	145125.00
Total Rs.						498909.00

Draft Schedule of Quantity No. 403 for the year 2025-26 approved for amounting to Rs. 498909/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road Ambehra Kokra Harot road (SH: P/L Interlocking paver block flooring in km 6/725 to 6/800) Under Head PDNA					Estimated Cost Rs	489234.00
					Earnest Money Rs	9800.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	66.56	Per cubic metre	90.00	Rupees Ninety Only	5990.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	26.63	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	101194.00
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	232.50	Per Square metre	950.00	Rupees Nine Hundred & Fifty Only	220875.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.00	Per cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	15600.00
5.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	40.50	Each	250.00	Rupees Two Hundred & Fifty Only	10125.00

Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
6.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	31.50	Per cubic metre	4300.00	Rupees Four Thousand Three Hundred Only	135450.00
Total Rs.		489234.00				

Draft Schedule of Quantity No. 404 for the year 2025-26 approved for amounting to Rs. 489234/-only

Abul Chakr
Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road Ambehra Kokra Harot road (SH: P/L Interlocking paver block flooring in km 6/650 to 6/725) Under Head PDNA					Estimated Cost Rs		490725.00
					Earnest Money Rs		9900.00
					Time Limit:		Two Month
Sr. No.	Description of work	Quantity	Unit		RATE	AMOUNT	
				Figures	Words	Rs. P	
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	67.50	Per cubic metre	90.00	Rupees Ninety Only	6075.00	
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	27.00	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	102600.00	
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	232.50	Per Square metre	950.00	Rupees Nine Hundred & Fifty Only	220875.00	
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.00	Per cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	15600.00	
5.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	40.50	Each	250.00	Rupees Two Hundred & Fifty Only	10125.00	

Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
6.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	31.50	Per cubic metre	4300.00	Rupees Four Thousand Three Hundred Only	135450.00
Total Rs.		490725.00				


Draft Schedule of Quantity No. 405.....for the year 2025-26 approved for amounting to Rs. 490725/-only

Avul Chari
Executive Engineer
Bangana Division
HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on U.A.M road to Harot (SH: C/o R/wall in Km 13/910 to 13/915 & V-shape Drain in Km 10/200 to 10/400) Under Head PDNA					Estimated Cost Rs	473790.00
					Earnest Money Rs	9500.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	36.860	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	9215.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	114.80	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	436240.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	Each	250.00	Rupees Two Hundred & Fifty Only	3000.00
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5.63	Per cubic metre	4500.00	Rupees Four Thousand Five Hundred Only	25335.00
Total Rs.					473790.00	

Draft Schedule of Quantity No. 406.....for the year 2025-26 approved for amounting to Rs. 473790/-only


Executive Engineer
Bangana Division
HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on U.A.M road to Harot (SH: C/o V-shape Drain with Edge wall in Km 3/675 to 3/827) Under Head PDNA						Estimated Cost Rs	492097.00
						Earnest Money Rs	9900.00
						Time Limit:	Two Month
Sr. No.	Description of work			Quantity	Unit	RATE	AMOUNT
				Figures	Words	Rs. P	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.			30.780	Per cubic metre	250.00 Rupees Two Hundred & Fifty Only	7695.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand.eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			109.44	Per Cubic metre.	3800.00 Rupees Three Thousand Eight Hundred Only	415872.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.			151.00	Each	250.00 Rupees Two Hundred & Fifty Only	37750.00
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.			6.84	Per cubic metre	4500.00 Rupees Four Thousand Five Hundred Only	30780.00
Total Rs.							492097.00

Draft Schedule of Quantity No 407...for the year 2025-26 approved for amounting to Rs. 492097/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on U.A.M road to Harot (SH: C/o V-shape Drain with Edge wall in Km 10/325 to 10/400 & 3/600 to 3/675) Under Head PDNA				Estimated Cost Rs		485620.00
				Earnest Money Rs		9800.00
				Time Limit:		Two Month
Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	30.380	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	7595.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	108.00	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	410400.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	149.00	Each	250.00	Rupees Two Hundred & Fifty Only	37250.00
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.75	Per cubic metre	4500.00	Rupees Four Thousand Five Hundred Only	30375.00
Total Rs.				485620.00		

Draft Schedule of Quantity No. 408...for the year 2025-26 approved for amounting to Rs. 485620/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on U.A.M road to Harot (SH: C/o V-shape Drain with Edge wall in Km 13/100 to 13/250) Under Head PDNA					Estimated Cost Rs	485620.00
					Earnest Money Rs	9800.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	30.380	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	7595.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	108.00	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	410400.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	149.00	Each	250.00	Rupees Two Hundred & Fifty Only	37250.00
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.75	Per cubic metre	4500.00	Rupees Four Thousand Five Hundred Only	30375.00
Total Rs.					485620.00	

Draft Schedule of Quantity No. for the year 2025-26 approved for amounting to Rs. 485620/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on U.A.M road to Harot (SH: C/o V-shape Drain with Edge wall in Km 3/827 to 3/980) Under Head PDNA					Estimated Cost Rs	495358.00
					Earnest Money Rs	10000.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	30.980	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	7745.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	110.16	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	418608.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	152.00	Each	250.00	Rupees Two Hundred & Fifty Only	38000.00
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.89	Per cubic metre	4500.00	Rupees Four Thousand Five Hundred Only	31005.00
Total Rs.					495358.00	

Draft Schedule of Quantity No. 410.....for the year 2025-26 approved for amounting to Rs. 495358/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on U.A.M road Km 2/000 to 19/000 (SH: C/o B/wall in Km 8/150 to 8/202) Under Head PDNA				Estimated Cost Rs	451250.00
				Earnest Money Rs	9100.00
				Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT
		Figures	Words	Rs. P	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	43.160	Per cubic metre	250.00 Rupees Two Hundred & Fifty Only	10790.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	109.20	Per Cubic metre.	3800.00 Rupees Three Thousand Eight Hundred Only	414960.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	102.00	Each	250.00 Rupees Two Hundred & Fifty Only	25500.00
Total Rs.				451250.00	

Draft Schedule of Quantity No. 451250.00 for the year 2025-26 approved for amounting to Rs. 451250/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on U.A.M road Km 2/000 to 19/000 (SH: C/o B/wall in Km 8/202 to 8/255) Under Head PDNA					Estimated Cost Rs	459938.00
					Earnest Money Rs	9200.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	43.990	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	10998.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	111.30	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	422940.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	104.00	Each	250.00	Rupees Two Hundred & Fifty Only	26000.00
Total Rs.						459938.00

Draft Schedule of Quantity No. 412.....for the year 2025-26 approved for amounting to Rs. 459938/-only



Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on U.A.M road Km 2/000 to 19/000 (SH: C/o B/wall in Km 8/255 to 8/306.50) Under Head PDNA					Estimated Cost Rs	447158.00
					Earnest Money Rs	9000.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	42.750	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	10688.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	108.15	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	410970.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	102.00	Each	250.00	Rupees Two Hundred & Fifty Only	25500.00
Total Rs.		447158.00				

Draft Schedule of Quantity No. 413....for the year 2025-26 approved for amounting to Rs. 447158/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on U.A.M road Km 2/000 to 19/000 (SH: C/o B/wall in Km 7/750 to 7/802) Under Head PDNA				Estimated Cost Rs	451250.00
				Earnest Money Rs	9100.00
				Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT
				Figures	Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	43.160	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	109.20	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	102.00	Each	250.00	Rupees Two Hundred & Fifty Only
Total Rs.					451250.00

Draft Schedule of Quantity No. 4/4....for the year 2025-26 approved for amounting to Rs. 451250/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road Boul to Madanpur Jogipanga road (SH: C/o Wire crate R/wall in km 8/819 to 8/839) Under PDNA					Estimated Cost Rs	498634.00
					Earnest Money Rs	10000.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
		Figures	Words	Rs. P		
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	15.600	Per cubic metre	250.00 Rupees Two Hundred & Fifty Only	3900.00	
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	115.78	Per Cubic metre	2800.00 Rupees Two Thousand Eight Hundred Only	324184.00	
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.80	Per Cubic metre.	3800.00 Rupees Three Thousand Eight Hundred Only	29640.00	
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.78	Per cubic metre	4500.00 Rupees Four Thousand Five Hundred Only	39510.00	
5.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	19.50	Per cubic metre	5200.00 Rupees Five Thousand Two Hundred Only	101400.00	
Total Rs.						498634.00

4/15
Draft Schedule of Quantity No.4/15...for the year 2025-26 approved for amounting to Rs. 498634/-only

Surinder Singh
Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road Boul to Madanpur Jogipanga road (SH: C/o Wire crate R/wall in km 8/800 to 8/815) Under PDNA					Estimated Cost Rs	485923.00
					Earnest Money Rs	9800.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	15.600	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	3900.00
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	112.81	Per Cubic metre	2800.00	Rupees Two Thousand Eight Hundred Only	315868.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4.8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.60	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	28880.00
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.55	Per cubic metre	4500.00	Rupees Four Thousand Five Hundred Only	38475.00
5.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)) nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	19.00	Per cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	98800.00
Total Rs.					485923.00	

Draft Schedule of Quantity No. 416...for the year 2025-26 approved for amounting to Rs. 485923/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road to Village Gehra Kothhi upto Baba Garib Nath Temple Km 0/000 to 9/920 (SH: P/L Interlocking paver Block flooring in Km 8/400 to 8/490) Under Head PDNA				Estimated Cost Rs	488367.00
				Earnest Money Rs	9800.00
				Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT
				Figures	Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	33.250	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only 8313.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	49.88	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only 189544.00
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	285.00	Per Square metre	950.00	Rupees Nine Hundred & Fifty Only 270750.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.80	Per cubic metre	5200.00	Rupees Five Thousand Two Hundred Only 19760.00
Total Rs.				488367.00	


Draft Schedule of Quantity No. 4/7....for the year 2025-26 approved for amounting to Rs. 488367/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road to Village Gehra Kothhi upto Baba Garib Nath Temple Km 0/000 to 9/920 (SH: P/L Interlocking paver Block flooring in Km 8/500 to 8/542) Under Head PDNA					Estimated Cost Rs	215901.00
					Earnest Money Rs	4400.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
Figures	Words	Rs. P				
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	14.700	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	3675.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	22.05	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	83790.00
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	126.00	Per Square metre	950.00	Rupees Nine Hundred & Fifty Only	119700.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	1.68	Per cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	8736.00
Total Rs.		215901.00				

Draft Schedule of Quantity No. 418...for the year 2025-26 approved for amounting to Rs. 215901/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road to Village Lamlehri (SH: C/o Edge wall in Km 0/150 to 0/232) Under Head PDNA					Estimated Cost Rs	448228.00
					Earnest Money Rs	9000.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	60.680	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	15170.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	109.06	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	414428.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	81.00	Each	230.00	Rupees Two Hundred & Thirty Only	18630.00
Total Rs.					448228.00	

Draft Schedule of Quantity No. 448228...for the year 2025-26 approved for amounting to Rs. 448228/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road to Village Lamlehri (SH: C/o Edge wall in Km 0/232 to 0/279) Under Head PDNA					Estimated Cost Rs		256813.00
					Earnest Money Rs		5200.00
					Time Limit:		Two Month
Sr. No.	Description of work			Quantity	Unit	RATE	
						Figures	Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.			34.780	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			62.51	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.			46.00	Each	230.00	Rupees Two Hundred & Thirty Only
Total Rs.							256813.00

Draft Schedule of Quantity No. 420 for the year 2025-26 approved for amounting to Rs. 256813/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road to Village Lamlehri (SH: C/o Edge wall in Km 0/323 to 0/314) Under Head PDNA

Sr. No.	Description of work	Quantity	Unit	Estimated Cost Rs		491980.00
				Earnest Money Rs		9900.00
				Time Limit:		Two Month
				RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	66.600	Per cubic metre	250.00 Rupees Two Hundred & Fifty Only	16650.00	
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	119.70	Per Cubic metre.	3800.00 Rupees Three Thousand Eight Hundred Only	454860.00	
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	89.00	Each	230.00 Rupees Two Hundred & Thirty Only	20470.00	
Total Rs.						491980.00

Draft Schedule of Quantity No. 421.....for the year 2025-26 approved for amounting to Rs. 491980/-only


Executive Engineer
Bangana Division
HP.PWD. Banga

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baba Balak Rupi Mandir Lam (SH: P/L Interlocking paver block flooring in Km 0/310 to 0/387) Under Head PDNA					Estimated Cost Rs	499956.00
					Earnest Money Rs	10000.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	128.850	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	32213.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.10	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	30780.00
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	292.60	Per Square metre	1045.00	Rupees One Thousand &Fourty Five Only	305767.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	25.23	Per cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	131196.00
Total Rs.					499956.00	

Draft Schedule of Quantity No. 422...for the year 2025-26 approved for amounting to Rs. 499956/-only


Executive Engineer
Bangana Division
HP.PWD. Banga


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baba Balak Rupi Mandir Lam (SH: C/o B/wall with V-shape Drain in Km 0/170 to 0/217) Under Head PDNA					Estimated Cost Rs	499996.00
					Earnest Money Rs	
					Time Limit:	
Sr. No.	Description of work			Quantity	Unit	AMOUNT Rs. P
Figures	RATE Words					
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.			101.520	Per cubic metre	250.00 Rupees Two Hundred & Fifty Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			114.21	Per Cubic metre.	3800.00 Rupees Three Thousand Eight Hundred Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.			92.00	Each	230.00 Rupees Two Hundred & Thirty Only
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			4.23	Per cubic metre	4600.00 Rupees Four Thousand Six Hundred Only
Total Rs.						499996.00

Draft Schedule of Quantity No. 423 for the year 2025-26 approved for amounting to Rs. 499996/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Banga

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baba Balak Rupi Mandir Lam (SH: C/o B/wall with V-shape Drain in Km 0/080 to 0/170 R.H.S.) Under Head PDNA					Estimated Cost Rs	499400.00
					Earnest Money Rs	10000.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
		Figures	Words	Rs. P		
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	97.200	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	24300.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	109.35	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	415530.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	178.00	Each	230.00	Rupees Two Hundred & Thirty Only	40940.00
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.05	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	18630.00
Total Rs.					499400.00	

Draft Schedule of Quantity No. 424...for the year 2025-26 approved for amounting to Rs. 499400/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baba Balak Rupi Mandir Lam (SH: C/o B/wall with V-shape Drain in Km 0/080 to 0/170 L.H.S.) Under Head PDNA					Estimated Cost Rs	493888.00	
					Earnest Money Rs		
					Time Limit:		
Sr. No.	Description of work		Quantity	Unit	RATE		
					Figures	Words	
		AMOUNT		Rs. P			
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		96.120	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	24030.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..		108.14	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	410932.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.		176.00	Each	230.00	Rupees Two Hundred & Thirty Only	40480.00
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..		4.01	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	18446.00
Total Rs.					493888.00		

Draft Schedule of Quantity No. 493888.00 for the year 2025-26 approved for amounting to Rs. 493888/-only


Executive Engineer
Bangana Division
HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baba Balak Rupi Mandir Lam (SH: C/o B/wall with V-shape Drain in Km 0/217 to 0/247 Both side) Under Head PDNA					Estimated Cost Rs	318980.00
					Earnest Money Rs	6400.00
					Time Limit:	Two Month
					RATE	AMOUNT
					Figures	Words
					Rs. P	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	64.800	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	16200.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	72.90	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	277020.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	58.00	Each	230.00	Rupees Two Hundred & Thirty Only	13340.00
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.70	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	12420.00
Total Rs.					318980.00	

Draft Schedule of Quantity No. 426...for the year 2025-26 approved for amounting to Rs. 318980/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road Batuhi to Badoli via Dharwal Mohalla (SH: C/o R/wall in Km 0/759 to 0/768.20) Under Head PDNA					Estimated Cost Rs	379978.00
					Earnest Money Rs	7600.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	45.449	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	11362.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	95.32	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	362216.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	32.00	Each	200.00	Rupees Two Hundred Only	6400.00
Total Rs.					379978.00	


Draft Schedule of Quantity No. 417...for the year 2025-26 approved for amounting to Rs. 379978/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road Batuhi to Badoli via Dharwal Mohalla (SH: C/o R/wall in Km 0/750 to 0/759) Under Head PDNA					Estimated Cost Rs	379351.00
					Earnest Money Rs	7600.00
					Time Limit:	Two Month
					RATE	
Sr. No.	Description of work	Quantity	Unit	AMOUNT		Rs. P
				Figures	Words	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	44.460	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	11115.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana,toll tax,GST,labour cess or other taxes imposed by the Government.	95.22	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	361836.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	32.00	Each	200.00	Rupees Two Hundred Only	6400.00
Total Rs.				379351.00		

Draft Schedule of Quantity No. 428...for the year 2025-26 approved for amounting to Rs. 379351/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road Batuhi to Badoli via Dharwal Mohalla (SH: C/o R/wall in Km 0/768.20 to 0/777.40) Under Head PDNA					Estimated Cost Rs	379978.00
					Earnest Money Rs	7600.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit		RATE	AMOUNT
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	45.449	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	11362.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	95.32	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	362216.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	32.00	Each	200.00	Rupees Two Hundred Only	6400.00
Total Rs.						379978.00

Draft Schedule of Quantity No. 429...for the year 2025-26 approved for amounting to Rs. 379978/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Ambehra Dhamandri road (SH: P/L Interlocking Paver Block flooring in Km 2/980 to 3/050 & 3/400 to 3/440 both side) Under Head PDNA					Estimated Cost Rs	324243.00
					Earnest Money Rs	6500.00
					Time Limit:	Two Month
					RATE	
Sr. No.	Description of work			Quantity	Unit	AMOUNT Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.			47.700	Per cubic metre	250.00 Rupees Two Hundred & Fifty Only 11925.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..			26.50	Per Cubic metre.	3800.00 Rupees Three Thousand Eight Hundred Only 100700.00
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.			203.00	Per Square metre	950.00 Rupees Nine Hundred & Fifty Only 192850.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.			3.68	Per cubic metre	5100.00 Rupees Five Thousand One Hundred Only 18768.00
Total Rs.					324243.00	

Draft Schedule of Quantity No. 430..for the year 2025-26 approved for amounting to Rs. 324243/-only

Ans Ch

**Executive Engineer
Bangana Division
HP.PWD. Banga**

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Ambehra Dhamandri road (SH: P/L Interlocking Paver Block flooring in Km 2/800 to 2/980) Under Head PDNA				Estimated Cost Rs	307476.00	
				Earnest Money Rs	6200.00	
				Time Limit:	Two Month	
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	45.360	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	11340.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	25.20	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	95760.00
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge). including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	180.00	Per Square metre	950.00	Rupees Nine Hundred & Fifty Only	171000.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres) nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	5.76	Per cubic metre	5100.00	Rupees Five Thousand One Hundred Only	29376.00
Total Rs.				307476.00		

Draft Schedule of Quantity No. 491...for the year 2025-26 approved for amounting to Rs. 307476/-only

Avul Chell
Executive Engineer
Bangana Division
HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Ghandawal to Chalola road (SH: Gabion wall in Km 0/850 to 0/870) Under Head PDNA					Estimated Cost Rs	387120.00
					Earnest Money Rs	7800.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	43.200	Per cubic metre	250.00 Rupees Two Hundred & Fifty Only	10800.00	
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetres) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	117.60	Per Cubic metre	3200.00 Rupees Three Thousand Two Hundred Only	376320.00	
Total Rs.						387120.00


Draft Schedule of Quantity No. 472 for the year 2025-26 approved for amounting to Rs. 387120/-only


Executive Engineer
Bangana Division
HP.PWD. Bangalore


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Ghandawal to Chalola road (SH: Gabion wall in Km 0/880 to 0/898 & B/wall Both side) Under Head PDNA					Estimated Cost Rs	497841.00	
					Earnest Money Rs	10000.00	
					Time Limit:	Two Month	
Description of work		Quantity	Unit	RATE		AMOUNT	
Sr. No.			Figures	Words	Rs. P		
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		47.450	Per cubic metre	384.00	Rupees Three Hundred & Eighty Four Only	18221.00
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetrr) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		105.84	Per Cubic metre	3200.00	Rupees Three Thousand Two Hundred Only	338688.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..		35.64	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	135432.00
4.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.		22.00	Each	250.00	Rupees Two Hundred & Fifty Only	5500.00
Total Rs.		497841.00					

Draft Schedule of Quantity No. 497841.00 for the year 2025-26 approved for amounting to Rs. 497841/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road Ghandawal to Batuhi (SH: C/o Wing wall in Km 2/113 to 2/126.10) Under PDNA					Estimated Cost Rs	499814.00
					Earnest Money Rs	10000.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
Figures	Words	Rs. P				
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	57.640	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	14410.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	124.58	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	473404.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	48.00	Each	250.00	Rupees Two Hundred & Fifty Only	12000.00
Total Rs.					499814.00	

Draft Schedule of Quantity No. 499814...for the year 2025-26 approved for amounting to Rs. 499814/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road Ghandawal to Batuhi (SH: C/o Wing wall in Km 2/100 to 2/113) Under PDNA				Estimated Cost Rs	496094.00
				Earnest Money Rs	10000.00
				Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT
				Figures	Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	57.200	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water: complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	123.63	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	48.00	Each	250.00	Rupees Two Hundred & Fifty Only
Total Rs.				496094.00	

Draft Schedule of Quantity No. 496094.00 for the year 2025-26 approved for amounting to Rs. 496094/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road Batuhi to Badoli via Dharwal Mohalla (SH: C/o 900mm dia & 300mm dia Hume Pipe culvert with wing wall in Km 0/650) Under Head PDNA					Estimated Cost Rs	431570.00
					Earnest Money Rs	33200.00
					Time Limit:	Three Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	72.050	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	18013.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	67.30	Per Cubic metre.	3999.00	Rupees Three Thousand Nine Hundred & Ninety Nine Only	269133.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	21.94	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	100924.00
4.00	Providing and laying (to level or slope) 900mm dia (nine hundred millimetre) diametre reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and MORD 2014 technical specifications clause 1101 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.50	Per Running meter	4000.00	Rupees Four Thousand Only	30000.00
5.00	Providing and laying (to level or slope) 300mm dia (three hundred millimetre) diametre reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and MORD 2014 technical specifications clause 1101 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.50	Per Running meter	1800.00	Rupees One Thousand Eight Hundred Only	13500.00
Total Rs.						431570.00

Draft Schedule of Quantity No. 431570.00 for the year 2025-26 approved for amounting to Rs. 431570/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Ghandawal to Chalola road (SH: Gabion wall in Km 0/870 to 0/880 Guid Bund & B/wall Both side) Under Head PDNA					Estimated Cost Rs	424892.00
					Earnest Money Rs	8500.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	32.400	Per cubic metre	384.00	Rupees Three Hundred & Eighty Four Only	12442.00
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	73.80	Per Cubic metre	3200.00	Rupees Three Thousand Two Hundred Only	236160.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	44.55	Per Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	169290.00
4.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical :20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.00	Each	250.00	Rupees Two Hundred & Fifty Only	7000.00
Total Rs.						424892.00

Draft Schedule of Quantity No.437..for the year 2025-26 approved for amounting to Rs. 424892/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road Bhiambi to Jole Km 0/000 to 0/700 (SH: C/o C.C. Pavement from RD 0/000 to 0/120) Under Head PDNA					Estimated Cost Rs	485548.00
					Earnest Money Rs	9800.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	135.00	Per cubic metre	93.30	Rupees Ninety Three - Paise Thirty Only	12596.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	42.00	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	161280.00
3.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	59.40	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred & Fourty Seven Only	311672.00
Total Rs.					485548.00	

Draft Schedule of Quantity No. 498 for the year 2025-26 approved for amounting to Rs. 485548/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road Bhiambi to Jole Km 0/000 to 0/700 (SH: C/o C.C. Pavement from RD 00/121 to 0/241) Under Head PDNA					Estimated Cost Rs	491841.00
					Earnest Money Rs	9900.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	Rs. P
Figures	Words					
1.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	42.00	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	161280.00
2.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	63.00	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred & Fourty Seven Only	330561.00
Total Rs.		491841.00				

Draft Schedule of Quantity No. 491841...for the year 2025-26 approved for amounting to Rs. 491841/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road Bhiambi to Jole Km 0/000 to 0/700 (SH: C/o C.C. Pavement from RD 00/242 to 0/361) Under Head PDNA					Estimated Cost Rs	487769.00
					Earnest Money Rs	9800.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	41.65	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	159936.00
2.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	62.48	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred & Fourty Seven Only	327833.00
Total Rs.					487769.00	

*440
139*
Draft Schedule of Quantity No. for the year 2025-26 approved for amounting to Rs. 487769/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road Bhiambi to Jole Km 0/000 to 0/700 (SH: C/o C.C. Pavement from RD 0/362 to 0/468) Under Head PDNA

Sl. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P	
				Figures	Words		
				Estimated Cost Rs			
				Earnest Money Rs	Two Month		
1.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	37.10	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	142464.00	
2.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	55.65	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred & Fourty Seven Only	291996.00	
Total Rs.						434460.00	

Draft Schedule of Quantity No. 440 for the year 2025-26 approved for amounting to Rs. 434460/-only

Amol Chauhan
Executive Engineer
Bangana Division
HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Bangana to Deehar Via Chaplah road Km 0/000 to 6/000 (SH: C/o R/wall from RD 2/110 to 2/130) Under Head PDNA				Estimated Cost Rs	352387.00	
				Earnest Money Rs	7100.00	
				Time Limit:	Two Month	
Sr. No.		Description of work	Quantity	Unit	RATE	
Figures	Words				AMOUNT	
					Rs. P	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		34.760	Per cubic metre	250.00 Rupees Two Hundred & Fifty Only	8690.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..		83.47	Per Cubic metre.	3840.00 Rupees Three Thousand Eight Hundred & Forty Only	320525.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.		38.00	Each	246.00 Rupees Two Hundred & Forty Six Only	9348.00
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		23.04	Per Cubic metre	600.00 Rupees Eight Hundred Only	13824.00
Total Rs.					352387.00	

Draft Schedule of Quantity No. 442...for the year 2025-26 approved for amounting to Rs. 352387/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Bangana to Deehar Via Chaplah road Km 0/000 to 6/000 (SH: C/o R/wall from RD 2/131 to 2/146) Under Head PDNA					Estimated Cost Rs	264650.00
					Earnest Money Rs	5300.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	26.070	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	6518.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	62.60	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	240384.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	30.00	Each	246.00	Rupees Two Hundred & Fourty Six Only	7380.00
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	17.28	Per Cubic metre	600.00	Rupees Eight Hundred Only	10368.00
Total Rs.					264650.00	

Draft Schedule of Quantity No. 443..for the year 2025-26 approved for amounting to Rs. 264650/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o C.C. Pavement from RD 17/700 to 17/784) Under Head PDNA				Estimated Cost Rs		478041.00
				Earnest Money Rs		9600.00
				Time Limit:		Two Month
Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	94.50	Per cubic metre	93.30	Rupees Ninety Three Paise Thirty Only	8817.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	44.10	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	169344.00
3.00	Providing and laying mechanically mixed and vibrated concrete for reinforced cement concrete of Grade M-30 (M-thirty) design mix with minimum cement contents @430 kg/cum (four hundred thirty kilogramme per cubic metre) using OPC - 43 Grade (ordinary protland cement - fourty three grade) and super plasticizer admixture in Sub Structure complete as per drawing and MORT&H technical specifications, clause 1500,1700,2100 and 2200 using batching plant, transit mixture and concrete pump as per direction of the Engineer-in-charge within all leads and lifts and other incidentals. The rates includes sale tax octroi, royalty, malkhana, toll tax, G.S.T, labour cess or other taxes imposed by the Government.	44.10	Per Cubic metre	6800.00	Rupees Six Thousand Eight Hundred Only	299880.00
Total Rs.				478041.00		

Draft Schedule of Quantity No. 446 for the year 2025-26 approved for amounting to Rs. 478041/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangan

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o C.C. Pavement from RD 17/785 to 17/801, U-shape drain 150mtr & R/wall from Rd 17/735 to 17/741) Under Head PDNA				Estimated Cost Rs		473235.00
				Earnest Money Rs		9500.00
				Time Limit:		Two Month
Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	18.00	Per cubic metre	93.30	Rupees Ninety Three Paise Thirty Only	1679.00
2.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	114.12	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	28530.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.40	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	32256.00
4.00	Providing and laying mechanically mixed and vibrated concrete for reinforced cement concrete of Grade M-30 (M-thirty) design mix with minimum cement contents @430 kg/cum (four hundred thirty kilogramme per cubic metre) using OPC - 43 Grade (ordinary protland cement - forty three grade) and super plasticizer admixtiure in Sub Structure complete as per drawing and MORT&H technical specifications, clause 1500,1700,2100 and 2200 using batching plant, transit mixture and concrete pump as per direction of the Engineer-in-charge within all leads and lifts and other incidentials. The rates includes sale tax octroi, royalty, malkhana, toll tax, G.S.T, labour cess or other taxes imposed by the Government.	8.40	Per Cubic metre	6800.00	Rupees Six Thousand Eight Hundred Only	57120.00

Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
5.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material within all leads and lifts and other incidentals .The rate includes octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	49.50	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	227700.00
6.00	Providing and laying cement concrete 1:5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	32.70	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only	118570.00
7.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	30.00	Each	246.00	Rupees Two Hundred & Fourty Six Only	7380.00
Total Rs.						473235.00

445
444
Draft Schedule of Quantity No. for the year 2025-26 approved for amounting to Rs. 473235/-only

Amrit
Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o R/wall from Rd 17/742 to 17/765) Under Head PDNA					Estimated Cost Rs	488950.00
					Earnest Money Rs	
					Time Limit:	
Sr. No.	Description of work		Quantity	Unit	RATE	
					Figures	Words
					Rs.	P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	92.460	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	23115.00
2.00	Providing and laying cement concrete 1:5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	125.35	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only	454519.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	46.00	Each	246.00	Rupees Two Hundred & Fourty Six Only	11316.00
Total Rs.		488950.00				

Draft Schedule of Quantity No. 446.....for the year 2025-26 approved for amounting to Rs. 488950/-only


Executive Engineer
Bangana Division
HP.PWD. Banga


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o R/wall from Rd 17/766 to 17/789) Under Head PDNA					Estimated Cost Rs	488950.00
					Earnest Money Rs	9800.00
					Time Limit:	Two Month
Sr. No.	Description of work			Quantity	Unit	RATE
				Figures	Words	AMOUNT Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	92.460	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	23115.00
2.00	Providing and laying cement concrete 1:5:10 (one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall/breast wall as per drawing and HP PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	125.35	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only	454519.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameter, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	46.00	Each	246.00	Rupees Two Hundred & Fourty Six Only	11316.00
Total Rs.		488950.00				


447
Draft Schedule of Quantity No. 447...for the year 2025-26 approved for amounting to Rs. 488950/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o R/wall from Rd 17/790 to 17/798 & B/wall from RD 17/735 to 17/758) Under Head PDNA					Estimated Cost Rs		483324.00
					Earnest Money Rs		9700.00
					Time Limit:		Two Month
Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT	
				Figures	Words	Rs. P	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	32.160	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	8040.00	
2.00	Providing and laying cement concrete 1.5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	125.08	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only	453540.00	
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	48.00	Each	246.00	Rupees Two Hundred & Fourty Six Only	11808.00	
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	16.56	Per Cubic metre	600.00	Rupees Eight Hundred Only	9936.00	
Total Rs.				483324.00			

Draft Schedule of Quantity No. 483324 for the year 2025-26 approved for amounting to Rs. 483324/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o B/wall from RD 17/758 to 17/785) Under Head PDNA					Estimated Cost Rs	394009.00
					Earnest Money Rs	7900.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	30.810	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	7703.00
2.00	Providing and laying cement concrete 1:5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	103.01	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only	373514.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	52.00	Each	246.00	Rupees Two Hundred & Fourty Six Only	12792.00
Total Rs.					394009.00	

449
449
Draft Schedule of Quantity No. for the year 2025-26 approved for amounting to Rs. 394009/-only


Executive Engineer
Bangana Division
HP.PWD. Banga


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Baruhi Dumkhar road Km 16/400 to 27/270 (SH: C/o B/wall from RD 17/790 to 17/817) Under Head PDNA					Estimated Cost Rs	393517.00
					Earnest Money Rs	
					Time Limit:	
Sr. No.	Description of work		Quantity	Unit	RATE	
					Figures	Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	30.810	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	7703.00
2.00	Providing and laying cement concrete 1:5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	103.01	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only	373514.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	50.00	Each	246.00	Rupees Two Hundred & Fourty Six Only	12300.00
Total Rs.						393517.00

450
449
Draft Schedule of Quantity No. for the year 2025-26 approved for amounting to Rs. 393517/-only


Asok Chauhan
Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on L/R to Village Nalwari Km 0/000 to 1/000 (SH: C/o C/o C.C. Pavement from RD 0/135 to 0/185, B/wall from RD 0/180 to 0/192 & U-shape drain 50mtr.) Under Head PDNA					Estimated Cost Rs	440550.00
					Earnest Money Rs	8900.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT
				Figures	Words	Rs. P
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	52.50	Per cubic metre	93.30	Rupees Ninety Three Paise Thirty Only	4898.00
2.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	38.35	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	9588.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	43.90	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Forty Only	168576.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	26.25	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred & Forty Seven Only	137734.00

Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
5.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	24.75	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	113850.00
6.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	24.00	Each	246.00	Rupees Two Hundred & Forty Six Only	5904.00
Total Rs.		440550.00				

Draft Schedule of Quantity No. 450 for the year 2025-26 approved for amounting to Rs. 440550/-only


Executive Engineer
Bangana Division
HP.PWD. Bangalore

DRAFT SCHEUDLE OF QUANTITY

Name of work:- Restoration of Rain Damages on L/R to Village Nalwari Km 0/000 to 1/000 (SH: C/o C/o C.C. Pavement from RD 0/186 to 0/236, B/wall from RD 0/192 to 0/203 &U-shape drain 50mtr.) Under Head PDNA					Estimated Cost Rs	444877.00
					Earnest Money Rs	8900.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit		RATE	AMOUNT
					Figures	Words
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	52.50	Per cubic metre	93.30	Rupees Ninety Three Paise Thirty Only	4898.00
2.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	37.66	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	9415.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	45.20	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	173568.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	26.25	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred & Fourty Seven Only	137734.00

Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
5.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water.dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	24.75	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	113850.00
6.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	22.00	Each	246.00	Rupees Two Hundred & Fourty Six Only	5412.00
Total Rs.		444877.00				

Draft Schedule of Quantity No. 452 for the year 2025-26 approved for amounting to Rs. 444877/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on L/R to Village Nichli Kharol Km 0/000 to 1/000 (SH: C/o C/o C.C. Pavement from RD 0/300 to 0/373 & U-shape drain 50mtr.) Under Head PDNA					Estimated Cost Rs	393231.00
					Earnest Money Rs	7900.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government.	76.65	Per cubic metre	93.30	Rupees Ninety Three - Paise Thirty Only	7151.00
2.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	43.80	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	10950.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	25.55	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	98112.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	38.33	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred & Fourty Seven Only	201118.00
5.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	16.50	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	75900.00
Total Rs.		393231.00				

Draft Schedule of Quantity No. 482 for the year 2025-26 approved for amounting to Rs. 393231/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on L/R to Village Nichli Kharol Km 0/000 to 1/000 (SH: C/o C/o C.C. Pavement from RD 0/374 to 0/446 & U-shape drain 50mtr.) Under Head PDNA				Estimated Cost Rs		385656.00
				Earnest Money Rs		7800.00
				Time Limit:		Two Month
Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT
				Figures	Words	Rs. P
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	76.65	Per cubic metre	93.30	Rupees Ninety Three - Paise Thirty Only	7151.00
2.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	30.00	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	7500.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	25.20	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Forty Only	96768.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	37.80	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred & Forty Seven Only	198337.00
5.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	16.50	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	75900.00
Total Rs.				454		
385656.00						

454
Draft Schedule of Quantity No. for the year 2025-26 approved for amounting to Rs. 385656/-only

Awf Chaw
Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on L/R to Village Dhatol Km 0/000 to 1/240 (SH: C/o C/o C.C. Pavement from RD 0/800 to 0/875 & U-shape drain 75mtr.) Under Head PDNA					Estimated Cost Rs	469588.00
					Earnest Money Rs	9400.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit		RATE	AMOUNT
				Figures	Words	Rs. P
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	78.75	Per cubic metre	93.30	Rupees Ninety Three - Paise Thirty Only	7347.00
2.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	49.20	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	12300.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	28.70	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	110208.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)) nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	43.05	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred & Fourty Seven Only	225883.00
5.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	24.75	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	113850.00
Total Rs.						469588.00

Draft Schedule of Quantity No. 455 for the year 2025-26 approved for amounting to Rs. 469588/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on L/R to Village Dhatol Km 0/000 to 1/240 (SH: C/o C/o C.C. Pavement from RD 0/876 to 0/951 & U-shape drain 82mtr.) Under Head PDNA				Estimated Cost Rs		451550.00
				Earnest Money Rs		9100.00
				Time Limit:		Two Month
Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	78.75	Per cubic metre	93.30	Rupees Ninety Three - Paise Thirty Only	7347.00
2.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	49.20	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	12300.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	26.25	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	100800.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	39.38	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred & Fourty Seven Only	206627.00
5.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	27.06	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	124476.00
Total Rs.		451550.00				

Draft Schedule of Quantity No. 458 for the year 2025-26 approved for amounting to Rs. 451550/-only


Executive Engineer
Bangana Division
HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on L/R to Village Dhatol Km 0/000 to 1/240 (SH: C/o C/o C.C. Pavement from RD 0/952 to 1/002 & U-shape drain 82mtr.) Under Head PDNA				Estimated Cost Rs		346608.00
				Earnest Money Rs		7000.00
				Time Limit:		Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government.	52.50	Per cubic metre	93.30	Rupees Ninety Three - Paise Thirty Only	4898.00
2.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	49.20	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	12300.00
3.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	17.50	Per Cubic metre.	3840.00	Rupees Three Thousand Eight Hundred & Fourty Only	67200.00
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	26.25	Per cubic metre	5247.00	Rupees Five Thousand Two Hundred & Fourty Seven Only	137734.00
5.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	27.06	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	124476.00
Total Rs.				457 456	346608.00	

Draft Schedule of Quantity No. for the year 2025-26 approved for amounting to Rs. 346608/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Hatli Talpi road Km 0/000 to 7/640 (SH: C/o U-shape Drain from RD 0/800 to 0/855 & 0/900 to 0/930) Under Head PDNA					Estimated Cost Rs	282880.00
					Earnest Money Rs	5700.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit		RATE	AMOUNT
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	68.00	Per cubic metre	250.00 Rupees Two Hundred & Fifty Only	17000.00	
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	57.80	Per cubic metre	4600.00 Rupees Four Thousand Six Hundred Only	265880.00	
Total Rs.						282880.00

Draft Schedule of Quantity No. 458 for the year 2025-26 approved for amounting to Rs. 346608/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangalore

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Hatli Talpi road Km 0/000 to 7/640 (SH: C/o B/wall from RD 1/382 to 1/402 & U-shape Drain from RD 0/600 to 0/660) Under Head PDNA				Estimated Cost Rs		396729.00
				Earnest Money Rs		8000.00
				Time Limit:		Two Month
Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	68.88	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	17220.00
2.00	Providing and laying cement concrete 1:5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	50.19	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only	181989.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	40.00	Each	246.00	Rupees Two Hundred & Forty Six Only	9840.00
4.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	40.80	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	187680.00
Total Rs.				396729.00		


459
UFCB
Draft Schedule of Quantity No.for the year 2025-26 approved for amounting to Rs. 396729/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Hatli Talpi road Km 0/000 to 7/640 (SH: C/o U-shape Drain from RD 0/661 to 0/798) Under Head PDNA				Estimated Cost Rs		455936.00
				Earnest Money Rs		9200.00
				Time Limit:		Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	109.60	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	27400.00
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	93.16	Per cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	428536.00
Total Rs.				455936.00		

Draft Schedule of Quantity No. 455936 for the year 2025-26 approved for amounting to Rs. 455936/-only


Executive Engineer
Bangana Division
HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Piploo Rachhoh road Km 0/000 to 21/770 (SH: C/o R/wall from RD 12/534 to 12/553) Under Head PDNA				Estimated Cost Rs	397955.00
				Earnest Money Rs	8000.00
				Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	
				Figures	Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	35.060	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only
2.00	Providing and laying cement concrete 1:5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	100.84	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	54.00	Each	246.00	Rupees Two Hundred & Fourty Six Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	17.10	Per Cubic metre	600.00	Rupees Eight Hundred Only
Total Rs.				397955.00	

Draft Schedule of Quantity No. 461 for the year 2025-26 approved for amounting to Rs. 397955/-only


Executive Engineer
Bangana Division
HP.PWD. Bangalore


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Piploo Rachhoh road Km 0/000 to 21/770 (SH: C/o R/wall from RD 4/421 to 4/431 & 12/520 to 12/533) Under Head PDNA					Estimated Cost Rs	481892.00
					Earnest Money Rs	9700.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	42.440	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	10610.00
2.00	Providing and laying cement concrete 1:5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	122.07	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only	442626.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	66.00	Each	246.00	Rupees Two Hundred & Fourty Six Only	16236.00
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	20.70	Per Cubic metre	600.00	Rupees Eight Hundred Only	12420.00
Total Rs.					481892.00	


Draft Schedule of Quantity No. 462, for the year 2025-26 approved for amounting to Rs. 481892/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Piploo Rachhoh road Km 0/000 to 21/770 (SH: C/o R/wall from RD 4/400 to 4/420) Under Head PDNA				Estimated Cost Rs	419685.00
				Earnest Money Rs	8400.00
				Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT
				Figures	Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	36.900	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only
2.00	Providing and laying cement concrete 1:5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	106.15	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	60.00	Each	246.00	Rupees Two Hundred & Fourty Six Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	18.00	Per Cubic metre	600.00	Rupees Eight Hundred Only
Total Rs.				419685.00	

Draft Schedule of Quantity No. 462 for the year 2025-26 approved for amounting to Rs. 419685/-only


Executive Engineer
Bangana Division
HP.PWD. Banga

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Hathi Talpi road Km 0/000 to 7/640 (SH: C/o B/wall from RD 1/280 to 1/330) Under Head PDNA					Estimated Cost Rs	492112.00
					Earnest Money Rs	9900.00
					Time Limit:	Two Month
Sr. No.	Description of work	Quantity	Unit	RATE	AMOUNT	
				Figures	Words	Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	52.200	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	13050.00
2.00	Providing and laying cement concrete 1.5.10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	125.47	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only	454954.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	98.00	Each	246.00	Rupees Two Hundred & Fourty Six Only	24108.00
Total Rs.						492112.00

464
463
Draft Schedule of Quantity No. 463 for the year 2025-26 approved for amounting to Rs. 492112/-only


Executive Engineer
Bangana Division
HP.PWD. Bangalore


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Hatti Talpi road Km 0/000 to 7/640 (SH: C/o B/wall from RD 1/331 to 1/381) Under Head PDNA					Estimated Cost Rs	492604.00	
					Earnest Money Rs		
					Time Limit:		
Sr. No.	Description of work		Quantity	Unit	RATE		
					Figures	Words	
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		52.200	Per cubic metre	250.00	Rupees Two Hundred & Fifty Only	13050.00
2.00	Providing and laying cement concrete 1:5:10(one cement :five sand: ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		125.47	Per Cubic metre	3626.00	Rupees Three Thousand Six Hundred & Twenty Six Only	454954.00
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.		100.00	Each	246.00	Rupees Two Hundred & Fourty Six Only	24600.00
Total Rs.					492604.00		

Draft Schedule of Quantity No. 465 for the year 2025-26 approved for amounting to Rs. 492604/-only


 Executive Engineer
 Bangana Division
 HP.PWD. Bangana