

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 29-11-2025 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 29-11-2025 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 01-12-2025 at 10.30 AM.
4. Date of opening of Tender:- 01-12-2025 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class o Contract or
1	Restoration of Awah Devi Bagwara Gharan Dera Parol road km 0/00 to 9/450. (SH:- C/O wire crate at RD 5/310 to 5/356) (PDNA)	4,99,852/-	10,000/-	Two Months	Rs. 350/-	Class-D
2	R/M of Awalidevi Bhamnoh road (SH:- R/M of shoulder & Unlined Drain at various RDs & Removal of slips)	99,143/-	2,000/-	Two Months	Rs. 350/-	Class-D
3	Restoration of link road Bhareri Badehar via Jol Kota road km 0/00 to 5/200 (SH:- Repair of pot holes) (PDNA)	4,97,886/-	10,000	Two Months	Rs. 350/-	Class-D
4	Restoration of link road Kalahu More to Bhareri via Bhukkar Sai Da Ghat Namalakh Jaroh road km 0/00 to 7/750. (Repair of pot holes) (PDNA)	4,98,177/-	10,000/-	Two Months	Rs. 350/-	Class-D
5	R/R damages on link road Bajroh School to Baroh Km 0/00 to 2/00 (SH:- C/O Crate wire wall at RD 1/390 to 1/435)(R.H.S (PDNA)	499561/-	10000/-	Two Months	Rs. 350/-	Class-D
6	C/O link road Chhatral to Lower Dadu km 0/00 to 1/630 (SH:- ROFD Bed cutting 5/7 mtr. Wide road at RD 1/505 to 1/565)	99028/-	2000/-	Two Months	Rs. 350/-	Class-D
7	R/R damages on Patta Awahdevi road in Km. 0/00 to 5/00 (ii) R/R damages on Kharwar Mehal road in Km 0/00 to 3/00 (SH:- Repair of pot hole at various RDs)(PDNA)	4,99,649/-	10,000/-	Two Months	Rs. 350/-	Class-D
8	Restoration of Awah Devi Bagwara Gharan Dera Parol road km 0/00 to 9/450 (SH:-C/O R/wall at RD 6/884 to 6/900) (PDNA)	4,99,995/-	10,000/-	Two Months	Rs. 350/-	Class-D
9	Restoration of Awah Devi Bagwara Gharan DeraParol road km 0/00 to 9/450 (SH:-C/O wire crate at RD 4/525 to 4/571) (PDNA)	4,99,852/-	10,000/-	Two Months	Rs. 350/-	Class-D

10	R/R Damages on Una Aghar Mandi road in km 67/00 to 91/00 (SH:- Repair of pot hole at various RDs) PDNA	4,99,649/-	10,000/-	Two Months	Rs. 350/-	Class-D
11	C/O Ambulance road Bhiar Dungri Tooh (MMGSY) (SH:- Formation cutting at various RDs)	99,652/-	2,000/-	Two Months	Rs. 350/-	Class-D
12	C/O Ambulance road Bhiar Dungri Tooh (MMGSY) (SH:-Formation cutting at various RDs)	99,652/-	2,000/-	Two Months	Rs. 350/-	Class-D
13	Restoration on link road Amroh Chandruhi km 0/00 to 4/225 (SH:- P/L interlocking Paver Block at RD 0/800 to 0/865 and V-shape drain) (PDNA)	4,96,691/-	10,000/-	Two Months	Rs. 350/-	Class-D
14	Restoration on link road Amroh Chandruhi km.0/00 to 4/225 (SH:- P/L Interlocking Paver Block at RD 0/920 to 0/985 and V-shape drain) (PDNA)	4,98,576/-	10,000/-	Two Months	Rs. 350/-	Class-D
15	Restoration of Awahdevi Bagwara Gharan Dera Parol road km 0/00 to 9/450 (SH:-C/O Causeway at RD 2/400 to 2/419) (PDNA)	4,99,063/-	10000/-	Two Months	Rs. 350/-	Class-D
16	R/R Una Aghar Mandi road km 67/00 to 79/00 (SH:- C/O R/wall at RD 76/500 to 76/515) (PDNA)	2,15,532/-	5,000/-	Two Months	Rs. 350/-	Class-D
17	C/O Shed at village Lag-Manwin near Ayurvedic Hospital in GP Manwin Bhoranj) (VKVY/2024/621)	3,82,093/-	8,000/-	Two Months	Rs. 350/-	Class-D
18	Restoration of link road kalahu More to Bhareri via Gudwin Bhukkar Beri Brahmina Sai Da Ghat Nam lakh Jaroh road km 0/00 to 7/720 (SH:- C/O R/wall at RD 7/220 to 7/242) (PDNA)	4,93,380/-	10,000/-	Two Months	Rs. 350/-	Class-D
19	A/R & M/O Kangu Galu to Kalahu More at RD 0/00 to 6/756 (SH:-Providing and installation of Crash Barrier at RD 1/405 to 1/433) (PDNA)	4,86,400/-	10,000/-	Two Months	Rs. 350/-	Class-D
20	Restoration on Luder Sulgwan road km. 0/00 to 5/00 (SH:- C/O R/wall at RD, 4/015 to 4/026) (PDNA)	4,99,260/-	10,000/-	Two Months	Rs. 350/-	Class-D
21	Restoration/Repair on Mundkhar to Manoh via Neli Jamli road 0/00 to 4/225. (SH:- C/O R/wall at RD 3/150 to 3/168) (PDNA)	3,43,210/-	7,000/-	Two Months	Rs. 350/-	Class-D
22	Restoration of Awah Devi Bagwara Gharan Dera Parol road km 0/00 to 9/450 (SH:-C/O wire crate at RD 7/210 to 7/241) (PDNA)	4,99,102/-	10000/-	Two Months	Rs. 350/-	Class-D
23	R/M of Samirpur to Bagwara via Samlehra km 0/00 to 2/200 (SH:-R/M of shoulder & Unlined Drain at various RDs & Removal of slips)	99,714/-	2,000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory. The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

- (i) No Violation of social distancing.
- (ii) Mandatorily wearing of face cover by everyone.
- (iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj
For and on behalf of Governor of HP.

No:-PW/BHD/TA/NIT/2025- 12735-75

Dated:- 22-11-2025

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP:PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj, Various Contractors/ Firms.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Awah Devi Bagwara Gharan Dera Parol road km. 0/00 to 9/450. (SH:- C/O Wire
Crate at RD.5/310 to 5/356) (PDNA)

Estimated Cost
Earnest Money

Rs 4,39,852/-
Rs. 10000/-

Sr No	Description of Items	Quantity	Unit	Rate	Time	
					Rate In words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	67.62	Per Cubic Meter			
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeters) dia GI with conforming to IS:280 and IS: 4826 in 100mmx100mm(one hundred millimeters into one hundred millimeters) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulder weightning not less than 25kg. (twenty five kilogramme) each as per drawing and technical specifications clause 1301 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	143.75	Per cubic metre			
3	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8. and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.50	Per Cubic Meter			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
V.P.W.D Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Awahdevi Bhamnoh road (SH:- R/M of Shoulder & Unlined Drain at various RDS. & Removal of Slips).

Estimated Cost

Rs. 99143/-

Earnest Money

Rs. 2000/-

Time

2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	977.25	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	600.00	Per Running Mtr.			
	Total					

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhamnoh Division
H.P. PWD Bhamnoh

SCHEDULE OF QUANTITY

NAME OF WORK:-Restoration of link road bhareil badhar via lol Kota road km 0/00 to 5/200.(SH:- Repair of pot holes) (PDNA)

Estimated Cost Rs 4,97,886/-
Earnost Money 10000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Ratos In Words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coal, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-30 bitumen specification clause 1904-2,503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1251.15	Per square metre			
2	Providing and laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone scseeing/binding material to fill up the Interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge Including entire carriage of material within all leads and lifts and other incidentals,including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.64	Per cubic meter			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of link road Kalahu more to Bhareri via Bhukkar sai da qhat namia kh Jaroh road km 0/00 to 7/750, (Sh:- Repair of pot holes) (PDNA)

Estimated Cost Rs 4,98,177/-
Earnest Money 10000/-

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-30 bitumen specification clause 1904-2.503 and 508-1 as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1265.95	Per square metre			
2	Providing and laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone screening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals, including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.45	Per cubic meter			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bharan] Division
(H/PWD Bharan]

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damages on Link road Bairoh School to Baroh km. 0/00 to 2/00, (SH:- C/O Crate wire wall at 1/390 to 1/435) R.H. S (PDNA)

Estimated Cost
Earnest Money

Rs. 4,99,561/-
Rs. 10000/-

Sr No	Description of Items	Time		Rate	Rates in Words	2 Months Amount
		Quantity	Unit			
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	70.31	Per Cubic Meter			
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeters) dia GI with conforming to IS:280 and IS: 4826 in 100mmx100mm(one hundred millimeters into one hundred millimeters) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulder weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specifications clause 1301 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	140.63	Per cubic Meter			
3	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carmge of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	24.57	Per cubic metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhorani Division
R.R. PWD Bhorani

SCHEDULE OF QUANTITY

Name of Work:-C/O Link road Chhatrail to lower Dadu Km. 0/00 to 1/630 (SH:- ROFD Bed cutting 5/7 mtr. wide road at RD. 1/505 to 1/565).

Estimated cost:- 99,028/-
Earnest Money:- 2000/-
Time:- 2 months

Sl. No.	Description of Item	Qty.	Rate	Rate in words	Unit	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage, disposal of unsuitable cut material in specified manner, trimming/finishing of unevenness, blinding and finishing of the road to specified dimensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made from the contractor and recovery of 19.04 cubic meter useful stones shall be made @ 300/- per cubic meter on pro-rata basis in each running bill. Any loss to the public and private property during the course of excavation shall be restored by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lifts as per the direction of Engineer in Charge.	380.875	260.00			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damages on Patla Awahdevi road In Km 0/00to 5/00.(II) R/R Damages on Kharwar Mehal road In Km 0/00to 3/00. (SH:- Repair of Pot Hole at various RDS.) PDNA

Estimated Cost
Earnest Money
Time
Rs 4,99,649-
Rs. 10000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 bitumen specification clause 1904-2.503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1308.54	Per square metre			
2	Providing Laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming dense stone screening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.70	Per cubic meter			
	Total					

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.O.PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Awah Devi Bagwara Gharan Dera Parol road km. 0/00 to 9/450 (SH:- C/O R/Wall at RD 6/884 to 6/900) (PONA)

Estimated Cost
Earnest Money
Rs 4,99,995/-
Rs. 10,000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	47.36	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand:ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	106.07	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plas/finolex/ veculus pipe having pressure 4kg per centimeter square. (four kilogram per centimeter square) extending through the full width of the structures with slopes of (V): .20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	24.80	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Sudhakar Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Awah Devi Bagwara Gharan Dera Parol road km. 0/00 to 9/450.(SH:- C/O Wire
Crate at RD.4/525 to 4/571) (PDNA)

Estimated Cost Rs 4,39,852/-
Earnest Money Rs. 10000/-

Sr No	Description of Items	Quantity	Unit	Rate	Time	
					Rate in words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire cartilage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	70.84	Per Cubic Meter			
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeters) dia GI with conforming to IS:280 and IS: 4826 in 100mmx100mm (one hundred millimeters into one hundred millimeters) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulder weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specifications clause 1301 as per the direction of the Engineer-in-charge including entire cartilage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	143.75	Per cubic metre			
3	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire cartilage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire cartilage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.50	Per Cubic Meter			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H/PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damages on Una Aghar Mandi road In Km 67/00to 91/00(SH:- Repair of Pot Hole at various RDs.) PDNA

Estimated Cost Rs 4,99,649-
Earnest Money Rs. 10000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 bitumen specification clause 1904-2.503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1308.54	Per square metre			
2	Providing Laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone screening/binding material to fill up the interstices of coarse aggregate watering and compacting to the required density grading-II as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.70	Per cubic meter			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhorani Division
HQPWD Bhorani

DRAFT SCHEDULE OF QUANTITY

Name of Work:-C/O Ambulance road Bhair Dungri Tooh (MMGSY) (SH:- Formation Cutting at Varigard)

Estimated cost:- 99,652/-
Earnest Money:- 2000/-
Time:- 2 months

Sr. No.	Description of Item	Qty.	Rate	Rate in words	Unit	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage. disposal of unsuitable cut material in specified manner, firming/filling of unevenness blindage and finishing of the road to specified dimensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made from the contractor and recovery of 21.20 cubic meter useful stones shall be made @ 300/-per cubic meter on pro rata basis in each running bill. Any loss to the public, and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified dimension in all leads and lifts as per the direction of Engineer in Charge.	424.05				
	Total					

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhorrani Division
H.P.W.D Bhorrani

SCHEDULE OF QUANTITY

Name of Work:-C/O Ambulance road Bhair Dungri Tooh (MMGSY) (SH:- Formation Cutting at Various Rds)

Estimated cost:- 99,652/-
Earnest Money:- 2000/-

Time:- 2 months

Sr. No.	Description of Item	Qty.	Rate	Rate in words	Unit	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion (damage to hill side, Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage. disposal of unsuitable cut material in specified manner, trimming/filling of unevenness bludge and finishing of the road to specified dimensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made from the contractor and recovery of 21.20 cubic meter useful stones shall be made @ 300/- per cubic meter on pro rata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lifts as per the direction of Engineer in Charge.	424.05	235.00			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer

Bhargan] Division

(HWPWD Bhargan]

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration on link road amroh Chandruhi Km. 0/00 to 4/225 (SH:- P/L Interlocking Paver Block at Rd.0/800 to 0/865 and V-Shape drain).
(PDNA)

Estimated Cost
Earnest Money
Time

Rs 4,96,691-
Rs.10000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	19.50	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	30.23	Per cubic meter			
4	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire cartage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.90	Per Cubic Meter			
5	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire cartage of materials within all leads and lifts including entire cartage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government	260.00	Per square meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HRA PWD Bhoranj
2

SCHEDULE OF QUANTITY

NAMU OR WORK: Restoration on link road around Channihalli Klu, 000 to 41226 (S.I. - P/L Interlocking Paver Block at Rd, 00020 to 00060 and V-Slope drain). (PDNA)

Estimated Cost
Estimate Money
Rs. 4,00,670/-
2 month

Sl No	Description of Items	Quantity	Unit	Rate	Rate in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, lateral walls, culverts, drains and parapets etc. etc. in all type of classification of soil. Compacting of ordinary soil, ordinary rock, hard rock, chiselling/breaking out or rock (where blasting is prohibited) as per drawings and construction of sloping and bracing removal of masonry and other debris materials and disposal of materials upto any lands and lifts including drilling of holes and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including allowing an allowance for pumping and bulking out water (waterloo and sub soil water) upto any depth and any quantity of water including cleaning of ditch which arise out during lowering as per the direction of the Engineer-in-Charge including entire carriage of material within all lands and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.00	Per Cubic Meter			
2	Providing concrete for plain reinforced concrete in P. C. C. Grade M-10 (M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm (twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-Charge including entire carriage of material within all lands and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	30.23	Per cubic meter			
3	Providing and laying mechanically mixed cement concrete (M-20) (M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm (twenty millimeters) for plain reinforcement concrete in open foundation complete including cast of form work, steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all lands and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.90	Per Cubic Meter			
4	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50 (M-fifty) grade including border or curb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement : four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm (eighty millimeters) thick interlocking blocks (ISI approved), and as per direction of the Engineer-in-Charge including entire carriage of materials within all lands and lifts including entire carriage of material within all lands and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	260.00	Per square meter			
Total						
Terms and Condition:-						

1 Work shall be executed as per PWD specification.

Executive Engineer
Bhargavi Division
H.P.W.D. Bhargavi

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Awah Devi Bagwara Charan Dora Parol road km. 0/00 to 9/450 (SH:- C/O Causeways at RD. 2/400 to 2/419) (PDNA)

Estimated Cost
Earnest Money
Time

Rs 4.99,063/-
Rs.10000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	134.62	Per Cubic Meter			
2	Providing and laying cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregates 40mm nominal size) and curing complete including cost of form work, in foundation and plinth as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.98	Per cubic meter			
3	Providing and laying mechanically mixed cement concrete (M-20) (M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain/reinforcement concrete in open foundation complete including cost of form work, steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	49.58	Per Cubic Meter			
4	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm to wet mix macadam (W/M/M) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical paver finisher in sub base/base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, completed as per specification and directions of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.	15.58	Per Cubic Meter			
5	Providing concrete for plain reinforced concrete in P.C.C grade M-10(M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	11.68	Per cubic meter			
6	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement. All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.79	Per Cubic Meter			
Total						
Terms and Conditions:-						

1. Work shall be executed as per PWD specification.

Ex-officio
Bhioranj Divisic
PWPWD Bhioranj

NAME OF WORK:- R/R Una Aghar mandal road km. 67/00 to 79/00 . (SH:- C/O R/Wall at RD 76/500 TO 76/515.) (PDNA)

SCHEDULE OF QUANTITY

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost	
					Earnest Money Time	Rs 2,15,532/- Rs. 5000/- 2 month
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of slumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.30	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.75	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe De-plas/finolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.80	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O. Shed at Village Lag-Manwin near Ayurvedic Hospital in GP Manwin Bhorani (VKVNY/2024/621)

Estimated Cost Rs 3,82,093/-
Earnest Money Rs. 8000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of slumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring a structure and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.729	Per Cubic Meter			
2	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1185.89	Per Kilogram			
3	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of putties, rafters and trusses and including cutting to size and shape wherever required, including entire carriage of material within all leads, lifts and technical specification as per direction of Engineer in charge and other incidentals. The rates are inclusive, royalty, GST or other taxes imposed by the Government.	211.21	Per Square Meter			
5	Providing ridges or hips of width 60mm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete, 12.4.2 0.63mm thick with zinc coating not less than 275gm/m. Including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	23.70	Per Running Meter			
6	Providing and fixing Insulating Board, Ceiling of approved quality with necessary frame work 12mm thick as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	133.2	Per square meter			
	Total					
	Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhorani Division
H.P.W.D Bhorani

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of link road Kalahu more to bhareri via gudwin bhukkar beri brahmna Sai da ghat Nam lakh Jaroh road km 0/00 to 7/720
to (Sh:- c/o RWall at RD 7/220 TO 7/242) (PDNA)

Estimated Cost Rs 493380/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	49.50	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	96.75	Per Cubic Meter			
3	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	70.00	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-A/R & M/O Kango Galu to Kalahu more at RD 0/00 TO 6/756
(S.H :- Providing and installation of crash barrier at RD/1405 TO 1/433. (PDNA)

Estimated Cost Rs 486400/-
Earnest Money Rs.10000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(Nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size i/c ereing W metal beam crash barrier comprising 3 mm thick corrugated sheet metal beam rail 70 cm (seventy centimeter) above the ground level fixed on ISMC series channel vertical post 150x75x5 mm spaced 2 mtr. Centre to centre 1.80 mtr. Height 1.010 meter below ground/road level and steel parts or fitment to be galvanised by hot dip process , all fitting to confirm to IS 1367 , metal beam rail to be fixed on the vertical posts with a spacer of channel section 150x75x5 mm 330 m long complete as per clause 810 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	128.00	Per running metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

NAME OF WORK:- Restoration on Luder Sulgwan road Km. 0/00 to 5/00 (SH:- C/O R/wall at RD,4/015 to 4/026 (P/DNA)

SCHEDULE OF QUANTITY

Estimated Cost Rs 4,99,260
Earnest Money Rs.10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	18.76	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	104.45	Per Cubic Meter			
3	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plas/finolex/ vectus pipe having pressure 4kg. per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	40.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. 1) Granular material. Including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	37.65	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration / Repair on Mundkhar to Manoh via Nell Jamli road 0/00 to 4/225.(SH.- C/O R/Wall at RD 3/150 to 3/168.) (PDNA)

Estimated Cost
Earnest Money
Rs 3,43,210/-
Rs. 7000/-
2 month

Sl No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of slumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring a structure and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	35.77	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	73.58	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe De-plast/finolex/ vecus pipe having pressure 4kg./per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.77	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
48 PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Awah Devi Bagwara Gharan Dera Parol road km. 0/00 to 9/450 /SH:- C/O Wire
Crate at RD.71210 to 71241) (PDNA)

Estimated Cost
Earnest Money

Rs 4,99,102/-
Rs. 10000/-

Sr No	Description of Items	Time		Amount
		Quantity	Unit	
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.37	Per Cubic Meter	290.15
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeters) dia GI with conforming to IS:280 and IS. 4826 in 100mmx100mm (one hundred millimeters) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulder weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specifications clause 1301 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	145.31	Per cubic metre	3250.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.20	Per Cubic Meter	900.00
Total				

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhorani Division
H.P.W.D. Bhorani

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Samirpur to Bagwara via Samleharra km 0/00 to 2/200 (SH:- R/M of Shoulder & Unlined Drain at various RDs. & Removal of Slips).

Estimated Cost Rs. 99714/-
Earnest Money Rs. 2000/-

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	2Months Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1005.25	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	540.00	Per Running Mtr.			
	Total					

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoreaji Division
H.P.W.D Bhoreaji