

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed item/ percentage rate tender on form NO. 6&8 are hereby invited by the Executive Engineer, Bilaspur Division No. I, HP.PWD., Bilaspur on behalf of Governor of Himachal Pradesh from the approved and eligible contractors enlisted in PWD Department so as to reach in this office on or before **01/12/2025** up to 10.30 A.M. and will be opened on the same day at **11.00 A.M.** in the presence of the intending contractors or their authorized representatives who may like to be present. If it happens to be holiday on that day tenders will be opened on next working day. The application for obtaining the tender forms will be received up to **27/11/2025** up to 5.00 PM and the tender form can be had from this office on **29/11/2024** during the office hours.

The Earnest money in the shape of National Saving Certificate Time deposit Accounts/FDR of any Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, Division No. I., HP.PWD., Bilaspur must be accompanied with each application for obtaining the tenders. The tender application received without earnest money /cost of tender forms will similarly be rejected. The undersigned reserves the right to reject the tenders without assigning any reason.

Sr. No	Name of work	Estimated cost (In Rs.)	Earnest Money (In Rs.)	Cost of form (In Rs.)	Time limit
1	Prepare room for Digital presentation of records n Distt. Session Court Bilaspur (H.P.). (SH:- P/F partition sliders shutter in aluminium and partition in gallery with aluminium shutters).	71,899/-	2000/-	350	One month
2	A/R & M/O on residential building Changer Sector Bilaspur (H.P.). (SH:- Wood painting emulsion exterior, toilet seats in ADC Qtrs and AC to DC Qtrs Bilaspur).	99,244/-	2000/-	350	One month
3	A/R & M/O residential building under Changer sector Bilaspur. (SH:- Providng services of sweeper in Circuit house Bilaspur period 01/12/2025 to 30/04/2026).	99,910/-	2000/-	350	One month
4.	Restoration of rain damages on Binayakghat-Bandla-Sihra-Bilaspur Km. 0/0 to 23/0. (SH:- C/o unlined drain at various RDs).	99,715/-	2000/-	350	One month
5	Repair & restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/625. (SH:- C/O B/wall at RD. 3/920 to 3/922.65) (Under PDNA 2023).	99,887/-	2000/-	350	One month
6	Restoration of rain damages on various road under Kuthera Sub-Divison. (SH:- Hiring of Excavator cum loader Hydraulic Excavator).	99,000/-	2000/-	350	One month
7	Restoration of rain damages on Chandigarh Mandi Manali rad Km. 133/0 to 136/0. (SH:- Dressing of berms at various RD's).	98,049/-	2000/-	350	One month
8	Repair & restoration of rain damages on Kothi Bhulswai Rangloh Bari road Km. 0/00 to 3/105. (SH:- Re-construction of U-shape drain at RD. 2/940 to 2/970). (Under PDNA 2023).	99,663/-	2000/-	350	One month
9	Repair & restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/625. (SH:- Re-construction of B/wall at RD. 16/660 to 16/667.90). (Under PDNA 2023).	98,218/-	2000/-	350	One month
10	Repair & restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/625. (SH:- Re-construction of B/wall at RD. 12/195 to 12/203). (Under PDNA 2023).	98,737/-	2000/-	350	One month

	Repair & restoration of rain damages on Kuthera Harlog via Dugli Tasli Km. 0/00 to 3/00. (SH:- Re-construction of U-shape drain at RD. 2/220 to 2/250). (Under PDNA 2023).	99,663/-	2000/-	350	One month
12.	Repair & restoration of rain damages on Harlog Ghattu Trifalghat road Km. 00 to 20/0. (SH:- C/O R/wall at RD. 17/400 to 17/402.65. (PNNA 2023).	99,887/-	2000/-	350	One month
13.	Repair & restoration of rain damages on Harlog Ghattu Trifalghat road Km. 00 to 20/0. (SH:- C/O B/wall at RD. 6/180 to 6/186. (PNNA 2023).	99,919/-	2000/-	350	One month
14.	Repair & restoration of rain damages on Harlog Ghattu Trifalghat road Km. 00 to 20/0. (SH:- C/O B/wall at RD. 3/100 to 3/106. (PNNA 2023).	99,919/-	2000/-	350	One month
15.	Repair & restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/625. (SH:- C/O B/wall at RD. 5/300 to 5/306) (Under PDNA 2023).	99,919/-	2000/-	350	One month
16.	Repair & restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/625. (SH:- C/O B/wall at RD. 5/350 to 5/356) (Under PDNA 2023).	99,919/-	2000/-	350	One month
17.	Restoration of rain damages on Chandigarh Mandi Manali rad Km. 127/0 to 131/0. (SH:- C/o unlined drain at various RDs).	99,900/-	2000/-	350	One month

1. Certified that the tenders for above said works are being called of emergent nature in exigency of public interest.

TERMS & CONDITIONS:-

1. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
2. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactorily including adherence to quality future work will be awarded to him. All undertaking that he is not having more than two works in hand must be recorded in the application, failing which application of such contractor shall be rejected without any notice to him.
3. Earnest money should be accompanied with application. Application without earnest money will not be entertained.
4. The photo copy of Pan Number/GST/EPF/Registration should be attached with the application otherwise tender form will not be issued.

NO.PW-BLP-I-CB-EA-I-Tender/ 2025-

14296-320

**Executive Engineer,
Bilaspur, Division No.I
HP.PWD, Bilaspur.
Dated :- 22/11/2025**

Copy forwarded to the following for information please.

1. The Engineer-in-Chief, HP.PWD; Shimla-I.
2. The Chief Engineer (HZ) HP.PWD, Hamirpur.
3. The Superintending Engineer, 10th Circle, HP.PWD, Bilaspur .
4. The Executive Engineer (IT) O/o the Engineer-in-Chief, HP.PWD, Shimla through email:- cc-pwd-hp@nic.in alongwith copies of Schedule of quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. All the contractors as per record of this office.
7. Accounts Branch/ Drawing Branch/Supdt. in this office.
8. Notice Board.

**Executive Engineer,
Bilaspur, Division No.I,
HP.PWD, Bilaspur.**

Schedule of Quantity

Schedule of Quantity						Estimated cost Rs. = 71,899/- only
						Earnest Money Rs. = 2,000/- only
						Time = One Month.
Name of work:- Prepare room for Digital presentation of records in Distt. Session Court Bilaspur (H.P.). (SH:- P/F partition sliders shutter in aluminium and partition in gallery with aluminium shutters).						
Sr No.	Description of items.	Qty.	Rate		Unit	Amount
			In Figure	In words		
1	2	3	4	5	6	7
1	Providing and fixing double glazed hermetically sealed glazing in aluminium windows, ventilators and partition etc. with 6 mm thick clear float glass both side, having 12 mm air gap, including providing EPDM gasket, perforated aluminium spacers, desiccants, sealant (Both primary and secondary sealant) etc. as per specifications, drawings and direction of Engineer-in-charge complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.69			Per Square Metre	
2	Providing and fixing Single Ptam with aluminium frame 62x37.5x2.5 mm thick with one number shutter including 12mm thick pre-laminated board partition with fitting gasket and rubbers including sliding door bolt, handle, twin bolt and hydraulic door spring in best quality including all types of fitting as per the direction of Engineer-in-charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.94			Per Square Metre	
		TOTAL				


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD, Bilaspur

Schedule of Quantity

Schedule of Quantity									
Name of work :- A/R & M/O on residential building at Changer Sector Bilaspur. (SH:- Wood painting emulsion exterior, toilet seats in ADC									
Time Limit. = One month									
Estimated cost Rs. = 99,244/- only									
Earnest Money Rs. = 2,000/- only									
Unit									
In Figure									
In words									
Unit									
Amount									
Qty.									
Description									
1									
2									
3									
4									
5									
6									
7									
8									
9									
10									
11									
12									
13									
14									
15									
16									
17									
18									
19									
20									
21									
22									
23									
24									
25									
26									
27									
28									
29									
30									
31									
32									
33									
34									
35									
36									
37									
38									
39									
40									
41									
42									
43									
44									
45									
46									
47									
48									
49									
50									
51									
52									
53									
54									
55									
56									
57									
58									
59									
60									
61									
62									
63									
64									
65									
66									
67									
68									
69									
70									
71									
72									
73									
74									
75									
76									
77									
78									
79									
80									
81									
82									
83									
84									
85									
86									
87									
88									
89									
90									
91									
92									
93									
94									
95									
96									
97									
98									
99									
100									

6	Providing and fixing PVC pipe D-plast or equivalent make approved by the Bureau of Indian Standard. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
6.1	100 mm (one hundred millimetre) dia	2.50	Each			
6.2	75 mm (Seventy millimetre) dia	2.70	Each			
7	Providing and fixing PVC floor trap FINOLEX of self cleaning design including fixing with approved adhesive etc. complete . including cost of cutting making good in the walls and floors complete . 100x75 mm (One hundred into seventy five millimetre) . including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Each			
8	Painting one coat(excluding priming coat)on previously painted wood and wood based surfaces with enamel paint brushing to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	198.26	Per Square Metre			
9	Removing dry oil bound distemper, water proofing cement paint and like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	258.90	Square Metre			
10	Providing and applying Birla white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	93.90	Per Square Metre			

11	Finishing wall with weather proof exterior grade emulsion of approved design (Apex ultima) or its equarried on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	258.90			Per Square Meter
		TOTAL			


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Schedule of Quantity							Estimated cost Rs. = 99,910/- only	
							Earnest Money Rs. = 2,000/- only	
							Time Limit. = One month	
Name of Work:- A/R & M/O residential building under Changer sector Bilaspur. (SH:- Providing services of sweeper in Circuit house Bilaspur period 01.12.2025 to 30.04.2026).								
Sr No	Description	Qty.	Rates		Unit	Amount		
			In Figure	In words				
1	2	3	5	6	7	8		
1	Providing services of sweeper for sweeping / cleaning in Govt. Non residential buildings under Circuit house HP.PWD Bilaspur from 9 AM to 5 PM including Sunday and public holidays as per the satisfaction of Engineer-in-Charge	152.00			Days			
	TOTAL							


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. IV

Estimated cost Rs. = 99,715/-only
 Earnest Money Rs. = 2,000/- only.
 Time Limit. = One month.

Schedule of Quantity

name of work :- Restoration of rain damages on Binayak Ghat Bandla Sihra Bilaspur road kM. 0/00 to 23/00. (SH:- C/O unlined drain at various 's).

No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other conscruction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1540.00	Per Runing Meter			
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

SCHEDULE OF QUANTITY.			Estimated cost Rs. = 99,886/-only Earnest Money Rs. = 2000/- only. Time Limit. = One Month				
Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-Construction of R/wall at RD. 3/920 to 3/922.65). (Under PDNA 2023).							
Sr No	Description of items.	Qty.	Rates		Amount		
			In Figure	In words			
1	2	3	4	5	6	8	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.83	Per Cubic metre				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.380	Per Cubic metre				
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.41	Per Cubic metre				
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.00	Each				
TOTAL							


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. 6

Estimated cost Rs. = 99,000/-only.
 Earnest Money Rs. = 2000/- only.
 Time Limit. = One Month

Schedule of Quantity

name of work :- Resoration of rain damages on various road under Kuthera Sub Division. (SH:- Hiring of Excavator-cum-loader/Hydraulic excavator).

Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	Providing one number Excavator cum loader/JCB in good condition on hire bases site of work for removal of slip with in all leades and lifts as per direction of Engineer-in-Charge. The dumping site of material be arranged by the contractor at his own level and no dumping will be allowed along road side or in forest land failing which the contractor will be responsible for any kind of panel action as per rule of Hon'ble court.	90.00	Hours	1100.00	Rupees One Thousand One Hundred Only	99000.00
						99000.00


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. V/H

Estimated cost Rs. = 98,049/- only
 Earnest Money Rs. = 2,000/- only.
 Time Limit. = One month.

Schedule of Quantity

Name of work :- Restoration of rain damages on Chandigarh Mandi Manali road Km. 133/00 to 136/00. (SH:- Dressing of berms at various Rd's).

Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Surface dressing of the ground including dressing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4830.00	Square Meter			
	TOTAL					


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

SCHEDULE OF QUANTITY.				Estimated cost Rs. = 99,663/-only		
				Earnest Money Rs. = 2000/- only.		
				Time Limit. = One Month		
Name of work:- Repair & Restoration of rain damages on <i>Katti Blows Road</i> Km. 0/00 to 3/00. (SH:- Re-Construction of U-shape						
Sr No	<i>RD 21940 to 21970</i>	Description of items.	Qty.	Rates		Amount
				In Figure	In words	
1			3	4		8
1		Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.50	Per Cubic metre	6	
2		Providing and laying mechanically mixed and vibrated plain/reinforced concrete 1:3:6 (One cement : three sand :six graded crushed stone aggregate 40 mm (forty millimetre) in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 . plain cement concrete grade M-10 (M-ten) Nominal mix including cost of form work and curing complete and including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	16.80	Per Cubic metre		
			TOTAL			0.00

Job No. 99

SCHEDULE OF QUANTITY.									
Estimated cost Rs. = 98,218/-only									
Earnest Money Rs. = 2000/- only.									
Time Limit. = One Month									
Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-Construction of B/wall at RD. 6/660 to 16/667.90). (Under PDNA 2023).									
Sr No	Description of items.	Qty.		Rates		Amount			
				In Figure	In words				
1	2	3	4	5	6	8			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.45	Per Cubic metre						
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	18.640	Per Cubic metre						
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Each						
TOTAL									


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. 10

Estimated cost Rs. = 98,737/-only
 Earnest Money Rs. = 2000/- only.
 Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-Construction of B/wall at RD. 2/195 to 12/203). (Under PDNA 2023).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2	2.48	Per Cubic metre	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty for any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.880	Per Cubic metre			
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Each			
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. ~~10~~ 11

Estimated cost Rs. = 99,663/-only
 Earnest Money Rs. = 2000/- only.
 Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of work:- Repair & Restoration of rain damages on Kuthera Harog via Dugli Tasli road Km. 0/00 to 3/00. (SH:- Re-Construction of U-shape drain at Rd. 2/220 to 2/250). (Under PDNA 2023).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2			5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty/or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.50	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated plain/reinforced concrete 1:3:6 (One cement : three sand :six graded crushed stone aggregate 40 mm (forty millimetre) in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 . plain cement concrete grade M-10 (M-ten) Nominal mix including cost of form work and curing complete and including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	16.80	Per Cubic metre			
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. ~~10~~ 12

Estimated cost Rs. = 99,886/- only
 Earnest Money Rs. = 2000/- only.
 Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of work:- Repair & Restoration of rain damages on Harlog Ghattu Trifalghat road Km. 0/00 to 20/00. (SH:- Re-Construction of R/wall at RD. 17/400 to 17/402.65). (Under PDNA 2023).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2			5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.83	Per Cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.380	Per Cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.41	Per Cubic metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.00	Each			
	TOTAL					


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. 0/13

SCHEDULE OF QUANTITY.									
Estimated cost Rs. = 99,919/-only									
Earnest Money Rs. = 2000/- only.									
Time Limit. = One Month									
Name of work:- Repair & Restoration of rain damages on Harlog Ghattu Trifalghat road Km. 0/00 to 20/00. (SH:- Re-Construction of B/wall at RD. 6/180 to 6/186). (Under PDNA 2023).									
Sr No	Description of items.	Qty.		Rates		Amount			
				In Figure	In words				
1	2	3	4	5	6	8			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.24	Per Cubic metre						
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18,900	Per Cubic metre						
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00	Each						
TOTAL									


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No. ~~10~~ 14

Estimated cost Rs. = 99,919/-only
 Earnest Money Rs. = 2000/- only.
 Time Limit. = One Month

SCHEDULE OF QUANTITY.

Name of work:- Repair & Restoration of rain damages on Harlog Ghattu Trifalghat road Km. 0/00 to 20/00. (SH:- Re-Construction of B/wall at RD. 3/100 to 3/106). (Under PDNA 2023).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure 5	In words 6	
1	2	15.24	Per Cubic metre		6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.900	Per Cubic metre			
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00	Each			
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

DRAFT SCHEDULE OF QUANTITY.		Estimated cost Rs. = 99,919/-only Earnest Money Rs. = 2000/- only. Time Limit. = One Month				
Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-Construction of B/wall at RD. /300 to 5/306). (Under PDNA 2023).						
Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.24	Per Cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	18.900	Per Cubic metre			
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00	Each			
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Name of work:- Repair & Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- Re-Construction of B/wall at RD. /350 to 5/356). (Under PDNA 2023).		Estimated cost Rs. = 99,919/-only Earnest Money Rs. = 2000/- only. Time Limit. = One Month			
		SCHEDULE OF QUANTITY.			
		Description of items.		Rates	
Sr No	Qty.		In Figure	In words	Amount
1	3	2	5	6	8
1	15.24	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Per Cubic metre		
2	18.900	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Per Cubic metre		
3	7.00	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	Each		
		TOTAL			


Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 17

Schedule of Quantity		Estimated cost Rs. = 99,900/- only
		Earnest Money Rs. = 2,000/- only.
		Time Limit. = One month.
Name of work :- Restoration of rain damages on Chandigarh Mandi Manali road Km. 127/00 to 131/00. (SH:- C/O unlined drain at various Rd's).		

Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1542.85	Per Running Meter			
	TOTAL					


Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur