

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWD/DEH/CB/Tender/2025.26-

8297-5312

Dated 27/11/25-

To

The Executive Engineer (IT Cell)
HPPWD Nirman Bhawan Nigam Bihar
HPPWD Shimla

Subject:-

Tender Notice

Sir,

Enclosing Kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No ; PWD/(B) A(3) 1/2024 dated 03.01.2024 as the works mentioned in the inviting tender are urgent in nature and public interest


Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

Copy to the F.C-cum- Secretary (PW) to the Govt. of Himachal Pradesh Shimla -
2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of
information please.

Copy to the Superintending Engineer 9th Circle HPPWD Nurpur for favour of
information please.

Copy to Notice Board

Copy to All the head of Branches

Copy to All the Contractors working under Dehra Division


Executive Engineer,
Dehra Division HPPWD.,
Dehra.

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.


TENDER SCHEULE:

- | | |
|---|--------------------------|
| 1. Date and time of receipt of application for tender form: | 02.12.2025 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 03.12.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 04.12.2025 upto 11.00 AM |
| 4. Date and time of opening of tenders: | 04.12.2025 at 11.30 AM |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Road km. 9/00 to 22/200 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD.18/210 to 18/248)	Rs.429410/-	Rs.10,000/-	Three Months	Rs350
2	Restoration of Rain Damages on Naker Bridge to Mandeli in Km. 0/00 to 2/035 (SH:- C/o Retaining wall at Rd.1/500 to 1/558)	Rs.495453/-	Rs.10,000/-	Three Months	Rs350
3	Restoration of Rain Damages on Naker Bridge to Mandeli in Km. 0/00 to 2/035 (SH:- C/o Cement concrete pavement at Rd. 0/600 to 0/650 & CC Berms at Rd. 1/200 to 1/420)	Rs.496898/-	Rs.10,000/-	Three Months	Rs350
4	Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Road km. 9/00 to 22/200 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD.11/200 to 11/320) PDNA	Rs.499708/-	Rs.10,000/-	Three Months	Rs350
5	Restoration of Rain Damages on Kaloha Pragpur Dhaliara Dadasiba Road in km.9/00 to 22/200 (SH:- Construction of V-shape drain at RD.13/430 to 13/540, 13/700 to 13/840 & U-shape drain at RD. 11/400 to 11/520, 11/540 to 11/670) .PDNA	Rs.464850/-	Rs.10,000/-	Three Months	Rs350
6	Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 22/0 to 39/180 (SH:- Construction of drain at RD. 13/600 to 13/900). (Under PDNA).	Rs.425610/-	Rs.9,000/-	Three Months	Rs350
7	Restoration of Rain Damages on Bankhandi to Haripur Road Km. 0/00 to 8/00 under PDNA (H.P) (SH:- Road side Amenities,) (Sub work:-Repair to Plaster ,Steel work, Painting , Aluminum work of Gang Hut at Bankhandi).	Rs.299415/-	Rs.6,000/-	Three Months	Rs350
8	Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH:- Construction of road side U-Shape drain at RD 5/400 to 5/752). Under PDNA	Rs.499363/-	Rs.10000/-	Three Months	Rs350
9	Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH:- Construction of road side U-Shape drain at	Rs.499363/-	Rs.10000/-	Three Months	Rs350

	RD 5/752 to 5/900 to 6/330 to 6/430 & 6/530 to 6/635). Under PDNA				
10	Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH:- Construction of road side U-Shape drain at RD 6/636 to 6/988). Under PDNA	Rs.499363/-	Rs.10000/-	Three Months	Rs350
11	Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH:- Construction of Grating on U-Shape drain at RD 10/510 to 10/560). Under PDNA	Rs.236234/-	Rs.5000/-	Three Months	Rs350
12	Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH:- Construction of R/wall at RD 10/810 to 10/828.50). Under PDNA	Rs.494328/-	Rs.10000/-	Three Months	Rs350
13	Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH:- Construction of road side U-Shape drain at RD 8/400 to 8/500, 8/500 to 8/700 & 10/810 to 10/862). Under PDNA	Rs.499363/-	Rs.10000/-	Three Months	Rs350
14	Restoration of rain damages on PWD Rest House to JHD road in Km 0/0 to 1/825. (SH:- Construction of R/wall at RD 1/430 to 1/440, 1/460 to 1/480). Under PDNA	Rs.447416/-	Rs.9000/-	Three Months	Rs350
15	Restoration of rain damages on PWD Rest House to JHD road in Km 0/0 to 1/825. (SH:- Construction of R/wall at RD 1/560 to 1/580). Under PDNA	Rs.425926/-	Rs.9000/-	Three Months	Rs350
16	Restoration of rain damages on PWD Rest House to JHD road in Km 0/0 to 1/825. (SH:- Construction of R/wall at RD 1/580 to 1/610). Under PDNA	Rs.406640/-	Rs.9000/-	Three Months	Rs350
1.	The contractors/firms should possess the following documents(Photocopy to be attached with the application): Copy of Registration/Latest renewal of enlistment. (i) PAN (Permanent Account No.) (ii) Registration under GST No. (iii) EPF(Employee Provident Fund Account No.) (iv) The proof ownership/hire/lease, buying of required machinery for micro surfacing works. (v)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
4	The offer of the tender shall remain valid upto 30 days after the opening.				


 Executive Engineer
 HPPWD Division Dehra
 Distt Kangra H.P
 on behalf of Governor of Himachal Pradesh
 HIM LOK SAMPARK

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 429410.00
 Earnest Money :-Rs. 9000.00
 Time Limit :- Three Month.

Name of work:- Restoration of Rain Damages on Kaloha Prāgpur Nehranpukhar Dhaliara Dadasiba Road km. 9/00 to 22/200 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD.18/210 to 18/248)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	26.60 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	7,714.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	26.60 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	1,07,730.00

Sr. No.	Description of Item.	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in solid causeway and Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	6.75 Cubic meter	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter	39,150.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	243.20 Square meter	1130.00	Rupees One Thousand One Hundred Thirty Only	Square meter	2,74,816.00
Total						4,29,410.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Percentage bill of quantity checked and approved for Rs. 4,29,410.00/- only.

Executive Engineer,
Dehra Division,
DHPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,95,453.00
 Earnest Money :-Rs. 10,000.00
 Time Limit :- Three Months.

Name of work:- Restoration of Rain Damages on Naker Bridge to Mandeli in Km. 0/00 to 2/035 (SH:- C/o Retaining wall at Rd. 1/500 to 1/558) PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	55.77 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	16,173.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/dephs and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	111.61 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	4,52,021.00

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	30.00 Number s	250.00	Rupees Two Hundred Fifty Only	Each	7,500.00
4	Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, toll tax or any other taxes imposed by the Government.	16.50 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	12,375.00
5	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in Parapets etcetera including cost of form work and curing complete as per MORD technical specification clauses 802, 804, 805, 806, 807, 1202 & 1204 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Toll tax, Sale tax or any other taxes imposed by the Government.	1.42 Cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	7,384.00
	Total					4,95,453.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked and approved for Rs. 495,453.00/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra.

PERCENTAGE BILL-OF-QUANTITY

Estimate Cost :- Rs. 4,96,898.00
 Earnest Money :-Rs. 10,000.00
 Time Limit :- Three Months.

Name of work:- Restoration of Rain Damages on Naker Bridge to Mandeli in Km. 0/00 to 2/035 (SH:- C/o Cement concrete pavement at Rd. 0/600 to 0/650 & CC Berms at Rd. 1/200 to 1/420) PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	71.50 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	20,735.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	38.50 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	1,55,925.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix: 1:1.5:3 (one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	46.75 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	3,20,238.00
	Total					4,96,898.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked and approved for Rs. 4,96,898.00/- only

Executive Engineer,
Dehra Division,
APWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 499708.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Month.

Name of work:- Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Road km. 9/00 to 22/200 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD.11/200 to 11/320) PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	31.86 Cubic meter	250.00	Rupees Two Hundred Fifty Only	Per Cubic meter	7,965.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	31.86 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	1,29,033.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in solid causeway and Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	9.66 Cubic meter	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter	56,028.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	271.40 Square meter	1130.00	Rupees One Thousand One Hundred Thirty Only	Square meter	3,06,682.00
Total						4,99,708.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Percentage bill of quantity checked and approved for Rs. 4,99,708.00/- only.

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.464850.00

Earnest Money :- Rs. 10,000.00

Time Limit :- Three Months.

Name of work:- Restoration of Rain Damages on Kaloha, Pragpur Dhaliara Dadasiba Road in km.9/00 to 22/200 (SH:- Construction of V-shape drain at RD.13/430 to 13/540, 13/700 to 13/840 & U-shape drain at RD. 11/400 to 11/520, 11/540 to 11/670) .PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	135.00 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	39,150.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, Toll tax or any other taxes imposed by the Government.	86.00 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	4,25,700.00
	TOTAL					4,64,850.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked
and approved for Rs. 4,64,850.00/- only.

Executive Engineer,
Dehra Division,
CHPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.425610.00

Earnest Money :- Rs. 9,000.00

Time Limit :- Three Months.

Name of work:- Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road 'Km 22/0 to 39/180 (SH:- Construction of drain at RD. 13/600 to 13/900). (Under PDNA).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	126.00 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	36,540.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, Toll tax or any other taxes imposed by the Government.	78.60 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	3,89,070.00
	TOTAL					4,25,610.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked and approved for Rs 425,610.90/- only.

Executive Engineer,
Dehra Division,
HPPWD Dehra

Job. No. 7.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 2,99,415.00

Earnest Money :- Rs. 6,000.00

Time Limit :- One Month.

Name of Work:-Restoration of Rain Damages on Bankhandi to Haripur Road Km. 0/00 to 8/00 under PDNA (H.P) (SH:- Road side Amenities,) (Sub work:-Repair to Plaster ,Steel work, Painting , Aluminum work of Gang Hut at Bankhandi).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Repair to plaster of thickness 12mm (Twelve millimetre) to 20mm (Twenty millimetre) in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	104.40 Square metre	399.75	Rupees Three Hundred Ninety Nine And Paise Seventy Five Only	Per Square metre	41,734.00
2	Providing and laying Vitrified tiles in 600x600mm (Six hundred into six hundred millimetre) (thickness to be specified by manufacturer).Mat finished with water absorption less than 0.08% (Zero point zero eight percent) and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 20mm (Twelve millimetre) thick bed of cement mortar 1:4 (One cement isto Four coarse sand) jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three kilogram per square metre) including grouting the joint with white cement and matching pigments etcetera complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	27.59 Square metre	1360.70	Rupees One Thousand Three Hundred Sixty And Paise Seventy Only	Per Square metre	37,542.00
3	Providing and laying 600x1200mm (Six hundred into twelve hundred millimetres) full body matt finish Ceramic tiles of Restile /Johnson/ Rak/Nitico/Kajaria (Etemity)/ AGL / Sompolo / Somany/Orient & Bell as per approved shade and design of the office and thickness to be specified by manufacturer), with water absorption less than 0.08% (Zero point zero eight percent) and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12mm (Twelve millimetre) thick bed of cement mortar 1:3 (One cement isto Three coarse sand) jointing with grey cement slurry @ 3.3 Kilogram/ Square metre (Three point three kilogram per suare metre) including grouting the joint with white cement and matching pigments etcetera complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	30.14 Square metre	1375.00	Rupees One Thousand Three Hundred Seventy Five Only	Per Square metre	41,443.00

330

4	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P.brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in charge. (Glazing, paneling and dash fasteners to be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) complete as per HPPWD specifications or as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, GST, toll tax or any taxes imposed by the Government.	116.25 Kilogram me	560.00	Rupees Five Hundred Sixty Only	Per Kilogramme	65,100.00
5	Providing and fixing 12mm (Twelve millimetres) thick (both Side) prelaminated water proof particle board in matt finish flat pressed three layer or graded wood particle board conforming to IS: 12823 as per of Action Tesa / Century / Greenlam / Merinolam / Kitlam / Vista approved shade Grade I Type II, in panelling fixed in aluminium/wood doors, windows shutters and partition frames with C.P. brass / stainless steel screws etcetera complete as per architectural drawings and directions of Engineer-in-Charge including entire carriage of materials within all leads, lifts and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	4.50 Square metre	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Square metre	5,625.00
6	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete. With 12 mm Aluminium steel U beading all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	7.74 Square metre	892.65	Rupees Eight Hundred Ninety Two And Paise Sixty Five Only	Per Square metre	6,909.00
7	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. With plane/ float glass panes of 4.00 mm thickness weight not less than 12.50 kg / sqm all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	3.84 Square metre	832.95	Rupees Eight Hundred Thirty Two And Paise Ninety Five Only	Per Square metre	3,199.00
8	Providing and fixing hydraulic door closer of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	2.00 Numbers	1200.00	Rupees One Thousand Two Hundred Only	Each	2,400.00

9	Providing and fixing 250x16 mm aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	4.00 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	1,000.00
10	Providing and fixing 150x10mm aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	44.00 Numbers	95.00	Rupees Ninety Five Only	Each	4,180.00
11	Providing and fixing 125 mm aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	28.00 Numbers	70.00	Rupees Seventy Only	Each	1,960.00
12	Painting Steel work with premium enamel of Asian/Nerolac Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.56 Square metre	120.00	Rupees One Hundred Fifteen Only	Per Square metre	547.00
13	Providing and applying white cement (Birla white/JK) /based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	89.42 Square metre	105.00	Rupees Ninety Five Only	Per Square metre	9,389.00
14	Providing and fixing plain M.S. grills of required patterns in steel frames of window etc. with M.S grill made of 10mm (ten millimeter) M.S square bar welded to 6mmx12mm (six millimeter into twelve millimeter) M.S. flat, round bars bolts and nuts or screws complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including of Toll Tax Sales tax, GST or any other taxes imposed by the Government.	30.00 Kilogram me	176.45	#NAME?	Per Kilogramme	5,294.00

15	Providing and fixing anodized aluminium work in frames/shutter of Jindal/Hindalco for door and window ventilators and partitions wall frames extruded built up standard tubular and other sections of approved make conforming to IS:733 and IS:1285 anodized transparent or dyed to required shade according to IS:1868 (Minimum anodic coating of grade AC 15) fixed with rawl plugs and screws or with fixing clips or with expansion hold fasteners including necessary filling up of gaps at junctions at top, bottom and sides with required PVC/ Netroprene felt etcetra Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically where ever required including cleat angle, aluminium snap beading for glazing/paneling C.P. brass/stainless steel screws all complete as per architectural drawing specifications, design and the direction of Engineer-in-Charge. The rate is inclusive for carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	27.00 Kilogram me	512.00	#NAME?	Per Kilogramme	13,824.00
16	Distempering with oil bound washable distemper of (Nerolac/Asian/Dulux/Berger) approved brand and manufacture (two or more coats) of required shade on new work over and including water thinnable priming coat with cement primer to give an even shade complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	89.42 Square metre	96.85	#NAME?	Per Square metre	8,660.00
17	Finishing walls with water proofing cement paint of required shade :Old work (one or more coats @ 2.20 k g/10 sqm) all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	78.85 Square metre	55.00	#NAME?	Per Square metre	4,337.00
18	Brick masonry work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven point Five) in super structure in Cement mortar 1:6 (One cement isto Six coarse sand) complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, GST and any other taxes imposed by the Government.	3.68 Cubic metre	5800.00	#NAME?	Per Cubic metre	21,344.00
19	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth, complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	19.31 Square metre	525.00	#NAME?	Per Square metre	10,138.00

21	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.55 Cubic metre	5800.00	#NAME?	Per Cubic metre	14,790.00
	Total					2,99,415.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked and approved for Rs. 2,99,415.00 only.

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,99,363.00
 Earnest Money :- Rs. 10,000.00
 Time Limit :- Three Months.

Name of work:- Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH)- Construction of road side U-Shape drain at RD 5/400 to 5/752). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	147.84 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	42,874.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	92.22 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	4,56,489.00
	Total					4,99,363.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked and approved for RD: 4,99,363.00 only.

[Signature]
 Executive Engineer,
 Dehra Division,
 HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,99,363.00
 Earnest Money :- Rs. 10,000.00
 Time Limit :- Three Months.

Name of work:- Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH:- Construction of road side U-Shape drain at RD 5/752 to 5/900 to 6/330 to 6/430 & 6/530 to 6/635). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	147.84 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	42,874.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	92.22 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	4,56,489.00
	Total					4,99,363.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked and approved for Rs. 4,99,363.00 only.

Executive Engineer,
Dehra Division,
APPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,99,363.00
 Earnest Money :- Rs. 10,000.00
 Time Limit :- Three Months.

Name of work:- Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH:- Construction of road side U-Shape drain at RD 6/636 to 6/988). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	147.84 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	42,874.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement into three sand into six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	92.22 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	4,56,489.00
	Total					4,99,363.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked and approved for Rs. 4,99,363.00 only

Executive Engineer,
 Dehra Division,
 HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 2,36,234.00
 Earnest Money :- Rs. 5,000.00
 Time Limit :- Three Months.

Name of work:- Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH:- Construction of Grating on U-Shape drain at RD 10/510 to 10/560). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Steel work of Tata/Sail riveted, bolted or welded in built up sections, framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royalty, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	2207.79 Kilogram me	107.00	Rupees One Hundred Seven Only	Per Kilogram me	2,36,234.00
	Total					2,36,234.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked and approved for Rs. 2,36,234.00 only.

Executive Engineer,
 Dehra Division,
 PWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,94,328.00
 Earnest Money :- Rs. 10,000.00
 Time Limit :- Three Months.

Name of work:- Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH:- Construction of R/wall at RD 10/810 to 10/828.50).
 Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	44.77 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	12,983.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	109.33 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	4,42,787.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	51.00 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	12,750.00
4	Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	34.41 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	25,808.00
	TOTAL					4,94,328.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked
and approved for Rs. 4,94,328.00 only.

Executive Engineer,
Dehra Division,
APPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,99,363.00
 Earnest Money :- Rs. 10,000.00
 Time Limit :- Three Months.

Name of work:- Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 4/000 to 39/180 (SH)- Construction of road side U-Shape drain at RD 8/400 to 8/500, 8/500 to 8/700 & 10/810 to 10/862). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	147.84 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	42,874.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	92.22 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	4,56,489.00
		Total				4,99,363.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Percentage bill of quantity checked and approved for Rs. 4,99,363.00 only

Executive Engineer,
Dehra Division,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,47,416.00
 Earnest Money :- Rs. 9,000.00
 Time Limit :- Three Months.

Name of work:- Restoration of rain damages on PWD Rest House to JHD road in Km 0/0 to 1/825. (SH):- Construction of R/wall at RD 1/430 to 1/440, 1/460 to 1/480).
 Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	37.90 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	10,991.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	98.00 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	3,96,900.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	45.00 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	11,250.00
4	Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	37.70 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	28,275.00
	TOTAL					4,47,416.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked and approved for Rs. 4,47,416.00/- only

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,25,926.00
Earnest Money :- Rs. 9,000.00
Time Limit :- Three Months.
Name of work:- Restoration of rain damages on PWD Rest House to JHD road in Km 0/0 to 1/825. (SH:- Construction of R/wall at RD 1/560 to 1/580). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	37.40 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	10,846.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, toll tax or any other taxes imposed by the Government.	93.60 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	3,79,080.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	48.00 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	12,000.00
4	Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	32.00 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	24,000.00
	TOTAL					4,25,926.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked and approved for Rs. 4,25,926.00/- only

Executive Engineer,
Dehra Division,
APPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,06,640.00
 Earnest Money :- Rs. 9,000.00
 Time Limit :- Three Months.

Name of work:- Restoration of rain damages on PWD Rest House to JHD road in Km 0/0 to 1/825. (SH:- Construction of R/wall at RD 1/580 to 1/610). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	34.50 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	10,005.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, GST, toll tax or any other taxes imposed by the Government.	88.20 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	3,57,210.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	56.00 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	14,000.00
4	Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	33.90 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	25,425.00
	TOTAL					4,06,640.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage bill of quantity checked and approved for Rs. 4,06,640.00 only.

[Signature]
Executive Engineer,
Dehra Division,
HPPWD Dehra