

**Himachal Pradesh
Public works Department
Notice Inviting Tender**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **01-12-2025 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non-refundable) up to 5.00 P.M. on **30-11-2025**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 29-11-2025**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	RRD on Bharari to Palahota serad road km. 0/0 to 3/900 (SH:- C/o PCC B/wall at RD 1/980 to 2/010 & C/o R/wall at RD 2/010 to 2/019)	2,93,580	5900	Two Months
2	RRD on Bharari Palohta Serad road km. 0/00 to 3/900 (SH:- Construction of PCC Breast Wall at RD 2/220 to 2/2/250)	2,68,355	5400	Two Months
3	RRD on Bharari Palohta Serad road km. 0/00 to 3/900 (SH:- C/o PCC U-Shape drain at RD 2/205 to 2/315)	1,53,170	3100	Three Months
4	RRD on Chunahan to Malhanu road km. 0/00 to 5/00 (SH:- C/o of PCC R/wall at RD 3/963 to 3/981)RHS	2,09,030	4200	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the percentage rates in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.

4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. Conditional and incomplete tenders shall be rejected.
8. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.

Dated 22-11-2025

No. PW-GHR-Tender/NIT/2025 6925-40


Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
1. The Superintending Engineer 1stCircle, HP.PWD Mandi.
2. **The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.**
3. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
4. The Block Development Officer Gohar.
5. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
6. Various contractors.
7. Notice Board/DB/AB.

Executive Engineer,
Gohar Division (B&R),
HPPWD, Gohar.

BILL OF QUANTITY

Name of Work:- RRD on Bharari to Palahota serad road km. 0/0 to 3/900 (SH:- C/o PCC B/wall at RD. 1/980 to 2/010 & PCC B/wall at RD. 2/010 to 2/019) Under PDNA					Estimated cost Rs. -	293580.00
					Earnest Money cost Rs. -	5900.00
					Time - Two Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	26.58	Per Cubic metre	230.00		
2	Providing and Laying concrete for plain/reinforced concrete in open foundations P.C.C nominal mix 1:5:10 (one cement :five sand : ten graded stone aggregate 40 mm fourty millimetre aggregates) complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.	61.28	Per cubic metre	4350.20		
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	7.56	Per cubic metre	1050.60		
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	34.00	Each	380.70		
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY


Name of work :- RRD on Bharari Palohta Serad road km 0/00 to 3/900 (SH:- Construction of PCC Breast Wall at RD 2/220 to 2/250) Under PDNA

Estimated cost Rs. - 2,68,355/-

Earnest Money cost Rs.5400/-


Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	27.90	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge complete in all respect.	58.20	Per Cubic meter	4350.20		
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	23.00	Each	380.70		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Bharari Palohta Serad road km 0/00 to 3/900 (SH:- C/o PCC U-Shape drain at rd 2/205 to 2/315) Under PDNA					Estimated cost Rs. - 1,53,170/-	
					Earnest Money cost Rs. 3100/-	
					Time - Three Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	50.05	Per Cubic meter	230.00		
2	Providing concrete for plain/reinforced concrete in open foundations 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) mechanically mixed and vibrated and curing complete including cost of formwork complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of material within all leads, lifts and other incidental charges.	28.05	Per Cubic Metre	5050.20		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

72

BILL OF QUANTITY

Name of work :- RRD on Chunahan to Malhanu road km 0/000 to 5/000 (SH:- Construction of PCC R/Wall at RD 3/963 to 3/981)RHS Under PDNA					Estimated cost Rs. - 2,09,030/-	
					Earnest Money cost Rs.4200/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.80	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802.803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	43.38	Per Cubic meter	4350.20		
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614.709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	17.00	Each	380.70		
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	9.72	Per Cubic meter	1050.60		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

86

Resay
 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar