HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO.SD-III-CB-Tender/2025-26-15181 Dated:-22/11/25

To

The Executive Engineer (IT Cell),
HP.PWD.,Nigam Vihar,Shimla-2.

Subject:- PUBLICATION OF TENDER NOTICE for PDNA

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on department website as per notification of Principal Secretary (PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16th July,2021 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:- as above

Executive Engineer,
Shimla Division No. III,
HP.PWD.Shimla-3.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Sealed percentage rate tenders on form No. 6&8 are hereby invited by the Executive Engineer, Shimla Division No. III, HP.PWD. Shimla-3 on behalf of the Governor of H.P. for the following works from the eligible Contractors/Firms enlisted in HP.PWD, so as to reach in his office on or before **01-12-2025** up to 10:30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of the intending Contractors/Firms or their authorized representatives. The tender form can be had from his office against cash payment (non-refundable) on any working day up to 04:30 P.M. on **29-11-2025** and the application for issue of tender form shall be received up to 1:00 P.M. on **28-11-2025.**

The earnest money in the shape of National saving Certificate/Time deposit account/saving account in any of the post office in HP, duly pledged in favour of Executive Engineer, Shimla Division No-III must accompany with the application form for the tender offer. Conditional tender and the tender received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tender without assigning any reason there to. Other conditions are applicable as perform No. 6&8. The offer shall remain open for 30 days.

Sr. No	Name of work	Estimated Cost in Rs.	Earnest Money in Rs.	Time	Form No	Cost of form
1	Restoration in rain damages to various residential Qtrs under Division No. III Shimla (SH:- R/R drain from type III and IV block at Majitha House to wheat research centre for providing proper drainage system under PDNA.)	**497627.00**	**9960.00**	One Month	6&8	350/-
2	Restoration in rain damages in various non-residential building under division No. III Shimla (R/R CPVC line to cabinet hall repair of rain water pipeline, UPVC fittings etc in armsdale Under PDNA.)	**320150.00**	**6410.00**	One Month	6&8	350/-
3	Restoration in rain damages in vrious residential Qtrs under division No. III Shimla (SH: R/R Store in attic floor of type IV qtrs at Majitha House set No. 3 and 4)	**495285.00**	**9910.00**	One Month	6&8	350/-
4	Restoration of rain damages in residential & Non Buildings under division No. III Shimla (SH:-R/R interlocking paver blocks in parking in front of Type IV qtrs at Majitha House Shimla Under PDNA.)	**499709.00**	**10000.00**	One Month	6&8	350/-
5	Restoration of rain damages to various non-residential buildings under Division No. III Shimla (SH:-R/R of roof and down pipes above room No. E310, E307 and near lift portion etc in Ellerslie main building Under PDNA.)	**499968.00**	**10000.00**	One Month	6&8	350/-
6	Restoration of rain damages to various non-residential buildings under division No. III Shimla (SH:- R/R replacing and repairing of damaged saniraty fittings in armsdale Phase-I,II,III Ellerslie main building and Yojna Bhawan at HP Sectt. Shimla Under PDNA .)	**428110.00**	**8570.00**	One Month	6&8	350/-
7	Restoration of rain damages to various non- residential buildings under Division No. III Shimla (SH: R/R of room No. G-23 & G-24 i.e Painting, Polishing, Flooring and construction of pantry etc Under PDNA .)	**76433.00**	**1530.00**	One Month	6&8	350/-
8	Restoration of rain damagesto various residential under Division No. III Shimla (SH: R/Rof stairs for Type-III	**409460.00**	**8190.00**	One Month	6&8	350/-

	block of Brockline at Majitha House Chotta Shimla Under PDNA .)					
9	Restoration of rain damages to various non-residential under Division No. III Shimla (SH:- Restoration of rain damages of Majitha House and repair of gutter and rain water pipes of new & Old building at Majitha House etc Under PDNA .)	**499086.00**	**9990.00**	One Month	6&8	350 -
10	Restoration of rain damages in various residential under Division No. III Shimla (SH:-R/R roof of servant qtrs in Elleslie Coloney at Chotta Shimla Under PDNA .)	**470963.00**	**9420.00**	One Month	6&8	350 -
11	Restoration of rain damages in various residential under Division No. III Shimla (SH:- R/RFixing wire gauge shutters in block 8 and block-6 and servant Qtrs at Ellerslie Under PDNA .)	**318067.00**	**6370.00**	One Month	6&8	350 -
12	Restoration of rain damages in various residential buildings under Division No. III Shimla (SH:-R/R in Block No. 11 Set No. 5 and 2 other minor repair work etc in Ellerslie Qtrs under PDNA.)	**415642.00**	**8320.00**	One Month	6&8	350 -

1.The contractor/firm shall have his GST No. and attested copy of the same be attached with the application for issue of tender form.

2. The contractor/firm should attach attested copy of registration/renewal.

3.Copy of PAN card be attached with the application form.

Executive Engineer,
Shimla Division No-III,
HP.PWD.Shimla-3.
Dated:-

NO.SD-III-CB-Tender/2025-26-

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in -Chief, HPPWD Nirman Bhawan, Nigam Vihar Shimla-2.
2. The Chief Engineer (S) HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2.
3. The Superintending Engineers,4th Circle HPPWD Shimla -3.
4. The Deputy Commissioner, Shimla Distt. Shimla.
5. The Sub-Divisional Magistrate (U) Shimla.
6. All the Assistant Engineers working under this Division.
7. All the heads of the branches in this office.
8. Notice board.

Executive Engineer,
Shimla Division No-III,
HP.PWD.Shimla-3

(1)

DRAFT SCHEDULE OF QUANTITY

					Estimated Cost Rs. :-		497627.00
					Earnest Money Rs. :-		9960.00
						Time:-	One Month.

Name of work:-Restoration in rain damages to various residential Qtrs under Division no III Shimla.(SH:- R/R drain from type III and IV block at Majitha House to wheat research centre for providing proper drainage system under PDNA)

Sl.	Items of work	Quantity		Rate		Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 15 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts.	47.84	Cum	350.00	Rupees Three Hundred Fifty Only	Per cubic metre.	16744.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)	60.59	Cum	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic metre.	393835.00
3	Providing and fixing on wall face PVC (finolex) type-B rain water pipes with collar and clamps etc. of working pressure not less than 4.5 kg/sqm including filling the joints with approved adhesive complete.110mm dia pipes including carriage of materials within all leads and lifts. 150mm dia	56.60	Rmt	780.00	Rupees Seven Hundred Eighty Only	Per running met	44148.00
4	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc.complete. including carriage of materials in all leads and lifts a) 150mm dia.	6.00	No	400.00	Rupees Four Hundred Only	Each	2400.00
5	Constructing manhole with R.C.C top slab in 1:2:4 mix in 1 cement 2 sand 4 graded stone aggregate 20mm nominal size) foundation concrete1:4:8 (1cement 4 sand 8 graded stone aggregate 40mm nominal size inside plastering 15mm thick with cement mortar 1:3 (1cement 3 sand) finished with a floating coat of neat cement and making channels in concrete 1:2:4 mix (1cement 2 sand 4 graded stone aggregate 20mm nominal size) finished smooth complete including curng and testing:- inside size 800mm x 800mm and 1000mm deep including 455x610mm dia precast R.C.C. covers of NTC make or equivalent manhole cover with frame (medium duty) with 200mm thick walls of brick masonry using common burnt clay building bricks in cement mortar 1:3 (1 cement : 3 sand) including carriage of materials within all leads and lifts.	3.00	No	13500.00	Rupees Thirteen Thousand Five Hundred Only	Each	40500.00
						Total	**497627.00**
	Quoted rate in figure.						
	Quoted rate in words						
	Conditions:-						
i	*Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.*			***Draft schedule of quantity No.....for the year 2025-26 duly approved amounting to ₹.497627/-only.***			
ii	*Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.*						
iii	*All above material shall be supplied in heavy quality .*			***#NAME?***			

Executive Engineer
Shimla Division No.III

DRAFT SCHEDULE OF QUANTITY

					Estimated Cost Rs. :-		320150.00
					Earnest Money Rs. :-		6410.00
						Time:-	One Month.

Name of work:- Restoration of rain damages in Various non residentail buildings under division no III Shimla. (R/R CPVC line to cabinet hall repair of rain water pipeline , UPVC fittings etc in armsdale Under PDNA)

Sl. No.	Items of work	Quantity			Rate	Unit	Amount
1	Providing and fixing on wall face 150 mm dia PVC (finolex) type-B rain water pipes with collar and clamps etc. of working pressure not less than 4.5 kg/sqm including filling the joints with approved adhesive complete including carriage of materials within all leads and lifts	50.00	Rmt	780.00	Rupees Seven Hundred Eighty Only	Per running Metre	39000.00
2	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc.complete. including carriage of materials in all leads and lifts. a) 150mm dia.	4.00	No	400.00	Rupees Four Hundred Only	Each	1600.00
3	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.:- 25 mm nominal outer dia Pipes.	68.80	Rmt	375.00	Rupees Three Hundred Seventy Five Only	Per running metre.	25800.00
4	Providing and fixing Partio Urinal Sensor with AC adaptor of Kohlar make item co Kohler 24199IN-C01-CP Patio Urinal Sensor including connection the urinal with waste pipe by means of white lead mixed with chopped hemp (waste pipe to be measured and paid for seperatly) incluiting carriage of materials within all leads and lifts	3.00	No.	17500.00	Rupees Seventeen Thousand Five Hundred Only	Each	52500.00
5	Providing and fixing 15mm dia C.P. brass Sensor pillar tap with capstan head of Jeguar cat No. OPP-15019 including carriage of materials within all leads and lifts	4.00	No.	11500.00	Rupees Eleven Thousand Five Hundred Only	Each	46000.00
6	Providing and fixing 15mm dia single lever sink mixer with out popup waste with 450mm long braided hoses including connection fitting in all respect complete including carriage of materials within all leads and lifts:- Jaquar cat No. ORP-CHR-10011BPM.	3.00	No.	4200.00	Rupees Four Thousand Two Hundred Only	Each	12600.00
7	Providing and Fixing UPVC window handle complete including carriage of material within all leads and lifts.	100.00	No.	750.00	Rupees Seven Hundred Fifty Only	Each	75000.00
8	Providing and Fixing Security lock for UPVC window complete including carriage of material within all leads and lifts.	100.00	No.	280.00	Rupees Two Hundred Eighty Only	Each	28000.00
9	Repair of urinal Sensor of kohlar complete including change eye and batries including carriage of meterials in all leads and lifts	35.00	No.	850.00	Rupees Eight Hundred Fifty Only	Each	29750.00
10	Repair of Wash basin Pillar cock Sensor of Jeguar complete including change eye and batries including carriage of meterials in all leads and lifts	18.00	No.	550.00	Rupees Five Hundred Fifty Only	Each	9900.00
						Total	**320150.00**
	Quoted rate in figure.						
	Quoted rate in words						
	Conditions:-						
i	*Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.*				***Draft schedule of quantity No.....for the year 2025-26 duly approved amounting to ₹.320150/-only.***		
ii	*Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.*						
					#NAME?		

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.

DRAFT SCHEDULE OF QUANTITYA

Estimated Cost Rs. :-	495285.00
Earnest Money Rs. :-	9910.00
Time:-	One Month.

Name of work:-Restoration of rain damages in various residential Qtrs under Division no III Shimla.(SH:-R/R store in attic floor of type IV qtrs at Majitha House set no 3 and 4 under PDNA)

Sl.	Items of work	Quantity		Rate	Unit	Amount
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	2228.00 Kg	105.00	Rupees one Hundered Five Only	Per Kilogramme	233940.00
2	Providing and fixing polycarbonate transparent sheet 2.0 mm thick in roofing with galvanised Jor I hooks bolts and nuts with G.I. limpet and bitumen rubber washer complete with all accessories asrequired in all leads and lifts as per direction of Engineer-in-charge.	98.70 Sqm	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per square metre	212205.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)	7.56 Cum	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic metre.	49140.00
					Total	495285.00
	Quoted rate in figure.					
	Quoted rate in words					
	Conditions:-					
i	*Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.*					
ii	*Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.*					

Draft schedule of quantity No.....for the year 2025-26 duly approved amounting to ₹.495285/-only.

#NAME?

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.

(4)

DRAFT SCHEDULE OF QUANTITY

					Estimated Cost Rs. :-		499709.00
					Earnest Money Rs. :-		10000.00
						Time:-	One Month.

Name of work:- Restoration of rain damages in Residential & non buildings under Division no III Shimla.(SH:- R/R interlocking paver blocks in in parking in front of type IV qtrs at Majitha House Shimla under PDNA.)

Sl.	Items of work	Quantity			Rate	Unit	Amount
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)	41.22	Cum	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic metre.	267930.00
2	Providing and laying heavy duty pre-polished precast cement conrete inter locking paver blocks of NTC make or equivalent of approved design and shade vibro compacted of approved design, shade and size border or kurb block grey or coloured over sub-base of concrete with 50 mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (Sub base concrete floor to be paid for sepretarly) 60mm thick block including carriage of materials within all leads and lifts.(**Labour Rate**).	206.00	Sqm	650.00	Rupees Six Hundred Fifty Only	Per Square Metre	133900.00
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	932.18	Kg	105.00	Rupees One Hundred Five Only	Per Kilogramme	97879.00
						Total	**499709.00**
	Quoted rate in figure.						
	Quoted rate in words						
	Conditions:-						
i	*Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.*				***Draft schedule of quantity No.....for the year 2025-26 duly approved amounting to ₹.499709/-only.***		
ii	*Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.*						
					#NAME?		

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.

DRAFT SCHEDULE OF QUANTITY

Estimated Cost Rs. :-	499968.00
Earnest Money Rs. :-	10000.00
Time:-	One Month.

Name of work:- Restoration of rain damages to various non residential buildings under Division no III Shimla.(SH:- R/R of roof and down pipes above room no E310, E307 and near lift portion etc in Ellerslie main building under PDNA)

Sl.	Items of work	Quantity		Rate		Unit	Amount
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1240.93	Kg	105.00	Rupees One Hundred Five Only	Per Kilogramme	130298.00
2	Providing and fixing precoated galvanised iron profile sheets Tata Durashine (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.60 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5 x 55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.complete including carriage of materials within all lead as directed by the Engineer-in-charge.	103.54	Sqm.	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Square metre	129425.00
3	Providing and fixing Plain galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS:277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete including carriage of materials within all leads and lifts:- Flashings/ Aprons.(Upto 600 mm).	31.30	Rmtr	650.00	Rupees Six Hundred Fifty Only	Per running metre	20345.00
4	Providing and fixing on wall face PVC (finolex) type-B rain water pipes with collar and clamps etc. of working pressure not less than 4.5 kg/sqm including filling the joints with approved adhesive complete.110mm dia pipes including carriage of materials within all leads and lifts. 150mm dia	275.00	Rmt	780.00	Rupees Seven Hundred Eighty Only	Per running metre	214500.00
5	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc.complete. including carriage of materials in all leads and lifts a) 150mm dia.	12.00	No	450.00	Rupees Four Hundred Fifty Only	Each	5400.00
						Total	499968.00
	Quoted rate in figure.						
	Quoted rate in words						
	Conditions:-						
i	*Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.*						
ii	*Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.*						

Executive Engineer
Shimla Division No.III
HP, PWD, Shimla-3.

DRAFT SCHEDULE OF QUANTITY

Estimated Cost Rs. :-	428110.00
Earnest Money Rs. :-	8570.00
Time:-	One Month.

Name of work:- Restoration of rain damages to Various non residentail buildings under division no III Shimla. (R/R Replacing and repairing of damaged saniraty fittings in armsdale Phase-I,II,III Ellerslie main building and Yojna Bhawan at H.P Sectt Shimla under PDNA)

Sl.	Items of work	Quantity		Rate		Unit	Amount
1	Providing and fixing Partio Urinal Sensor with AC adaptor of Kohlar make item co Kohler 24199IN-C01-CP Patio Urinal Sensor including connection the urinal with waste pipe by means of white lead mixed with chopped hemp (waste pipe to be measured and paid for seperatly) incluiting carriage of materials within all leads and lifts	13.00	No.	13500.00	Rupees Thirteen Thousand Five Hundred Only	Each	175500.00
2	Providing and fixing 15mm dia C.P. brass Sensor pillar tap with capstan head of Jeguar cat No. OPP-15019 including carriage of materials within all leads and lifts	14.00	No.	9500.00	Rupees Nine Thousand Five Hundred Only	Each	133000.00
3	Repair of urinal Sensor of kohlar complete including change eye and batries including carriage of meterials in all leads and lifts	55.00	No.	850.00	Rupees Eight Hundred Fifty Only	Each	46750.00
4	Repair of Wash basin Pillar cock Sensor of Jaguar complete including change eye and batries including carriage of meterials in all leads and lifts	36.00	No.	550.00	Rupees Five Hundred Fifty Only	Each	19800.00
5	Providing & fixing 32 mm (thirty two milimetre) dia, PVC waste pipe for wash basin or sink including check nut complete within all leads, lifts of materials and other incidentals. including carriage of materials in all leads and lifts	42.00	No	150.00	Rupees One Hundred Fifty Only	Each	6300.00
6	Providing and fixing 500ml soap dispenser of VIKING or equivalent with C.P. brass brackets fixed to wooden cleats with C.P. brass screws including carriage of materials within all leads and lifts.	28.00	No.	1050.00	Rupees One Thousand Fifty Only	Each	29400.00
7	Providing and fixing 8mm dia C.P. / S.S. Jet spray multi cardian with flexible tube upto 1 metre long with S.S. triangular plate to Eureopean type W.C. of quality and make as approved by Engineer - in - charge.	6.00	No.	450.00	Rupees Four Hundred Fifty Only	Each	2700.00
8	Providing and fixing viterous China wash down water closet (European type W.C. pan) with intergal P or S trap along with seat cover including jointing the trap with soil pipe in cement mortar 1 : 1 (1 cement : 1 sand) including carriage of materials within all leads and lifts :- Complete set of Popular Hindware closet cat No. 20044 star white.	2.00	No	4300.00	Rupees Four Thousand Three Hundred Only	Each	8600.00
9	Providing and fixing PTMT Coloured / white high density polyethylene / poly propylene 10 litres capacity (full flush) European standard control low level flushing cistern with fittings with a pair of brackets with fittings such as lead valve, syphon, 15mm nominal size PVC ball valve with polythene float, with push button, couplings for connections with inlet, outlet and over flow pipe, 40mm dia C.P. flush bend including cutting holes in walls and making good the same and connecting the flush bend with cistern and closet (overflow pipe to be measured and paid for separately) .	3.00	No	1150.00	Rupees One Thousand One Hundred Fifty Only	Each	3450.00
10	Providing and fixing slick plastic seat (solid / Hollow type) and cover for wash down water closet with C.P. brass hinges and rubber buffers in coloured plastic seat and cover solid type including carriage of materials within all leads and lifts in White plastic seat and cover.	3.00	No.	570.00	Rupees Five Hundred Seventy Only	Each	1710.00

11	Providing & fixing 100 mm (one hundred milimetre) dia, C.P. grating complete within all leads, lifts of materials and other incidentals. including carriage of materials in all leads and lifts	10.00	No	90.00	Rupees Ninety Only	Each	900.00
	Quoted rate in figure.					**Total**	**428110.00**
	Quoted rate in words						
	Conditions:-						
i	Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.						
ii	Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.						

Draft schedul

########

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.

DRAFT SCHEDULE OF QUANTITY

Estimated Cost Rs. :-	76433.00
Earnest Money Rs. :-	1530.00
Time:-	One Month.

Name of work:- Restoration of rain damages to various non-residential buildings under division no III Shimla. (SH:- R/R of room No G-23 & G-24 i.e Painting, polishing, flooring and construction of pantry etc. under PDNA)

Sl.	Items of work	Quantity			Rate	Unit	Amount
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	18.33	Sqm	10.00	Rupeen ten only	Per square metre.	183.00
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete.	18.33	Sqm	60.00	Rupees Sixty Only	Per square metre.	1100.00
3	Wall painting(two coat) with plastic emulsion paint of approved brand and manufacture on decorated wall surface to give an even shade including thoroughly brushing the surface clean of all dirt grease, loose pieces of scale and sand papered smooth including carriage of material in all leads and lifts.	41.08	Sqm.	75.00	Rupees Seventy Five Only	Per Square metre	3081.00
4	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) i) 6mm thick	1.72	Sqm	650.00	Rupees Six Hundred Fifty Only	per square metre	1118.00
5	Providing and fixing 19mm thick commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc complete including carriage of materials within all leads and lifts.	11.41	Sqm	1400.00	Rupees One Thousand Four Hundred Only	Per square metre.	15974.00
6	Providing and fixing 19mm thick Commercial Board water proof shutters for up boards i/c fixing with nickel plated piano hinges with screws etc complete)	1.72	Sqm	1500.00	Rupees One Thousand Five	per square metre	2580.00
7	Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete.	3.62	Sqm	890.00	Rupees Eight Hundred Ninety	per square metre	3222.00
8	Providing and fixing aluminium handles anodized transparent or dyed to required colour and shade with necessary screws etc. completed within all leads, lifts of materials and other incidentals.125 mm size	6.00	No	75.00	Rupees Seventy Five Only	Each	450.00
9	Providing and fixing Brass butt hinges of size 100x85x5.5mm completed within all leads, lifts of materials and other incidentals.	2.00	No	60.00	Rupees Sixty Only	Each	120.00
10	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. c" complete as specified and as directed by the Engineer-in-Charge.comlete including carriage of materials within all leads and lifts.Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent	0.85	Sqm	5500.00	Rupees Five Thousand Five Hundred Only	Per Square metre	4675.00
11	Making rounded/half rounded nosing in granite stone complete. 20mm.thick including carriage of materials within all leads and lifts.	0.85	Rmtr	220.00	Rupees Two Hundred Twenty	Per running metre	187.00
12	Providing and fixing stainless steel kitchen sink 610x510mm with bowl depth 200mm of approved standard ISI make with drain board and C.P. waste with C.I. or M.S. Brackets painted white including cutting holes and making good the same but excluding fitting (	1.00	No	3200.00	Rupees Three Thousand Two Hundred Only	Each	3200.00

13	P/F C.P. Waste for basin 32mm viking made CAT no. 6242 comlete including carriage of materials within all leads and lifts	1.00	No	248.00	Rupees Two Hundred Forty	Each	248.00
14	Providing & fixing 32 mm (thirty two milimetre) dia. PVC waste pipe for wash basin or sink including check nut complete within all leads, lifts of materials and other incidentals.	1.00	No	95.00	Rupees Ninety Five Only	Each	95.00
15	Providing and fixing magnetic catcher ISI marked with necessary screws etc. complete including carriage of materials within all leads and lifts.	3.00	No	40.00	Rupees Forty Only	Each	120.00
16	Providing and fixing oxidized M.S. hasps and stapple for cup board 100 mm size with necessary screws etc complete. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals	4.00	No	70.00	Rupees Seventy Only	Each	280.00
17	Providing and fixing bright finished brass handles with screws etc. complete: 100mm.complete including carriage of materials within all leads and lifts	2.00	No	180.00	Rupees One Hundred Eighty	Each	360.00
18	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.:- 25 mm nominal outer dia Pipes.	3.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Per running metre.	1050.00
19	Providing and fixing C.P. brass angle cock 15mm (fifteen millimetre.) nominal bore including carriage of materials within all leads and lifts:- Ess Ess make Cat No. C-204.	2.00	No.	850.00	Rupees Eight Hundred Fifty Only	Each	1700.00
20	Providing and fixing PVC connection pipe with brass union complete within all leads, lifts of materials and other incidentals. :-45cms (forty five centimetres) length :-15mm (fifteen millimetre) nominal bore.	2.00	No.	150.00	Rupees One Hundred Fifty Only	Each	300.00
21	Providing and fixing 15mm dia single lever basin mixer with out popup waste with 450mm long braided hoses including connection fitting in all respect complete including carriage of materials within all leads and lifts:-Jaquar cat No. ORP-CHR-10011BPM.	1.00	No	4300.00	Rupees Four Thousand Three Hundred Only	Each	4300.00
22	Providing and fixing 1.50mm thick PVC antistatic venyl Flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately)	6.84	Sqm	970.00	Rupees Nine Hundred Seventy Only	Per square metre.	6635.00
23	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 4.0 mm thick glass panes. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	0.80	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per square metre	680.00
24	Painting two coats (excluding priming costs) on new wood and wood based surfaces with enamel paint brushing to give an any shade including cleaning the surfaces of all dirt, dust and other foreign matters sand papering and stopping within all leads, lifts of materials and other incidentals.	99.72	Sqm	70.00	Rupees Seventy Only	per square metre	6980.00
25	Polishing one or more coats with malamine polish of required shade on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt, dust and sand papered smooth and including a coat of wood filler.complete including carriage of materials within all leads and lifts	22.29	Sqm	260.00	Rupees Two Hundred Sixty Only	Per running metre	5795.00
26	Providing and fixing Aquagaurd as per approved qualityand make complete including carriage of materials within all leads and lifts.	1.00	No	12000.00	Rupees Twelve Thousand Only	Each	12000.00
						Total	76433.00

	Quoted rate in figure.					
	Quoted rate in words					
	Conditions:-					
i	*Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.*		*Draft schedule of quantity No.....for the year 2025-26 duly approved amounting to ₹.76433/-only.*			
ii	*Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.*					
			#NAME?			

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.

DRAFT SCHEDULE OF QUANTITY

					Estimated Cost Rs. :-		409460.00
					Earnest Money Rs. :-		8190.00
						Time:-	One Month.

Name of work:- Restoration of rain damages in various residential under Division no III Shimla.(SH:- R/R of stairs for type-III block of Brockline at Majitha House Chotta Shimla under PDNA)

Sl. No.	Items of work	Quantity			Rate	Unit	Amount
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	3198.95	Kg	105.00	Rupees One Hundred Five Only	Per Kilogramme	335890.00
2	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat of approved brand and manufacture ncluding carriage of materials within all leads and lifts.	107.00	Sqm.	65.00	Rupees Sixty Five Only	Per Square metre	6955.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)	7.11	Cum	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic Metre	46215.00
4	Providing and fixing high pressure Type- B PVC spigot and socket ,waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete including carriage of materials in all leads and lifts. a) 150mm dia.	24.00	Rmt	850.00	Rupees Eight Hundred Fifty Only	Per running metre.	20400.00
						Total	**409460.00**
	Quoted rate in figure.						
	Quoted rate in words						
	Conditions:-						
i	*Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.*						
ii	*Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.*						
		#NAME?					

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.

DRAFT SCHEDULE OF QUANTITY

						Estimated Cost Rs. :-	499086.00
						Earnest Money Rs. :-	9990.00
						Time:-	One Month.

Name of work:- Restoration of Ran damages in various non-residential under Division no III Shimla.(SH:- Restoration of rain damages of Majitha House and repairof gutter and rain water pipes of new & old building at Majitha House etc) Under PDNA

Sl. No.	Items of work	Quantity			Rate	Unit	Amount
1	Taking out and Refixing doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead :	50.00	No	70.00	Rupees Seventy Only	Each	3500.00
2	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws.40mm thick.2nd class Deodar wood.	62.96	Sqm	4500.00	Rupees Four Thousand Five Hundred Only	Per square metre.	283320.00
3	Providing and fixing aluminium handles anodized transparent or dyed to required colour & shade with necessary screws etc. complete. including carriage of materials in all leads and liftsA) 125 mm	36.00	No	75.00	Rupees Seventy Five Only	Each	2700.00
4	Providing and fixing aluminium tower bolts (berrel type) anodized trans parent or dyed to required shade and colour with screws etc. complete. including carriage of materials in all leads and lifts A) 150x10mm	64.00	No	95.00	Rupees Ninety Five Only	Each	6080.00
5	Providing and fixing anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete. including carriage of materials in all leads and lifts 250x16mm	4.00	No	240.00	Rupees Two Hundred Forty Only	Each	960.00
6	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 4.0 mm thick glass panes. complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	32.04	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per square metre	27234.00
7	Providing and fixing 15cm wide 45cm overall semicircular plain G.I. sheet gutter with iron brackets 40mm x 3mm size bolts and nuts and washers etc. including making necessary conections with rain water pipe complete as per design including carriage of materials within all leads and lifts:- 0.63mm thick sheet.	29.40	Rmt	650.00	Rupees Six Hundred Fifty Only	Per running metre	19110.00
8	Providing and fixing high pressure Type- B PVC spigot and socket ,waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete including carriage of materials in all leads and lifts. a) 150mm dia.	157.00	Rmt	850.00	Rupees Eight Hundred Fifty Only	Per running metre.	133450.00
9	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc.complete. including carriage of materials in all leads and lifts a) 150mm dia.	21.00	No	400.00	Rupees Four Hundred Only	Each	8400.00

10	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10sqm of approved brand and manufacture including carriage of materials within all leads and lifts.	191.09	Sqm	75.00	Rupees Seventy Five Only	Per square metre	14332.00
	Quoted rate in figure.					**Total**	**499086.00**
	Quoted rate in words						
	Conditions:-						
i	*Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.*						
ii	*Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.*						

Draft schedule of quantity No.....for the year 2025-26 duly approved amounting to ₹.499086/-only.

#NAME?

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.

DRAFT SCHEDULE OF QUANTITY

Estimated Cost Rs. :-	470963.00
Earnest Money Rs. :-	9420.00
Time:-	One Month.

Name of work:- Restoration of rain damages in various residential under Division no III Shimla.(SH:-R/R roof of servant qtrs in Elleslie Coloney at Chotta Shimla under PDNA)

Sl. No.	Items of work	Quantity		Rate	Unit	Amount
1	Dismantling roofing including ridges, hips, valleys, gutters etc. stacking the serviceable materials and disposal of un-serviceable materials within 20 metres lead including carriage of material in all leads and lifts as per direction of the Engineer-in-charge. a) G.I. Sheet roofing	96.90 Sqm	150.00	Rupees One Hundred Fifty Only	Per square metre.	14535.00
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	2801.73 Kg	105.00	Rupees One Hundred Five Only	Per Kilogramme	294182.00
3	Providing and fixing MS BP sheet 2.00 mm thick in eves board/facia/soffits/ ceiling including cutting fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (base members of steel work shall be measured and paid seperately)	18.48 Sqm	1700.00	Rupees One Thousand Seven Hundred Only	Per square metre	31416.00
4	Providing and fixing precoated galvanised iron profile sheets Tata Durashine (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.60 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5 x 55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.complete including carriage of materials within all lead as directed by the Engineer-in-charge.	96.90 Sqm.	1200.00	Rupees One Thousand Two Hundred Only	Per Square metre	116280.00
5	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gm/m². including carriage of materials within all leads and lifts.	19.40 Rmt	750.00	Rupees Seven Hundred Fifty Only	Per running metre	14550.00
					Total	**470963.00**
	Quoted rate in figure.					
	Quoted rate in words					
	Conditions:-					
i	*Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.*			***Draft schedule of quantity No.....for the year 2025-26 duly approved amounting to ₹.470963/-only.***		
ii	*Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.*					
				#NAME?		

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.

DRAFT SCHEDULE OF QUANTITY

			Estimated Cost Rs. :-		318067.00
			Earnest Money Rs. :-		6370.00
				Time:-	One Month.

Name of work:- Restoration of rain damages in various residential under Division no III Shimla.(SH:- R/R Fixing wire gauge shutters in block 8 and Block-6 and servant Qtrs at Ellerslie Qtrs under PDNA)

Sl. No.	Items of work	Quantity	Rate	Unit	Amount
1	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws.40mm thick.2nd class Deodar wood.	69.03 Sqm 4000.00	Rupees Four Thousand Only	Per square metre.	276120.00
2	Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete. 125 mm ESS ESS made (doors and windows) complete including carriage of materials within all leads and lifts as per direction of Engineer - in - charge.	65.00 No 125.00	Rupees One Hundred Twenty Five Only	Each	8125.00
3	Providing and fixing anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete. including carriage of materials in all leads and lifts 250x16mm	21.00 No 220.00	Rupees Two Hundred Twenty Only	Each	4620.00
4	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads and lifts.	183.62 Sqm 60.00	Rupees Sixty Only	Per square metre.	11017.00
5	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads and lifts	183.62 Sqm 65.00	Rupees Sixty Five Only	Per square metre.	11935.00
6	Providing and fixing bright finished hydraulic door closer of Godrej make or equivalant with screws etc. complete including carriage of materials in all leads and lifts.	5.00 No. 1250.00	Rupees One Thousand Two Hundred Fifty Only	Each	6250.00
				Total	**318067.00**
	Quoted rate in figure.				
	Quoted rate in words				
	Conditions:-				
i	*Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.*	***Draft schedule of quantity No.....for the year 2025-26 duly approved amounting to ₹.318067/-only.***			
ii	*Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.*				
		#NAME?			

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.

Draft schedule of Quantity

Estimated Cost Rs. :-	415642.00
Earnest Money Rs. :-	8320.00
Time:-	One Month.

Name of work:-Restoration of rain damages in Residential buildings under Division no III Shimla.(SH:- R/R in block No 11 set no 5 and 2 other minor repair work etc in Ellerslie Qtrs under PDNA)

Sl.	Items of work	Quantity			Rate	Unit	Amount
1	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) complete including carriage of materials within all leads and lifts. i) 6mm thick	43.80	Sqm	650.00	Rupees Six Hundred Fifty Only	Per square metre.	28470.00
2	Providing and fixing 19mm thick commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc complete including carriage of materials within all leads and lifts.	60.09	Sqm	1400.00	Rupees One Thousand Four Hundred Only	Per square metre.	84126.00
3	Providing and fixing 19mm thick Commercial Board water proof shutters for up boards i/c fixing with nickel plated piano hinges with screws etc complete including carriage of materials within all leads and lifts.	43.80	sqm	1500.00	Rupees One Thousand Five Hundred Only	Per square metre.	65700.00
4	Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete including carriage of materials within all leads and lifts.	251.58	Sqm	890.00	Rupees Eight Hundred Ninety Only	Per square metre.	223906.00
5	Providing and fixing magnetic catcher ISI marked with necessary screws etc. complete including carriage of materials within all leads and lifts.	28.00	No	40.00	Rupees Forty Only	Each	1120.00
6	Providing and fixing bright finished brass handles with screws etc. complete including carriage of materials within all leads and lifts. i) 100mm	28.00	No	170.00	Rupees One Hundred Seventy Only	Each	4760.00
7	Providing and fixing polycarbonate transparent sheet 1.50 mm thick in roofing with galvanised Jor I hooks bolts and nuts with G.I. limpet and bitumen rubber washer complete with all accessories asrequired in all leads and lifts as per direction of Engineer-in-charge.	4.32	Sqm	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per square metre	7560.00
						Total	**415642.00**
	Quoted rate in figure.						
	Quoted rate in words						
	Conditions:-						
i	*Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.*						
ii	*Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.*						
iii	*All above material shall be supplied in heavy quality .*						

Draft schedule of quantity No.....for the year 2025-26 duly approved amounting to ₹.415642/-only.

#NAME?

Executive Engineer
Shimla Division No.III
HP. PWD. Shimla-3.