

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DPD/CB/EA-I/Tender/2025- 5012-13
To

Dated: - 28-11-2025


The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: -
Sir,

Publishing of tender Notice.

Enclosed please find herewith tender notice of work as given in the Notice inviting Tender along with Schedule of Quantities for uploading the same on department website as per Notification No. Pr. Secy. (PW) to the Govt. of HP letter No. PBW (B) A (3) 1/2024 dated Shimla-2, the 03.01.2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ As above.


Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

Copy along with tender notice is forwarded to the Superintending Engineer, 15th Circle, HPPWD Una for information please.
DA/ As above.


Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed **Percentage rates** tenders on form 6 & 8 are hereby invited by the Executive Engineer Daulatpur Chowk Division, HPPWD, Daulatpur Chowk on behalf of Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office and opened as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tenders.

Date and time of receipt of applications for the tender form	: 06.12.2025 up to 05.00 PM
Date and time of issue/Sale of tender forms against cash Payment	: 08.12.2025 (03.00 PM to 5.00 PM)
Date and time of receipt of tenders	: 09.12.2025 up to 11.00 AM
Date and time of opening of tenders	: 09.12.2025 at 11.30 AM

The tender forms will be issued against cash payment (non-refundable). The earnest money in the shape of NSC/Time Deposit/FDR of nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

Sr. No.	Name of Work	Estimated Cost	Earnest money	Time Limit	Cost of Form	Eligible Class of Contractor
1	Restoration of Damages due to laying of Fire Hydrant by IPH Department on Daulatpur Bhera road km. 0/0 to 4/425. (SH: Re-Laying due to damaged road crust between RD 0/410 to 0/540) Under IPH Deposit	96915.00	2000.00	One Month	350-	Class-D
2	Repair & Restoration of Rain Damages Link road to Village Chalet Kabir Panthi Mohallah Km 0/0 to 0/680, (SH- Construction of V-Shape Drain at Various RD,s)	99934.00	2000.00	Three Month	350-	Class-D
3	A/R & M/O HPPWD Rest house at Gagret Tehsil Ghanari Distt. Una (SH:- Painting to Rest house building)	99886.00	2000.00	Two Month	350-	Class-D
4	Repair & Restoration of Rain Damages of Jeepable road from Swan Nadi to Railway Station Daulatpur Chowk Km. 0/0 to 1/0, (SH:- Repair to pot Hole between RD 0/0 to 0/5	99300.00	2000.00	One Month	350-	Class-D
5	Restoration of Damages due to laying of Fire Hydrant by IPH Department on Daulatpur Bhera road km. 0/0 to 4/425. (SH: Re-Laying due to damaged road crust between RD 0/550 to 0/675) Under IPH Deposit	99844.00	2000.00	One Month	350-	Class-D
6	Balance work SDF/2024/602, R/O (Repair of) Repair & Restoration of Rain Damages link road to village Chalet Km. 0/0 to 6/030, (SH:- Construction of Retaining wall in G.P. Chalet Km. 2/530 to 2/535) Under SDRF	90978.00	2000.00	One Month	350-	Class-D
7	A/R & M/O HPPWD Rest house at Daulatpur Chowk Tehsil Ghanari Distt. Una (SH: -Painting to Rest house building)	99436.00	2000.00	Two Month	350-	Class-D
8	Repair & Restoration of Rain Damages link road to Maidangarh to Up Mohal Joh Km. 0/0 to 4/000, (SH:- Construction of Retaining wall in G.P. Jon near House of Sh. Bali Ram Km.1/800 to 1/813)	98502.00	2000.00	Three Month	350-	Class-D
9	Restoration of Rain Damages on various roads in Daulatpur Sub Division, (SH: Painting to Nangal Jarialan Khad Bridge-I & II, and Parapets)	99629.00	2000.00	Two Month	350-	Class-D
10	Repair & Restoration of Rain Damages link road to Maidangarh to Up Mohal Joh Km. 0/0 to 4/000, (SH:- Construction of Retaining wall in G.P. Joh near House of Sh. Bali Ram Km.1/815 to 1/828)	99204.00	2000.00	Three Month	350-	Class-D

11	Balance work SDF/2024/607, R/O (Repair of) Repair & Restoration of Rain Damages link road from Gram Panchyat Nangal Jarialan to Mohalla Kabirpanthi. (SH:- Balance work C/o 2.75/5.00 mtr wide Jeepable road Cutting/Filling between Km. 0/0 to 0/220) Under Deposit	99241.00	2000.00	Three Month	350-	Class-D
12	Repair & Restoration of Rain Damages of Jeepable road from Swan Nadi to Railway Station Daulatpur Chowk Km. 0/0 to 1/0, (SH:- Repair to pot Hole between RD 0/600 to 0/950)	98314.00	2000.00	One Month	350-	Class-D
13	Repair & Restoration of Rain Damages Link road to Village Pirthipur Nichla km. 0/0 to 3/265 and link road from Joh Chowk to Mohalla Tillu Village Joh km. 0/0 to 2/250. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)	98219.00	2000.00	One Month	350-	Class-D

TERMS AND CONDITIONS: -

1. The contractor should produce a copy of enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his registration and GST No. and copy of the same be attached with the application.
3. The earnest money for the above works should be submitted duly pledged in favour of Executive Engineer, Daulatpur Chowk Division, HPPWD Daulatpur chowk with the application for the purchase of tender forms. The application received without earnest money shall be summarily rejected.
4. The contractor/firms are required to insert the rate in words as well as in figures failing which Executive Engineer reserves the right to accept/rejects any or all tenders.
5. If any of the date mentioned above happens to be Local/Gazetted Holidays the same shall be process on next date.
6. The tender form will be issued to those contractors who have relevant machinery and equipment, list of which may be attached with their application along with proof of ownership of machinery/legal tie up.
7. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.

No. PWD/DPD/CB-Tender/2025- 5005-11

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-Chief, HPPWD Nirman Bhawan Shimla.
2. The Chief Engineer (HZ) HPPWD Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD Una.
4. All the Assistant Engineers working under this division.
5. Drawing Branch in this office.
6. Notice Board.

Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

Dated: - 28-11-2025

Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

CERTIFICATE

Certified that tenders called vide this office letter No. PWD/DPD/CB-Tender/2025- 5005-11 dated 28-11-2025 are required to be carried out immediately being emergent nature of work in the public interest.


Executive Engineer,
Daulatpur chowk Division,
HPPWD Daulatpur Chowk.

Job - 1

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 96915/-
 Earnest Money: Rs. 2000/-
 Time Limit : One Months.

Name of Work:- Restoration of Damages due to laying of Fire Hydrant by IPH Department on Daulatpur Bhera road km. 0/0 to 4/425. (SH: Re-Laying due to damaged road crust between RD 0/410 to 0/540) Under IPH Deposit

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Preparation and consolidation of sub grade with power road roller of 8 (eight) to 12 (twelve) tonne capacity after excavating earth to an average of 22.5 cm (twenty two point five centimeter depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with any lead as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	182.000	Square metre	69.50	Rupees Sixty Nine And Paise Fifty Only	Per square metre	12649.00
2	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM)specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical paverfinisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	18.200	Cubic metre.	1500.00	Rupees One Thousand Five Hundred Only	Per cubic metre	27300.00
3	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer with bitumen emulsion pressure distributor at the rate of 0.40 kg (zero point forty kilogram) On W.B.M / W.M.M. of road surface as per CPWD technical specifications and as per the directions of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	182.000	Square metre	30.00	Rupees Thirty Only	Per square metre	5460.00
4	Providing and applying tack coat with bitumen emulsion RS-1, including cleaning the road surface with hydraulic brooms and spraying with emulsion pressure distributor at the rate 0.275 kg (zero point two seven five kilogramme) per square meter on the prepared granular surface treated with, primer complete as per MORTH technical specifications section 500, and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	182.000	Square metre	18.00	Rupees Eighteen Only	Per square metre	3276.00

Continued

P-2

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
		Figures	Words	Figures	Words		
5	Providing, laying and rolling of open graded premix carpet of 20mm (twenty millimeter) compacted thickness, composed of type-A 13.2mm to 5.6mm (thirteen point two millimeter to five point six millimeter) aggregates at the rate of 0.27 cum (zero point two seven cubic meter) premixed with bitumen binder Viscosity grade 30 (thirty) bitumen, at the rate of 14.6 kgs (fourteen point six kilogram) per 10 (ten) square meter of road surface, to the required line, grade and level to serve as wearing coarse on a previously prepared base including mixing and heating binder and aggregate in hot mix plant of 30/40 (thirty/fourty) tonne per hour capacity transporting mixed materials with tipper and laying with paver finisher hydrostatic with sensor attachment and rolling with three wheeled 80-100 (eighty to hundred) kN static roller finished to required level and grades to be followed by seal coat of type-B complete as per MORTH technical specifications section 500 and as per the entire satisfaction and direction of Engineer-in-Charge excluding the cost of tack coat and seal coat but including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	182.000	Square metre	185.00	Rupees One Hundred Eighty Five Only	Per square metre	33670.00
6	Providing and laying seal coat for sealing the voids in a bituminous surface laid to the specified levels, grade and cross falls using Type-B as per MORTH technical specifications section 500 using bitumen Viscosity grade 30 (thirty) at the rate of 6.80kg (six point eight zero kilogramme) premixed with 0.06 (zero point zero six) cubic meter of fine aggregate per 10 Sqm. (Ten square meter) of road surface heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 80-100 (eighty to hundred) kN static roller, as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	182.000	Square metre	80.00	Rupees Eighty Only	Per square metre	14560.00
TOTAL							96915.00
						% above/below	
						Quoted Rate in Figure	
						Quoted Rate in Words	


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-2

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99934/-
 Earnest Money: Rs. 2000/-
 Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages Link road to Village Chalet Kabir Panthi Mohallah Km 0/0 to 0/680, (SH- Construction of V-Shape Drain at Various RD,s)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Dismantling/Demolishing of existing structure like Drain, retaining wall and other structure comprising of Cement concrete Nominal concrete 1:3:6 or richer mix (1/c equivalent design mix) manually/ by mechanical, including unserviceable material and stacking the serviceable material and stocking the serviceable material with in all leads and lifts as per CPWD specification The rate shall include carriage of machineries, equipment, tolls and materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-Charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	12.150 Cubic metre	650.00	Rupees Six Hundred Fifty Only	Per cubic metre	7898.00
2	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	16.200 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	2916.00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (Twenty millimeter) nominal size) in or under water in open foundations and the like for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORTH technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	22.280 Cubic metre	4000.00	Rupees Four Thousand Only	Per cubic metre	89120.00
TOTAL						99934.00
					% above/below	
			Quoted Rate in Figure			
			Quoted Rate in Words			


 Executive Engineer,
 HPPWD Division,
 Daultapur Chowk.

Job-3

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99886/-
Earnest Money: Rs. 2000/-
Time Limit : Two month

Name of Work:- A/R & M/O HPPWD Rest house at Gagret Tehsil Ghanari Distt. Una (SH: -Painting to Rest house building)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Removing dry or oil bound distemper, cement paint and the like by scrapping, sand paperaing and preparing the surface smooth including necessary repairs to scratches etcetera complete as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	470.00 Square metre	11.15	Rupees Eleven And Paise Fifteen Only	Per square metre	5241.00
2	Providing and applying white cement based putty of average thickness 1 mm (one millimeter), of approved brand and manufacturer J.K wall Putty/ Brila White Putty, over the plastered wall surface to prepare the surface even and smooth complete upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	170.00 Square metre	85.10	Rupees Eighty Five And Paise Ten Only	Per square metre	14467.00
3	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface complete upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	470.00 Square metre	37.40	Rupees Thirty Seven And Paise Forty Only	Per square metre	17578.00
4	Wall painting (Two coats) with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 (Fifty) grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	230.00 Square metre	95.00	Rupees Ninety Five Only	Per square metre	21850.00
5	Painting wood work with Deluxe Multi Surface Paint of required shade two or more coat applied @ 0.90 ltr/10 sqm (Zero point nine zero litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (Zero point seven five litre per ten square metre) of approved brand and manufacture upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	85.00 Square metre	90.00	Rupees Ninety Only	Per square metre	7650.00
6	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point nine zero litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (Zero point eight zero litre per ten square metre) of approved brand and manufacture upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	80.00 Square metre	95.00	Rupees Ninety Five Only	Per square metre	7600.00

Contd. P-2

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
7	Finishing walls (Old work) with Acrylic Smooth exterior paint of required shade (Two or more coat) applied @ 1.67 ltr/ 10 sqm (at the rate one point six seven litre per ten square metre) on existing cement paint surface upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	340.00 Square metre	75.00	Rupees Seventy Five Only	Per square metre	25500.00
	TOTAL					99886.00
			Quoted Rate in Figure			
			Quoted Rate in Words			
			% above/below			


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-4

BILL OF QUANTITY

Estimate Cost :- Rs. 99300/-

Earnest Money :-Rs. 2000/-

Time Limit :- One Month.

Name of work:- Repair & Restoration of Rain Damages of Jeepable road from Swan Nadi to Railway Station Daulatpur Chowk Km. 0/0 to 1/0, (SH:- Repair to pot Hole between RD 0/0 to 0/500)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing, laying, spreading and compacting graded stone aggregate size range 53 mm to 0.075 mm (Fifty three millimetre to zero point zero seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical/manual mean in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per MORTH technical specification section 400 and as per the directions of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.02	Cubic meter	Rupees One Thousand Five Hundred Only	Per Cubic meter	10530.00
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer with bitumen emulsion pressure distributor at the rate of 0.85 kg (zero point eight five kilogram) per square metre of road surface as per MORTH technical specifications section 500 and as per the directions of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	93.60	Square metre	Rupees Forty Eight Only	Per Square meter	4493.00
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 3Kg per ten square metre, 20mm (Twenty millimetre) thick pre-mix carpet with 0.27 cubic metre of stone aggregate mixed with bitumen VG-10 @ 14.6Kg per ten square metre and seal coat type B using with bitumen VG-10 specification Clause 1904.2, 503 and 508.1, and as per the directions of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	300.99	Square metre	Rupees Two Hundred Eighty Only	Per Square meter	84277.00
	TOTAL					99300.00
					% above/below	
					Quoted Rate in Figure	
					Quoted Rate in Words	

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-5

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99844/-
 Earnest Money: Rs. 2000/-
 Time Limit : One Months.

Name of Work:- Restoration of Damages due to laying of Fire Hydrant by IPH Department on Daulatpur Bhera road km. 0/0 to 4/425. (SH: Re-Laying due to damaged road crust between RD 0/550 to 0/675) Under IPH Deposit

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
			Figures	Words			
1	Preparation and consolidation of sub grade with power road roller of 8 (eight) to 12 (twelve) tonne capacity after excavating earth to an average of 22.5 cm (twenty two point five centimeter depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with any lead as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	187.500	Square metre	69.50	Rupees Sixty Nine And Paise Fifty Only	Per square metre	13031.00
2	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM)specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical paverfinisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	18.750	Cubic metre.	1500.00	Rupees One Thousand Five Hundred Only	Per cubic metre	28125.00
3	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer with bitumen emulsion pressure distributor at the rate of 0.40 kg (zero point fourty kilogram) On W.B.M / W.M.M. of road surface as per CPWD technical specifications and as per the directions of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	187.500	Square metre	30.00	Rupees Thirty Only	Per square metre	5625.00
4	Providing and applying tack coat with bitumen emulsion RS-I, including cleaning the road surface with hydraulic brooms and spraying with emulsion pressure distributor at the rate 0.275 kg (zero point two seven five kilogramme) per square meter on the prepared granular surface treated with primer complete as per MORTH technical specifications section 500, and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	187.500	Square metre	18.00	Rupees Eighteen Only	Per square metre	3375.00

Contd= P-2

P-2

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
5	Providing, laying and rolling of open graded premix carpet of 20mm (twenty millimeter) compacted thickness, composed of type-A 13.2mm to 5.6mm (thirteen point two millimeter to five point six millimeter) aggregates at the rate of 0.27 cum (zero point two seven cubic meter) premixed with bitumen binder Viscosity grade 30 (thirty) bitumen, at the rate of 14.6 kgs (fourteen point six kilogram) per 10 (ten) square meter of road surface, to the required line, grade and level to serve as wearing coarse on a previously prepared base including mixing and heating binder and aggregate in hot mix plant of 30/40 (thirty/fourty) tonne per hour capacity transporting mixed materials with tipper and laying with paver finisher hydrostatic with sensor attachment and rolling with three wheeled 80-100 (eighty to hundred) kN static roller finished to required level and grades to be followed by seal coat of type-B complete as per MORTH technical specifications section 500 and as per the entire satisfaction and direction of Engineer-in-Charge excluding the cost of tack coat and seal coat but including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	187.500	Square metre	185.00	Rupees One Hundred Eighty Five Only	Per square metre	34688.00
6	Providing and laying seal coat for sealing the voids in a bituminous surface laid to the specified levels, grade and cross falls using Type-B as per MORTH technical specifications section 500 using bitumen Viscosity grade 30 (thirty) at the rate of 6.80kg (six point eight zero kilogramme) premixed with 0.06 (zero point zero six) cubic meter of fine aggregate per 10 Sqm. (Ten square meter) of road surface heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 80-100 (eighty to hundred) kN static roller, as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	187.500	Square metre	80.00	Rupees Eighty Only	Per square metre	15000.00
TOTAL							99844.00
				% above/below			
				Quoted Rate in Words			
				Quoted Rate in Figure			


 Executive Engineer,
 HPPWD Division,
 Daulatpur Chowk.

Job-6

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 90978/-
 Earnest Money: Rs. 2000/-
 Time Limit : One Month

Name of Work:- Balance work SDF/2024/602, R/O (Repair of) Repair & Restoration of Rain Damages link road to village Chalet Km. 0/0 to 6/030, (SH:- Construction of Retaining wall in G.P. Chalet Km. 2/530 to 2/535) Under SDRF

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	7.28 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	1310.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement four sand eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depts on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depts and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORTH technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	21.32 Cubic metre	3800.00	Rupees Three Thousand Eight Hundred Only	Per cubic metre	81016.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Reipipe, working pressure not less than 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORTH technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	14.00 Number	240.00	Rupees Two Hundred Forty Only	Each	3360.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORTH technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	7.56 Cubic metre	700.00	Rupees Seven Hundred Only	Per cubic metre	5292.00
TOTAL						90978.00
Quoted Rate in Figure		% above/below				
Quoted Rate in Words						

Executive Engineer,
 HPPWD Division,
 Daulatpur Chowk.

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99436/-
Earnest Money: Rs. 2000/-
Time Limit : Two month

Name of Work:- A/R & M/O HPPWD Rest house at Daulatpur Chowk Tehsil Ghanari Distt. Una (SH:-Painting to Rest house building)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Removing dry or oil bound distemper, cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etcetera complete as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	470.00 Square metre	11.15	Rupees Eleven And Paise Fifteen Only	Per square metre	5241.00
2	Providing and applying white cement based putty of average thickness 1 mm (one millimeter), of approved brand and manufacturer J.K wall Putty/ Brila White Putty, over the plastered wall surface to prepare the surface even and smooth complete upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	170.00 Square metre	85.10	Rupees Eighty Five And Paise Ten Only	Per square metre	14487.00
3	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface complete upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	470.00 Square metre	37.40	Rupees Thirty Seven And Paise Forty Only	Per square metre	17578.00
4	Wall painting (Two coats) with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 (Fifty) grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	230.00 Square metre	95.00	Rupees Ninety Five Only	Per square metre	21850.00
5	Painting wood work with Deluxe Multi Surface Paint of required shade two or more coat applied @ 0.90 ltr/10 sqm (Zero point nine zero litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (Zero point seven five litre per ten square metre) of approved brand and manufacture upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	80.00 Square metre	90.00	Rupees Ninety Only	Per square metre	7200.00
6	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point nine zero litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (Zero point eight zero litre per ten square metre) of approved brand and manufacture upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	80.00 Square metre	95.00	Rupees Ninety Five Only	Per square metre	7600.00

Contd. 2

P-2

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
7	Finishing walls (Old work) with Acrylic Smooth exterior paint of required shade (Two or more coat) applied @ 1.67 ltr/ 10 sqm (at the rate one point six seven litre per ten square metre) on existing cement paint surface upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	340.00 Square metre	75.00	Rupees Seventy Five Only	Per square metre	25500.00
	TOTAL					
			Quoted Rate in Figure			
			Quoted Rate in Words			
			% above/below			
						99436.00


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-8

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 98502/-
 Earnest Money: Rs. 2000/-
 Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages link road to Maidangarh to Up Mohal Joh Km. 0/0 to 4/000, (SH:- Construction of Retaining wall in G.P. Jon near House of Sh. Bai Ram Km. 1/800 to 1/813)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	5.20 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	936.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement concrete in all heights/depts on graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depts on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depts and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORTH technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	24.70 Cubic metre	3600.00	Rupees Three Thousand Six Hundred Only	Per cubic metre	88920.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less than 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORTH technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	12.00 Number	220.00	Rupees Two Hundred Twenty Only	Each	2640.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORTH technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	8.58 Cubic metre	700.00	Rupees Seven Hundred Only	Per cubic metre	6006.00
TOTAL						98502.00
Quoted Rate in Figure		% above/below				
Quoted Rate in Words						

Executive Engineer,
 HPPWD Division,
 Daultapur Chowk.

BILL OF QUANTITY

Estimate Cost :- Rs. 99629/-
Earnest Money :-Rs. 2000/-
Time Limit :- Two Month.

Name of work:-Restoration of Rain Damages on various roads in Daulatpur Sub Division, (SH: Painting to Nangal Jarialan Khad Bridge-I & II, and Parapets)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removing dry or oil bound distemper, cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etcetera complete as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	505.35 Square metre	11.15	Rupees Eleven And Paise Fifteen Only	Per square metre	5635.00
2	Providing and applying white cement based putty of average thickness 1 mm (one millimeter), of approved brand and manufacturer J.K wall Putty/ Brila White Putty, over the plastered wall surface to prepare the surface even and smooth complete upto all level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	165.50 Square metre	85.00	Rupees Eighty Five Only	Per Square metre	14068.00
3	Finishing with Epoxy paint (two or more coats) of HPPWD approved brand and manufacture on unplastered concrete work at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete upto all level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	605.50 Square metre	132.00	Rupees One Hundred Thirty Two Only	Per Square metre	79926.00
TOTAL						99629.00
Quoted Rate in Figure			% above/below			
Quoted Rate in Words						


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-10

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99204/-

Earnest Money: Rs. 2000/-

Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages link road to Maidangarh to Up Mohal Joh Km. 0/0 to 4/000, (SH:- Construction of Retaining wall in G.P. Jon near House of Sh. Ball Ram Km.1/815 to 1/828)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	5.20 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	936.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/dephs on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/dephs and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORTH technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	25.35 Cubic metre	3600.00	Rupees Three Thousand Six Hundred Only	Per cubic metre	91260.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less than 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORTH technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	12.00 Number	220.00	Rupees Two Hundred Twenty Only	Each	2640.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORTH technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	6.24 Cubic metre	700.00	Rupees Seven Hundred Only	Per cubic metre	4368.00
	TOTAL					99204.00
			% above/below			
			Quoted Rate in Figure			
			Quoted Rate in Words			


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-11

DRAFT BILL OF QUANTITY

Estimate Cost :- Rs. 99241/-
 Earnest Money :-Rs. 2000/-
 Time Limit :- Three Month.

Name of work:- Balance work SDF/2024/607, R/O (Repair of) Repair & Restoration of Rain Damages link road from Gram Panchayat Nangal Jarialan to Mohalla Kabirpanthi. (SH:- Balance work C/o 2.75/5.00 mtr wide Jeepable road Cutting/Filling between Km. 0/0 to 0/220) Under Deposit

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D technical specification clause 1603.1 Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-charge including carriage of materials disposing of excavated earth within all leads and lifts. The rate includes octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	276.25 Cubic metre	145 00	Rupees One Hundred Forty Five Only	Per cubic metre	40056.00
2	Construction of embankment with approved materials deposited at site obtained from roadway cutting and excavation from drains and foundation of all other structures or other sources, or obtained from borrow pits within all leads and lifts, graded and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor-Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 of MORD technical specification section 300 and 1600 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, toll tax, goods service tax, labour cess or any other taxes imposed by the Government.	190.00 Cubic metre	130 00	Rupees One Hundred Thirty Only	Per cubic metre	24700.00
3	Construction of embankment for roadway with approved material obtained from borrow pits and laid in layers of suitable thickness not exceeding 200mm (two hundred millimetres) spreading to required slope and compacted with three wheel 80-100 kN static/ vibratory road roller to meet the requirements of Tables 300.1 and 300.2 as per MORTH technical specifications section 300 as per drawings or directions of the Engineer-in-charge including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water wherever required including hauling of materials for construction of embankment within all leads and lifts. The rate shall include carriage of materials, equipment, tools and materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects and per direction of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	156.75 Cubic metre	220 00	Rupees Two Hundred Twenty Only	Per cubic metre	34485.00
TOTAL						99241.00
Quoted Rate in Figure		% above/below				
Quoted Rate in Words						

Executive Engineer,
 HPPWD Division,
 Daulatpur Chowk.

Job-12

BILL OF QUANTITY

Estimate Cost :- Rs. 98314/-

Earnest Money :-Rs. 2000/-

Time Limit :- One Month.

Name of work:- Repair & Restoration of Rain Damages of Jeepable road from Swan Nadi to Railway Station Daulatpur Chowk Km. 0/0 to 1/0, (SH:- Repair to pot Hole between RD 0/600 to 0/950)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing, laying, spreading and compacting graded stone aggregate size range 53 mm to 0.075 mm (Fifty three millimetre to zero point zero seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical/manual mean in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per MORTH technical specification section 400 and as per the directions of Engineer-in-Charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	6.69	1500 00	Rupees One Thousand Five Hundred Only	Per Cubic meter	10035.00
2	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer with bitumen emulsion pressure distributor at the rate of 0.85 kg (zero point eight five kilogram) per square metre of road surface as per MORTH technical specifications section 500 and as per the directions of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	89.20	48 00	Rupees Forty Eight Only	Per Square meter	4282.00
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 3Kg per ten square metre, 20mm (Twenty millimetre) thick pre-mix carpet with 0.27 cubic metre of stone aggregate mixed with bitumen VG-10 @ 14.6Kg per ten square metre and seal coat type B using with bitumen VG-10 specification Clause 1904.2, 503 and 508.1, and as per the directions of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	299.99	280 00	Rupees Two Hundred Eighty Only	Per Square meter	83997.00
TOTAL						98314.00
		Quoted Rate in Figure		% above/below		
		Quoted Rate in Words				


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-13

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 98219/-
Earnest Money: Rs.2000/-
Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages Link road to Village Pirthipur Nichla km. 0/0 to 3/265 andlink road from Joh Chowk to Mohalla Tillu Village Joh km. 0/0 to 2/250. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972 00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880 00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543 00 Running metre	30.00	Rupees Thirty Only	Per running metre	16,290.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	405 00 Cubic metre	80.00	Rupees Eighty Only	Per Cubic metre	32400.00
Total Amount in Rs.						98219.00
Quoted Rate in Figure						
Quoted Rate in Words						
% above/below						


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.