

NO/PW/TLD/Tender/2025; -  
To

Himachal Pradesh  
Public Works Department  
8073-82

Dated: - 14.11.2025

Executive Engineer IT Cell),  
Nirman Bhawan, Nigam Vihar, Shimla-2


Subject: -

Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of HP letter No. PBW (B) 1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA: - NIT.

  
Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

HPPWD Mandi for information please.


Copy is forwarded to Superintending Engineer, 1<sup>st</sup> Circle,

Division.

Copy to All the Assistant Engineers working under this


Copy to AB/DB in this office.

Copy to Notice board.

  
Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

### Certificate

Certified that the tender called vide this office letter No. PW/TLD/Tender/2025- 8063-72 dated 14.11.2025 is emergent nature and in Public interest.



Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
"NOTICE INVITING TENDER"**

below hereby invited by the Executive Engineer, HPPWD Division (B&R), Thalout at Pandoh on behalf of Governor of Himachal Pradesh from the eligible contractors of appropriate Class registered in HPPWD as per revised enlistment rule so as to reach in his office on 24.11.2025 at 11.00 A.M. The tenders shall be opened on the same date at 11.30 A.M. in the presence of intending contractors or their authorized representative who wish to be present. The request for issuing tenders form along with earnest money must reach in his office up to 3.00 P.M. on 21.11.2025 and that tender documents can be had from his office on cash payment noted against each (Non-Refundable) on 22.11.2025 up to 5.00 P.M on any working day. Notice Inviting Tender and other specification and conditions of the tender can be seen by the contractor in the office of the Executive Engineer, Thalout Division, HPPWD, Thalout during office hour on any working day.

Sr. No.	Name of work	Estimate cost	Earnest money	Cost of form	Time Period	Form No.	Eligibility of Contractors
1	R.R.D on road from Dhamu to Masad Km. 0/0 to 4/680 (SH: Hiring of Excavator cum loader for removal of slips/debris/mucks etc. at various RDs.)	99600	2,000	Rs. 350/-	One month	6&8	Class D enlisted in HPPWD
2	R.R.D on Mani to Shegali road Km. 0/0 to 4/00 (SH: Hiring of Excavator cum loader for removal of slips/debris/mucks etc. at various RDs.)	99600	2,000	Rs. 350/-	One month	6&8	-do-
3	R.R.D on various roads under Balichowki Sub Division (SH: - Hiring of excavator cum loader for removal of slips/debris/mucks etc. at various RDs of Balichowki Section) Job-2	99600	2,000	Rs. 350/-	One month	6&8	-do-
4	RRD on Sansoi to Kashna road Km. 0/0 to 6/250 (SH: C/O Crated B/Wall at RD 6/150 to 6/156.50)	97581	2000	Rs. 350/-	One month	6&8	-do-
5	R.R.D on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh section-I) Job No. 3	99600	2,000	Rs. 350/-	One month	6&8	-do-
6	R.R.D. on various roads under Balichowki Sub Division (SH: Hiring of Excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs of Balichowki Section) Job No. 1	99600	2,000	Rs. 350/-	One month	6&8	-do-
7	R.R.D on Bounchari to Kandha road Km. 0/0 to 12/00 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 5/00 to 7/500)	99600	2,000	Rs. 350/-	One month	6&8	-do-
8	RRD on Suhani Nallah to Dali road Km. 0/0 to 2/500 (SH: Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs)	99600	2,000	Rs. 350/-	One month	6&8	-do-
9	RRD on Sansoi to Kashna road Km. 0/0 to 6/250 (SH: C/o Crated B/Wall at RD 6/163 to 6/169.50)	97581	2,000	Rs. 350/-	One month	6&8	-do-
10	RRD on Bhurah to Panjain road Km. 0/0 to 11/00 (SH: Hiring of Tipper for carriage/Disposal of slips in various RDs in Km. 5/00 to 11/00).	98000	2,000	Rs. 350/-	One month	6&8	-do-



11	Repair of Maintenance of Govt. Sen. Sec. School at Balichowki in Tehsil Balichowki Mandi (HP) (SH: P/L Distempering with oil bound and Painting on steel work.)	93956	2,000	Rs. 350/-	One month	6&8	-do-
12	Maintenance of Four Laning of End Pandoh bypass to Takoli Kullu Section of NH-21 Km. 222/700 to 227/600 (SH: Removal of slips/boulders, muck debries etc. at various RDs) Job No. 2	99462	2,000	Rs. 350/-	One month	6&8	-do-
13	RRD on Thatta to Rangcha road km. 0/0 to 2/00 (SH: Removal of land slides, slips/boulders, muck debries etc. at various RDs)	99462	2,000	Rs. 350/-	One month	6&8	-do-
14	RRD on Basan to Somgad road Km. 0/0 to 8/500 (SH: Hiring of Tipper for carriage/Disposal of slips in various RDs in Km. 0/0 to 4/00).	98000	2,000	Rs. 350/-	One month	6&8	-do-
15	RRD on Jawalapur to parashar road Km. 0/0 to 12/525 (SH: Hiring of Excavator cum loader for Removal of slips/boulders, muck debries etc. at various RDs) Job No. 3	99600	2,000	Rs. 350/-	One month	6&8	-do-
16	Maintenance of Four Laning of End Pandoh bypass to Takoli Kullu Section of NH-21 Km. 222/700 to 227/600 (SH: Earthwork in filling at 223/300 to 223/400) Job No. 4	99980	2,000	Rs. 350/-	One month	6&8	-do-
17	RRD on Bakhali to Kholanal road Km. 0/0 to 8/400 (SH: C/o Parapet on slab culvert at various RDs)	84335	2,000	Rs. 350/-	One month	6&8	-do-
18	RRD on Jawalapur to parashar road Km. 0/0 to 12/525 (SH: Hiring of Excavator cum loader for Removal of slips/boulders, muck debries etc. at various RDs) Job No. 1	99600	2,000	Rs. 350/-	One month	6&8	-do-
19	R/R Damages on Pandoh Takoli by pass road km. 222/700 to 227/600 (SH: C/o R/Wall at RD 225/964 to 225/968).	82619	2,000	Rs. 350/-	One month	6&8	-do-
20	RRD on Sansoi to Kashna road Km. 0/0 to 6/250 (SH: C/o Crated B/Wall at RD 6/156.50 to 6/163)	97581	2,000	Rs. 350/-	One month	6&8	-do-
21	R/R Damages on Pandoh Takoli by pass road km. 222/700 to 227/600 (SH: C/o R/Wall at RD 225/960 to 225/964).	82619	2,000	Rs. 350/-	One month	6&8	-do-
22	Maintenance of Four laining of End Pandoh bypass to Takoli Kullu Section of NH-21 Km. 222/700 to 227/600 (SH: Removal of slips/boulders, muck debries etc. at various RDs) Job No. 1	99462	2,000	Rs. 350/-	One month	6&8	-do-
23	R/R Damages on Pandoh Takoli by pass road Km. 222/700 to 227/600 (SH: R/Wall in PCC 1:3:6 km. 225/965.50 to 225/968).	99533	2,000	Rs. 350/-	One month	6&8	-do-
24	RRD on Takoli Bhamsoi to Bhalther road Km. 0/0 to 4/00 (SH: Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs) Job No. 1	99600	2,000	Rs. 350/-	One month	6&8	-do-
25	RRD on various roads of Panarsa Sub Division (SH: Hiring of Tipper for carriage of muck/debris etc. at various RDs in Nagwain Section) Job No. 1	98000	2,000	Rs. 350/-	One month	6&8	-do-



26	Maintenance of Four Lining of End Pandoh bypass to Takoli Kullu Section of NH-21 Km. 222/700 to 227/600 (SH: Clearing of Grass & white washing in Km. 222/500 to 227/600).	94027	2,000	Rs. 350/-	One month	6&8	-do-
27	RRD on Thach to Khahari road Km. 0/0 to 5/0 (SH: C/o Crated R/wall at RD 3/610 to 3/620).	97873	2,000	Rs. 350/-	One month	6&8	-do-
28	RRD on various roads of Panarsa Sub Division (SH: Hiring of Excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section)	99600	2,000	Rs. 350/-	One month	6&8	-do-
29	RRD on Shalla Nallah Odidhar Dhraunli road Km. 0/0 to 8/00 (SH: Hiring of excavator cum loader for removal of slips/debris/mucks etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
30	RRD on Thach to Khahari road Km. 0/0 to 5/00 (SH: C/o Crated R/wall at RD 3/638 to 3/648).	98290	2,000	Rs. 350/-	One month	6&8	-do-
31	RRD on Banogi Bashout Patonsh road Km. 0/0 to 4/00 (SH: Hiring of Excavator cum loader for removal of slips/boulders, muck debris etc. at various RDs).	99600	2,000	Rs. 350/-	One month	6&8	-do-
32	RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-II) Job No. 1	99600	2,000	Rs. 350/-	One month	6&8	-do-

**TERMS & CONDITIONS: -**

1. The Tender form will not be issued to those contractors whose performance is not found satisfactory.
2. The Contractor whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to complete in tendering for four months.
3. The Contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only upto completion of work Satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.
4. The rates beyond the limit over +5% will be rejected besides this the Additional Performance security will have to borne @ 20 % & 30 % for unbalanced bid in case the rates is lower than 10 % but upto 20 % & lower than 20 % upto 30 % respectively. The tender will be accepted beyond the limit of -30 % also.

Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

NO/PW/TLD/Tender/2025:-

8063-72

Dated: - 14.11.2025

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP.
3. The Sub Divisional Officer Balichowki, Distt. Mandi HP.
4. The Chief Engineer, (MZ) HPPWD Mandi.
5. The Superintending Engineer, 1<sup>st</sup> Circle, HPPWD Mandi HP.
6. The Distt. Panchayat Officer Mandi HP.
7. All AEs under this Division.
8. The President of Contractor's Association.
9. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.

Executive Engineer,  
HPPWD Division (B&R),  
Thalout at Pandoh

# SCHEDULE OF QUANTITY

Name of work: R.R.D. on road from Dammu to Masad km 0/000 to 4/650. (Sst. - Hiring of excavator cum loader for removal of slips/debris/muck etc. at various R.D.s.)

Estimated Cost:-99600.00

Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Kachha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any loads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/PO, charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



**BILL OF QUANTITY**

Name of work:- RRD on Mani to Shegali road km 0/0 to 4/00 (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDS).

**Estimated Cost:-99600.00**

**Earnest Money:-2000.00**

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per diction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operation staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00
		Bill of Quantity	approved for Rs.	99600/-		

**Executive Engineer,**  
**Thalout Division,**  
**11HP PWD Thalout.**

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

# BILL OF QUANTITY

Name of work:- R.R.D. on various roads under Balichowki Sub Division (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs of Balichowki Section) Job-2

Estimated Cost:- 99600.00

Earnest Money:- 2000.00

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per drection of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty ) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, if may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Bill of quantity approved for Rs. 99600/-

Executive Engineer,  
Thalout Division,  
HP PWD Thalout



Name of work:- RRD on Sansoi to Kashna road km 0/0 to 6/250 (SH: - C/O crated B/wall at RD 6/150 to 6/156.50).

Estimated Cost: 97581.00
--------------------------

**Earnest Money :- 2000.00**

Time :- One Month

Executive Engineer  
Thalot Division,  
HP, PWD, Thalot

### SCHEDULE OF QUANTITY

Name of work:- RRD on various roads of Pandoh Sub Division (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDS under Pandoh Section-I) Job No-3

Estimated Cost:-99600.00  
Earnest Money:-2000.00  
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty ) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Quoted rate in figures

Quoted rate in words

Executive Engineer,  
Thalout Division,  
HP PWD Thalout



### SCHEDULE OF QUANTITY

Name of work:- R.R.D. on various roads under Balichowki Sub Division (SH:- Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs of Balichowki Section) Job-1

Estimated Cost:-99600.00  
Earnest Money:-2000.00  
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



**SCHEDULE OF QUANTITY**

Name of work:- R.R.D. on Bounchari to Kanda road km 0/0 to 12/000 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at RD 5/000 to 7/500).

Estimated Cost:-99600.00
Earnest Money:-2000.00
Time:- One Month

[illegible]

Executive Engineer,  
Thalout Division,  
HP PWD Thalout



SCHEDULE OF QUANTITY	
Name of work:- RRD on Suhani Nallah to Dali road km 0/0 to 2/500 (SH:- Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs)	

Estimated Cost:-99600.00
Earnest Money:-2000.00

Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



Name of work:- RRD on Sansoi to Kashna road km 0/0 to 6/250 (SH:- C/O crated B/wall at RD 6/163 to 6/169.50)

Name of work:- RRD on Sansoi to Kashna road km 0/0 to 6/250 (SH:- C/O crated B/wall at RD 6/163 to 6/169.50)

Estimated Cost: 97581.00
--------------------------

Earnest Money :- 2000.00
--------------------------

Time :- One Month

Executive Engineer,  
Thalout Division,  
HP, PWD, Thalout



SCHEDULE OF QUANTITY	
Name of work:- RRD on Bhurah to Panjain road km 0/0 to 11/00 (SH:-Hiring of Tipper for carriage /Disposal of slips in various RDs in km 5/00 to 11/00)	

Estimated Cost:-98000.00
Earnest Money:-2000.00
Time:- One Month

Executive Engineer,  
Thalout Division (B&R),  
HP PWD Thalout.

# SCHEDULE OF QUANTITY

Name of Work:- Repair and Maintenance of Govt. Sen. Sec. School at Balichowki in Tehsil Balichowki Mandi (HP) (SH:- P/L Distempering with oil bound and Painting on steel work.)

Estimated Cost:- 93,956.00  
Earnest Money :- 2,000.00  
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade (two or more coats) over and including water-thinnable priming coat with cement primer complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge as per hereto specifications, drawings and direction of Engineer-in-charge complete.	393.74	136.90	Rs. One hundred thirty six and paise ninety only	Per Square Metre	539
2	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge as per specifications, drawings and direction of Engineer-in-charge complete.	340.88	117.50	Rs. One hundred seventeen and paise fifty only	Per Square Metre	400
<b>Total in figures</b>					<b>Total</b>	<b>93</b>
			Percent			
Quoted rate in figure						
Quoted rate in words						
Rate quoted by contractor +/-						

Executive Engineer  
Thalout Division  
HPPWD, Thalout



### SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY	
Name of work:- Maintenance of Four Lining of End Pandoh bypass to Takoi Kullu Section of NH-21	
Km 222/700 to 227/600 (SH:-Removal of slips/boulders, muck debries etc. at various RDS) Job No-2	

Estimated Cost:- 99462.00
Earnest Money:-2000.00

Time:- One Month

[illegible]

SCHEDULE OF QUANTITY	
Name of work:- RRD on Thatta to Rangcha oad km 0/0 to 2/00 (SH:- Removal of land slides, slips/boulders, muck debries etc. at various RDs)	

Estimated Cost:- 99462.00
---------------------------

**Earnest Money:-2000.00**

Time:- One Month

Executive Engineer,  
Thalout Division  
HP PWD Thalout.



### SCHEDULE OF QUANTITY

**Name of work:-** RRD on Basan to Somgad road km 0/0 to 8/500 (SH:-Hiring of Tipper for carriage /Disposal of slips in various RDs in km 0/0 to 4/00).

**Estimated Cost:-98000.00**

**Earnest Money:-2000.00**

Time:- One Month

[illegible]

**SCHEDULE OF WORK**

Sl. No.	Particulars of work	Estimated cost	Actual cost
1	Name of work:-RRD on Jawalpur to Parashar road Km 0/00 to 12/525 (SH:- Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDs) Job No-3		

Estimated Cost:-99600.00

Earnest Money:-2000.00
------------------------

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty ) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	9960
	Quoted rate in figures				Total	9960
	Quoted rate in words					

Executive Engg  
 Thilout Divis  
 HP PWD Thalid

Executive Eng  
Thalout Divisi  
HP PWD Thalco



Name of work:- Maintenance of Four Laining of End Pandoh bypass to akoli Kullu Section of NH-21  
Km 222/700 to 227/600 (SH: - Earthwork in filling at 223/300 to 223/400) Job No-4

**Earnest Money:- 2000.00**

Time:- One Month


Executive Engineer  
Thalout Division,  
HP PWD Thalout.

**SCHEDULE OF QUANTITY**

**Name of work:- RRD on Bakhali to Kholanal road km 0/0 to 8/400 (SH:- C/O Parapet on slab culvert at various RDS).**

**Estimated Cost:- 84335.00**  
**Earnest Money :-2000.00**  
**Time :- One Month**

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Centering and shuttering including strutting, propping etc. and removal of form work for including carriage of material with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	47.16	540.00	Rs. five hundred forty and paise zero only	Per Cubic Metre	25466.00
2	Providing and laying concrete for plain/reinforced concrete in 1:3:6 (one cement: three sand: six crushed/ stone aggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	8.85	6651.90	Rs. Six thousand six hundred fifty one and paise ninety only	Per Cubic Metre	58869.00
					<b>Total</b>	<b>84335.00</b>
	Quoted rate in figure					
	Quoted rate in words					

  
 Executive Engineer,  
 Thabout Division,  
 HP PWD, Thabout



# SCHEDULE OF QUANTITY

Name of work:-RRD on Jawalpur to Parashar road Km 0/00 to 12/525 (SH: - Hiring of Excavator cum loader for Removal of slips/boulders, muck debris etc. at various RDs) Job No-1

Estimated Cost:-99600.00  
Earnest Money:-2000.00  
Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of slips/debris/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (six) hours daily and remove at least 20.00(Twenty ) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					Total	99600.00

Quoted rate in figures

Quoted rate in words

Executive Engineer,  
Thalout Division,  
HP PWD Thalout

**SCHEDULE OF QUANTITY**

Name of work:- R/R Damages on Pandoh-Takoli by pass road km. 222/700 to 227/600 (SH:- C/O R/wall at RD 225/964 to 225/968.)

Estimated Cost:- 82,619.00  
Earnest Money :- 1700.00  
Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	7.84	398.20	Rs. Three hundred ninety eight and paise twenty only.	Per Cubic Metre	3122.00
2	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	14.10	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	73281.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	4.92	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	6216.00
<b>Total in figures</b>					<b>Total</b>	<b>82619.00</b>
	Rate quoted by contractor +/-		Percent			
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,  
Thalout Division (B&R),  
HPPWD, Thalout



SCHEDULE OF QUANTITY	
----------------------	--

(SH: - C/O crated B/wall at RD 6/156.50 to 6/163)

Estimated Cost: 97581.00

Earnest Money :- 2000.00
--------------------------

Time :- One Month

[illegible]

Executive Engineer,  
Thalout Division  
HP, PWD, Thalout



225/960 to 225/964.)

SCHEDULE OF QUANTITY

Damages on Pandoh-Takoli by pass road km. 222/700 to 227/600 (SH:- C/O R/wall at RD

Sr. No.

Description of item

Estimated Cost:- 82,619.00  
Earnest Money :- 1700.00  
Time :- One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.84	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	3122.00
2	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702.704.1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement : six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	14.10	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	73281.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	4.92	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	6216.00
		Total in figures			Total	82619.00
		Rate quoted by contractor +/-		Percent		
		Quoted rate in figure				
		Quoted rate in words				

Executive Engineer,  
Thalout Division (B&R),  
HPPWD, Thalout



### SCHEDULE OF QUANTITY

Name of work:- Maintenance of Four Laining of End Pandoh bypass to akoli Kullu Section of NH-21 Km 222/700 to 227/600 (SH:-Removal of slips/boulders, muck debries etc. at various RDs) Job No-1

Estimated Cost:- 99462.00
Earnest Money:-2000.00
Time:- One Month

[illegible]

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.



# SCHEDULE OF QUANTITY

Name of work: R/R Damages on Pandoh-Takoli by pass road km. 222/700 to 227/600 (SH:- C/O R/wall in PCC 1:3:6 Km 225/965.50 to 225/968.)

Estimated Cost:- 99,533.00  
Earnest Money :- 2,000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other detritious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	7.95	648.00	Rs. Six hundred forty eight and paise zero only	Per Cubic Metre	5152.00
2	Providing and laying dowel bar in foundation in hard rock including making holes for dowel bar and fixing 25mm (Twenty five millimeter) dia for steel in cement slurry. complete within all leads, lifts, carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	4	817.13	Rs. Eight hundred seventeen and paise thirteen only		3269.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803.1202 and 1203 in cement concrete 1:3:6 (one cement: three sand : six graded stone aggregate 20mm nominal size) as per entire satisfaction and direction of Engineer-in-Charge.	12.10	7293.65	Rs. Seven thousand two hundred ninety three and paise sixty five only	Per Cubic Metre	88253.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material and other incidentals.	4.00	298.73	Rs. Two hundred ninety eight and paise seventy three only	Each	1195.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	1.07	1554.71	Rs. One Thousand five hundred fifty four and seventy one only	Per Cubic Metre	1664.00
Total in figures					Total	99533.00
Rate quoted by contractor +/-			Percent			
Quoted rate in gigure						
Quoted rate in words						

Executive Engineer,  
Thalout Division (B&R),  
HPPWD, Thalout



SCHEDULE OF QUANTITY	
Name of work:-	R/D on Takoli Bhamsoi to Bhalthar road km 0/0 to 4/00 (SH: - Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs). Job No-1

loader for removal of slips/clearance of berms, debris etc. at various RDs). Job No-1

Estimated Cost:-99600.00
--------------------------

Earnest Money:-2000.00
------------------------

Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout.

### SCHEDULE OF QUANTITY

**Name of work:- RRD on various roads of Panarsa Sub Division (SH: - Hiring of Tipper for carriage of muck/debris etc. at various RDS in Nagwain Section) Job No-1**

**Estimated Cost:- 98000.00**  
**Earnest Money:- 2000.00**  
**Time:- One Months**

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
	Hiring of Tipper for carriage of debris/ muck / unservicable material from the various reaches of the road including all leads, lifts and unloading of material at suitable places as per entire satisfaction of Engineer-in-Charge (9.00 am to 5.00 pm ) <b>Terms and conditions:-</b> 1. The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge. 2. During working hours any type of accident the owner is responsible. 3. Driver will be provided by the owner.	28	3500.00	Rupees Three thousand five hundred only	Per day	98000.00
					<b>Total</b>	<b>98000.00</b>
	Quoted rate in figures					
	Quoted rate in words					

  
**Executive Engineer,**  
**Thalout Division,**  
**HP PWD Thalout**



### SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY	
Name of work:-	Maintenance of Four Laining of End Pandoh bypass toTākoli Kullu Section of NH-21 Km 222/700 to 227/600 (SH:- clearing of Grass & white washing in Km 222/500 to 227/600),

**Estimated Cost:-94027.00**

**Earnest Money :- 2000.00**

Time :- One Month

[illegible]

Executive Engineer,  
Thalout Division (B&R),  
HPPWD, Thalout



Name of work:- RRD on Thach to Khahari road km 0/0 to 5/00 (SH: - C/O crated R/wall at RD 3/610 to 3/620).

SCHEDULE OF QUANTITY

S.No

Description of item

Quantity

In figure

Rate

In word

Unit

Amount

Estimated Cost: 97873.00  
Earnest Money :- 2000.00

Time :- One Month

1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides soil and as per the entire satisfaction and direction of Engineer-in-Charge.	4.10	609.90	Rs. Six hundred nine and paise ninety only	Per Cubic Metre	2501.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts, carriage of materials and other incidental complete.	13.82	3381.20	Rs. Three thousand three hundred eighty one and paise twenty only	Per Cubic Metre	46728.00
3	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structur and super structure complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	9.00	4002.10	Rs. Four thousand two and paise	Per Cubic Metre	36019.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	7.78	1622.75	Rs. One thousand six hundred twenty two and paise seventy five only	Per Cubic Metre	12625.00
	Total					97873.00
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,  
Thalout Division  
HP, PWD, Thalout



SCHEDULE OF QUANTITY	
Name of work:- RRD on various roads of Panarasa Sub Division (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section)	Estimated Cost:-99600.00
	Earnest Money:-2000.00

SCHEDULE OF QUANTITY	
Name of work:- RRD on various roads of Panarasa Sub Division (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Nagwain Section)	Estimated Cost:-99600.00
	Earnest Money:-2000.00

Estimated Cost:-99600.00
Earnest Money:-2000.00

Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Shalla Nallah Shara Odidhar Dhraunli road km 0/0 to 8/00 (SH: - Hiring of excavator cum loader for removal of slips/debries/mucks etc. at various RDs).

<b>S. No.</b>	<b>Description of item</b>	<b>Qty.</b>	<b>Figure</b>	<b>Rate in Words</b>	<b>Unit</b>	<b>Amount</b>
---------------	----------------------------	-------------	---------------	----------------------	-------------	---------------

<p>1 Hiring of Excavator-cum-loader for removal of snow/slips/debries/muck, road side berms, Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable material materials from the road surface upto any leads and lifts in emergent cases as work 6 (six) hours daily and remove at least 20.00 (Twenty) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.</p>	<p>83.00</p> <p>1200.00</p> <p>Rs. One thousand two hundred and paise zero only</p> <p>Per Hours</p> <p>99600.00</p>
---	--

<b>Quoted rate in figures</b>	<b>Quoted rate in words</b>	<b>Total</b>	<b>99600.00</b>
-------------------------------	-----------------------------	--------------	-----------------

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout.



**SCHEDULE OF QUANTITY**  
Name of work:- RRD on Thach to Khahari road km 0/0 to 5/00 (SH:- C/O crated R/wall at RD 3/638 to 3/648).

Estimated Cost: 98290.00

Earnest Money :- 2000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	5.46	609.90	Rs. Six hundred nine and paise ninety only	Per Cubic Metre	3330.0
2	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	13.82	3381.20	Rs. Three thousand three hundred eighty one and paise twenty only	Per Cubic Metre	46728.
3	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structur and super structure complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	8.82	4002.10	Rs. Four thousand two and paise paise ten only	Per Cubic Metre	35299
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	7.97	1622.75	Rs. One thousand six hundred twenty two and paise seventy five only	Per Cubic Metre	12933
	Total					98290
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer  
Thalout Division,  
HP,PWD,Thaloud



**SCHEDULE OF QUANTITY**

Name of work:-RRD on Banogi Bashout Patonsh road Km 0/00 to 4/00 (SH:- Hiring of Excavator cum loader for Removal of slips/boulders, muck debries etc. at various RDs)

Estimated Cost:-99600.00  
Earnest Money:-2000.00

Time:- One Month

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Excavator-cum-loader for removal of slips/debries/muck, road side berms,Katcha drain and boulder in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or unservicable material materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge.The machine should work 6 (six) hours daily and remove at least 20.00(Twenty ) cubic metre quantity of soil per hour Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel/POL charges and operationla staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the record entry, it may be ensured that the quantam of work done shall be minimum prescribed quantity and not less than 20.00 (Twenty) cubic metre per hour.	83.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	99600.00
					<b>Total</b>	<b>99600.00</b>
	Quoted rate in figures					
	Quoted rate in words					

  
 Executive Engineer,  
 Thalout Division,  
 HP PWD Thalout



SCHEDULE OF QUANTITY	
Name of work:-	
RRD on various roads of Pandoh Sub Division (SH:- Hiring of excavator cum loader for removal of slips/clearance of berms, debris etc. at various RDs under Pandoh Section-II)	Job No-1

Estimated Cost:-99600.00
Earnest Money:-2000.00

Time:- One Month

Executive Engineer,  
Thalout Division,  
HP PWD Thalout